

**Himachal Pradesh
Public works Department**
NO-PW-JDT-EA-I Tender NIT/2022-23:-

14728-30

Dated:- 27/03/23

To,

The Executive Engineer (IT Cell)
Nigam Bihar Shilma-2

Subject:-

Publishing of Tender notice

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Pr. Sec.(PW)to the Govt.of HP letter No-PBW(B)A9(3)1/2020 dated Shilma -2the 16th july 2021 as the work mentioned in the tender notice are urgent in nature and public interest

DA:- Notice Inviting Tender

Executive Engineer
Jhandutta Division
HP PWD Jhandutta


Copy forwarded the Superintending Engineer 10th Circle
Bilaspur HP PWD Bilaspur for information please

Copy forwarded to the Computer Cell O/O Executive Engineer
(IT Cell) Nigam Bihar Shimla -2 for information and further necessary action

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Certificate

Certified that the tenders called vide this office letter
No. PW-JDT EA-I-Tender /2022-23- 14717-27 dated
27/03/23 is emergent nature and in Public interest


Executive Engineer
Jhandutta Division
HPPWD Jhandutta

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage / item rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

**1. Date of receipt of application for the tender
Form a/w requisite documents:-**

04/04/2023 up to 02:30 PM

**2. Date of issue/sale of Tender forms against
Cash payment (Non-refundable):-**


05/04/2023 up to 03:00 PM

The tender shall be received up to **11:00A.M. on 06/04/2023** and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on **06/04/2023**.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta. a must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

| S.No. | Name of work | Estimate d cost | Earnest Money | Cost of form | Time limit | D cla ss |
|-------|--|--------------------|------------------|-----------------|----------------|----------------|
| 1. | R/R damages in Talai to Deot sidh road Km 0/0 to 1/00 (SH:- C/O Repair of pot holes | 499144/- | 10000/- | 350/- | Three month | D |
| 2. | R/R damages in Talai to Deot sidh road Km 1/0 to 2/610 (SH:- C/O Repair of pot holes | 476100/- | 9600/- | 350/- | Three month | D |
| 3. | R/R damages MDR-116 Ghumarwin Kodra Shah Talai road Km 25/0 to 31/00 (SH:-C/o Repair of pot holes | 499648/- | 10000/- | 350/- | Three month | D |
| 4. | C/O link road to village Kaller Km 0/00 to 1/500 (SH:- C/O 900mm dia HPC at RD 0/510 with wire crate and R/wall Earth filling etc | 499640/- | 10000/- | 350/- | Three month | D |
| 5. | C/O link road to village Kaller Km 0/0 to 1/500 (SH:- C/O Re-Grading of Formation deficiency in Km 0/0 to 0/600 & C/O900mm Dia hume pipe culvert at RD 0/150 with wing wall)(Under OTMNP) | 499620/- | 10000/- | 350/- | One month | D |
| 6. | R/R damages in various roads under Berthin Sub- Division (Talai section (SH:- C/o Repair of pot holes | 499765/- | 9600/- | 350/- | Three month | D |
| 7. | Restoration ofa roain damages Gurna Jhadi Temple to Halipad road 0/0 to 1/300 (SH:- C/O Repair of pot holes in Km 0/600 to 1/00 | 261893/- | 5400/- | 350/- | Three month | D |
| 8. | Restoration of rain (RO)damages Gurna jhadi Temple to Halipad road Km 0/0 to 1/300 (SH:- C/o Repair to pot holes in Km 0/300 to 0/600 | 499043/- | 10000/- | 350/- | Three month | D |
| 9. | R/R damages in Talai to Deotsidh road Km 0/0 to 2/645 (SH:- C/O R/wall at RD 2/020 to 2/028.25 | 480968/- | 9700/- | 350/- | Two month | D |
| 10 | A/R & M/O Bhager Berthin road Km 7/00 to 9/480 (SH:- C/O Repair of pot holes between Km7/00 to8/100 | 498200/- | 10000/- | 350/- | Three month | D |
| 11 | A/R & M/O Bhager Berthin road Km 7/00 to 9/480 (SH:- C/O Repair of pot holes between Km 8/100 to 9/480 | 499080/- | 10000/- | 350/- | Three month | D |
| 12 | A/R & M/O Bhallu Balori Raod Km 0/00 to 4/500 (SH:- C/O Repair of pot holes between Km 8/100 to 9/480 | 499601/- | 10000/- | 350/- | Three month | D |

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.
2. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy Application will not be entertained.


Executive Engineer
Jhandutta Division
HPPWD Jhandutta

No-PW-JDT-CB-Tender NIT/2022-23:-


14717-27

Dated:-

27/03/23

Copy forwarded to the following for information and necessary action Please:-

- The Engineer -in-Chief HP PWD Nirman Bhawan Shimla
- All the Chief Engineer in HP PWD
- The Superintending Engineer 10th Circle HP PWD Bilaspur
- All the Assistant Engineer Working under this Division
- The B.D.O Jhandutta
- A/B & D/B in this office
- Various Contractors working under this office
- Notice Board


Executive Engineer
Jhandutta Division
HPPWD Jhandutta

SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITIES | | | | | | | | | |
|---|---|------------------------------|---------|---|------------------|-----------|--|--|--|
| Name of Work :- R/R damages in Talai to Deotsidh road Km 0/0 to 1/00 (SH:- C/o Repair of Pot holes .) | | Estimated cost:- ₹ 499144.00 | | Only | | | | | |
| | | Earnest Money:- ₹ 10000.00 | | Only | | | | | |
| | | Time allowed:- Three Month | | | | | | | |
| Sr. No. | Description of iteams | Quantity | Figures | Rate | Unit | Amount | | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 237.99 | 263.83 | Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 62789.00 | | | |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1189.95 | 366.70 | Rs. three hundred sixty six and paise seventy only | Per Square Meter | 436355.00 | | | |
| Total:- | | | | | | 499144.00 | | | |
| Quated Rate in Figure:- | | % | | age +/- | | | | | |
| Quated Rate in Words:- | | | | | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITY | | | | | | |
|---|---|-----------------------------------|---------|---|------------------|-----------|
| Name of Work :- R/R damages in Talai to Deotsidh road Km 1/0 to 2/610 (SH:- C/o Repair of Pot holes .) | | Estimated cost:- ₹ 476100.00 Only | | | | |
| | | Earnest Money:- ₹ 9600.00 Only | | | | |
| | | Time allowed:- Three Month | | | | |
| | | | | | | |
| St. No. | Description of iteams | Quantity | Rate | | Unit | Amount |
| | | | Figures | words | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906,including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 275.10 | 263.83 | Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 72580.00 |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1100.41 | 366.70 | Rs. three hundred sixty six and paise seventy only | Per Square Meter | 403520.00 |
| Total:- | | | | | | 476100.00 |
| Quated Rate in Figure:- | | % | | +/- | | |
| Quated Rate inWords:- | | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD. Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damages in Talai to Deotsidh road Km 1/0 to 2/610 (SH:- C/o Repair of Pot holes .)

| SCHEDULE OF QUANTITIES | | | | | | | | | |
|---|--|-----------------------------------|---------|---|------------------|-----------|--|------|--|
| Name of Work :- R/R damages in Talai to Deotsidh road Km 1/10 to 2/610 (SH:- C/o Repair of Pot holes .) | | Estimated cost:- ₹ 499648.00 Only | | | | | | | |
| | | Earnest Money:- ₹ 10000.00 | | | | | | Only | |
| | | Time allowed:- Three Month | | | | | | | |
| | | | | | | | | | |
| Sr. No. | Description of iteams | Quantity | Figures | Rate | Unit | Amount | | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 501.04 | 263.83 | Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 132189.00 | | | |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508. 1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1002.07 | 366.70 | Rs. three hundred sixty six and paise seventy only | Per Square Meter | 367459.00 | | | |
| Total:- | | | | | | 499648.00 | | | |
| Quoted Rate in Figure:- | | %age +/- | | | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- C/O Link road to village Kaller km 0/00 to 1/500 (SH:-C/O 900 mm dia HPC at Rd.0/510 with wire crate and R/wall, Earth filling etc)

Estimated cost:- ₹ 499640.00

Only

Earnest Money:- ₹ 10000.00

Only

Time allowed:- Three Month

| Sr. No. | Description of items | Quantity | Rate | | Unit | Amount |
|---------|---|----------|---------|---|-----------------|--------|
| | | | Figures | words | | |
| 1 | Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 14.55 | 212.70 | Two Hundred Twelve and Paise seventy Only | Per Cubic Meter | 3095 |
| 2 | Providing and laying cement concrete 1:3:6 (one cement : three sand: six graded stone agg. 20 mm. nominal size) and curing complete including the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 9.24 | 5897.85 | Five thousand eight Hundred ninety seven & Paise eighty five only | Per Cubic Meter | 54496 |
| 3 | P/L NP2 class R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of (1:2): 19.6.10 900 mm dia. R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 Cement : 2 fine send)including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract | 7.50 | 3882.55 | Three thousand eight hundred eighty two and paise fifty five only | Per/ metre | 29119 |
| 4 | Providing & making Gabion structure with MechanicallyWoven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012.MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100mm with tolerance of ± 2%) Zinc coated, Mesh wire diameter 3.0 mm, mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist,tying with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge. | 15.62 | 3004.05 | Three thousand four and paise zero five only | Per Cubic Meter | 39547 |

| | | | | | | |
|---------|--|----------|--------|--|-----------------|-----------|
| 5 | Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1003.31 | 364.80 | Three hundred sixty four and paise eighty only | Per cubic metre | 366007.00 |
| Total:- | | | | | | |
| | Quated Rate in Figure:- | %age +/- | | | | |
| | Quated Rate in Words:- | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

| Name of Work :- C/O link road to Village Kaller Km 0/0 to 1500 (SH:- C/O Re-Grading of Formation deficiency in km 0/0 to 0/600 & C/O 900 mm dia Hume Pipe Culvert at RD 0/150 With wing wall). Under OTMNP | | Estimated cost:- ₹ 499620.00 | | Only | | |
|---|---|------------------------------|---------|---|-----------------|-----------|
| | | Earnest Money:- ₹ 10000.00 | | Only | | |
| | | Time allowed:- one Month | | | | |
| | | | | | | |
| Sr. No. | Description of iteams | Quantity | Rate | Unit | Amount | |
| | | | Figures | words | | |
| 1 | Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302,1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 946.53 | 296.00 | INR two Hundred Ninety six and Paise Zero Only | Per Cubic Meter | 280173.00 |
| 2 | Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 37.15 | 212.70 | INR Two Hundred Twelve and Paise seventy Only | Per Cubic Meter | 7902 |
| 3 | Proiding and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement isto four sand isto eight graded stone aggregate 25 mm.(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.59 | 5368.80 | INR Five thousand three hundred sixty eight and paise eighty only | Per cubic metre | 8536 |
| 4 | Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open oundation of Head walls as per drawings & Technical Specification Clause 1109. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 12.02 | 5897.85 | INR Five thousand Eight hundred ninety seven and paise eighty | Per Cubic Meter | 70892 |

| | | | | | | |
|---------|--|-------|---------|--|-------------------|--------|
| 5 | Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 900 mm The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 7.50 | 4020.60 | INR Four Thousand twenty and Paise sixty Only | Per Running Meter | 30155 |
| 6 | Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 19.89 | 4732.80 | INR Four Thousand Seven Hundred thirty Two and Paise eighty Only | Per Cubic Meter | 94135 |
| 7 | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 4.30 | 1345.70 | INR one Thousand three Hundred forty five and Paise seventy Only | Per Cubic Meter | 5787 |
| 8 | Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 6.00 | 339.95 | INR Three Hundred thirty nine and Paise ninty fiveOnly | Each | 2040 |
| Total:- | | | | | | 499620 |

%age +/-

Quoated Rate in Figures
Quoated Rate in Words

Executive Engineer,
Jhandutta Division,
HPPWD. Jhandutta

SCHEDULE OF QUANTITY

| Name of Work :- R/R damages in Various Roads Under Berthin Sub-Division (Talai Section) (SH:- C/o Repair of Pot holes .) | | | | Estimated cost:- ₹ | 499765.00 | Only |
|--|--|----------|---------|---|------------------|-----------|
| | | | | Earnest Money:- ₹ | 9600.00 | Only |
| | | | | Time allowed:- Three Month | | |
| Sr. No | Description of iteams | Quantity | Rate | | Unit | Amount |
| | | | Figures | words | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 238.29 | 263.83 | Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 62868.00 |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1191.4 | 366.70 | Rs. three hundred sixty six and paise seventy only | Per Square Meter | 436897.00 |
| Total:- | | | | | | 499765.00 |
| Quoted rate in Figures | | | | %age +/- | | |
| Quoted rate in Words | | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

| Name of Work :- Restoration of Rain (RO) damage Gurna Jhadi Temple to Halipad road Km 0/0 to 1/300 (SH:- C/o Repair of Pot holes.0/600 to 1/000) | | Estimated cost:- ₹ 261893.00 | | Only | | |
|--|---|------------------------------|----------|---|------------------|-----------|
| | | Earnest Money:- ₹ 5400.00 | | Only | | |
| | | Time allowed:- Three Month | | | | |
| | | | | | | |
| Sr. No. | Description of iteams | Quantity | Rate | Unit | Amount | |
| | | | Figures | words | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 124.87 | 263.83 | Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 32944.00 |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 624.35 | 366.70 | Rs. three hundred sixty six and paise seventy only | Per Square Meter | 228949.00 |
| Total:- | | | | | | 261893.00 |
| Quoted rate in Figures | | | %age +/- | | | |
| Quoted rate in Words | | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITY | | | | | | | |
|--|---|----------------------------|----------|---|------------------|-----------|--|
| Name of Work :- Restoration of Rain (RO) damage Gurma Jhadi Temple to Halipad road Km 0/0 to 1/300 (SH:- C/o Repair of Pot holes.0/300 to 0/600) | | Estimated cost:- ₹ | | 499043.00 | | Only | |
| | | Earnest Money:- ₹ | | 100000.00 | | Only | |
| | | Time allowed:- Three Month | | | | | |
| | | | | | | | |
| Sr. No. | Description of teams | Quantity | Rate | | Unit | Amount | |
| | | | Figures | words | | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 237.94 | 263.83 | Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 62776.00 | |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1189.7 | 366.70 | Rs. three hundred sixty six and paise seventy only | Per Square Meter | 436267.00 | |
| | | Total:- | | | | | |
| | | | %age +/- | | | | |
| Quoted rate in Figures | | | | | | | |
| Quoted rate in Words | | | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD. Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damages in Talai to Deodsih road Km 0/0 to 2/645 (SH:- C/O R/wall at RD 2/020 to 2/028.25).

| Name of Work :- R/R damages in Talai to Deodsith road Km 0/0 to 2/645 (SH:- C/O R/wall at RD 2/020 to 2/028.25). | | Estimated cost:- ₹ 480968.00 | | Only | | |
|--|---|------------------------------|---------|---|-----------------|-----------|
| | | Earnest Money:- ₹ 9700.00 | | Only | | |
| | | Time allowed:- Two Months | | | | |
| | | Quantity | Rate | Unit | Amount | |
| Sr. No. | Description of teams | Figures | words | | | |
| 1 | Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 41.08 | 212.70 | INR Two Hundred twelve and Paise seventy Only | Per Cubic Meter | 8738.00 |
| 2 | Providing and laying cement concrete 1:4:8 (one cement :four sand: eight graded stone agg. 40 mm. nominal size) and curing complete in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. Including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 83.23 | 5368.30 | INR Five Thousand three hundred sixty eight and Paise thirty Only | Per Cubic Meter | 446804.00 |
| 3 | Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 17.00 | 339.95 | INR Three Hundred thirty nine and Paise ninety five Only | Each | 5779.00 |
| 4 | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 14.60 | 1345.70 | INR One thousand three Hundred forty five and Paise seventy Only | Per Cubic Meter | 19647.00 |
| Total:- | | | | | | 480968.00 |

Quoted Rate in Figures

Quoted Rate inWords

Executive Engineer,
Jhandaulla Division
HPPWD, Jhandaulla

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/o Bhager Berthin Road Km. 7/00 to 9/480 (SH:-
C/o Repair of Pot holes between Km. 7/000 to 8/100)

| | | Estimated cost:- ₹ 498200.00 | | Only |
|---------|---|------------------------------|---|-------------------------------|
| | | Earnest Money:- ₹ 10000.00 | | Only |
| | | Time allowed:- Three Month | | |
| Sr. No. | Description of items | Quantity | Rate Figures words | Unit Amount |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 302.28 | 263.83 Rs. two hundred sixty three and paise eighty three only | Per Square Meter 79751.00 |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1141.12 | 366.70 Rs. three hundred sixty six and paise seventy only | Per Square Meter 418449.00 |
| Total:- | | | | 498200.00 |
| | Quoted rate in Figures | | %age +/- | |
| | Quoted rate in Words | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/o Bhager Berthin Road Km. 7/100 to 9/480 (SH:-
C/o Repair of Pot holes between Km. 8/100 to 9/480)

| SCHEDULE OF QUANTITY | | | | | | | |
|--|---|----------------------------|----------|---|------------------|-----------|------|
| Name of Work :- A/R & M/o Bhager Berthin Road Km. 7/00 to 9/480 (SH:- C/o Repair of Pot holes between Km. 8/100 to 9/480) | | Estimated cost:- ₹ | | 499080.00 | | | Only |
| | | Earnest Money:- ₹ | | 10000.00 | | | Only |
| | | Time allowed:- Three Month | | | | | |
| Sr. No. | Description of Items | Quantity | Rate | | Unit | Amount | |
| | | | Figures | words | | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 302.28 | 263.83 | Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 79751.00 | |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1143.5 | 366.70 | Rs. three hundred sixty six and paise seventy only | Per Square Meter | 419329.00 | |
| Total:- | | | | | | 499080.00 | |
| Quoted rate in Figures | | | %age +/- | | | | |
| Quoted rate in Words | | | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/o Bhallu Balori Road Km. 0/00 to 4/500 (SH:- C/o Repair of Pot holes)

| Sr. No. | Description of Items | Quantity | Estimated cost:- ₹ 499601.00 | | Only |
|------------------------|---|----------|---|------------------|-----------|
| | | | Earnest Money:- ₹ 10000.00 | | Only |
| | | | Time allowed:- Three Month | | |
| | | | Rate | Unit | Amount |
| | | | Figures words | | |
| 1 | Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 340.2 | 263.83 Rs. two hundred sixty three and paise eighty three only | Per Square Meter | 89755.00 |
| 2 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1117.66 | 366.70 Rs. three hundred sixty six and paise seventy only | Per Square Meter | 409846.00 |
| Total:- | | | | | 499601.00 |
| Quoted rate in Figures | | | %age +/- | | |
| Quoted rate in Words | | | | | |

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta