

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Scaled item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **26.04.2023** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **25.04.2023** up to **4:00 P.M.** and the application for issue of tender form shall be received on **24.04.2023** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Restoration of rain damages on Kufri Patialkar road Km 0/000 to 5/485 in District Kangra (HP) (SH:-Construction of retaining wall at 0/412 to 0/424).	234645/-	4700/-	Three months
2	Construction of Pucca Path to the House of Sh Balbir Kohli in G.P. Kawari in District Kangra (HP) Deposit work (SH:- Providing and laying interlocking paver block)	199973/-	4000/-	Three months
3	Construction of R/wall in the house of Kuldeep Chand ward No 3 at Bhuli Majethly in Tehsil Nagrota Bagwan Distt Kangra (HP) (SH:-Construction of retaining wall alongwith Nallah).	100508/-	2050/-	Two months
4	Construction of Gheena to Luhar Lahari road Km 0/000 to 5/100 in Distt Kangra (HP) (SH:-Providing and laying cement concrete pavement road in Km 3/294 to 3/320 and construction of road side parapets in various RDs between Km 1/700 to 3/200).	198513/-	4000/-	Two months
5	Construction of link road from NH -154 to Dharanvir house at RD 0/000 to 0/165 in District Kangra (HP) (SH:-Construction of 2.00 mtr span RCC span culvert 0/003 alongwith approaches).	499270/-	10000/-	Three months

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

No.PW/NBD/TA/Tender/NIT/2023-24- **332-61**

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla
5. The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Principal, Dr. RPGMC, Tanda.
8. The Deputy Commissioner, Kangra at Dharamshala.
9. All the S.E.s/E.E.s under North Zone.
10. The Sub-Divisional Officer(C) Nagrota Bagwan.
11. The Block Development Office Nagrota Bagwan
12. All the Assistant Engineer under this Division.
13. The Drawing /Accounts Branch in this office.
14. The Contractors concerned.
15. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

(On behalf of Governor of Himachal Pradesh)

Dated/ **17/04/2023**

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- 234645.00
 EARNEST MONEY :- 4700.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Restoration of rain damages on Kufri Patialkar road Km 0/000 to 5/485 in District Kangra, (H.P.).
SUB-HEAD :- Construction of Retaining wall at 0/412 to 0/424.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	27.72 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	56.04 Cubic metres			Per cubic metre	
3	Providing and fixing 100 mm (One hundred millimetres) diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetres) gap for thermal expansion, Single socketed pipes complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	48.00 Running metre			Per Running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.32 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagfota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - 199973.00
 EARNEST MONEY :- 4000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Pucca path to the house of Sh. Balbir Kohli in G.P. Kawari in District Kangra, (H.P.). Deposit Work
SUB-HEAD :- Providing and laying Interlocking Paver block

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying 60mm (Sixty millimetre) thick cement concrete paver block of M-35 grade with approved colour, design & pattern factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in- Charge complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	122.85 Square metres			Per square metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:3:6 (One cement; three sand; six graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.20 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 100508.00
 EARNEST MONEY :- ₹ 2050.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :-

Construction of Retaining wall in the House of Kuldeep Chand Ward No-3 at Bhuli Majehltly in Tehsil Nagrota Bagwan, Distt. Kangra (H.P)

SUB-HEAD :- Construction of Retaining wall alongwith Nallah. DEPOSIT WORK.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	21.15 Cubic metres			.	
2	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	8.00 Running metres			Per running metre	
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	18.40 Cubic metres			Per cubic metre	
TOTAL :-						



 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 198513.00
 EARNEST MONEY: - ₹ 4000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of Gheena to Lohar Lahari road Km 0/000 to 5/100 in Distt Kangra (HP).
SUB-HEAD :- Providing and laying Cement Concrete Pavement road in Km 3/294 to 3/320 and Construction of road side parapets in various RDs between Km 1/700 to 3/200

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying concrete for plain reinforcement concrete in open foundation including the cost of centering and shuttering complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 40mm (Forty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	12.87 Cubic meters			Per cubic metre	
2	Providing concrete for plain/reinforced concrete in open foundations including the cost of centering and shuttering complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 in 1:2.5:5 (One cement : Two and half sand : five graded) broken/crushed stone aggregate 20mm (Twenty millimeters) nominal size PCC grade M-15 (M-Fifteen), as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	26.89 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P. W.D., Division,
 Tanda at Nagrota-Bagwan.


SCHEDULE OF QUANTITY

ESTIMATED COST :- 499270.00
EARNEST MONEY :- 10000.00
TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of link road from NH-154 to Dharamvir House at RD 0/000 to 0/165 in District Kangra, (H.P.).
SUB-HEAD :- Construction of 2.00 mtr. Span RCC span culvert 0/003 alongwith approaches.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	40.92 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	31.64 Cubic metres			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated for plain cement concrete in open foundation complete using plain cement concrete grade M-15 (M-Fifteen) 1:2.5:5 (one cement : two point five sand : five graded crushed stone aggregate) design mix with cement contents not less than 275kg (two hundred seventy five kilogramme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	38.97 Cubic metres			Per cubic metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	28.15 Cubic metres			Per cubic metre	

5	Providing and laying mechanically mixed and vibrated Reinforced Cement Concrete in super-structure for all type of structure using cement concrete grade M-25 (M-Twenty five) 1:1.5:3 (one cement : one point five sand : three graded crushed stone aggregate) designed mix with cement contents not less than 400 Kgs (Four hundred kilograms) per cubic metre with 20mm (Twenty millimetres) nominal size graded crushed stone aggregate as per drawing and M.O.R.D. technical specification for Rural Roads Clause 800, 1205.4 and 1205.5 including the cost of form work and curing complete but excluding the cost of reinforcement for reinforced concrete work in bed block, dirt wall and deck slab complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.50 Cubic meters		Per cubic metre
6	Providing Tor steel reinforcement of Thermo Mechanically Treated bars of grade Fe-500D of Tata Tiscon/Sail for reinforced cement concrete work including bending, binding, cutting, straightening and placing in position complete including cost of binding wires complete upto all floor levels as per approved specifications, drawing, design, as per entire satisfaction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	841.00 Kilograms		Per kilo-gram
7	Construction of embankment with approved materials obtained from borrow pits free from Pebbles/Stones with a lift upto 1.5m (One point five meters) transport to sill spreading grading to required slope and compacted to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m (One thousand meters) as per Technical Specification Clause 301.5, including entire carriage of materials within all leads, lifts and other incidentals.	80.15 Cubic metres		Per cubic metre
8	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	28.50 Running metre		Per Running metre
TOTAL :-				


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.