



E- Mail id – pg-hil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 27/04/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 26/04/2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Repair and Maintenance of veterinary Hospital Building at Tarsooh in Distt. Bilaspur (HP) (SH:- Repair of Plaster, wood work, distemping) Deposit work	Rs. 1,30,766/-	Rs. 2,700/-	Rs. 350/-	Three Month
2	Construction of Panjail Tunighat road Km. 0/0 to 3/500 (SH:- C/o 900mm dia hume pipe culvert at RD 1/105 to 1/760) Deposit work	Rs. 3,85,728/-	Rs. 7,700/-	Rs. 350/-	Three Month
3	Widening of Patwarkhana Plog Dungloo road Km. 0/0 to 7/0 (SH:- Improvement of curve in Km. 5/535 to 5/580 and 6/250 to 6/300)	Rs. 1,94,741/-	Rs. 3,900/-	Rs. 350/-	Three Month
4	C/o link road Manjot to lower Seola in Km. 0/0 to 1/0 (SH:- C/o B/wall at RD 0/500 to 0/545) under PMGSY	Rs. 4,29,295/-	Rs. 8,600/-	Rs. 350/-	Three Month
5	Special repair to Junior Engineer's office cum residence at Namhol in Distt. Bilaspur (HP) (SH:- demolition, dismantling, P&L RCC slab, Plastering & Tile work etc.)	Rs. 4,93,949/-	Rs. 9,900/-	Rs. 350/-	Three Month
6	Construction of Panjail Tunighat road Km. 0/0 to 3/500 (SH:- C/o R/wall at RD 3/480 to 3/495) Deposit work	Rs. 2,72,079/-	Rs. 5,400/-	Rs. 350/-	Three Month
7	Construction of Balance work of Ambulance road to village Junah Km. 0/0 to 0/350 (SH:- C/o retaining wall at RD 0/134 to 0/147 alongwith parapets on hair pin bend)	Rs. 47,429/-	Rs. 1,000/-	Rs. 350/-	Three Month
8	Restoration of Rain damage damages on Swahan Katired Pangwana road Km. 0/0 to 7/0 (SH:- Hiring of Tractor wit trolley for removal of slips a various RDs) for the year 2023-24 Job No. 1	Rs. 99,930/-	Rs. 2,000/-	Rs. 350/-	Three Month
9	Restoration of Rain damages on NH-205 CMM road Km. 86/0 to 105/0 (SH:- Hiring of Tractor with trolley for removal of slips at RD in Km. 94/0 to 97/0) for the year 2023-24 Job No. 3	Rs. 99,360/-	Rs. 2,000/-	Rs. 350/-	One Month
10	Restoration of Rain damages due to digging of OFC cable on various roads under Namhol Sub Divsiion (SH:- Hiring of JCB for dressing of berms and clearance of drain at various RDS) for the year 2023-24 Job No. 1	Rs. 99,162/-	Rs. 2,000/-	Rs. 350/-	Three Month
11	Restoration of Rain damages on NH-205 CMM road Km. 86/0 to 105/0 (SH:- Hiring of Excavator cum loader/JCB for removal of slips at RD in Km. 94/0 to 97/0) for the year 2023-24 Job No. 2	Rs. 99,162/-	Rs. 2,000/-	Rs. 350/-	One Month

12	A/R & M/O Residentail Building (A.E. Residence) at Swarghat Distt.Bilaspur (HP) (SH:- Providing and laying Distempering, Painting wall putty and finishing with Acrylic smooth exterior paint etc)	Rs. 59,627/-	Rs. 1,200/-	Rs. 350/-	Three Month
13	Restoration of Rain damage damages on Swahan Katired Pangwana road Km. 0/0 to 7/0 (SH:- Hiring of Excavator cum loader/JCB for removal of slips at various RDs) for the year2023-24 Job No. 1	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	Three Month
14	C/o link road Sosan Bag Sohri Km. 0/0 to 5/0 (SH:- C/o Catch pit and NP-2 900mm dia hume pipe at RD 0/300) Deposit	Rs. 53,464/-	Rs. 1,100/-	Rs. 350/-	Three Month
15	C/o link road Bada Saloor Kaurawala Km. 0/0 to 0/600 (SH:- Providing and laying WBM Grading-III in Km. 0/0 to 0/500, C/o R/wall in Km. 0/530 to 0/540, C/o Road side drain at RD 0/410 to 0/430 and 0/480 to 0/500)	Rs. 4,37,352/-	Rs. 8,800/-	Rs. 350/-	Three Month
16	C/o link road Bada Saloor Kaurawala Km. 0/0 to 0/600 (SH:- providing and laying Interlocking concrete block in Km. 0/500 to 0/550)	Rs. 2,26,517/-	Rs. 4,500/-	Rs. 350/-	Three Month
17	Construction of Balance work of link road to Sosan Bag Shori Km. 0/0 to 5/0 (SH:- Providing and laying Grade-I and Grade-II in Km. 0/295 to 0/560 and tarring in Km. 0/295 to 0/560 alongwith Retaining wall at RD 0/300 to 0/300) (DC Deposit)	Rs. 3,99,753/-	Rs. 8,000/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2023-

361-71

Dated:- 19-04-2023

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs. =1,30,766/-Only.						
Earnest Money:- Rs. =2,700/-						
Time:- Three Months						
Name of Work:- Repair & Maintenance of veterinary Hospital Building at Tarsooh in Distt Bilaspur (H.P)(SH:- Repair of Plaster, wood work, distempering). (Depost Work)						
Sr. No.	Sub-Head and Items of work.	Qty	Figure.	Rates in Words.	Unit	Amount.
1	2	3			5	6
1	Repairs to plaster in patches of 2.50 sqm and under and 10 to 15 mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 meters with cement mortar 1:4 (One cement : Four sand) including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	75.21		Square metre.	Per Square metre.	
2	Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters including chowkhats, architraves, hold fasts and other attachments etc. complete and stacking them within 20 Metres lead including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.00		No.	Each	
3	Providing wood work in frames of doors, windows, clerestory windows and other frames wrought, framed and fixed in position 2nd class deodar wood including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.6325		Cubic metre.	Per Cubic metre.	
4	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows, including black enamelled iron butt hinges with necessary screws, 40mm (Forty millimetres) Second Class Deodar wood, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.	12.51		Square metre.	Per Square Metre	
5	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. (Eighty five G) with wire of dia 0.56 mm (Zero point five six) millimetre for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws. 2nd class Deodar wood including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.15		Square Meter.	Per Square metre	
6	Providing and fixing anodized aluminum sliding door bolt anodized colour and shade with bolts and nuts and screws etcetra complete including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
i)	300 X 16mm (Three hundred into sixteen millimetre)	1.00		No.	Each	

	Providing and fixing aluminium tower bolts (barrel type) anodized colour and shade with bolts and nuts screws etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, maikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.								
i)	300 X 10mm (Three hundred into Ten millimetre)	6.00	No.					Each	
ii)	150x10mm(One hundred fifty into ten millimetre)	14.00	Nos.					Each.	
8	Providing and fixing aluminium handles anodized, transparent or dye to required colour and shade with necessary screws etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, maikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.								
i)	125mm(One hundred twenty five millimetre).	6.00	No.					Each	
ii)	100mm(One hundred millimetre).	10.00	No.					Each	
9	Applying priming coat over new steel and other metal surfaces after and including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wood scrapers and sand paper complete with readymixed priming paint brushing red lead, Red oxide/zinc oxide chrome including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.92	Square Meter					Per Square Meter	
10	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt dust and other foreign matter. With enamel white paint including carriage of materials, within all leads and lifts as per direction by the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.53	Square metre.					Per Square metre	
11	Distemping (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on un-decorated wall surface to give an even shade over and l/c priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter also l/c preparing the surface even and sand papered smooth including priming coat with distemper primer including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	120.42	Square metre.					Per Square metre.	
12	Finishing wall with weather proof exterior grade emulsion of approved shade of (Apexultima) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.71	Square Meter					Per Square Meter	

	ing and fixing 10mm (Ten millimetre)thick anti skid water proof stain and impact resistant heavy duty verified tiles Nitco or equivalent 600x600mmx10mm (Six hundred millimetre into six hundred millimetre into ten millimetre manufactured of approved shade and colour in flooring, treads of 1:3 (One cement : Three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.84	Square Meter		Per Square Meter
14	Providing and laying Duro stone verified tiles (300x300mmx8mm) (Three Hundred millimeter into Three Hundred millimeter in to eight millimeter) in grey/coloured of required shade in skirting risers of steps and dados on 12 mm thick cement mortar 1:3 (one cement: three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	3.20	Square Meter		Per Square Meter
	Total:-				

Executive Engineer
Bilaspur Division No. 6
BPPWD Bilaspur-17600
(B)

SCHEDULE OF QUANTITY

Name of Work :- Construction of Panjail Tunghat road Km 0/0 to 3/500 (SH:- Construction of 900 mm dia Hume pipe Culvert at RD 1/105 & 1/760). Deposit Work.		Estimated cost:-		385728.00	Only
		Earnest Money:-		7700.00	Only
		Time allowed:- Three Month			
		Quantity	Rate	Unit	Amount
Sr. No.	Description of items	Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth upto a all lead and lift, as directed by Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	105.42		Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement into three coarse sand) into six graded stone aggregate 40 mm (forty millimeter) nominal size) including cost of form work and curing complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.14		Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 (one Cement into four coarse sand) into eight graded stone aggregate 40 mm (forty millimeter) nominal size) including cost of form work and curing complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.74		Per Cubic metre	

4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one cement into five coarse sand) into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including cost of form work and curing complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.60		Per Cubic metre
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00		Each
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.80		Per Cubic metre
7	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars joined with stiff mixture of cement mortar in the proportion of 1:2 (one cement into two fine sand) including testing of joints etc. complete : 900 mm (nine hundred millimeter) dia. R.C.C. pipe including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00		Per Running metre
Total:-				

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.1,94,741/-Only.						
Earnest Money :- Rs. 3,900/- only						
Time:- Three Months.						
NAME OF WORK:- Widening of Patwarkhana plog Dungloo road km 0/00 to 7/00 (SH):- Improvement of curve in km 5/535 to 5/580 and 6/250 to 6/300)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 300,1603 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing .and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana,toll tax, Goods & service Tax or other taxes imposed by the Government. A recovery of useful stones for 38.04 (Thirty Eight point zero Four) cubic metre @ Rs. 300/- (Three Hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item	634.35	Cubic Metre		Per Cubic Metre	
Total:-						



 Government of Karnataka

 Highway Division No. 6

 BPPWD Bangalore-17400



SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,29,295/- Only.				
		Earnest Money :- Rs.8,600/-				
		Time:- Three Months.				
NAME OF WORK:- C/O link road Manjhot to Lower Seola in km 0/00 to 1/00 (SH:- C/O B/wall at RD 0/500 to 0/545). (Under MMGSY)						
Sr No.	Description of Items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	6.75	Cubic Metre		Per Cubic Metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one Cement : Five coarse sand) : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials : within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	105.75	Cubic metre		Per Cubic metre	
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	51.00	Nos.		Each	
Total						

Executive Engineer
Highways Division Ho. #
444WD Bilaspur-17400

(B)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs. =4,93,949/-Only.
 Earnest Money:- Rs. =9,900/-
 Time:- Three Months

Name of Work:- Special Repair to Junior Engineer's Office Cum Residence at Namhol in Distt Bilaspur(HP)(SH:- Demolition,dismantling. P&L RCC Slab , Plastering & Tile work etc.).

Sr. No.	Sub-Head and Items of work.	Qty	Rates In		Unit	Amount.
			Figure.	Words.		
1	2	3			5	6
1	Demolition above ground level upto floor two level including stacking disposal of unserviceable materials and disposal of unserviceable materials with 20 metres lead and including cutting the necessary reinforcement and separating from R.C.C/R.B work. and as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals. The rates includes octroi, royalty ,Malkhana toll tax ,sale tax or other taxes imposed by the Government ,GST ,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.16	Cubic Metre		Per Cubic Metre	6
2	Demolition of stone masonry above G.L upto floor two level including stacking of of serviceable materials and disposal of un- serviceable material within 20 metre lead dressed stone in cement mortar. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.18	Cubic Metre		Per Cubic Metre	
3	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 Metres lead (wooden/concrete joists to be measured and paid for separately) for thickness of tiles upto 25 mm including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.04	Square metre		Per Square metres.	
4	Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters including chowkhat, architraves,hold fasts and other attachments etc. complete and stacking them within 20 Metres lead including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	No.		Each	

	Providing form work with steel plates 3.15 mm (Three point fifteen millimetres) thick welded with angle iron in frames, 30x30x5mm (Thirty into five millimetres) so as to give a fair finish including centering, shuttering, strutting and propping etcetra with wooden battens and ballies upto height propping and centering below supporting floor to ceiling and removal of the same for insitu reinforced concrete and plain concrete work Columns pillar, post and struts, square, rectangular or polygonal in plan, including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, malikana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.							
i)	Flat surfaces such as soffits of suspended floor, roofs, landing and the like floor etc. up to any thickness.	174.40	Square Meter				Per Square Meter	
ii)	Edges of slabs and breaks in floors and walls	59.60	Running metre				Per Running metre	
6	Providing and laying mechanically mixed & vibrated cement concrete 1:1.5:3 (One point five sand : three graded crushed stone aggregate of 20mm (Twenty millimetres) nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in upto floor all level including carriage of material within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.							
i)	Suspended floor roofs landing and shelves and their support balconies, beams, girders, bressumers and cantilever upto all floor level.	20.93	Cubic Meter				Per Cubic Meter	
7	Providing Tor steel Fe-500 sale/Tisco reinforcement for Reinforced Cement Concrete work including bending, binding straightening and placing in position complete in all heights including cost of binding wires completed and other incidentals due for its completion for all floors including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1675.00	Kilogram				Per Kilogram	
8	Cement concrete flooring, 1:2:4 (One Cement two sand four graded stone aggregate, 20mm nominal size) laid in one layer finished with a floating coat of neat cement, 40mm thick, including carriage of materials, within all leads and lifts as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malikana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.63	Square metre				Per Square metres.	

	one rolling properly hand packed filling interstices with Kharanja Stone and consolidating with power road road to the required gradient and camber including spreading watering and rolling of binding materials moonum or earth etc. complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.98	Cubic metres		Per Cubic metre
10	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802.803, 1202 & 1203. P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand : six graded stone aggregate 40mm (Forty millimetre) nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.98	Cubic metres		Per Cubic metre
11	Brick work using Second class common burnt clay buildings bricks in Cement mortar 1:6 (One Cement six sand) in super structure to all floor levels including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.90	Cubic Meter.		Per Cubic Metre
12	Providing wood work in frames of doors, windows, clerestory windows and other frames wrought, framed and fixed in position 2nd class deodar wood including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.22	Cubic metre.		Per Cubic metre.
13	6 mm plaster to ceiling in cement mortar 1:3 (One Cement three sand) including carriage of materials, within all leads and lift as per direction of the Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	142.76	Square Metre		Per Square Metre

	mm(fifteen millimetres) cement plaster in single coat in cement mortar 1:6 (One cement :six sand) on the rough side of brick/ concrete/ stone walls for interior plastering upto all heights including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finishing even and smooth including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.19	Square Meter	Per Square Meter
15	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	327.27	Square Meter	Per Square Meter
16	While glazed tiles 30x45 cm thick in skirting, risers of steps and Dado 6 mm (Six millimeter) thick cement mortar 1:3 (One cement and three sand) and jointed with cement slurry including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.21	Square metre	Per Square Meter
17	Providing and laying spartic ceramic tiles 5.5mm.thick in flooring 300 x300mm.(three hundred into three hundred millimeter size) treads of steps laid on a bed of 12mm (twelve millimeter) thick cement mortar 1:3 (one cement: three sand) finished with flush pointing in white cement. including carriage of materials within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.53	Square metre	Per Square Meter
18	Providing and fixing 10mm (Ten millimetre) thick anti skid water proof stain and impet resistant heavy duty vitrified tiles Nitco or equivalent 600x600mmx10mm (Six hundred millimetre into six hundred millimetre into ten millimetre manufactured of approved shade and colour in flooring, treads of 1:3 (One cement : Three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.31	Square Meter	Per Square Meter
Total:-				

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Construction of Panjail Tunghat road Km 0/0 to 3/500 (SH:- Construction of R/Wall at RD 3/480 to 3/495) . Deposit Work.				Estimated cost:- 272079.00		Only
				Earnest Money:- 5400.00		Only
				Time allowed:- Three Month		
Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth upto a all lead and lift, as directed by Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.70			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one cement into five coarse sand) into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including cost of form work and curing complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.40			Per Cubic metre	
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm (one hundred millimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00			Each	
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.20			Per Cubic metre	
Total:-						

Executive Engineer,
Bilaspur Division No. 6
SPWD Bilaspur-17488
(R/L)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs. 47,429/- Only.
 Earnest Money :- Rs.1,000/- Only.
 Time:- Three Months.

NAME OF WORK:- Construction of Balance work of Ambulance road to Village Junah km. 0/0 to 0/350(SH:- C/O Retaining wall at R.D.0/134 to 0/147 alongwith parapets on hair pin bend).

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning or slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.83	Cubic Metre		Per Cubic Metre	7
2	Providing and laying concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.(CC 1:5:10) without plumb including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.11	Cubic metre.		Per Cubic meter	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.70	Cubic metre.		Per Cubic Metre	

4.	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malakhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	Nos.			Each.	
Total:-							


 Executive Engineer
 Suburban Division No. 6
 Ahmedabad Bilaspur-17685
 (Bh)

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,360 /-Only.	
				Earnest Money:- Rs. = 2,000/-	
				Time:- one Months.	
Name of work :- Restoration of Rain Damages on Swahan katirad Pangwana road km 0/00 to 7/00 (SH):- Hiring of Tractor with trolly for removal of slips at various RDs for the Year 2023-24 Job No.-1					
Sr No.	Description of items.	Quantity	Rate In	Unit	Amount
			In Figure	In words.	
1	3 1 Providing one number tractor with trolly in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge .The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 238.00	5 Hours	Per Hours	6
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The tractor with trolly will be engaged on per hours bases working at site of work including cost of POL, establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
Total					

Executive Engineer
Bilaspur Division No. 8
HPPWD Bilaspur-176002

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,360 /-Only.	
				Earnest Money:- Rs.= 2,000/-	
				Time:- One Months.	
Name of work :- Restoration of Rain Damages on NH-205 CMM road km 86/00 to 105/00(SH):- Hiring of Tractor with trolly for removal of slips at Rd in km 94/000 to 97/000)For the Year 2023-24 Job No.-2					
Sr No.	Description of items.	Quantity	Rate In In Figure In words.	Unit	Amount
1	3 1 Providing one number tractor with trolly in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge .The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 288.00	5 Hours	Per Hours	6
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
i)	The tractor with trolly will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
Total					

Accepted & Engaged
Vijapur Division No. 2
PPWD Bilaspur-17000
(Bh)

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=99,162 /-Only.	
							Earnest Money:- Rs.= 2,000/-	
							Time:- one Months.	
Name of work :- Restoration of Rain Damages due to digging OFC cable on various roads under Namhol Sub Division (SH:- Hiring of JCB for dressing of berms and clearance of drain at various RDs). For the Year 2023-24 (Job No.-1)								
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount	
			In Figure	In words.				
1	3	4	5				6	
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malakhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	126.00	Hours			Per Hours.		
Terms and Condition:-								
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge							
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery							
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period							
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work							
Total								

Executive Engineer,
Highway Division No. 8
HPPWD Bilaspur-176002
(Bh)

SCHEDULE OF QUANTITY.			Estimated Cost:- Rs.=99,162 /-Only.			
			Earnest Money:- Rs.= 2,000/-			
			Time:- One Months.			
Name of work :- Restoration of Rain Damages on NH-205 CMM road km 86/00 to 105/00(SH):- Hiring of Excavator cum loader/JCB for removal of slips at Rd in km 94/000 to 97/000)For the Year 2023-24 Job No.-2						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3	4	5		Per Hours	6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	126.00	Hours			
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
i)	The tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
	Total					

Executive Engineer
Highway Division No. 8
HPPWD Bilaspur-17480
BK

SCHEDULE OF QUANTITY.		Estimated cost:- Rs. 59,627/- Only.				
		Earnest Money :- Rs.1,200/- Only.				
		Time:- Three Months.				
NAME OF WORK:-A/R & M/O to Residential Building (A.E Residence) at Swarghat Distt. Bilaspur (HP) (Sh:-providing & Laying Distempering, Painting, Wall Putty and Finishing with Acrylic smooth exterior paint etc)						
Sr No.	Description of items.	Quantity	Rates in Figure. Words.	Unit	Amount	
1	2	3	4	5	6	7
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	272.63	Square Meter	Per Square Meter		
2	Providing roviding and applying Birla White cementputty of average thickness 2 mm (two millimeter), of proved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	136.31	Square Meter	Per Square Meter		
3	Distempering with 1st quality acrylic distemper (ready made) of approved manufacturer and of required shade andcolour complete. as per manufacturer's specification one or more coats on old work. within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	272.63	Square Meter	Per Square Meter		
4	Finishing walls with Acrylic Smooth exterior paint of required shade old work (Two or more coat applied @ 1.67ltr/ 10 sqm) on existing cement paint surface within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	257.28	Square Meter	Per Square Meter		

5

Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

141.42	Square Meter			Per Square Meter	
Total:-					

Executive Engineer
Bilaspur Division No. 3
Bilaspur-174001
(3)

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=99,949 /-Only.

Earnest Money:- Rs.= 2,000/-

Time:- one Months.

Name of work :- Restoration of Rain Damages on Swahan katirad Pangwana road km 0/00 to 7/00 (SH):- Hiring of Excavator cum loader/JCB for removal of slips at various RDs) For the Year 2023-24 Job No.-1

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	3	4	5				6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	127.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							


 Engineer-in-Charge,
 Suburban Division No. 8
 UPWD Bilaspur-17600

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.53,464/-Only.			
				Earnest Money :- Rs.1,100/-			
				Time:- Three Months.			
NAME OF WORK:- Construction of link road Sosan Bag Sohari km 0/00 to 5/00(SH:- C/O Catch pit and NP2 900 mm dia RCC hume pipe at R.D 0/300)(Deposit work)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 .P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand : six graded stone aggregate 40mm (Forty millimetre)nominal size.The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.80	Cubic metres			Per Cubic metre	
2	Providing and laying(to level or slopes)900mm dia(Nine hundred millimetre dia)reinforced cement concrete pipe I.S.Class NP2 for culverts on first class bedding of granular material in single row, including fixing collars, with cement mortar 1:2(One Cement two sand)but excluding the cost of excavation, M.O.R.D Technical specification clause 1108 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges .The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.50	Running metre			Per Running metre.	
Total							

Executive Engineer,
Vidyanagar Division No. 8
UPPWD Bilaspur-17400

(B)

DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/o link road Bada Saloor Kaurawala Km 0/0 to 0/600 (SH:- Providing & Laying WBM Grading -III in Km 0/0 to 0/500, C/o R/Wall in Km 0/530 to 0/540 C/o Road side Drain at RD 0/410 to 0/430 & 0/480 to 0/500).									
		Estimated cost:- ₹ 437352.00		Only					
		Earnest Money:- ₹ 88000.00		Only					
Time allowed:- three Month									
Sr. No.	Description of items	Quantity	Rate		Unit	Amount			
			Figures	words					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990 .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.70			Per Cubic metre				
2	Providing and laying in position cement concrete of specified grade including/ excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one cement into five fine sand into ten graded stone aggregate 40 mm (forty millimeter) nominal size) Including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990 .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.60			Per Cubic metre				
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990 .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.80			Per Cubic metre				
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm (one hundred) dia. PVC pipe extending through the full width of the structures with slope of 1 V :20 H towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990 .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00			Each				

5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement into three coarse sand) into six graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.10			Per Cubic metre
6	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-II as per Technical Specification Clause 405. By Mechanical Means including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	120.09			Per Cubic metre
Total:-					

Executive Engineer,
Bilaspur Division No. 3
H.P.W.D., Bilaspur (H.P.)

DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/o link road Bada Saloor Kaurwala Km 0/0 to 0/600 (SH:- Providing & Laying Interlocking Concrete Block in Km 0/500 to 0/550).

Name of Work :- C/o link road Bada Saloor Kaurawala Km 0/0 to 0/600 (SH:- Providing & Laying Interlocking Concrete Block in Km 0/500 to 0/550).					Estimated cost:- ₹ 226517.00		Only
					Earnest Money:- ₹ 4500.00		Only
					Time allowed:- three Month		
Sr. No.	Description of items	Quantity	Rate		Unit	Amount	
			Figures	words			
1	Providing and laying in position cement concrete of specified grade including/ excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one cement into five fine sand into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990 .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.50			Per Cubic metre		
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50 mm (fifty millimeter) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge 80 mm (eighty millimeter) thick C.C. paver block of M-30 (thirty) grade with approved color design and pattern. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge As per HP.PWD specification 1990 .The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	165.00			Per square metre		
Total:-							

Executive Engineer,
Bijapur Division Mg. N
HP PWD., Baleshwar

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.3,99,753/-Only.		
				Earnest Money:- Rs.=8,000/-		
				Time:- Three Months.		
Name of work :- Construction of Balance work of link road to Sosan Bag Shori km. 0/0 to 5/0(SH)- Providing and laying Grade-I and Grade-II in km. 0/295 to 0/560 and Tarring in km. 0/295 to 0/560 alongwith Retaining wall at R.D. 0/300 to 0/315(D.C Deposit).						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiselling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts and other incidentals as per direction of Engineer-in-Charge .Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.75			Per Cubic Metre	7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses,802,803,1202 and 1203 (1:5:10) without plum, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.80			Per Cubic metre	
3	Providing back filling with granular material behind abutment, wing walls, return walls and retaining/breast walls to the full height compacted to firm condition complete as per drawing and M.O.R.D technical specification clause 1204.3.8 and as per direction of Engineer-in-Charge including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.00			Per Cubic metres	

4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.00	Nos.		Each.
5	Providing laying , spreading and compacting stone aggregates of specific sizes 90 mm to 45mm,Ninety millimetre to forty five millimetre) Grading-I 100mm (One hundred millimetre) consolidated thick water bound macadam specification including spreading in uniform thickness using template , hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming , graded crushed stone screening type - A of size , 13.2 mm (Thirteen point two millimetre) nominal size at the rate of 0.27 cubic metre (Zero point twenty Seven cubic metre) per 10 square metre (Ten square metre) to fill up the interstices of course aggregate watering and compacting to the required density of grading -1 as per Technical Specifications Clause 404 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	93.21	Cubic Metre		Per Cubic Metre
6	Providing laying , spreading and compacting stone aggregates of specific sizes 63 mm to 45mm(Sixty three millimetre to forty five millimetre) Grading-II 75 mm (Seventy five millimetre) consolidated thick water bound macadam specification including spreading in uniform thickness using template , hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming , graded crushed stone screening type -B of size , 11.2 mm (Eleven point two millimetre) nominal size at the rate of 0.20 cubic metre (Zero point twenty cubic metre) per 10 square metre (Ten square metre) to fill up the interstices of course aggregate watering and compacting to the required density of grading -2 as per Technical Specifications Clause 405 , including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.65	Cubic Metre		Per Cubic Metre
7	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 -1.00 (Zero point seven zero to one point zero)Kilogramme per Square metre using mechanical means as per Technical Specifications Clause 502. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax ,building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	848.66	Square metre.		Per Square metre.

8	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 Kg. (Zero point two five to Zero point three zero) Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service, building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	848.66	Square metre		Per Square metre
10	Compacted of crushed stone aggregate 13.2 mm to 5.6 mm (Thirteen point two millimetre to five point six millimetre) @ 0.27 cubic metres (Zero point two seven) per 10 square metre (Ten Square metre) mixed with penetration grade paving bitumen VG-10 (Viscosity grade-10) at the rate of 14.6 kg. (Fourteen point six kilogramme) per ten square metre of road surface to required line, grade and level to serve as wearing course on a previously prepared base including mixing and heating binder and aggregate in suitable plant, laying with paver finisher and rolling with a three wheel 80-100 KN (Eighty - hundred) capacity static road roller/ manually finished to required level and grade to be followed by seal coat of type-B by manual means as per MORD technical specification clause 508 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service, building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	848.66	Square metre		Per Square metre
	Providing and laying seal coat sealing the voids in a bitumenous surface laid to the specified levels, grade and cross fall using Type-B as per Technical Specification Clause 510 ((BY Manual Means)(Bitumen (S-90) Viscosity grade-10 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rates includes octroi, royalty, Malkana toll tax, goods and service, building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	848.66	Square metre		Per Square metre
					Total:-


 Executive Engineer
 Division No. 17
 Bilaspur-174001