

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PWD/KB/CB /Tender/2023-

29-31

Dated: 10/4/2023


To

The Executive Engineer (IT CELL)  
Nigam Bihar Shimla-2.  
Himachal Pradesh.

Subject:- Publication of tender Notice.


Enclosed please find herewith the tender Notice of work as give in the notice inviting Tender For uploading on department website as per notification Principal Secretary (PWD) to the Govt. of Himachal Pradesh letter NO. PBW-(B) A9 (3)1/2020 dated Shimla -2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/As above.

  
Executive Engineer,  
Kotla Behar Division,  
HPPWD, Kotla Behar

1. Copy forwarded to the Superintending Engineers 9<sup>th</sup> Circle, HPPWD, Nurpur. For information please.
2. Copy forwarded to the Computer cell O/O Executive Engineer (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action

DA/As above.

  
Executive Engineer,  
Kotla Behar Division,  
HPPWD, Kotla Behar



HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated **20.04.2023 up to 10.30AM** and the same will be opened on the same day at **11.30 AM** in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to **2.00 PM** on dated **18.04.2023** and tender forms can be obtained from this office against cash payment (nonrefundable) on **19.04.2023 from 10.00 AM to 5.00 PM** and no tender form shall be issued by the post. The amount of earnest money in shape of **FDR of any nationalized bank in HP** duly pledged in the Name of **Executive Engineer HPPWD Kotla Behar Division Kotla Behar**

The conditional tender and tender received without **earnest money** (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Repair & Maintenance on various roads under Pragpur Sub Division (Section Rakkar ) (SH; Repair of pot holes)	494550.00	10000.00	Three Month	350/-	6&8
2	Repair & Maintenance on various roads under Pragpur Sub Division (Section Pirsaluhi ) (SH; Repair of pot holes)	494550.00	10000.00	Three Month	350/-	6&8
3	C/o Balance work on link road from Seul Khad to Salyah road KM. 0/0 to 2/0 (P/L Cement concrete pavement at RD 1/092 to 1/135) (Under OTMNP)	176868.00	4000.00	Two Month	350/-	6&8
4	Restoration of Rain Damages on Upper Nari to Lower Nari road KM 0/0 to 3/600 (SH: Construction of R/Wall on various RDs)	302900.00	6000.00	Three Month	350/-	6&8
5	C/o Balance work on L/R Rakkar Shantla road to House of Sh. Pardhan Sansar Chand Via Kaur Basti to Connect with Sit Pak road KM 0/0 to 3/0 (SH: Removal of Formation Deficiency at various RDs)	385186.00	8000.00	Three Month	350/-	6&8
6	Repair & Maintenance on various roads under Dada siba Sub Division (Section Kotla ) (SH; Repair of pot holes)	494550.00	10000.00	Three Month	350/-	6&8
7	Restoration of Rain Damage on Bharwain Chintpurni Kandrori Damtal road Km. 15/310 to 32/560 (SH:- C/o Unlined Drain and Maintenance of Earthen Shoulder in Various RD's)	341450.00	7000.00	Three Month	350/-	6&8
8	Repair & Maintenance on various roads under Pragpur Sub Division (SH:- Repair of Pot Holes on Bani to Pragpur via Dangrta road in between Km. 0/300 to 0/360 & Bani to Sehri road in between Km. 2/500 to 4/000)	499958.00	10000.00	Three Month	350/-	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,

Executive Engineer,  
Kotla Behar Division HPPWD.,  
Kotla Behar

32-36

DATED 10/4/2023

NO.PWD/KB/CB/TENDER/ 2023

information please.

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of  
Copy to the Engineer-in-Chief HPPWD Shimla for information please.  
Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.  
Copy to the Superintending Engineer 9<sup>th</sup> Circle HPPWD Nurpur for favour of information please.

Executive Engineer,  
Kotla Behar Division HPPWD.,  
Kotla Behar.



## SCHEDULE OF QUANTITY

JOB NO. 1

Estimate Cost :- Rs. 4,94,550/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

**Name of work:- Repair & Maintenance on various roads under Pragnpur Sub-Division (Section Rakkar) (SH: Repair of Pot Holes)**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	1570.00 Square meter			Per square meter	
	<b>TOTAL</b>					

Executive Engineer,  
Kotla Behar Division,  
HPWD Kotla Behar.



## SCHEDULE OF QUANTITY

JOB NO. 2

Estimate Cost :- Rs. 4,94,550/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

**Name of work:- Repair & Maintenance on various roads under Pragnpur Sub-Division (Section Pir Saluhi) (SH: Repair of Pot Holes)**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government	1570.00 Square meter			Per square meter	
	<b>TOTAL</b>					

Executive Engineer,  
Kotla Behar Division,  
HPPWD Kotla Behar.



## SCHEDULE OF QUANTITY

JOB NO. 3

Estimate Cost :- Rs. 176968/-

Earnest Money :- Rs. 4000/-

Time Limit :- Two Months.

Name of work:- C/O Balance work on link road from Seul Khad to Salyah road Km 0/0 to 2/0 (SH:- P/L Cement concrete Pavement at RD. 1/092 to 1/135) (Under OTMNP)

Sl. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	26.01 Cubic metre			Per Cubic metre	
<b>TOTAL</b>						

Executive Engineer,  
Kotla Behar Division,  
HPPWD Kotla Behar.



# Name of work:- Restoration of Rain damage on Upper Nari to Lower Nari Km. 0/0 to 3/600 (Sh:- Const. of Retaining wall at Various RD's).

## **SCHEDULE OF QUANTITY**

### Description of Item

JOB NO. 4  
Estimate Cost :- Rs. 302900.00  
Earnest Money :- Rs. 6000.00  
Time Limit :- Three Month.

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	25.40 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	80.56 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	30.76 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical : to twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3, 7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	18.00 Number			Each	
<b>TOTAL</b>						

Executive Engineer,  
Kotla Behar Division,  
HPPWD Kotla Behar.



# SCHEDULE OF QUANTITY

JOB NO. 5

Estimate Cost :- Rs. 85186.00

Earnest Money :- Rs. 8000.00

Time Limit :- Three Month.

of work:- C/o Balance work on L/R Rakkar Shantla road to House of Sh. Pardhan Sansar Chand Via Kaur Basti to Connect with Sit Pak road KM 0/0 to 3/0

(SH: Formation cutting at various RDs)

NO.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, width, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in-Charge complete in according to MORD Technical Specification section 300 & 1600 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 31.98 cubic metre quantity at the rate of Rs. 300/- only (Rupees three hundred only) per cubic meter shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1100.53 Cubic metre			Per Cubic metre	
	TOTAL					

Executive Engineer,  
Kotla Behar Division,  
HPPWD Kotla Behar.



## SCHEDULE OF QUANTITY

JOB NO. 6

Estimate Cost :- Rs. 4,94,550/-

Earnest Money :- Rs. 10000/-

Time Limit :- Three Months.

**Name of work:- Repair & Maintenance on various roads under Dada siba Sub-Division (Section Kotla) (SH: Repair of Pot Holes)**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	1570.00 Square meter			Per square meter	
	<b>TOTAL</b>					

Executive Engineer,  
Kotla Behar Division,  
HPPWD Kotla Behar.



# SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Bharwain Chintpurni Kandrori Danttal road Km. 15/310 to 32/560 (SH: C/o Unlined drain and Maintenance of Earthen Shoulder in Various RD's)

JOB NO. 67  
Estimate Cost :- Rs. 3,41,450/-  
Earnest Money :- Rs. 7000/-  
Time Limit :- Three Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of unlined surface drains by manual means of average cross-sectional area 0.40 (Zero decimal four zero) square metre in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment within all leads, lifts and other incidentals as per Technical Specification Clause 307 and as per the direction and entire satisfaction of Engineer-in-Charge.	1450.00 Running Metre			Per running meter	
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	5310.00 Square meter			Per square meter	
TOTAL						

Executive Engineer,  
Kotla Behar Division  
HPPWD Kotla Behar.



## SCHEDULE OF QUANTITY

**Name of work:- Repair & Maintenance on various roads under Pragpur Sub-Division (SH: Repair of Pot Holes on Bani to Sehri road in between Km. 2/500 to 4/000)**

JOB NO. **2**  
 Estimate Cost :- Rs. 4,99,958/-  
 Earnest Money :- Rs. 10000/-  
 Time Limit :- Three Months.

**0/300 to 0/360 & Bani to Sehri road in between Km. 2/500 to 4/000)**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement is to five sand and ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	50.24 Cubic metre			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	1319.02 Square meter			Per square meter	
	<b>TOTAL</b>					

Executive Engineer,  
 Kotla Behar Division,  
 HPPWD Kotla Behar.