



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **19/04/2023 up to 11:30 A.M.** and will be opened on the same day at **(12:00 noon)** in the presence of intending contractors. The tender application will be received in this office against cash payment on **17/04/2023 up to 10.00 A.M. to 12:30 P.M.** and tender form can be had from this office on **18/04/2023 from 2.00 P.M. to 5.00 Pm.** The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST, work done certificate, proof of machinery etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	A/R & M/O various road under Joginder Nagar Sub Division HPPWD., Joginder Nagar (Sub Head:- Supplying and stacking of crushed stone aggregate 10mm to 12.5mm size and clean coarse sand at Hot Mix Plant Badoun for patch work).	Rs. 4,85,500/-	Rs. 9,700/-	Rs. 350/-	Class "D"	Three months
2	A/R & M/O various road under Joginder Nagar Sub Division HPPWD., Joginder Nagar (Sub Head:- Supplying and stacking of crushed stone aggregate 10mm to 12.5mm size and clean coarse sand for patch work).	Rs. 4,53,750/-	Rs. 9,100/-	Rs. 350/-	Class "D"	Three months
3	Improvement of black spot on Joginder Nagar Sarkaghat Ghumarwin road Km. 0/0 to 34/300 (Sub Head:- Providing and fixing "W" metal beam crash barriers system at Km. 13/700 to 13/800).	Rs. 3,77,474/-	Rs. 7,500/-	Rs. 350/-	Class "D"	Three months
4	Construction of link road from Kurati Shel Nallah to Joun Km. 0/0 to 2/0 (Sub Head:- P/L soling grade-I in Km. 0/950 to 1/500).	Rs. 4,45,017/-	Rs. 8,900/-	Rs. 350/-	Class "D"	Three months
5	Construction of link road from Kurati Shel Nallah to Joun Km. 0/0 to 2/0 (Sub Head:- P/L wearing grade-II in Km. 0/950 to 1/500).	Rs. 4,51,316/-	Rs. 9,000/-	Rs. 350/-	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest
Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.

6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2021-22-

Dated:-

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. Drawing Branch in this office.
7. Notice Board.
8. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

Schedule of Quantity

Estimated Cost:- 485500.00
 Earnest Money:- 9700.00
 Time:- Three months

Name of work:- A/R & M/O various road under Joginder Nagar sub division HPPWD Joginder Nagar.
 Sub Head:- Supplying and stacking of crushed stone aggregate 10mm to 12.5mm size and clean coarse sand at Hot Mix Plant Badaun for patch work.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
2	Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	180.00			Per cubic metre	
3	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	50.00			Per cubic metre	
				Total:-		


 Executive Engineer,
 B&R Division HP.PWD.,
 Joginder Nagar.

(2)

Schedule of Quantity

Estimated Cost:- 453750.00
Earnest Money:- 9100.00
Time:- Three months

Name of work:- A/R & M/O various road under Joginder Nagar sub division HPPWD Joginder Nagar.
Sub Head:- Supplying and stacking of crushed stone aggregate 10mm to 12.5mm size and clean coarse sand for patch work.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
2	Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	170.00			Per cubic metre	
3	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	45.00			Per cubic metre	
				Total:-		


Executive Engineer,
B&R Division HP.PWD.,
Joginder Nagar.


SCHEDULE OF QUANTITY

Name of Work : Improvement of Balak Spot on Joginder Nagar Sarkaghat Ghumarwin road km 0/00 to 21/500
(SH: Construction of "W" Metal Beam Crash Barrier at km 13/700 to 13/800)

Estimate Cost: 3,77,474.00
Earnest Money: 7,500.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.74	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded/crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.66	Per cubic metre			

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and erecting a "W" Metal Beam Crash Barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam guard rail 70cm (seventy centimetre). Above road/ ground level fixed on ISMC series channel vertical posts 150x75x5mm thick (one hundred fifty X seventy five X five-millimetre) spaced 2.00 (two point zero) metre centre to centre 1.80 metre (one point eight X five-millimetre) high 1.10 metre (one point one zero) below ground/ road level all steel parts and fittings to be galvanised by hot deep process, all fittings to confirm to IS: 1364, metal beam guard rail to be fixed on the vertical posts with a spacer of channel section 150x75x5mm (one hundred fifty X seventy five X five millimetre), 330mm (three hundred thirty millimetre) long complete as per clause 810 within all leads, lifts carriage of material and other incidentals and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	100.00	Per Running Meter			
	Total					



 Executive Engineer
 B & R Division HP.PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

name of Work : Construction of Kurati Sheel Nallah to Village Joun road km 0/00 to 2/00
 Sub Head:- Providing and laying Soling Grade-I at km 0/950 to 1/500)

F. No.	Description of work	No. or Qty.	Unit	Estimate Cost:		Earnest Money:		AMOUNT Rs. P
				Figures	Rate Words	Time Limit :	Three Months	
1	Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to paid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charg. The rate is inclusive all taxes levy by the government time to time excluding GST.	1588.13	Per square metre					
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charg. The rate is inclusive all taxes levy by the government time to time excluding GST.	1588.13	Per square metre					
3	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-1 (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charg. The rate is inclusive all taxes levy by the government time to time excluding GST.	158.81	Per cubic metre					
Total								


(4)


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

name of Work : Construction of Kurati Sheel Nallah to Village Joun road km 0/00 to 2/00
 H: Providing and laying Wearing Grade-II in km 0/950 to 1/500)

Sl. No.	Description of work	No. or Qty.	Unit	Estimate Cost:		Earnest Money:		AMOUNT Rs. P
				Figures	Rate Words	Time Limit :	Three Months	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charg. The rate is inclusive all taxes levy by the government time to time excluding GST.	159.47	Per cubic metre					
Total								


 Executive Engineer
 B & R Division HP.PWD,
 Jodhpur Nagar