



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

eepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2022-23-

To

2773-75

Dated:- 31/03/2023

**The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2**

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

**Executive Engineer,
Chowari Division,
HPPWD, Chowari.**

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,
Chowari Division,
HPPWD, Chowari.**



Tel.01899-299219.
cepwd-chowari@hp.gov.in

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- | | |
|------------------------------------------------------------------------------------|------------|
| 1. Date of receipt of application for the tender
Form a/w requisite documents:- | 10/04/2024 |
| 2. Date of issued/sale of tender form against
Cash payment (non refundable). | 11/04/2024 |

The tender shall be received upto 11.00 AM on 12/04/2024 and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 12/04/2024.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost tender of	Time Limit	Class
1.	Restoration of rain damage on various roads under Sihunta Sub Division (SH:- Hiring of Excavator cum loader for removal of slips under Thulel Section).	482625/-	9653/-	Rs. 350/-	Three Month	Class-D & C
2.	Restoration of rain damage on various roads under Chowari Sub Division (SH:- Hiring of Excavator cum loader for removal of slips under Raipur Section).	492375/-	9848/-	Rs. 350/-	Three Month	Class-D & C
3.	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba road Km 0/0 to 52/00 (SH:- Hiring of excavator cum loader for removal of slips in Km 0/0 to 52/00).	497250/-	9945/-	Rs. 350/-	Three Month	Class-D & C
4.	Restoration of rain damage on Binna Godhra Siyun road Km 0/0 to 7/00 (SH:- Hiring of excavator cum loader for removal of slips in Km 0/0 to 7/00).	487500/-	9750/-	RS. 350/-	Three Month	Class-D & C
5.	Restoration of rain damage on Patka to Dalhousie road Km 32/00 to 45/00 (SH:- Hiring of excavator cum loader for removal of slips in Km 32/500 to 45/00).	497250/-	9945/-	Rs. 350/-	Three Month	Class-D & C
6.	Restoration of rain damage on Nurpur Sanjha Nallah Lahlru Tunnuhatti road Km 15/390 to 25/00 (SH:- Hiring or excavator cum loader for removal of slips in 16/500 to 25/00).	456300/-	9126/-	Rs. 350/-	Three Month	Class-D & C

7.	Restoration of rain damage (R& RD) on Various roads under HPPWD Sub Division Kakira (SH:- Hiring and disposal of slips by deploying excavator cum loader & Tipper on various roads under Dundhiyara Section & Mail Section).	454125/-	9083/-	Rs. 350/-	Three Month	Class-D & C
8.	A/R & M/O Shahpur Sihunta Chowari road (SH:- Preparation of DPR of Shahpur Sihunta Chowari road MDR-87 under CRF Km 24/00 to 42/500).	499500/-	9900/-	Rs. 350/-	Three Month	Class-D & C
9.	A/R & M/O various roads under Chowari Division HPPWD, Chowari (SH:- preparation of DPR of (i) Balance work including Metalling and Tarring of Nagali to Sanjap Samleau road Km 0/0 to 9/740 (SH:- preparation of DPR). (ii) /R & M/O Shahpur Sihunta Chowari road (SH:- Preparation of DPR of Shahpur Sihunta Chowari road MDR-87 under CRF Km 42/500 to 47/430 = 5.030 Km)	398790/-	7976/-	Rs. 350/-	Three Month	Class-D & C
10	A/R & M/O Balance work including Metalling and tarring of Ghatsani Pul (Lahru to Bhalog and Motla to Sukhiyar road Km 0/0 to 15/820 (SH:- Preparation of DPR).	427140/-	8543/-	Rs. 350/-	Three Month	Class-D & C
11	Restoration of rain damage on Pukhru via Padwal Km 0/0 to 6/400(SH:- Providing crate work at Rd 3/465 to 3/485).	490870/-	9817/-	Rs. 350/-	Three Month	Class-D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

No. PWD-CHW/Tender /2022-23- 2776-2826

Dated:- 31/3/23

Copy forwarded to the following for information and necessary action please:-


Copy forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HPPWD, Shimla.
2. All the Chief Engineer in HPPWD.
3. All SEs/EE in HPPWD.
4. All AEs/Contractor under this Division.
5. Deputy Commissioner, Chamba
6. The BDO Bhattiyat.
7. Sub Divisional Magistrate/B.D.O/Tehsildar Chowari.
8. Notice Board of this office.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Certificate

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2022-23-2773-75 dated..31/3/23 Is emergent nature and in Public interest.



Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Schedule of Quantity

Estimate Cost :- Rs.	492375
Earnest Money	9,848
Time Limit	Six Month

Name of work:- Restoration of Rain Damage on Various Road Under Chowari Sub Division (SH :- Hiring of Excavator cum Loader for Removal of Slip under Raipur Section

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface up to any leads and lifts up to any heights and depths as per direction and entire satisfaction of Engineer-in-charge . Any loss to the Public/Private property or any accident etc. happened during the course hiring period /execution shall be absolute responsibility of the JCB Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner . The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	505.00			per hours	
Total:-						



Executive Engineer
 Chowari Division
 Hppw Chowari

Schedule of Quantity

Estimate Cost :- Rs.	497250
Earnest Money	9,945
Time Limit	Six Month

Name of work:- Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road Km. 0/00 to 52/00 (SH :- Hiring of Excavator cum Loader for Removal of Slips in Km. 0/00 to 52/00

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Hiring of JCB/Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface up to any leads and lifts up to any heights and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the Public/Private property or any accident etc. happened during the course hiring period /execution shall be absolute responsibility of the JCB Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in - charge.	510.00			per hours	
Total :-						


Executive Engineer
 Chowari Division
 HPPWD, Ahowari

Schedule of Quantity

Estimate Cost :- Rs.	487500
Earnest Money	9,750
Time Limit	Six Month

Name of work:- Restoration of Rain Damage on Binna Godhra Siyun Road Km. 0/00 to 7/00 (SH :- Hiring of Excavator cum Loader for Removal of Slips in Km. 0/00 to 7/00

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface up to any leads and lifts up to any heights and depths as per direction and entire satisfaction of Engineer-in-charge . Any loss to the Public/Private property or any accident etc. happened during the course hiring period /execution shall be absolute responsibility of the JCB Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner .The daily log book will be maintained at site which should be duly verified by the Engineer-in - charge.	500.00			per hours	
Total :-						


Executive Engineer
 Chowari Division
 Hppw Chowari

Schedule of Quantity

Estimate Cost :- Rs.	497250
Earnest Money	9,945
Time Limit	Six Month

Name of work:- Restoration of Rain Damage on Patka to dalhousie Road Km. 32/00 to 45/00 (SH :- Hiring of Excavator cum Loader for

Removal of Slips in Km. 32/500 to 45/00

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface up to any leads and lifts up to any heights and depths as per direction and entire satisfaction of Engineer-in-charge . Any loss to the Public/Private property or any accident etc. happened during the course hiring period /execution shall be absolute responsibility of the JCB Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner .The daily log book will be maintained at site which should be duly verified by the Engineer-in - charge.	510.00			per hours	
Total :-						



Executive Engineer
 Chowari Division
 Hppmrd Chowari

Schedule of Quantity

Estimate Cost :- Rs.	456300
Earnest Money	9,126
Time Limit	Six Month

Name of work:- Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 15/390 to 25/00 (SH :- Hiring of Excavator cum Loader for Removal of Slips in Km. 16/500 to 25/00

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface up to any leads and lifts up to any heights and depths as per direction and entire satisfaction of Engineer-in-charge . Any loss to the Public/Private property or any accident etc. happened during the course hiring period /execution shall be absolute responsibility of the JCB Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner .The daily log book will be maintained at site which should be duly verified by the Engineer-in - charge.	468.00			per hours	
Total :-						


Executive Engineer
 Chowari Division
 Hppwq Chowari

Schedule of Quantity

Estimate Cost :- Rs.	454125
Earnest Money	9,083
Time Limit	Six Month

Name of work:- Restoration of Rain Damage on (R&RD) on Various Roads Under HPPWD Sub Division Kakira (SH :- Removal & Disposal of Slips by Deploying Excavator Cum Loader & Tipper on Various Roads Under Dhundiyara Section & Mail section

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface up to any leads and lifts up to any heights and depths as per direction and entire satisfaction of Engineer-in-charge . Any loss to the Public/Private property or any accident etc. happened during the course hiring period /execution shall be absolute responsibility of the JCB Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner .The daily log book will be maintained at site which should be duly verified by the Engineer-in – charge.	400.00			per hours	
2	Hiring of tipper having capacity 5.50 (Five decimal five Zero) cubic meter for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in Charge . Any loss to the Public/Private property or any accident etc. happened during the course hiring period shall be absolute responsibility of the trucker Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for truck will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner .The daily log book will be maintained at site which should be duly verified by the Engineer-in – charge.	125.00			per hours	
Total :-						


Executive Engineer
 Chowari Division
 HPPWD Chowari

Schedule of Quantity

Estimate Cost :- Rs.	482625
Earnest Money	9,553
Time Limit	Six Month

Name of work:- Restoration of Rain Damage on Various Road Under Situmta Sub Division (SH :- Hiring of Excavator cum Loader for

Removal of Slips Under Thulel Section

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Hiring of JCB/Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface up to any leads and lifts up to any heights and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the Public/Private property or any accident etc. happened during the course hiring period /execution shall be absolute responsibility of the JCB Owner which shall have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the Owner. The repair and spare, watch & ward of machine also be borne by the Contractor/Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in - charge.	495.00			per hours	
Total :-						


Executive Engineer
 Chowari Division
 Hippiya Chowari

Schedule of Quantity

Name of work:- A/R & M/O Shahpur Sihunta Chowari Road (SH :- Preparation of DPR of Shahpur Sihunta Chowari Road MDR-87 under CRF Km. 24/00 to 42/500	Estimated Cost:-	499500.00
	Earnest Money:-	9990.00
	Time:-	Three month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Detailed project report of Up Gradation of Shahpur Sihunta Chowari via Jot Chamba Bharmour Road (Portion Sihunta to Lahru) km 24/00 to 47/430 in Dist. Chamba Himachal Pradesh (Under CRF) Including ellocation of relevent field data, preparation of draft copy and after approval from the competent authourity, the same shall be faired out and be supplied in four sets duly printed on A4 size paper in spiral binding form and as per the direction of Engineer in charge	18.500			Per Km.	
					Total	


Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

<div>Schedule of Quantity</div>		Estimated Cost:-		398790.00
		Earnest Money:-		7976.00
		Time:-		Three month
Name of work:- A/R & M/O Various Roads under Chowari Division HPPWD Chowari (SH :- Preparation of DPR of (i) Balance work including Metalling & Tarring of Nagali to Sanjap Samleau road Km. 0/00 to 9/740 (SH :- Preparation of DPR) . (ii) A/R & M/O Shahpur Sihunta Chowari road (SH :- Preparation of Dpr of Shahpur Sihunta Chowari road MDR-87 under CRF Km. 42/500 to 47/40 = 5.030 Km)				
Sr. No.	Description of item	Qty.	<div>Rate</div> <div>In FigureIn Words</div>	<div>Unit</div> <div>Amount</div>
1	Detailed project report of Up Gradation of Shahpur Sihunta Chowari via Jol Chamba Bharmour Road (Portion Sihunta to Lahru) km 24/00 to 47/430 in Distt. Chamba Himachal Pradesh (Under CRF) Including clllection of relevent field data, preparation of draft copy and after approval from the competent authority, the same shall be faired out and be supplied in four sets duly printed on A4 size paper in spiral binding form and as per the direction of Engineer in charge	14.770		Per Km.
				Total

Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

Name of work:- A/R & M/O Balance work including Metalling and Tarring of Ghatasani Pul (Lahru to Bhalog and Motla to Sukhyar Road Km. 0/00 to 15/820 (SH :- Preparation of DPR)

Estimated Cost:-	427140.00
Earnest Money:-	8543.00
Time:-	Three month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Detailed project report of Up Gradation of Shapur Sihunta Chowari via Jot Chamba Bharnour Road (Portion Sihunta to Lahru) km 24/00 to 47/430 in Dist. Chamba Himachal Pradesh (Under CRF) Including ellocation of relevent field data, preparation of draft copy and after approval from the competent authourity, the same shall be faired out and be supplied in four sets duly printed on A4 size paper in spiral binding form and as per the direction of Engineer in charge	15.820			Per Km.	
					Total	

Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

Name of Work :- Restoration of Rain Damages on Dramanala Dhulara Rajain Road Km. 0/00 to 9/00 (SH :- C/O R/Wall at Rd 46/825 to 46/837)						Estimate Cost :- Rs.		372830
						Earnest Money		7.457
						Time Limit		Three Month
S.No.		Description	Quantity	Rate		Unit	Amount	
				in Fig.	in Word			
1		Earthwork in excavation for structure as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other detritious materials and disposal upto any lead and lifts dressing of sides and bottom and back filling in trenches with excavated suitable material in all type of soil within all leads and lifts upto any depths as per directions of Engineer-in-Charge including cartage of materials and other incidentals.	51.97					
2		Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS-283 and IS-4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.	178.60					
Total :-								


 Executive Engineer
 Chowari Division
 HPPWD Chowari