

Himachal Pradesh
Public Works Department
NO.PW.TH.D/CB-TENDER/2022- 638-49
To

Dated:- 25-4-2023


The Executive Engineer, (I.T. Cell),
O/O Engineer-in-Chief,
H.P.P.W.D., Nirman Bhawan,
Shimla-2

Subject:- Publication of Tender Notice
Sir,

I am enclosing herewith Notice Inviting Tenders for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW(B)A(3)1/2020 dated 16th July,2021.

As the works mentioned in the tender notice are urgent in nature and in public interest.

Encl:- As above


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- 1 The Deputy Commissioner, Shimla Distt. Shimla, HP
- 2 The Superintending Engineer, 4th Circle, H.P.P.W.D., Shimla-3 . He is requested to grant permission for awarding of tender without publication in pursuance of Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter NO. PBW(B)A(3)1/2020 dated 7th January 2021.
- 3 The Sub-Divisional Officer(C) Theog
- 4 The Municipal Council Theog
- 5 Block Development Officer, Theog Block
- 6 All the Assistant Engineers working under this division
- 7 Superintendent Gr-II (Estt.) in this division
- 8 Drawing branch in this office.
- 9 Notice Board .


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **03/05/2023 up to 11:00 PM.** and the same shall be opened on the same day at 11:30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **02/05/2023 up to 4:00 P.M.** and the application for issue of tender form shall be received on **01/05/2023 up to 4:00 P.M.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 60 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.


Sr. No	Name of work	Estimated cost(Rs.)	Earnest money (Rs.)	Cost of form (Rs)	Time allowed for completion
1	2	4	5	6	7
1	Special repair to Govt. Degree College at Theog (SH:- Painting and distempering etc.) outside of building	4,99,950	10,000	350	one Month
2	Special repair to Govt. Degree College at Theog (SH:-Painting and distempering etc. Basement canteen and first floor)	4,99,989	10,000	350	one Month
3	Special repair to Govt. Degree College at Theog (SH:- Painting & distempering etc.) 1 st floor and Admin.blcok)	4,99,989	10,000	350	one Month
4	Special repair to Govt. Degree College at Theog (SH:-Painting and distempering etc. 2 nd floor and ground floor Admn. Blcok)	4,99,989	10,000	350	One month
5	Restoration of rain damages on Bhakhality Majhar road km. 0/0 to 6/500 ((SH:- C/O PCC R/wall at RD 5/660 to 5/675)	4,97,571	10,000	350	One month
6	A/R & M/O PWD office building at Theog (SH:- P/F paneling work and flooring in Divisional Accounts officer office)	2,28,694	4,600	350	One month
7	R/R damages on Nanoo Kuthar Basadhar Giankot road km. 0/0 to 36/0 (SH:- C/O wire crate R/wall at RD 0/550 to 0/565)	2,83,134	5,700	350	One month
8	R/R damages on Nanoo Kuthar Basadhar Giankot road km. 0/0 to 36/0 (SH:- C/O PCC R/wall at RD 4/600 to 4/618)	4,48,440	9,000	350	One month
9	C/O P.H.C. building at Ghorna (Balson) Tehsil Theog Distt. Shimla H.P. (SH:-P/L C.C Bed edging i/c steel work etc.)	2,57,498	5,200	350	One month
10	C/O PHC bldg. at Ghorna (Balson) Tehsil Theog Distt. Shimla, HP (SH:-P/L inter locking paver block)	4,86,432	9,750	350	One month

11	C/O Kiari to Talin road km. 0/0 to 3/0 (SH:- C/O R/wall at Rd 1/310 to 1/318.50)	4,92,209	9,850	350	One month
12	C/O Kiari to Talin road km. 0/0 to 2/0 (SH:- C/O R/wall in PCC at RD 1/075 to 1/095)	3,17,903	6,400	350	One month

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. Following documents should accompany the application for tenders: -

- (1) The contractors are required to be produce a copy of their PAN No. Sale tax No. with sales tax clearance Certificate and should produce a copy of enlistment /renewal letter.
- (2) Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- (3) The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act 1952 (EPF number) within a month from award of work/contract. Failure to observe this condition shall render the tender of contractor liable to summary rejection.
- (4) The bidder are advised to quote rates inclusive of G.S.T. as applicable notified vide Additional Chief Secretary (PW) to the Govt. of H.P. letter No. PBW(B)C(17)2/2012 dated 07/08/2018 ,G.S.T. shall not be paid extra.
- (5) The contractor will give affidavit duly attested from the competent authority that he has not more than two works in hand for execution failing which the application shall be rejected.
- (6) The provision of notification issued vide Addl. Chief Secretary (PW) to the govt. of H.P. Notification No.PBW(B)A(3)1/2020 dated 13th April 2021 shall also be applicable.

On Behalf of Governor of Himachal Pradesh


Executive Engineer,
Theog Division, B&R,
H.P. W.D., Theog

"Exigency Certificate"

It is certified that the tenders for various works as called
for vide this office letter No. PW.THD/CB-tender/2022-.....638-49.....
dated 25/4/2023.....are of emergent nature in exigency of public interest.

Dated: _____ April, 2023

Place: Theog

[Signature]
Executive Engineer,
Theog Division B&R,
H.P.P.W.D., Theog
[Signature]

SCHEDULE OF QUANTITY

Estimated Cost Rs.499950

Earnest Money:-10000/

Time: Three months

Name of Work : - S/R to Govt. Degree College at Theog (SH:-Painting and Distempering etc.) out side of building.

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Finishing walls with water proofing cement paint /apexultima of required shade (Two or more coats applied @ 3.84 kg/10 sqm) including strutting all lead and lift as per direction of the Engineer-in-Charge	2777.50	180.00	Rupees One Hundred Eighty Only	Per square meter	499950


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.499989/

Earnest Money:-10000/

Time: One months

Name of Work : S/R to Govt. Degree College at Theog (SH:- Painting and Distempering etc.)Basement Canteen and 1st floor.

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade (two or more coats) over and including water thinnable priming coat with cement primer including all lead and lift as	1990.00	100.00	Rupees One Hundred Only	Per square meter	199000
2	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coats including all lead and lift as per	132.89	95.00	Rupees Ninety Five Only	Per square meter	12625
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including all	392.21	95.00	Rupees Ninety Five Only	Per square meter	37260
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including all lead and lift as per direction of the Engineer -in -Charge	259.50	105.00	Rupees One Hundred Five Only	Per square meter	27248
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, including all lead and lift as per direction of the Engineer -in -Charge	400.00	350.00	Rupees Three Hundred Fifty Only	Per square meter	140000
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including all lead and lift as per direction of the Engineer -in -Charge	645.05	130.00	Rupees One Hundred Thirty Only	Per square meter	83857
						499989

Not
Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.499989/

Earnest Money:-10000/

Time: One months

Name of Work : S/R to Govt. Degree College at Theog (SH:- Painting and Distempering etc.) 1st floor and Admin block Basement

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade (two or more coats) over and including water thinnable priming coat with cement primer including all lead and lift as per direction of the Engineer -in -Charge	1990.00	100.00	Rupees One Hundred Only	Per square meter	199000
2	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coats including all lead and lift as per direction of the Engineer -in -Charge	132.89	95.00	Rupees Ninety Five Only	Per square meter	12625
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including all lead and lift as per direction of the Engineer -in -Charge	392.21	95.00	Rupees Ninety Five Only	Per square meter	37260
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including all lead and lift as per direction of the Engineer -in -Charge	259.50	105.00	Rupees One Hundred Five Only	Per square meter	27248
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, including all lead and lift as per direction of the Engineer -in -Charge	400.00	350.00	Rupees Three Hundred Fifty Only	Per square meter	140000
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including all lead and lift as per direction of the Engineer -in -Charge	645.05	130.00	Rupees One Hundred Thirty Only	Per square meter	83857
						499989

A. N. S.
Executive Engineer
Theog Division,
H.P.P.W.D. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.499989/

Earnest Money:-10000/

Time: One months

Name of Work : S/R to Govt. Degree College at Theog (SH):- Painting and Distemping etc.) 2nd floor and Ground floor Admin block.

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade (two or more coats) over and including water thinnable priming coat with cement primer including all lead and lift as per direction of the Engineer-in -Charge	1990.00	100.00	Rupees One Hundred Only	Per square meter	199000
2	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coats including all lead and lift as per direction of the Engineer-in -Charge	132.89	95.00	Rupees Ninety Five Only	Per square meter	12625
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including all lead and lift as per direction of the Engineer-in -Charge	392.21	95.00	Rupees Ninety Five Only	Per square meter	37260
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including all lead and lift as per direction of the Engineer-in -Charge	259.50	105.00	Rupees One Hundred Five Only	Per square meter	27248
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, including all lead and lift as per direction of the Engineer-in -Charge	400.00	350.00	Rupees Three Hundred Fifty Only	Per square meter	140000
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including all lead and lift as per direction of the Engineer-in -Charge	645.05	130.00	Rupees One Hundred Thirty Only	Per square meter	83857
						499989


EXECUTIVE ENGINEER
 Theog Division H P P W D
 Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.497571/
 Earnest Money:- 10000/
 Time: One months
 Name of Work : R/R damages on Bheekity to Majhar road km 0/0 to 6/400 (SH:- C/O PCC R/wall at km 5/660 to 5/675.)

Sr. No.	Description of item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	74.25	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	15897
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm	95.00	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only	Per cubic meter	396948
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	81.20	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	19663
4	Stone filling behind retaining wall. Complete as per Drawing and technical specification Clause 1204.2.8.all leads and lifts as per direction of the Engineer -in -Charge.	18.00	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	22656
5	Providing mild/Tor Steel reinforcement the RCC work in including , bending binding and fixing in position .Tor Steel	471.20	90.00	Rupees Ninety Only	Per cubic meter	42408
						497571

A.M.D.
 Executive Engineer,
 Theog Division,
 HP.PWD. Thog

SCHEDULE OF QUANTITY

Estimated Cost Rs.228694/
 Earnest Money:-4600/
 Time: One months
 Name of Work : A/R and M/O to PWD Office Building at Theog (SH:- P/F Panelling work and Flooring in DAO. Office.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Providing 60x60x60mm wooden plugs including cutting bricks/stone work and fixing in cement mortar 1:3 (1 cement : 3 sand) and making good the walls etc.including all leads and lifts as per direction of the Engineer-in-Charge. 2nd class deodar wood.	64.00	23.56	Rupees Twenty Three and Paise Fifty Six Only	each	1508
2	Providing and fixing wooden ground 50x25 mm including priming coat complete including all leads and lifts as per direction of the Engineer-in-Charge. 2nd class deodar wood.	0.084	115000.00	Rupees One Lakh Fifteen Thousand Only	per cubic meter	9660
3	Providing and fixing plain lining with tongued and groved jointing and screws (frame work and cover fillets to be measured and paid for separately with including all leads and lifts as per direction of the Engineer-in-Charge. 2nd class deodar wood 12 mm thick.	46.470	901.00	Rupees Nine Hundred One Only	Per square meter	41869
4	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete including all leads and lifts as per direction of the Engineer-in-Charge.	4.230	1669.00	Rupees One Thousand Six Hundred Sixty Nine Only	Per square meter	7060
5	Providing and fixing 25mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete including all leads and lifts as per direction of the Engineer-in-Charge.	2.930	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per square meter	6593
6	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete including all leads and lifts as per direction of the Engineer-in-Charge.	12.890	950.00	Rupees Nine Hundred Fifty Only	Per square meter	12246

SCHEDULE OF QUANTITY

Estimated Cost Rs.283134

Earnest Money: 5700/

Time: one months

Name of work:- R/R of rain Damages on Nanoo Kuthar BasaDhar Roads km 0/0 to 36/0 (SH:-P/F W-Beam Crash Barrier in Km 0/550 to 0/565)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	29.29	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	6271
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 130 including all leads and lifts as per direction of the Engineer-in-Charge.	87.90	2950.00	Rupees Thousand Hundred Fifty Only	Per cubic meter	259305
3	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	13.95	1258.65	Rupees Thousand Hundred Fifty Sixty Five Only	Per cubic metre	17558
						283134


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.448440
Earnest Money:-9000/
Time: One month

Name of Work : - R/R of rain damages on Nanoo Kuthar BasaDhar GianKot BasaDhar Gain Kot road KM0/0 to 36/0 (SH:- C/O PCC R/wall at RD4/600 to 4/618.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	48.24	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	10328
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm	96.30	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only	Per cubic meter	402380
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	54.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Per running meter	13076
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	18.00	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic metre	22656
						448440


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.257498

Earnest Money:-5150/

Time: One month

Name of Work : C/O PHC Building at Ghorna (Balson) Tehsil Theog Theog Distt. Shimla HP (SH:- P/L CC Bed edging i/c steel work etc.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 nominal mix (1:4:8) 25 mm (Twenty five milli metre)including all leads and lifts as per direction of the Engineer-in-Charge	50.15	4492.00	Rupees Four Thousand Four Hundred Ninety Two Only	Per cubic meter	225274
2	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint In gratings framed guard bars, ladders, railing, brackets and similar works. i/c all leads and lifts as per direction of the Engineer-in-Charge.	339.20	95.00	Rupees Ninety Five Only	Per Kilo gram	32224
						257498


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 257498/-
 Earnest Money: 5450/-
 Time: one Month

Name of Work : - C/O PHC Building at Ghorna (Balson) Tehsil Theog Distt. Shimla HP (SH:- P/L nter locking paver blocksa PHC coat yard).)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M- 50 grade i/c border or kurb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete (Sub base concrete floor to be paid for including all leads and lifts as per direction of the Engineer-in-Charge. 60mm thick inter locking blocks	432.00	1126.00	Rupees Thousand Hundred Twenty Only	each	486432
						486432


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs:-
Earnest Money:-
Time: One month

492209
9844

Name of Work : - C/O Kiari to Talin road Km 0/0 to 3/0 (SH:- C/O R/wall at RD 1/310 to /318.50)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	39.02	179.70	Rupees One Hundred Seventy Nine and Paise Seventy Only	Per cubic meter	7012
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	27.88	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	5969
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:6:12)	15.30	3503.65	Rupees Three Thousand Five Hundred Three and Paise Sixty Five Only	Per cubic meter	53606
4	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm	1.70	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only	Per cubic meter	7103
5	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts as per direction of the Engineer-in-Charge.)	100.65	3365.50	Rupees Three Thousand Three Hundred Sixty Five and Paise Fifty Only	Per cubic meter	338738
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including all leads and lifts as per direction of the Engineer-in-Charge.	24.34	2328.25	Rupees Two Thousand Three Hundred Twenty Eight and Paise Twenty Five Only	Per cubic meter	56670
7	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer in -Charge.	18.36	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic metre	23109
						492209


N. M. T.
EXECUTIVE ENGINEER
Theog Division H P P W D
Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs:- 317904
 Earnest Money:- 6400
 Time: One month

Name of Work : - C/O Kiari to Talin road Km 0/0 to 3/0 (SH:- C/O PCC R/wall at RD 1/075 to 1/095)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	26.00	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per cubic meter	3868
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	46.80	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	10020
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm	71.60	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only	Per cubic meter	299173
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	20.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	4843
						317904


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog