

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2023-24

2090

Dated:- 16.05.2023


To,

✓ The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:- Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 23.05.2023 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above


Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat

**Himachal Pradesh
Public Works Department
"Notice Inviting Tender"**

Sealed item rate tender are hereby invited in form No. 6&7 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP, on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968.The important dates of tender are as under:-

The last date and time of receipt of application for tender form 23.05.2023 up to 4.00 P.M.

The last date for sale of tender is up to 24.05.2023 at 4.00PM.

The tender shall be received up to 11:00 AM on 25.05.2023 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 25.05.2023. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.

Sr. No.	Name of work	Estimated cost.	Earnest Money.	Cost of form.	Time allowed.
1.	A/R & M/O on Various Roads under Sarkaghat Sub- Division HPPWD Sarkaghat (SH:- Supplying and Staking of dual directional Delineators) Job No- I	99840	2000	350	Two Months
2.	A/R & M/O on Various Roads under Sarkaghat Sub- Division HPPWD Sarkaghat (SH:- Supplying and Staking of dual directional Delineators) Job No- II	99840	2000	350	Two Months
3.	Restoration of Rain Damages on Link Road Harijan Basti Rihda Chatter Km. 0/0 to 8/500 (SH:- Providing and laying CC Pavement at RD 0/150 to 0/265)	461890	10000	350	One Month
4.	Construction of Link Road Tikkari to Mandoli Khudla via Gehra Km. 0/0 to 2/500 (SH:- Providing & Laying WBM-III (Correction layer) for providing & laying metalling and tarring work in Km. 0/300 to 0/675 & 0/700 to 1/100)	111300	2250	350	One Month
5.	Construction of Nabahi Bastala Matehri Batahri Gopalpur Road (SH:- Hiring of Excavator cum loader)	129600	2600	350	Two Months
6.	Construction of various Road Under sarkaghat Sub- Division HP PWD Sarkaghat (SH:- Supplying of RCC Spun pipe inclusive collars)	497850	10000	350	One Month

TERMS AND CONDITONS:-

Following documents should accompany with the application for tenders.


1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.
4. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
5. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.

6. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)

7. The tender shall be awarded to the lowest bidder without any negotiation if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.

8. The earnest money shall be deposited duly pledged in favour of Executive Engineer B& R Division HPPWD Sarkaghat & Cost of tender form for the above works should be submitted with the application for the purchase of the tender forms.

9. All the required documents should be submitted with the application others wise single application may be rejected.



Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat

Dated: 16-05-2023

No. PW-SKT-CB-Tender/2023-24

2080-89

1. The Engineer - in- Chief HPPWD Nirman Bhawan Shimla for information please.
2. The Chief Engineer Hamirpur Zone HP.PWD . Hamirpur for information please.
3. The Superintending Engineer Dharampur Circle, HP.PWD. Dharampur for information please.
4. Block Development officer Sarkaghat for information please.
5. Copy to the Assistant Engineer B&R Sub- Division HP.PWD Sarkaghat/ Baldwara /Bhaderwar for information.
6. Copy to Drawing Branch of this office for information.
7. Notice Board.


Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O on various roads under Sarkaghat Sub-Division, HPPWD Sarkaghat. (SH:- Supplying and Stacking of dual directional Delineators). Job No.- I

Estimated cost :- Rs. 99840.00
Earnest Money:- Rs. 2,000.00
Time Limit:- Two months

Sr. No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Supplying and Stacking dual directional Delineator made of dia 18 (eighteen) guage MS rectangular pipe of size 25x63 mm (twenty five into sixty three millimetre) and of length 600mm (six hundred millimeter) pipe stove enameled and baked to 120 powder coated head made of ABS plastic rectangular molded with flat face provided with high intensity prismatic reflectors of colour (yellow) of size 100x125 (one hundred into one hundred twenty five millimetre) with additional to reflective strips of 20mm (twenty millimetre) wide make greens / lite including carriage with in all leads and lifts as per the direction of Engineer-in-charge.	256.00	390.00	Rupees three hundred ninety and paise nil only	Each	99840.00
Total:-						99840.00

DRAFT NO 67 for the year 2023-24
approved for Rs 99840/- only

Executive Engineer
B&R Division HPPWD
Sarkaghat

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O on various roads under Sarkaghat Sub-Division, HPPWD Sarkaghat. (SH:- Supplying and Stacking of dual directional Delineators). Job No. II

Sr. No	Description of item/Sub Head	Quantity	Estimated cost :-		Earnest Money:-	
			In	In words	Rs. 2,000.00	Two months
1	Supplying and Stacking dual directional Delineator made of dia 18 (eighteen) guage MS rectangular pipe of size 25x63 mm (twenty five into sixty three millimetre) and of length 600mm (six hundred millimeter) pipe stove enameled and baked to 120 powder coated head : made of ABS plastic rectangular molded with flat face provided with high intensity prismatic reflectors of colour (yellow) of size 100x125 (one hundred into one hundred twenty five millimetre) with additional to reflective strips of 20mm (twenty millimetre) wide make greens / life including carriage with in all leads and lifts as per the direction of Engineer-in-charge.	256.00	390.00	Ruppes three hundred ninety and paise nil only	Each	99840
					Total:-	99840

DNI T NO 68 for the year 2023-24
approved for Rs 99840 only

Executive Engineer
B&R Division HPPWD
Sarkaghat

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.


327
3/2/22
2022

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of link Road Harijan Basti Rinda Chatter km 6/6 to 8/500 (SH:-Providing and Laying CC Pavement at RD 0/153 to 0/265).

Name of Work:- Restoration of link Road Harijan Basti Rihda Chatter km 0/6 to 3/500 (SH:-Providing and Laying CC Pavement at RD 0/150 to 0/265).					Estimated cost :-	Rs. 4,61,890.00
					Earnest Money:-	Rs. 10,000.00
					Time Limit:-	One month
Description of item/Sub Head	Quantity	Rates		Unit	Amount	
		In Figure	In words			
1 Stone soling properly hand packed filling interstices with khraja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP,PWD specification. 100mm (one hundred millimetre) spread thickness (finished work including materials and labour) including carriage of materials within all leads and lifts and other incidentals.	54.34	1900.00	Rupees one thousand nine hundred and paise nil only	Per cubic metre	103246.00	
2 Providing and laying Cement concrete 1:2:4 (one Cement :two coarse sand: four graded crushed stone aggregate) 20 mm (twenty millimetre) nominal size, in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete as per drawing and HP,PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	54.34	6600.00	Rupees six thousand six hundred and paise nil only	Per cubic metre	358644.00	
				Total:-	461890.00	

Draft No 385 for the year 2022-23
approved for Rs 4,61,890/- only


Executive Engineer
B&R Division HP PWD
Sarkaghat

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of Link Road Tikkari to Mandoli Khudla via Gehra km 0/600 to 2/500 (Sht: Providing & laying WBM-III (Correction Layer) for providing & laying metalling and tarring work in km 0/300 to 0/675 & 0/700 to 1/100)

Estimated Cost: 98700.00

Earnest Money: 2000.00

Time Limit: One Month

S. No.	Description of item/ Sub Head	Quantity	Unit	Rates		Amount
				In Figure	In Words	
1	2	3	6	4	5	7
1	Providing & laying at site of work grades/ broken crushed stone aggregate of approved free from disintegrated pieces deleterious and organic matter supply is to be made from any stone crusher approved by the Engineer in Charge and carriage of materials within all leads and lifts and proper stacking in all respect as per the direction of Engineer in Charge. WBM -III 53.2mm to 22.4mm nominal size	42.00	Per Cum	2350.00 2650/-	Rupees Two Thousand Three Hundred Fifty & Paise nil only	98700.00 111300
			TOTAL			98700.00

DNR No 107 for the year 2023-24
approved for Rs 111300/- only

~~Executive Engineer~~
B&R Division HPPWD
Sarkaghat

~~Assistant Engineer~~
B&R Sub-Division
HPPWD Baldwara

Executive Engineer
B&R Division
HPPWD Sarkaghat

DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O Nabahi Bastla Matehri Batahri Gopalpur road (SH:- Hiring of Excavator cum *Loader*)

Estimated Cost Rs.129600.00
Earnest Money Rs.2600.00

Time Limit:- Two Months

Sr.No.	Description of item	Quantity	In Fig.	Rates	In words	Unit	Amount
1.	Hiring of Excavator cum loader for cutting work, filling and disposal etc. with a minimum quantity not less than 30 cubic metre per hour including pay of operators , P.O.L. charges , maintenance or any minor or major accidents , and other damages to private and govt. property is the whole responsibility of the contractor . The work shall be executed as per the PWD specification and the direction of Engineer –in-charge.	96.00	1350.00	(Rupees One Thousand Three Hundred Fifty)only	Per Hour		129600.00
Total:-							129600.00

DRAFT NO 7 for the year 2023-24
approved for Rs 1,29,600/- only

Executive Engineer
B&R Division HP PWD
Sarkaghat

Assistant Engineer,
B&R Sub-Division,
HP. PWD, Sarkaghat.

DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O various road under Sarkaghat Sub-Division, HP PWD, Sarkaghat (SH:- Supplying of RCC Spun pipe inclusive collars)		Estimated Cost	Rs. 497850.00			
		Earnest Money	Rs.10000.00			
		Time Limit:-	One month			
Sr.No.	Description of item	Quantity	Rates	Unit	Amount	
		In Fig.	In words			
1.	Supplying of RCC Spun pipe NP2 450 mm dia inclusive collars complete as per specification (ISI mark) including carriage within all leads & lifts	65.00	2390.00	(Rupees Two Thousand Three Hundred Ninety)only	Per Rmt	155350.00
2.	Supplying of RCC Spun pipe NP2 600mm dia inclusive collars complete as per specification (ISI mark) including carriage within all leads & lifts	65.00	3250.00	(Rupees Three Thousand Two Hundred Fifty)only	Per Rmt.	211250.00
3.	Supplying of RCC Spun pipe NP2 900mm dia inclusive collars complete as per specification (ISI mark) including carriage within all leads & lifts	35.00	3750.00	(Rupees Three Thousand Seven Hundred Fifty)only	Per Rmt.	131250.00
				Total:-	497850.00	

DRAFT No 86 dated 10.02.2023-24
approved for Rs 4,97,850/-

Executive Engineer
B & R Division
HP PWD Sarkaghat

Assistant Engineer,
B&R Sub-Division,
HP.PWD, Sarkaghat.