



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Telephone No:-01782-240075
e-mail:-ee-kum-hp@nic.in

No. PW-KMS-AB-NIT/2023-24- 1272-74

Dated: -11/05/2023

To


✓ The Executive Engineer (IT Cell),
HP, PWD, Shimla-2

Subject: -

Publication of Tender Notice

Enclosed please find herewith the tender of works as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)1/2020 dated 16.07.2021 as the works mentioned in the tender notice are urgent in nature and public interest.

Encl: - Notice Inviting tender &
Schedule of Quantity and certificate.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain


Copy to the Superintending Engineer, 11th Circle,
HP.PWD., Rampur Bsr. for information please.

Copy to Drawing Branch in this office.

✓
Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO. PW-KMS-AB-NIT/ 2023-24-
122d-71 DATED 11-05-2023 ARE URGENT NATURE AND
PUBLIC INTEREST.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed item/percentage rate tenders are hereby invited by the Executive Engineer, Kumarsain Division, and HP.PWD. Kumarsain from the experienced contractors enlisted with PWD for B&R works, so as to reach in this office on or before **19.05.2023** up to **10:30 AM** and will be opened on same day at **11:00 AM**, in the presence of intending contractors or their authorized representatives who may wish to be present.

The application for issue of tender form shall be received on **18.05.2023** up to **1.00 PM**. The tender form can be had from his office against cash payment (Non-refundable) on same day up to **5.00 P.M.**

The earnest money in the shape of National saving certificate/Time deposit receipt of any recognized Bank in H.P. duly pledged in the name of XEN must accompany with each application for obtaining the tender form. The Executive Engineer reserves the right to reject the tenders without assigning any reasons.

1. **Name of Work :-** A/R & M/O on Narkanda Thanedhar Kotgarh Bithal road Km.0/000 to 44/000 (SH:- Providing & Fixing road signages at Rd.1/405 Shilli Kandli). Estimated Cost:-4,91,712/- Earnest Money:-9900/-Time:- One Month.
2. **Name of Work :-** A/R & M/O on Narkanda Thanedhar Kotgarh Bithal road Km.0/000 to 44/000 (SH:- Providing & Fixing road signages at Rd.1/405 Shilli Kandli). Estimated Cost:-4,48,427/- Earnest Money:-9000/-Time:- One Month.
3. **Name of Work :-** R/O R/D on Lauga Badubagain Changadhar Dadesh Banot Nllah road Km.0/000 to 6/970 (SH:- Removal of slips at various Rds). Estimated Cost:-2,82,313/- Earnest Money:-5700/-Time:- One Month.
4. **Name of Work:-** R/O R/D on Tikkar Aldi Baza Road Km.0/000 to 5/090 (SH:-Removal of slips at various Rds). Estimated Cost:-2,34,678/- Earnest Money:-4700/- Time:- One Month.

Terms and conditions:-

1. The contractors shall produce their latest registration/renewal of their registration/GST No/EPE No along with their application.
2. The single/conditional tender will be rejected.
3. The offer shall remain valid up to 90 days.

Executive Engineer,
Kumarsain Division
HP.PWD, Kumarsain

Dated:- 11/05/2023

No.PW-KMS-AB-NIT/2023-24-

1222-3)

Copy to the Engineer-in-Chief, HP.PWD., Shimla-2.
Copy to the Deputy Commissioner Shimla, District Shimla (H.P.)
Copy to the Sub-Divisional Officer @ Kumarsain, Distt. Shimla (H.P.)
Copy to the Superintending Engineer, XIth Circle, HP.PWD., Rampur.
Copy to Block Development office, Narkanda Distt. Shimla, (H.P.)
Copy to all Assistant Engineers under this Division for information & n.a.
Copy to various contractors for information.
Copy to Notice Board of this office.

Executive Engineer,
Kumarsain Division,
HP.PWD, Kumarsain

SCHEDULE OF QUANTITY


Estimated cost:-Rs.282313/-

Earnest money:-Rs.5700/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on Louga Badubgain Changadhar Dadesh Banot Nallah road Km.0/000 to 6/970 (SH:- Removal of slips at various RDs).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	in words.		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611 including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	2258.50 m3			Per cubic metre.	
	Total:-					


Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

SCHEDULE OF QUANTITY


Estimated cost:-Rs.234678/-

Earnest money:-Rs.4700/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on Tikkar Aldi Baza road Km.0/000 to 5/090 (SH:- Removal of slips at various RDs).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	in words.		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611 including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	1877.42 m ³			Per cubic metre.	
	Total:-					


Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

SCHEDULE OF QUANTITY

Estimated cost:-Rs.491712/-


Earnest money:-Rs.9900/-

Time allowed:-One month.

Name of work:-A/R & M/O Narkanda Thanedhar Kotgarh Bithal road Km.0/000 to 44/000 (SH:-Providing and fixing road signages at RD.1/405 Shilli Kandli).

S. No.	Sub-Head Items of work.	Quantity.	Rate.		Unit.	Amount
			In fig.	In words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator) - manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed. All kinds of soil upto all leads and lifts as per directions of the Engineer-in-Charge.	15.75 m ³			Per cubic metre.	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	1.90 m ³			Per cubic metre.	
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	12.69 m ³			Per cubic metre	
4	Steel reinforcement for R.C.C. work including straightening, cutting, ending, placing in position and binding all complete upto plinth level 1:1.5:3 steel and Medium Tensile steel bars including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	1522.80 Kg.			Per Kilogram	
5	Providing and fixing uni stone 12mm thick cladding on R.C.C.surface side as on faces of Arch masonry walls etc.on 12mm. Thick cement plaster 1:3(1cement:3sand) and jointed with cement slurry i/c scaffolding etc. complete including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	19.92 m ²			Per square metre	

6	Providing and fixing 0.60mm thick prepainted steel sheet of TATA Durashine in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i.e fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete as per HP.PWD., Specifications of 1990 volume-I, including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	64.23 m2			Per square metre	
7	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board-facia soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	37.26 m2			Per square metre	
Total:-						


 Executive Engineer,
 Kumarsain Division,
 HP.PWD., Kumarsain.

SCHEDULE OF QUANTITY


Estimated cost:-Rs.448427/-

Earnest money:-Rs.9000/-

Time allowed:-One month.

Name of work:-A/R & M/O Narkanda Thanedhar Kotgarh Bithal road Km.0/000 to 44/000 (SH:-Providing and fixing road signages at RD.1/405 Shilli Kandli).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	2844.65 Kg.			Per Kilogram	
2	Painting two coat with synthetic enamel paints of approved shade of asian paint or its equivalent finish for interior painting with brushes plains smooth finish and including papering the surface by thoroughly brushing the surface free from mortar droppings and other foreign mortar, sand papering the surface smooth including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	38.61 m2			Per square metre.	
	Total:-					


Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.