

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2023-24

1079

Dated:- 27.04.2023

To,


The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 10.05.2023 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above


**Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat**

**Himachal Pradesh
Public Works Department
"Notice Inviting Tender"**

Sealed item rate tender are hereby invited in form No. 6&7 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968.The important dates of tender are as under:-

The last date and time of receipt of application for tender form 03.05.2023 up to 4.00 P.M.

The last date for sale of tender is up to 04.05.2023 at 4.00PM.

The tender shall be received up to 11:00 AM on 06.05.2023 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 06.05.2023. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.

Sr. No.	Name of work	Estimated cost.	Earnest Money.	Cost of form.	Time allowed.
1.	Construction of Govt. Senior Secondary School at Baldwara (SH:- Balance work)	158757	3500	350	One Month
2.	Construction of Link Road Govt. ITI Mohin in Tehsil Sarkaghat Distt. Mandi (HP) (SH:- Construction of U-Shape Drain in Km. 0/225 to 0/450)	268199	6000	350	One Month
3.	A/R & M/O Bah to Gahar Road Km. 0/0 to 8/720 (SH:- Construction of R/wall in PCC 1:4:8 at Km. 6/660 to 6/675)	409914	8200	350	One Month
4.	Construction of Veterinary Hospital at Thona Tehsil Sarkaghat Distt. Mandi (HP) (SH:- Construction of site development work) Deposit	354803	7000	350	One Month
5.	Construction of Link Road Bataldi Bridge to Dhaul Khan Road Km. 0/0 to 1/500 (SH:- Providing and laying (WBM G-II) and Cement concrete 1:2:4 reduced distance 0/0 to 0/010 and 0/090 to 0/265)	488413	10000	350	One Month
6.	Repair of link Road Panchyat Ghar to Kunlela Mohal Jehmat Km. 0/0 to 6/500 (SH:- Construction of stone soling and cement concrete at RD 0/0 to 0/110) Deposit work	389558	8000	350	Two Months
7.	Construction of Sarkaghat Chamyaru Via Lukawanu Road Km. 0/0 to 0/300 (SH:- Providing and laying WMM at RD 2/0 to 2/500)	492270	10000	350	One Month
8.	Construction of Deberwal Jamanwal Banmangoh Jaboth Road Km. 0/0 to 8/300 (SH:- Suppling of RCC spun pipe with inbuilt collars) Budget provision for the year 2023-24	95000	2000	350	One Month
9.	A/R & M/O various Roads under Baldwara Sub- Division (SH:- Supplying and staking at site crushed stone aggregate 13.2mm to 5.6mm nominal size and sand for patch work in various section of Baldwara Sub-Division) (Section Smaila)	99300	2000	350	One Month
10.	Construction of Link Road Rissa to Garroru (Mujarari) Km. 0/0 to 1/100 SH:- Construction of R/wall in 1:5:10 at RD 1/025 to 1/031.10) MLA LAD Deposit	99612	2000	350	One Month

TERMS AND CONDITONS:-

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.
4. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
5. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
6. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)
7. The tender shall be awarded to the lowest bidder without any negotiation if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The earnest money shall be deposited duly pledged in favour of Executive Engineer B& R Division HPPWD Sarkaghat & Cost of tender form for the above works should be submitted with the application for the purchase of the tender forms.
9. All the required documents should be submitted with the application others wise single application may be rejected.

Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

Dated: 27-04-2023

No. PW-SKT-CB-Tender/2023-24

1070 - 78

1. The Engineer - in- Chief HPPWD Nirman Bhawan Shimla for information please.
2. The Chief Engineer Hamirpur Zone HP.PWD . Hamirpur for information please.
3. The Superintending Engineer Dharampur Circle, HP.PWD. Dharampur for information please.
4. Block Development officer Sarkaghat for information please.
5. Copy to the Assistant Engineer B&R Sub- Division HP.PWD Sarkaghat/ Baldwara /Bhaderwar for information.
6. Copy to Drawing Branch of this office for information.
7. Notice Board.

Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

Draft Schedule of Quantity

Name of work:- Construction of Govt. Senior Secondary School at Baldwara (SH:- Balance work)					Estimated cost :-	
					Earnest money:-	Rs.1,58,757/-
					Time allowed:-	Rs.3200 /-
Sr.No	Description of item/Sub Head	Quantity	In figure	In words	Unit	Amount
1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm (Twenty millimetre) nominal size including all leads and lifts and as per the direction of Engineer-in-Charge	0.88			Per cubic metre	
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting hoisting, fixing in position and applying a priming coat of pproved steel primer all complete,including all leads and lifts and as per the direction of Engineer-in-Charge	76.00			kilogram	
3	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7D,F4B, K11 B and K12 B etcetra complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design, (sectional weight of only steel members shall be measured for payment including all leads and lifts and as per the direction of Engineer-in-Charge					
(i)	Fixing with 15x3 mm (Fifteen into three lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (One Cement : three coarse sand : six graded stone aggregate 20 mm (Twenty millimetre) nominal size including all leads and lifts and as per the direction of Engineer-in-Charge	208.2			kilogram	
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including all leads and lifts and as per the direction of Engineer-in-Charge	208.78			kilogram	
5	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4.0 mm (Four point zero millimetre)thick glass panes including all leads and lifts and as per the direction of Engineer-in-Charge	18.90			Per square metre	

6	Providing and fixing ISI marked oxidised M.S. tower bolt black finish. (Barrel type) with necessary screws etcetra complete 100x10 mm(one hundred into ten millimetre) including all leads and lifts and as per the direction of Engineer-in-Charge	36.00			Each	
7	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete 125 mm (One twenty five millimetre)including all leads and lifts and as per the direction of Engineer-in-Charge	36.00			Each	
8	15 mm cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: six coarse sand) including all leads and lifts and as per the direction of Engineer-in-Charge	38.10			Per square metre	
9	White washing two coat with lime on undecorated wall surfaces to give and even shade including thoroughly brooming the surface to remove all dirt, dust mortar dirt and other foreign matter on ceiling including all leads and lifts and as per the direction of Engineer-in-Charge	1014.79			Per square metre	
10	Finishing walls with water proofing cement paint of required shade including all leads and lifts and as per the direction of Engineer-in-Charge	349.87			Per square metre	
11	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point nine zero /square metre) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seven five litre / ten square metre) of approved brand and manufacture including all leads and lifts and as per the direction of Engineer-in-Charge	246.93			Per square metre	
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point nine zero /square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (zero point eight zero litre/ten square metre) of approved brand and manufacture including all leads and lifts and as per the direction of Engineer-in-Charge	55.6			Per square metre	
13	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetre) gap for thermal expansion, (i) Single socketed pipes 110 mm (One hundred ten millimetre)diameter including all leads and lifts and as per the direction of Engineer-in-Charge	49.60			Per Running metre	
14	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetre) gap for thermal expansion including all leads and lifts and as per the direction of Engineer-in-Charge	16.00			Each	

15	Providing and fixing precast galvanised iron profile sheet (size shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50 mm (zero point five millimetre) (0.05 %) (zero point zero five percent) total coated thickness with zinc coated 120 (One hundred twenty) grams including all leads and lifts and as per the direction of Engineer-in-Charge	5.10				Per square metre	
						Total	

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:-Construction of Link Road Govt I.T.I Mohin in Tehsil Sarkaghat Distt Mandi (H.P) (SH:-Construction of U-Shape Drain in km 0/225 to 0/450) Estimated cost :- Rs. 2,68,199.00

Earnest Money:- Rs. 6000.00

Time Limit:- One month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
1 Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre)in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	55.68			Per cubic metre	
2 Centering and shuttering including strutting, propping etcetra and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etcetra. Including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	236.25			Per square metre	
3 Providing, laying, in position cement concrete of specified grade excuding the cost of centering and shuttering all work up to plinth level 1:3:6 (one cement :three coarse sand:six graded stone aggregate) 20 mm (twenty millimetre) nominal size as per drawing and HP,PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	36.00			Per cubic metre	
				Total:-	

Executive Engineer,
B&R Divison,
HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O Bah to Gahar Road km. 0/0 to 8/720 (SH:-Construction of R/wall in PCC 1:4:8 at RD 6/660 to 6/675). Estimated cost :- Rs. 4,09,914.00

Description of item/Sub Head	Quantity	In Figure	Rates		Unit	Amount
			In words	Time Limit:-		
1 Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre)in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m. (one point five metre) including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	36.60				Per cubic metre	
2 Centering and shuttering including strutting, propping etcetra and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etcetra including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	63.84				Per square metre	
3 Providing and Laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level 1:4:8: (one Cement :four coarse sand: eight graded stone aggregate) 40 mm(forty millimetre) nominal size as per drawing and HP,PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	71.37				Per cubic metre	
4 Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7with in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in- Charge.	24.00				Each	
5 Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	12.60				Per cubic metre	
					Total:-	

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.


NAME OF WORK :- Construction of Vaternary Hospital at Thona Tehsil-Sarkaghat Distt. Mandi HP (SH:-construction of site development work) Deposit work

SCHEDULE OF QUANTITY

Estimated cost :-
Earnest money:-
Time allowed:-

Rs. 3,54,800/-
Rs. 7000/-
One month

Sr.No	Description of Item	Quantity	Rates		Unit	Amount
			In figure	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan including dressing of sides and ramming of bottoms, lift upto 1.5 m,(one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. (fifty metre)	661.50			Per cubic metre.	
2	Excavation in Hilly area in all kinds of soil such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer-In-Charge at site and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his on cost in all cases. Recovery for useful stone 132.29 cubic metre at the rate of Rs.300/- per cubic metre shall be made from the contractor on prorata basis from every running bill. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge.	992.26			Per cubic metre.	
					Total:-	


Executive Engineer
B & R Division HPPWD
Sarkaghat

SCHEDULE OF QUANTITY

Name of Work:- Construction of link road Bataldi bridge to Dhaul Khan Road km 0/0 to 1/500 (SH:- Providing and Laying (WBM G- II) and Cement Concrete 1:2:4 reduced distance 0/0 to 0/010 and 0/090 to 0/265)

Estimated cost :- Rs. 4,88,413.00
 Earnest Money:- Rs. 10,000.00
 Time Limit:- One month

Item No.	Description of Item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity dressing to camber and consolidating with road roller including sub grade making good the undulations etcetra. And re-rolling the sub grade and direction of Engineer-in-Charge.	555.00			Per cubic metre	
2	Providing, laying, spreading and compacting stone aggregates of 63mm to 45mm (sixty three millimetre to forty five millimetre) nominal size to water bound macadam specifications including in uniform thickness, hand packing, rolling with smooth wheel roller 80-100K N in stages to proper grade and camber, applying and brooming, stone screening and binning materials to fillup the interstices of coarse aggregate, watering and compacting to the required density grading-II as per technical specifications clause 405 by manual means including entire carriage of materials within all leads and lifts and other incidentals.	41.63			Per cubic metre	
3	Providing and laying Cement concrete 1:2:4 (one Cement :two coarse sand: four graded crushed stone aggregate) 20 mm (twenty millimetre) nominal size, in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping concrete as per drawing and HP, PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	55.50			Per cubic metre	
	Total:-					

Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- Repair of Link Road Panchyat Ghar to Kunhela Mohal Jahmat km. 0/0 to 6/500 (SH:-
Construction of stone soling and cement concrete at RD 0/00 to 0/110), (Deposit work)

Estimated cost :- Rs. 3,89,558.00
Earnest Money:- Rs. 8000.00
Time Limit:- One month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
1 Stone soling properly hand packed filling interstices with khraja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100mm (one hundred millimetre) spread thickness (finished work including materials and labour) including carriage of materials within all leads and lifts and other incidentals.	51.98			Per cubic metre	
2 Providing and laying Cement concrete 1:2:4 (one Cement :two coarse sand: four graded crushed stone aggregate) 20 mm (twenty millimetre) nominal size, in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete: as per drawing and HP.PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	42.62			Per cubic metre	
				Total:-	

Executive Engineer,
B&R Divison,
HP PWD, Sarkaghat.

[illegible]

Estimated cost :-	Rs. 4,92,270. 00
Earnest Money:-	Rs. 10,000.00

Time Limit:-	One month
--------------	-----------

**Executive Engineer,
B&R Divison,
HP PWD, Sarkaghat.**


SCHEDULE OF QUANTITY

NAME OF WORK :- A/R&M/O varolus roads under Baldwara Sub-Division HPPWD, Baldwara (SH:- Supplying and stacking at site graded crushed stone aggregate 13.2 mm to 5.6 mm nominal size and coarse sand for patch work) smalla section

Estimated cost :-
Earnest Money:-
Time Limit:-

Rs. 99,30
Rs. 2,000
one mon

Sr. No	Description of item/Sub Head	Quantity	In Figure		Rates		Unit	Amou
1	2	3	4	5	6	7		
1	Supplying and stacking at site of work graded crushed stone aggregate 13.2 mm to 5.6 mm (thirteen point two millimetre to five point six millimetre) nominal size free from disintegrated pieces deleterious and organic matter including entire carriage of material within all leads and lifts and proper stacking in all respect as per the direction of Engineer-in-charge.	24.00			Per cubic metre			
2	Supplying and stacking at site of work coarse sand free of dust, dirt and other organic matter for binding material including entire carriage of material within all leads and lifts and other incidentals.	25.00			Per cubic metre			
Total :-								


Executive Engineer
B & R Division HPPWD
Sarkaghat

SCHEDULE OF QUANTITY

Name of Work:- Construction of link road Rissa to Garoru (Mujarari) Km 0/0 to 1/100 (SH:- Construction of R/Wall in 1:5:10at Rd 1/025 to 1/031.10) MLA LAD deposit.

Name of Work:- Construction of link road Rissa to Gairoru (Mujarari) Km 0/0 to 1/100 (SH:- Construction of R/Wall in 1:5:10at Rd 1/025 to 1/031.10) MLA LAD deposit.					Estimated cost :-	Rs.99,612/-	
					Earnest Money:-	Rs.2000/-	
Sr.N o	Description of Item/Sub Head	Quantit y	In Figure	In words	Rate	Unit	Amount
1	Earth work in excavation in for structures as per drawing and technical specification Clause 305.01 including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth up to a lead of 50 Metre in specified site and as per the direction of Engineer-in-charge complete.	6.65				Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) with in all lead and lift and as per the direction of Engineer -in -charge.	19.34				Per cubic metre	
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge.	4				Each	
4	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per the direction of Engineer-in-Charge.	8.23				Per cubic metre	
						Total:-	


Executive Engineer
B & R Division HPPWD
Sarkaghat