



Office of
Executive Engineer Baijnath Division H.P.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item/percentage rate tenders on forms 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **03.06.2023** up to **11.00 A.M** and will be opened on the same day at **11.30 A.M** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **02.06.2023** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **01.06.2023** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 90 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of work.	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Dismantling of existing old store building and C/O Store/Godown at Mahakal Temple in Tehsil Baijnath.	Rs. 4,88,514/-	Rs. 9,800/-	Rs. 350/-	Three Months
2	Special Repair to Xen office HPPWD., Baijnath (SH: Supplying and fixing glass panes, P/F Plain cement bonded sheet and exhausting fan etc.)	Rs. 87,059/-	Rs. 1800/-	Rs. 350/-	Two Months
3	C/O Rakkar Rajot Noun Road km 0/00 to 4/00 (SH: C/O 0.60 Mtr. Span RCC Slab Culvert at RD 3/900)	Rs. 1,04,284/-	Rs.2,100	Rs. 350/-	Two Months
4	C/o link road from Chordu to Baba Chori Sidh Mandir Road km 0/00 to 1/200. (SH: Providing and laying WBM G-I (90 to 45mm) thick at km 0/00 to 0/350)	Rs. 4,01,331/-	Rs.8,100/-	Rs. 350/-	Two Months
5	C/O Baijnath Pantehar via Ghartholi Road Km 0/00 to 1/500 (SH: C/O U-Shape Drain at RD 0/280 to 0/340)	Rs. 79,680/-	Rs.1,600/-	Rs. 350/-	Two Months
6	C/O Utrala to Surahi Pass Road Km 0/0 to 32/600 (SH: Preparation of Revised DPR Km 19/0 to 32/600)	Rs. 3,12,800/-	Rs. 6300/-	Rs. 350/-	Three Months
7	A/R & M/O Dharaman Sungal Jadiyahal Jandpur Majherna Railway Station Road km 0/00 to 7/00 (SH: C/O U-Shape drain at RD 2/925 to 3/125)	Rs. 1,92,463/-	Rs. 3,900/-	Rs. 350/-	Two Months
8	Sagoor to Chhahban Janehar Road Km 0/00 to 1/500 (SH: C/O 1.00 Mtr. Span RCC Slab Culvert at RD 0/900)	Rs. 1,45,091/-	Rs. 2,900/-	Rs. 350/-	One Month
9	A/R & M/O various Roads under Bir Sub-Division, HPPWD, Bir. (SH: Painting and writing Sign board, km Stone, Rain Shelter & PMGSY Board etc)	Rs. 1,93,336/-	Rs. 3,900/-	Rs. 350/-	Two Months
10	C/O Community Bhawan Near Bansi Chand House Upper Thehad Mohal Kudang (SH: Providing and Laying brick work, RCC 1:2:4, wood work and steel work etc.)	Rs. 1,93,086/-	Rs.3,900/-	Rs. 350/-	Three Months
11	R/D Barot to Polling Road km 0/00 to 8/050 (SH: C/O R/wall at RD 6/370 to 6/382)	Rs. 4,094,00/-	Rs. 8,500/-	Rs. 350/-	Three Months

12	A/R & M/O Rakkar Rajot Noun Road Km 0/00 to 4/00 (SH: Providing & Laying WBM, G-II & Repair of Pot hol at RD 0/00 to 4/00)	Rs. 4,90,442/-	Rs. 9,900/-	Rs. 350/-	Two Months
13	NH Kukaina to Nouri Labol Behru Road km 0/00 to 5/345 (SH: Providing and Laying WBM, G-II and Repair of Pot hol at RD 2/00 to 3/00 and 4/00 to 5/00)	Rs. 4,08,383/-	Rs. 8,200/-	Rs. 350/-	Two Months
14	Construction of Link Road to Village Majhoti Gram Panchayat Majhoti km 0/00 to 0/500 (SH: Construction of 900mm dia RCC Hume Pipe culvert at RD 0/350)	Rs. 1,24,267/-	Rs. 2,500/-	Rs. 350/-	Two months

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act, 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No(Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. The application form should accompany the earnest money in the shape of FDR/NSC duly pledged in favour of Executive Engineer, PWD Baijnath otherwise no forms will be issued .
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper , Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2023-24/-1764-1814

Dated:- 20-5-23

1. Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. Drawing Branch in this office.
7. Notice Board.
8. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

SCHEDULE OF QUANTITY

Name of Work: - Dismantling of Existing Old Store Building and C/O Store / Godown at Mahakal Temple in Tehsil Baijnath.
(Sub Head : Civil Work)

Estimate Cost: 4,88,514.00
Earnest Money: 9800.00
Time Limit : Three Months

SCHEDULE OF WORKS


Sr. No.	Description of work	No.or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Demolition above G.L. upto floor two level including disposal of unserviceable materials within 20 meters (Twenty metres) lead and including cutting the necessary reinforcement and separating out from R.C.C. /R.B. works:-R.C.C. work. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.50	Per Cubic metre			
2	Demolition of Brick work above G.L. upto floor two level including stacking of serviceable materials and disposal of unserviceable material within 20 meters (Twenty metres) lead. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.80	Per Cubic metre			
3	Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters not exceeding 3 Sqm (three square meter) in area including chowkhats, architraves, hold fasts and other attachments etc. complete and stacking them within 20 meters (Twenty metres) lead. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.00	Each			

4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation, trenches or drains (not exceeding 1.5 m in width or 10 sqm), (one point five meter in width or ten square meter) including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (fifty meter). All kinds of soil, with in all leads by any mode of transportation and other incidental, as per direction and entire satisfaction of Engineer -in -charge. The rate also including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	153.23	Per Cubic metre			
5	Supplying and filling in plinth with stone boulder dry hand packed under floors, including watering, ramming, consolidating and dressing complete. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.17	Per Cubic metre			
6 (a)	Providing form work with steel plates of 3.15mm thick, (three point one five millimeter thick) welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in foundation, Footings bases of columns and mass concrete. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.64	Per Square metre			

6(b)	Providing form work with steel plates of 3.15mm thick, (three point one five milimeter thick) welded with angle iron in frames of 30mmx30mmx5mm, (thirty into thirty into five milimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs, landings and the like floor etc. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	86.29	Per Square metre			
6(c)	Providing form work with steel plates of 3.15mm thick, (three point one five milimeter thick) welded with angle iron in frames of 30x30x5mm, (thirty into thirty into five milimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in beams cantilevers, girders lintels, sides, and soffits of beams haunchings, cantilevers bressumers and lintels upto all depths. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	70.72	Per Square metre			
6 (d)	Providing form work with steel plates of 3.15mm thick, (three point one five milimeter thick) welded with angle iron in frames of 30x30x5mm, (thirty into thirty into five milimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights and removal of the same for in-situ reinforced concrete and plain concrete work in columns, pillars, posts and struts, square, rectangular, polygonal in plain. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	31.20	Per Square metre			


7	Providing and laying cement concrete 1:4:8 (One cement: Four sand: Eight graded crushed/broken stone aggregate 40mm (forty millimeter) nominal size and curing complete, excluding cost of form work in foundation and plinth. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	14.40	Per Cubic Meter			
8	Providing and laying cement concrete 1:6:12 (One cement: six sand: twelve graded crushed/broken stone aggregate 40mm (forty millimeter) nominal size and curing complete, excluding cost of form work in foundation and plinth. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.43	Per Cubic Meter			
9	Providing and laying Mechanically mixed / vibrating Plain /work excluding the cost of Form work in foundation and plinth: reinforced cement concrete, cement concrete work 1:2:4 (one Cement:two Sand:four graded stone aggregate 20 mm (twenty millimeter nominal size) and curing complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Government.	1.98	Per Cubic Meter			
10	Providing and laying Cement concrete work 1:2:4 (one Cement:two Sand:four graded stone aggregate 20 mm (twenty millimeter nominal size) and curing complete, excluding cost of from work and rainforced concrete work in- Footings bases of columns and mass concrete. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Government.	7.37	Per Cubic Meter			
11	Providing and laying Cement concrete work 1:2:4 (one Cement:two Sand:four graded stone aggregate 20 mm (twenty millimeter nominal size) and curing complete, excluding cost of from work and rainforced concrete work in- Columns, Pillars, posts and struts up to floor two level. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Government.	2.66	Per Cubic Meter			

12	Providing and laying Cement concrete work 1:2:4 (one Cement:two Sand:four graded stone aggregate 20 mm (twenty millimeter nominal size) and curing complete.excluding cost of form work and reinforced concrete work in- flat surfaces such as soffits of suspended floors roofs, landings and the like floor etc .The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	21.95	Per Cubic Meter			
----	--	-------	-----------------	--	--	--


Executive Engineer
Bajnat Division
H.P.R.W.D., Bajnath

SCHEDULE OF QUANTITY						
Name of Work: Special Repair of Xen Office HPPWD Division Bainath. (SH: Supplying and fixing glass panes, P/F plain cement bonded sheet and exhausting fan, etc)				Estimated Cost: Rs. 8705/- Earnest Money: Rs. 1800/- Time Limit : Two Months		
SCHEDULE OF WORKS						
S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Supplying and fixing glass panes with putty and nails including complete in all respect and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	3.58	Per Sqm			
2	Providing and fixing 6mm (six) millimeter cement bounded partial board sheet for ceiling of approved quality with bolt jointing and screws complete in all respect and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	28.80	Per Sqm			
3	Providing and fixing exhausting fan including necessary fitting complete in all respect and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	2.00	Each			
4	Providing and fixing vitreous china division plate for urinal 600mm x 300mm of approved brand IS marks with C.I. or M.S. brackets painted white i/e cutting holes and making good the same complete in all respect and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	2.00	Each			
5	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete in all respect and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	207.11	Per Sqm			
6	Providing Tractor Acrylic Distemper (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including and priming coat with distemper primer and manufacture after thoroughly brushing the surface free from mortar drooping and other foreign matter and also including preparing the surface even and smooth priming coat with distemper primer complete in all respect and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	260.92	Per Sqm			

7	Providing and fixing PVC 110mm (one hundred ten) millimetre nominal bore / diameters for rain water pipe with jointing of approved adhesive within all leads and lifts and other incidentals and entire satisfaction/direction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	4.50	Run			
8	Providing and laying PVC bend 150mm (one hundred fifty) millimetre nominal bore / diameters for rain water pipe and jointing with approved adhesive within all leads and lifts and other incidentals and entire satisfaction/direction of Engineer-In-Charge.	1.00	Each			
9	Providing and fixing hydraulic door closer of approved brand complete in all respect and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	2.00	Each			
10	Painting two coats (excluding priming costs) on previously painted wall and other surfaces with whether proof paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	31.96	Per Sqm			
11	Providing and fixing vitreous china pedestal of approved brand IS marks for wash basin with C.I. or M.S. brackets painted white i/c cutting holes and making good the same but excluding fitting and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	1.00	Each			
12	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows including black enamelled iron butt hinges with necessary screws 40mm (forty millimeter) thick second class deodar wood and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	2.16	Per Sqm			
13	Providing and fixing 1st class sal wood work in frames of doors and windows clerestory, windows and other frames wrought framed and fixed in position. and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government time to time.	0.05	Per Cum			


 Executive Engineer
 Baijnath Division
 H.P.W.D., Baijnath

SCHEDULE OF QUANTITY

Name of Work:- C/O Rakkar Rajot Noun Road Km 0/00 to 4/00.
(SH:- C/O 0.60 Mtr. Span RCC Slab Culvert at RD 3/900.)

Estimated Cost: Rs. 104284.00

Earnest Money: Rs. 2,100.00


Time Limit : Two Months

SCHEDULE OF WORKS

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT	
				Figure	Words	Rs.	P
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, (Fifty meters) dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	15.39	Cum				
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 M-10 (1:3:6) (one cement: three coarse sand: six graded stone aggregate 40mm (forty milimeter) nominal size) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	2.59	Cum				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 (1:2.5:5) (one cement: two point five coarse sand: five graded stone aggregate) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	9.93	Cum				
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800, 1205.4 and 1205.5 RCC M-25 (1:1.5:3) (one cement: one point five coarse sand: three graded stone aggregate 20mm (twenty milimeter) nominal size) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	1.68	Cum				

Steel Reinforcement for RCC work including straightening, Cutting, Bending, placing in position and binding all complete upto plinth level. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	150	Kg			
--	-----	----	--	--	--

3


 Executive Engineer
 Baijnath Division
 HPPWD, Baijnath

4

SCHEDULE OF QUANTITY

Name of work :- C/O link road from Chordu to Baba Chori Sidh Mandir Road Km 0/00 to 1/200.
(Sh:-Providing and Laying WBM G-I (90 to 45mm) thick at Km 0/00 to 0/350.)

Estimate Cost: 401331/-
Earnest Money: 8100/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Preparation and Consolidation of sub grade with power road roller of 8 to 12 tonne (Eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (twenty two point five centimeter) depth, dressing to camber and consolidation with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 mtr. (Fifty meters) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	588.00	Sqm				
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405.(90mm to 45mm) (Ninety milimeter to forty five milimeter) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	123.11	Cum				

Executive Engineer
Bajnath Division
HPPWD Bajjnath

5

SCHEDULE OF QUANTITY


Name of Work:- C/O Baijnath Pantehar via Ghartholi Road Km 0/00 to 1/500.
(SH:- C/O U-Shape Drain at RD 0/280 to 0/340.)

Estimated Cost 79680.00
 Earnest Money 1600.00
 Time limit Two Months

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. (Fifty Meters) dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	23.10	Per Cubic Meter			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-10 (1:3:6) (one cement: three sand: six stone aggregate 20mm nominal size) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	13.65	Per Cubic Meter			

Executive Engineer
 Baijnath Division
 HPPWD Baijnath

SCHEDULE OF QUANTITY						
Name of Work: C/O Utrala to Surahi Pass Road Km 0/0 to 32/600 (SH: Preparation of Revised DPR Km 19/0 to 32/600).					Estimated Cost: Rs. 3128000; Earnest Money: Rs. 6500; Time Limit: Three Months	
SCHEDULE OF WORKS						
S. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P.
				Figure	Words	
1	Preparation of revised Detailed Projects Report of new connectivity road complete in all respect in manuscript from and submission of the same to higher officer for approval. If any correction / amendment has desired by the head office the same may be corrected as desired and directed by Engineer-in-Charge after approval the same should be submitted in fair form complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge.	13.600	Per Km			


Executive Engineer
 Baijnath Division,
 H.P.P.W.D.-Baijnath (H.P.)

7

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O Dharaman Sungal Jadiyal Jandpur Majhera Railway Station Road road Km 0/00 to 7/00.
(SH:- C/O U Shape drain at RD 2/925 to 3/125.)

Estimated Cost 192463.00
Earnest Money 3900.00
Time limit Two Months

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. (fifty meter) dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	63.00	Per Cubic Meter			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-10 (1:3:6) (one: cement three: sand six: stone aggregate 20mm (twenty milimeter) nominal size The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	31.50	Per Cubic Meter			

Executive Engineer
Bijnath Division
HPPWD Bijnath

D.N.I.T / SCHEDULE OF QUANTITY

Name of Work: Sagoor to Chhabhan Janchar Road Km 0.00 to 1/500.
(SRI: C/O 1.00 mtr Span RCC Slab Culvert at R.D 0/200.)

Estimated Cost: Rs. 145091.00


Earnest Money: Rs. 2,000.00

Time Limit: One Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate		Amount	
				Figure	Words	Rs.	P.
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	23.66	Cum				
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-10 (1:3:6) (one: cement three: sand six: stone aggregate) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	2.37	Cum				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 (1:2.5:5) (one: cement two and half: sand five: stone aggregate) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	13.55	Cum				
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1205 RCC M-20 (1:2:4) (one: cement two: sand four: stone aggregate) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.60	Cum				
5	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 RCC grade M-25 (1:1.5:3) (one: cement one and half: sand three: stone aggregate) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	1.92	Cum				

6	Steel Reinforcement for RCC work including straight cutting, bending, placing in position and binding all complete upto plinth level. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	228.93	K.g			
---	---	--------	-----	--	--	--


Executive Engineer
Bajinath Division
HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O Various Roads Under Bir Sub- Division, H.P PWD Bir . (SH: Painting and Writing Sign board, Km Stone, Rain shelter & PMGSY Board etc.)						
				Estimated Cost	193336.00	
				Earnest Money	3900.00	
				Time limit	Two Months	
Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Painting two coats (excluding priming costs) on Previously Painted and other metal surface with white readymixed paint of nerolac/dulex/Asain Paint other than white to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete including carriage of material within all leads and lifts and other incidental as per approved specification, drawing, design and as directed by Engineer-in-Charge. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	151.96	Sqm			
2	Painting two coats (excluding priming costs) on Previously Painted Conrete/masonary/plastered surface with readymixed paint of nerolac/dulex/Asain Paint other than white to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete including carriage of material within all leads and lifts and other incidental as per approved specification, drawing, design and as directed by Engineer-in-Charge. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	124.88	Sqm			
3	Writring letter of figures on any surface with black japan paint (stop,commas,hyphens and like not to be measured and paid separately) with in all leads and lifts.The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.					
	Block letters/figures	75000.00	Per Cmt/ Per height			
4	Writring letter of figures on any surface with black japan paint (stop,commas,hyphens and like not to be measured and paid separately) with in all leads and lifts.The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.					
	Indian letters/figures	20000.00	Per Cmt/ Per height			

5	Painting index hands normal size or arrows (upto 40cm long) on any surface with black japan paint with in all leads and lifts.The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	60.00	Sqm			
---	---	-------	-----	--	--	--

Executive Engineer
Bajjnath Division
HPPWD Bajjnath


SCHEDULE OF QUANTITY

Name of Work: C/O Community Bhawan Near Banshi Chand House Upper Thehad Mohal Kudang.
(SH: Providing and Laying brick work, RCC 1:2:4, wood work and steel work etc.)

Estimated Cost 193086.00
Earnest Money 3900.00
Time limit Three Months

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT	
				Figure	Words	Rs.	P
1	Brick work with Cement Mortar 1:6 (one cement : six coarse sand) common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level up to all floor level in all shapes and sizes including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	9.40	Cum				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm (twenty millimeter nominal size) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.02	Cum				
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	122.40	Kg				
4	Providing and fixing wood work in frames of door windows ventilator clearstory window and other frames, wrought framed and fixed in position with hold fast, lugs or with desh fasteners of required data and length (hold fast, lugs or dash fastener shall be paid for separately) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate also including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.371	Cum				
5	Steel work welded in built up section framed work in cutting hoisting fixing in position The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate also including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	402.63	Kg				

6	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete Fixed to steel windows by welding The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	108.00	Kg		
---	--	--------	----	--	--


Executive Engineer
Bajnath Division
HPPWD Bajjnath

SCHEDULE OF QUANTITY

11

Name of work:- R/D Barot to Polling Road Km 0/00 to 8/050.
(SH:- C/O R/wall at RD 6/370 to 6/382.)

Estimate Cost: 409400/-
Earnest Money: 8500/-
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	11.38	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	87.72	Per Cum			
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	13.10	Per Cum			

Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.

12.00

Each

Executive Engineer
Bajjnath Division
HPPWD Bajjnath

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Rakkar Rajot Noun Road Km 0/00 to 4/00. (Sh:- Providing & Laying WBM, G-II & Repair of Pot hol at RD 0/00 to 4/00.)					Estimate Cost: 490442/- Earnest Money: 9900/- Time Limit : Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per Technical Specification Clause 405.(63mm to 45mm) (sixty three milimeter to forty five milimeter) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	20.48	Cum			
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20 mm (twenty milimeter) thick pre-mix carpet and seal coat type B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.1. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	1105.20	Sqm			

Executive Engineer
Bajjnath Division
HPPWD Bajjnath

(13)

SCHEDULE OF QUANTITY

Name of work :- NH Kukaina to Nouri Labol Behru Road Km 0/00 to 5/345.


(Sh:- Providing and Laying WBM, G-II and Repair of Pot hol at RD 2/00 to 3/00 and 4/00 to 5/00.)

Estimate Cost: 408383/-

Earnest Money: 8200/-

Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per Technical Specification Clause 405.(63mm to 45mm) (sixty three milimeter to forty five milimeter) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	14.09	Cum			
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20 mm (twenty milimeter) thick pre-mix carpet and seal coat type B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.1.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	939.74	Sqm			


 Executive Engineer
 Baijnath Division
 HPPWD Baijnath


SCHEDULE OF QUANTITY

Name of work : Construction of Link Road to Village Majhoti Gram Panchayat Majhoti Km 0/00 to 0/500.
(SH: Construction of 900mm dia RCC Hume pipe culvert at RD 0/350.)

Estimate Cost: 124267/-
Earnest Money: 2500/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earthwork in excavation for all type of road structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. (Fifty meters) dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	34.65	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	4.30	Per Cubic metre			
3	Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	9.42	Per Cubic metre			

<p>Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.</p>	7.50	Per Running metre			
--	------	-------------------	--	--	--



 Executive Engineer
 Rajnath Division
 HPPWD Rajnath



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
1764-1814 DATED 20-5-23 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.