

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER**

Sealed percentage rate tenders are hereby invited on Form No.6 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 16-05-2023 upto 11.00 A.M and shall be opened on the same day 11.30 A. M in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working day before opening upto 2:00 P.M. The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form
1	R/R Damages Machher Jabiyana Wasni Road Km 0/0 to 7/160 (SH: - C/O R/Wall in Km 2/600 to 2/606).	456380/-	9500/-	Three Month	Rs.350/-
2	R/R damages on Macher Jabiyana Wasni road Km 0/0 to 7/160 (SH: - C/O R/Wall in Km 1/150 to 1/159).	484354/-	9700/-	Three Month	Rs.350/-
3	A/R & M/O on Banethi Bagthan Rajgarh Chandol road Km 7/00 to 28/00 (SH:- Improvement of curve between Km 12/00 to 18/130 & 27/00 to 28/00)	374643/-	7500/-	Three Month	Rs.350/-
4	R/R Damages on Banethi Bagthan Rajgarh Chandol road Km 7/00 to 28/00 (SH:- C/o G.I wire crate at RD 25/510 to 25/524)	477345/-	9600/-	Two Month	Rs.350/-
5	C/O Macher Jabiyana road Km 0/0 to 7/0 (SH:- P/L interlocking paver block in Km 0/470 to 0/570) SCSP	495759/-	10000/-	Three Month	Rs.350/-
6	A/R & M/O on Banethi Bagthan Rajgarh Chandol road Km 7/00 to 28/00 (SH:- Improvement of curve between Km 18/530 to 21/00)	403563/-	8300/-	Three Month	Rs.350/-
7	Geotechnical investigation for construction of 19.75 m span RCCT-Beam Bridge over Gaithal Bajhed Mandi Kharana road at RD 6/195 (SH:- Soil investigation two pits left benk and two pits on right benk on both bridges)	316800/-	6500/-	One Month	Rs.350/-
8	Geotechnical investigation for construction of 19.75 m span RCCT-Beam Bridge over Thani Thamani Tindu Kharimu road at RD 5/555 (SH:- C/O (SH:- Soil investigation two pits left benk and two pits on right benk on both bridges)	316800/-	6500/-	One Month	Rs.350/-
9	C/O Macher Jabiyana road Km 0/0 to 7/0 (SH:- P/L interlocking paver block in Km 0/250 to 0/350) SCSP	489165/-	10000/-	Three Month	Rs.350/-
10	C/O Baru Sahib Mangarh road Km 0/00 to 3/120 (SH:- ROFD in Km 0/980 to 1/020)	245536/-	5000/-	Three Month	Rs.350/-
11	A/R & M/O Bhureshwar Mahadev Km 0/00 to 2/315 (SH:- C/O R/Wall at RD 0/360 to RD 00/387 L 27 m and H 3.66 m)	448556/-	9000/-	Three Month	Rs.350/-
12	C/O Bantighat Bhagyanghat Road Km 0/0 to 4/0 (SH:- P/L G-II at RD 1/00 to 1/800) MNP.	475650/-	10000/-	Three Month	Rs.350/-
13	C/O Sikken Dinger Kinner Bhagyanghat Road Km 0/0 to 9/330 (SH:-ROFD in Km 2/850 to 2/870 and 3/030 to 3/060 to 3/165) MNP.	155884/-	3500/-	Three Month	Rs.350/-

Certificate:- It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.

4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW (B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right any or all the tenders without assigning any reason.
12. The tender document shall be issued to only those contractors who submit registration of GST No.


 Executive Engineer
 HPPWD Division Sarahan
 Distt Sirmour HP
 on behalf of Governor of Himachal Pradesh
 Tel. No. 01799-221023 Mail.

No.PW/SRN/Estt-Tender/2022-23- 636-56
Copy forwarded for information and necessary action to:-

Dated:- 8-5-23

1. The Engineer-in-Chief, HP.PWD.Shimla-171002.
2. The Chief Engineer (South) HP.PWD.Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental wesite please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


 Executive Engineer,
 Sarahan B&R Division,
 HP.PWD. Sarahan.

Estimated cost:-Rs. 4,56,380/-
Earnest money:- Rs. 9500/-
Time Limit:- Three Months

Time Limit: - Three Months.

DNIT No.	For the year 2023-24
Draft Schedule of Quantity approved for Rs.	

Executive Engineer
Sarahan Division
UD D/W Canehan

1/ page rate of DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages Macher Jabiyana Wasni Road km 0/0 to 7/160 (SH:- C/O R/Wall in km 1/150 to 1/159)

Estimated cost:-Rs. 4,84,354/-

Earnest money:- Rs. 9700/-

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	58.95	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	11436.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	96.30	Per Cubic Meter.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	454266.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	16.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	4325.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	19.44	Per Cubic Meter.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	14347.00
						484374.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

484374.00

only.


Executive Engineer
Sarahan Division
H.P. PWD, Sarahan

% age rate of DRAFT SCHEDULE OF QUANTITY

Name of work:- work A/R & M/O Banethi Bagthan Rajgarh Chandol Road 7/00 to 28/00 (SH:- Improvement of curve between km 12/00 to 18/130 & 27/00 to 28/00)

Estimated cost:-Rs.3,74,643/-

Earnest money:- Rs. 7500/-

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones,whether useful or not, for 303.37 cum (three hundred three and paise thirty seven) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1620.52	Per cubic Metre	231.19	Rupees two hundred thirty one and paise nineteen only	374643.00
						374643.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

374643.00

only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

0% oag rate of DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages BBRC Road km 7/00 to 28/00 (SH:- C/O G.I Wire Crate at RD 25/510 to 25/524)

Estimated cost:-Rs. 4,77,345/-

Earnest money:- Rs. 9600

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	70.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	13580.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of Engineer-in-transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	153.13	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	435869.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	37.80	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	27896.00
						477345.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

477345.00

only.


Executive Engineer
Saraha Division
HP, PWD, Saraha

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs 4,95,759/-
 Earnest money:- Rs. 10,000/-
 Time Limit:- Three Month.

Name of work:- C/O Macher Jabiyaana Road km 0/0 to 7/0 (SH:- P/L Interlocking Paver blocks in km 0/470 to 0/570) *scg*

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	4.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	776.00
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per cubic meter.	5819.60	Rupees Five thousand eight hundred nineteen and paise six only	46557.00
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	374.00	Per Square meter.	1199.00	Rupees One thousand one Hundred ninty nine and paise zero Only.	448426.00
						495759.00

DNIT No. For the year 23-24
 Draft Schedule of Quantity approved for Rs. 495759.00 only.

Signature
 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- work A/R & M/O Banethi Bagthan Rajgarh Chandol Road 7/00 to 28/00 (SH:- Improvement of curve between km 18/530 to 21/00)

Estimated cost:-Rs. 4,03,563/-

Earnest money:- Rs. 8300/-

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 254.46 cum (two hundred fifty four and paise forty six) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1972.45	Per cubic Metre	204.60	Rupees two hundred four and paise sixtyt only	403563.00
						403563.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

403563.00

only.


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY						
NAME OF WORK:- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION OF 19.75 m span						
RCC T- Beam Bridge over Gaithal Bajhed Mandi Kharana Road at RD 6/195 (SH:- Soil						
Investigation two pits left bank and two pits on right bank on both bridges)						
				Estimated Cost : Rs	316800.00	
				Earnest Money : Rs	6500.00	
				Time Limit	One Month	
S.No	Description of Item	Quantity	In fig.	Rate	Unit	Amount
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia (4 no bores of 11.0 m depth each) for investigation of soil rock conditions at site of work including mobilization and de- mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	44.00	7200.00	Rupees seven thousand two hundred and paise nil only	Per running meter	316800.00
					Total:-	316800.00

DNIT No. For the year 2023-24
Draft Schedule of Quantity approved for Rs. 316800.00 only.


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

Page rate of DRAFT SCHEDULE OF QUANTITY						
NAME OF WORK:- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION OF C/O 19.75 m span RCC T-Beam Bridge over Thani Thamani Tindu Kharimu Road at RD 5/555 (SH:- Soil Investigation two pits left benk and two pits on right benk on both bridges)				Estimated Cost : Rs	316800.00	
				Earnest Money : Rs	6500.00	
				Time Limit :	One Month	
S.No	Description of Item	Quantity	In fig.	In word	Unit	Amount
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia (4 no bores of 11.0 m depth each) for investigation of soil rock conditions at site of work including mobilization and de- mobiization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of comlex site of work including carriage of materials within all leads and lift as pe rthe direction of Engineer-in Charge.	44.00	7200.00	Rupees seven thousand two hundred and paise nil only	Per running meter	316800.00
					Total:-	316800.00

DNIT No. For the year 2023-24
Draft Schedule of Quantity approved for Rs. 316800.00 only.


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O Macher Jabiya Road km 0/0 to 7/0 (SH:- P/L Interlocking Paver blocks in km 0/250 to 0/350) *scsp*

Estimated cost:-Rs 4,89,165/-
Earnest money:- Rs. 10,000/-
Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	4.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	776.00
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per cubic meter.	5819.60	Rupees Five thousand eight hundred nineteen and paise six only	46557.00
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	368.50	Per Square meter.	1199.00	Rupees One thousand one Hundred ninety nine and paise zero Only.	441832.00
						489165.00

DNIT No. For the year 23-24

Draft Schedule of Quantity approved for Rs.

489165.00

only.

Paul
Executive Engineer
Sarahan Division
HP, PWD, Sarahan

1/09/2024 at DRAFT SCHEDULE OF QUANTITY

Name of work:- C/o Baru Mangarh Road km 0/0 to 3/120 (SH:- Improvement of curve between km 0/980 to 1/020)

Estimated cost:- Rs. 2,45,536/-

Earnest money:- Rs. 5000-

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 154.425 cum (one hundred fifty four and paise four two five) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1544.25	Per cubic Metre	159.00	Rupees one hundred fifty nine and paise nil only	245536.00
						245536.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

only.


Executive Engineer
Saraha Division
HP, PWD, Saraha

11

100% rate of ~~work~~ SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Bhureshwar Mahadev road km 0/0 to 2/315 (SH:- C/O R/Wall at RD 0/360 to 0/380)

Estimated cost:-Rs. 4,48,556/-
Earnest money:- Rs. 9,000/-
Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	58.40	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	11330.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	88.09	Per Cubic Meter.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	415538.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	30.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	8109.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	18.40	Per Cubic Meter.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	13579.00
						448556.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

only.

448556.00


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

10092 Role of ~~DRAFT~~ SCHEDULE OF QUANTITY

Name of work:- C/O Bantighat Bhagyanghat Road km 0/0 to 4/0 (SH:- P/L G-II at RD 1/00 to 1/800) MNP

Estimated cost:-Rs. 4,75,650/-
Earnest money:- Rs. 10000-
Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per Technical Specification Clause 405.including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	211.20	Per cubic Metre	2252.13	Rupees two thousand two hundred fifty two and paise thirteen only	475650.00
						475650.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

475650.00

only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

1/0 aq rate of ~~DRAFT~~ SCHEDULE OF QUANTITY

Estimated cost:-Rs. 1,55,884/-

Name of work:- -C/o Sikken Dinger Kinner Bhagyanghat Road km 0/0 to 9/330 (SH:- ROFD in km 2/850 to 2/870 and 3/030 to 3/060 to 3/165) MNP

Earnest money:- Rs. 3500-

Time Limit:- Three Month.


Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 98.04 cum (ninety eight point zero five) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	980.40	Per cubic Metre	159.00	Rupees one hundred fifty nine and paise nil only	155884.00
						7
						155884.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

155884.00

only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan