

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Sealed percentage /item rates tenders on PWD form 6 & 7/8 are hereby invited by the Executive Engineer H.P.P.W.D. Division Ghumarwin on behalf of Governor of Himachal Pradesh from the eligible contractors/firms of appropriate class for the following works as per detail given below. The important date of tenders are as under:-

1. Date of receipt of application for the tenders 23-5-2023
2. Date of issue/sale of tender forms = 24-5-2023

The tender which will received on **25-05-2023 up to 11.00** shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on **24-5-2023**


The Earnest Money in the shape of NSC/Deposit at call/Time Deposit/Account in any of the Post Office/Nationalized Bank in H.P. duly pledged of undersigned must accompany with each application. The conditional tenders and tenders received without earnest money will be rejected. The offer of the tender will be kept open for 90 days. The undersigned reserved the right to accept or reject the tenders without assigning any reason.

| Sr. No. | Name of Work | Estimated Cost | Earnest Money | Time Period | Cost of Tender Form. |
|---------|---|----------------|---------------|-------------|----------------------|
| 1 | Restoration of rain damage on House of Sh. Hans Raj to Pump House. (link road Boni Bani to Bani Panditan). (SH:-P/L cement concrete pavement length = 120.50 mtrs). | 490638 | 9900 | Two Months | 350/ |
| 2. | Restoration of rain damage on House of Sh. Bansi Ram to Chil Tree (Barog to Lanjta Road) (SH:-P/L cement concrete pavement length = 118.55 mtrs). | 488202 | 9800 | Two Months | 350/ |
| 3 | Restoration of rain damage on Kanchi Mod to Mango Tree. (link road to Village Lalwan) Length of Road = 60.75 Mtr.(SH:-P/L cement concrete pavement length =60.75mtrs). | 256905 | 5200 | Two Months | 350/ |
| 4 | Restoration of rain damage on Pully to house of Sh. Balvant Singh . (link road Barota to Thana) Length of Road = 126.00 Mtr.(SH:-P/L cement concrete pavement length = 126.00 mtrs). | 496485 | 10000 | Two Months | 350/ |
| 5. | Restoration of rain damage on Electric Taber to Hukam Chand Field (Link road Dehra to Markota Jahu)(SH:-P/L cement concrete pavement length = 138.40 mtrs). | 469016 | 9480 | Two Months | 350/ |
| 6 | Restoration of rain damage on Amrit Lal field to Amrit Lal field (Link road Dehra to Markota Jahu)(SH:-P/L cement concrete pavement length = 138.99mtrs). | 470952 | 9500 | Two Months | 350/ |

| | | | | | |
|----|--|----------|-------|------------|------|
| 7 | Restoration of rain damage on Desh Raj to Balbir Singh cowshed.(link road Malot to Fagat)(SH:-P/L cement concrete pavement length = 155.38mtrs). | 498544 | 10000 | Two Months | 350/ |
| 8. | Restoration of rain damage on house of Rajab khan to house of Durga Ram (link road Malot to Fagat)(SH:-P/L cement concrete pavement length = 153.53 mtrs). | 497930 | 10000 | Two Months | 350/ |
| 9. | Restoration of rain damage on pump house to kanchi mod -II (link road Bum to village Kamlu)(SH:-P/L cement concrete pavement length = 130.45mtrs). | 476055 | 9600 | Two Months | 350/ |
| 10 | Restoration of rain damage on Santosh Kumar cowshed to mango tree, Gian chand house to Mansa Ram house (link road Dehra Markota Jahu & link road to vill. Kot)(SH:-P/L cement concrete pavement length = 28.75 mtrs)ii Gian Chand House to Mansa Ram (SH:-P/L cement concrete pavement length = 42.21 mtrs). | 285011 | 5700 | Two Months | 350/ |
| 11 | Restoration of Rain Damages on House of Sh. Anil Kumar to Vermi Post . (Link road Kursai to Balh Ward No. 5) & Restoration of Rain Damages on Pump house to Bawadi . (Link road NH-103 to village Bhagunda) Length of Road = 40.20 Mtr. | 499652 | 10200 | Two Months | 350/ |
| 12 | Restoration of rain damages from Upper Padyalag Chowk to house of Sh. Sunil Kumar G.P. Padyalag Tehsil Ghumarwin Distt Bilaspur (SH :- Providing and laying cement concrete pavement essential reaches in km 0/0 to 0/104.80) | 4,99,580 | 10000 | Two Months | 350/ |
| 13 | Restoration of rain damages from G.P. School Doon to Bowari (water Tank) on link road Doon to Mata Sohani Devi G.P. Kotlu Brahmna Tehsil Ghumarwin Distt Bilaspur (Sh;- Providing and laying cement concrete pavement essential reaches in km 0/0 to 0/098) | 469035 | 9400 | Two Months | 350/ |
| 14 | Restoration of rain damages from Bowari to Chil tree on link road Doon to Mata Sohani Devi G.P. Kotlu Brahmna Tehsil Ghumarwin Distt Bilaspur (Sh :- Providing and laying cement concrete pavement essential reaches in km 0/0 to 0/096) | 4,59,463 | 9200 | Two Months | 350/ |
| 15 | Restoration of rain damages from main road Bah upto House of Sh Madan Lal on link road to SC Basti Bah G.P Gahar Tehsil Ghumarwin Distt Bilaspur (Sh :- Construction of Retaining wall at RD 0/020 to 0/041 and Breast wall at RD 0/060 to 0/072) | 4,99,335 | 10000 | Two Months | 350/ |

| | | | | | |
|----|---|----------|------|------------|-------|
| 16 | Balance work of SDM office sitting/meeting hall at Ghumarwin District Bilaspur (H.P)(SH:- P/F aluminium work of door windows and ceiling work etc.) | 398187 | 8000 | Two Months | 350/- |
| 17 | R/R of rain damages on Sanour Patta Karyalag H/Basti Churan Gugga Temple km. 0/0 to 6/095(SH;-C/o B/Wall at R.D. 3/381 to 3/392.50) | 354150 | 7100 | Two Months | 350/- |
| 18 | C/o Veterinary Hospital at Bharari Tehsil Ghumarwin Distt. Bilaspur H.P.(C/o Building Portion, W.S & S.I.) | 429569 | 9000 | Two Months | 350/- |
| 19 | R/R on link road to village Bagtheru Km. 0/0 to 1/0(SH;-C/o B/Wall in Km. 0/185 to 0/210 & U-shape drain in Km. 0/185 to 0/220) | 123257/- | 2500 | Two Months | 350/- |

1. The undersigned reserves the right to accept or reject the tenders without assigning any reasons.
2. The tender form will not be issued to those contractors whose performance is not found satisfactory.
3. G.S.T, EPF, Earnest Money, Cost of Tender & copy of enlistment should be accompanied with the application.
4. Application without documents will not be entertained.
5. Proxy application will not be entertained.
6. The Contractors should have executed two similar types of works 1/3 of each amount put to tender.
7. Tender form shall not be issued to those Contractors who have two or more works in hand.



Executive Engineer,
Ghumarwin Division,
H.P.P.W.D. Ghumarwin.

No/PW/GHD//CB/EA-I/Tender/2023- 1103-07

Dated- 8/5/2023

Copy along with NIT is forwarded to:-

1. The Engineer-in-chief HPPWD Shimla-2 for information please.
2. The Chief Engineer (HZ) HPPWD Hamirpur for information please.
3. The Superintending Engineer, 10th Circle, HPPWD Bilaspur.
4. All the Assistant Engineers working under this Division for information and necessary action.
5. Drawing Branch.
6. Account Branch.
7. Notice Board.



Executive Engineer,
Ghumarwin Division,
H.P.P.W.D. Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 4,90,638.00
 Earnest Money:- Rs. 9,900.00
 Time :- Two Month

Name of Work:- Restoration of rain damage on House of Sh. Hans Raito Pump House. (Link road Boni Bant to Bant Pandhian). (SH:-P/L cement concrete pavement length = 120.50 mtrs.)

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|----------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 385.90 | Per Cum | | | |
| 2 | Stone rolling properly hand packed filling interstices with Kharaia stone and consolidating with power road roller to the requested gradient and combber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 57.89 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for: Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.28 | Per Sqm. | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level : 1:3:6 (One Cement : three coarse sand): six graded stone aggregate 40 mm nominal size (forty millimetre) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 38.59 | Per Cum | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level : (C.C. 1:1.5:3) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 28.94 | Per Cum | | | |
| Total= | | | | | | |



Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of rain damage on House of Sh. Bansai Ram to Chil Tree (Barrow to Lantia Road) (SI:-P/L cement concrete pavement length = 118.55 mtrs).

Estimated Cost- Rs 4,88,202.00
Earnest Money- Rs 9,800.00
Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|---|----------|----------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-In-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 379.67 | Per Cum | | | |
| 2 | Stone softing properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 56.95 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for :Walls (any thickness) including attached plaster, butresses, plinth and string courses etc. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 43.57 | Per Sqm. | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : three coarse sand) : six graded stone aggregate 40 mm nominal size)(forty millimetre) The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 37.97 | Per Cum | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C/C 1:1.5:3)The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 28.47 | Per Cum | | | |
| Total= | | | | | | |


Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of rain damage on Kanchi Mod to Mango Tree, Jink road, to Village Lalwan) Length of Road = 60.75 Mtrs.)
Sr. No. **Description Item** **Quantity** **Unit** **In figure** **Rates** **In words** **Amount**

Estimated Cost:- Rs. 2,56,906.00
 Earnest Money:- Rs. 9,800.00
 Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|----------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 194.55 | Per Cum | | | |
| 2 | Stone rolling properly hand packed filling intersices with Kharanja stone and consolidating with power road roller to the requested gradient and corbber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.18 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for :Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 22.33 | Per Sqm. | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : three coarse sand): six graded stone aggregate 40 mm nominal size)(forty millimetre) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 19.46 | Per Cum | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C.C. 1:1.5:3) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 14.59 | Per Cum | | | |
| Total= | | | | | | |



Exeutive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost- Rs. 4,96,485.00
Earnest Money- Rs. 10,000.00
Time :- Two Month

Name of Work:- Restoration of rain damage on Pully to house of Sh. Balvant Singh. (link road Barora to Thana) Length of Road = 126.00 Mtr. (SH:-P/L cement concrete pavement length = 126.00 mtrs).

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------|---|----------|----------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes; octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 403.52 | Per Cum | | | |
| 2 | Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes; octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 60.53 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc. The rate includes; octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 46.31 | Per Sqm. | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : three coarse sand) : six graded stone aggregate 40 mm nominal size)(forty millimetre) The rate includes; octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 40.35 | Per Cum | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C.C. 1:1.5:3)The rate includes; octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 30.26 | Per Cum | | | |
| Total= | | | | | | |



 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of rain damage on Electric Taber to Hukam Chand Field (Link road Dehra to Markota Jahu) (SIH:-P/L cement concrete pavement length = 138.40 mtrs).

Estimated Cost:- Rs. 4,69,016.00
 Earnest Money:- Rs. 9,400.00
 Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|----------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 392.36 | Per Cum | | | |
| 2 | Stone rolling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 58.85 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for : Walls (any thickness) including attached plasters, butteresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 50.86 | Per Sqm. | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : three coarse sand) : six graded stone aggregate 40 mm nominal size) (forty millimetre) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 39.24 | Per Cum | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C.C. 1:1.5:3) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.43 | Per Cum | | | |
| Total= | | | | | | |


Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of Train damage on Amrit Lal field to Amrit Lal field (Link road Dehra to Markola Jahu) (SH:-P/L cement concrete pavement length = 138.99mtrs).

Estimated Cost- Rs. 4,70,952.00
 Earnest Money- Rs. 9,500.00
 Time :- Two Month


| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|----------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 394.04 | Per Cum | | | |
| 2 | Stone rolling property hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 59.11 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 51.08 | Per Sqm. | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : three coarse sand): six graded stone aggregate 40 mm nominal size) (forty millimetre) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 39.40 | Per Cum | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C.C. 1:1.5:3) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.55 | Per Cum | | | |
| Totals | | | | | | |


 Ex. Dy. Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

| | |
|---|---|
| Name of Work:- Restoration of rain damage on Desh Pal to Balbir Singh covered (Link road Malot to Faraq) (SH:-P/L cement concrete pavement length = 155.38mtrs). | Estimated Cost:- Rs. 4,98,544.00 |
| | Earnest Money:- Rs. 10,000.00 |
| | Time :- Two Month |

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|-----------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 440.50 | Per Cum | | | |
| 2 | Stone rolling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 33.04 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for: Walls (any thickness) including attached plasters, butresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 57.10 | Per Sqm. | | | |
| 4 | providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level.(C.C.1:4:8). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.05 | Per Cubic metre | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: (C.C.1:1.5:3).The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 33.04 | Per Cum | | | |
| Total= | | | | | | |



Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 4,97,930.00
 Earnest Money:- Rs. 10,000.00
 Time :- Two Month

Name of Work:- Restoration of rain damage on house of Rajab Khan to house of Durza Bam (link road Malot to Fagat JSH-P/L cement concrete pavement length = 153.53 mtrs).

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|-----------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 435.26 | Per Cum | | | |
| 2 | Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 32.64 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for :Walls (any thickness) including attached plasters, butresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 56.42 | Per Sqm. | | | |
| 4 | providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level.(C.C.1:4:8).The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 43.53 | Per cubic metre | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C.C. 1:1.5:3)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 32.64 | Per Cum | | | |
| Total= | | | | | | |


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work: Restoration of rain damage on pump house to kanchi mod II (Link road from to village Kamla JSH. P/L cement concrete pavement length = 124.68mtr)

Estimated Cost: Rs. 4,76,055.00
 Earnest Money: Rs. 10,000.00
 Time: Two Month


| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|--------------|--|----------|-----------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all heads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malibhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 199.29 | Per Cum | | | |
| 2 | Stone rolling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malibhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 59.89 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for: Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc. The rate includes, octroi, Malibhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 45.82 | Per Sqm | | | |
| 4 | Grouting and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (C.C.1:4:8). The rate includes, octroi, Malibhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 39.93 | Per Cubic metre | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: (C.C. 1:1.5:3) The rate includes, octroi, Malibhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.95 | Per Cum | | | |
| Total | | | | | | |


Engineer
 Construction Division
 HPPWD Channarayana

Schedule of Quantity

| Name of Work:- Restoration of rain damage on Santosh Kumar cowshed to mango tree, Gian chand house to Mansa, Ram house (Link road Dehra Markota Jahu & link road to vill, Kol 1)SH-P/L cement concrete pavement length = 28.75 mtrs; 2)Gian Chand House to mansa Ram (SH-P/L cement concrete pavement length = 42.21 mtrs). | | Estimated Cost:- Rs. 2,85,109.00 | | | | |
|--|---|----------------------------------|-----------------|-----------|----------|--------|
| | | Earnest Money:- Rs. 5,800.00 | | | | |
| Time :- | | Two Month | | | | |
| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
| | | | | In figure | In words | |
| 1 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 0 | Per Cum | | | |
| 2 | Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 0 | Per Cum | | | |
| 3 | Centering and shuttering including etc. and removal of form work for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 0 | Per Sqm. | | | |
| 4 | providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level, (C.C.1:4:8). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 10.57 | Per cubic metre | | | |

| | | | | | | |
|---|---|-------|---------|--|-------|--|
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : three coarse sand): six graded stone aggregate 40 mm nominal size (forty millimetre) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever In this respect of the same. | 13.38 | Per Cum | | | |
| 6 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C.C. 1:1.5:3)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever In this respect of the same. | 0 | Per Cum | | | |
| | | | | | Total | |


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of Rain Damages on House of Sh. Anil Kumar to Verml Post. (Link road Kusal to Balh Ward No. 5) & Restoration of Rain Damages on Pump house to Bawadi. (Link road NH-103 to village Bhaugunda) (SH:-P/L cement concrete pavement. Length of Road = 40.20 Mtr. Balh ward no -5) U-shape drain length =40 mtrs. B/wall length =10 mtrs on link road NH-103 to

Estimated Cost:- Rs. 4,99,653.00
Earnest Money:- Rs. 10,000.00
Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | In figure | | Rates | | Amount |
|---------|---|----------|-----------------|-----------|--|----------|--|--------|
| | | | | | | In words | | |
| 1 | Earth work in surface excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. Hard rock (blasting prohibited) including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 30.00 | Per Cum | | | | | |
| 2 | Stone soling properly hand packed filling interstices with Kharranja stone and consolidating with power road roller to the requested gradient and combber including spreading watering and rolling of binding materials moorum or earth etc. Complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 18.39 | Per Cum | | | | | |
| 3 | Centering and shuttering including etc. and removal of form work for: Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 124.54 | Per Sqm. | | | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (One Cement: three coarse sand): six graded stone aggregate 40 mm nominal size) (forty millimetre) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 16.40 | Per Cum | | | | | |
| 5 | Providing and laying cement concrete work 1:2:4 (One cement:two sand:four graded stone aggregate 20 mm (twenty millimeter) nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in suspended floor roofs, landing shelves and their support balconies, beams girders bressumers and cantilevers pillar posts and struts upto all floor level, including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 5.10 | Per cubic metre | | | | | |

| | | | | | |
|---|--------------|------------------------|--|---------------|--|
| <p>6 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (C.C. 1:1.5:3) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p> | <p>10.33</p> | <p>Per Cum</p> | | | |
| <p>7 Providing and Laying concrete 1:5:10 (one cement five sand:ten crushed stone aggregate) 40 mm (forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p> | <p>47.07</p> | <p>Per cubic metre</p> | | | |
| | <p>19</p> | <p>Each</p> | | <p>Total=</p> | |


Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin


Schedule of Quantity

Estimated Cost:- Rs. 4,99,580.00
Earnest Money:- Rs. 10,000.00

Time :- Two Month

Name of Work:- Restoration of rain damages from Upper Padvalaig Chowk to house of Sh. Sunil Kumar G.P. Padvalaig Tehsil Ghumarwin Distt Bilaspur (SH :- Providing and laying cement concrete pavement essential reaches in km 0/0 to 0/104.80)

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 314.40 | Per square metre | | | |
| 2 | Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge With material conforming to Grade-III (size range 53 mm to 0.075 mm (fifty three to zero point seven five millimetre) having CBR Value-20 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 47.25 | Per cubic metre | | | |
| 3 | Providing and Laying concrete 1:4:8 (one cement : four sand : eight crushed stone aggregate) (40mm forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 31.44 | Per cubic metre | | | |
| 4 | providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. (C.C.:1:1.5:3) 40 mm (forty millimetre) nominal size. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 23.58 | Per cubic metre | | | |
| Total= | | | | | | |



Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of rain damages from G.P. School Doon to Bowari (water Tank) on link road Doon to Mata Sahani Devi G.P. Kohli Brahmana Tehsil Ghumarwin Distt Bilaspur (Sh. No.)

Estimated Cost:- Rs. 4,69,035.00
Earnest Money:- Rs. 9,400.00
Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 294.00 | Per square metre | | | |
| 2 | Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-In-Charge With material conforming to Grade-III (size range 53 mm to 0.075 mm (fifty three to zero point zero seven five millimetre) having CBR Value-20 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.10 | Per cubic metre | | | |
| 3 | Providing and laying concrete 1:4:8 (one cement : four sand : eight crushed stone aggregate) (40mm forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.40 | Per cubic metre | | | |
| 4 | providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (C.C. 1:1.5:3) 40 mm (forty millimetre) nominal size. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 22.05 | Per cubic metre | | | |
| Total= | | | | | | |


Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of rain damages from Bowari to Chil tree on link road Doon to Mata Sohani Devi G.P. Kotlu Brahama Tehsil Ghumarwin Distt Bilaspur (Sh. :- Providing and laying cement concrete pavement essential reaches in km 0/0 to 0/096)

Estimated Cost:- Rs. 4,59,464.00
 Earnest Money:- Rs. 9,200.00
 Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|--|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 288.00 | Per square metre | | | |
| 2 | Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-In-Charge With material conforming to Grade-III (size range 53 mm to 0.075 mm (fifty three to zero point zero seven five millimetre) having CBR Value-20 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 43.20 | Per cubic metre | | | |
| 3 | Providing and Laying concrete 1:4:8 (one cement : four sand : eight crushed stone aggregate) (40mm forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 28.80 | Per cubic metre | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level.(C.C.1:1.5:3) 40 mm (forty millimetre) nominal size. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 21.60 | Per cubic metre | | | |
| Total= | | | | | | |

Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of rain damages from main road Bah upto House of Sh Madan Lal on link road to SC Basti Bah G.P. Gahar, Tehsil Ghumarwin Distt. Bhaspur (Sh :- Construction of Retaining wall at RD 0/020 to 0/041 and Breast wall at RD 0/060 to 0/071)

Estimated Cost- Rs. 4,99,335.00
 Earnest Money- Rs. 10,000.00
 Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------------|---|----------|-----------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all height and all lead as per Technical Specification Clause 1603.1 including carriage of material with in all leads and lifts as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 16.50 | Per Cubic Metre | | | |
| 2 | Earth work in surface excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-In-Charge. Hard rock (blasting prohibited) including carriage of material with in all leads and lifts as per the direction of Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 45.27 | Per Cubic Metre | | | |
| 3 | Providing and Laying concrete 1:5:10 (one cement: five sand: ten crushed stone aggregate) 40 mm (forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 86.15 | Per Cubic metre | | | |
| 4 | Centering and shuttering including: and removal of form work for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 94.25 | Per Sqm. | | | |
| 5 | Providing weep holes in brick masonry/plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.00 | Each | | | |
| Total= | | | | | | |

Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity


Name of Work:- Balance work of SDM office setting/ meeting hall at Chumarwin District bilaspur HP(SH:- P/F aluminium work or door windows and sillig work etc.)

Estimated Cost:- Rs. 3,98,187.00
Earnest Money:- Rs. 8,000.00
Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------|--|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | <p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitted and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p> | 197.81 | Per KG | | | |
| | <p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitted and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p> | 87.97 | Per KG | | | |
| 2 | <p>Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p> | 15.48 | Per Square metre | | | |
| 3 | <p>Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/ pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment); The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p> | 32.04 | Per KG | | | |

| | | | | | | |
|----|--|--------|------------------|--|--|--|
| 4 | Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge With cement mortar 1:4 (1 cement : 4 fine sand). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.21 | Per Square metre | | | |
| 5 | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhat, architrave, holdfasts etc. complete and stacking within 50 metres lead of area 3 sq. metres and below. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | Each | | | |
| 6 | Providing and fixing GI Clip in Metal Ceiling System of 600x600 mm module which includes providing and fixing 'C' wall angle of size 20x30x20 mm made of 0.5 mm thick pre painted steel along the perimeter of the room with help of nylon sleeves and wooden screws at 300 mm center to center, suspending the main C carrier of size 10x38x10 mm made of G.I steel 0.7 mm thick from the soffit with help of soffit cleat 37x27x25x1.6 mm, rawl plugs of size 38x12 mm and C carrier suspension clip and main carrier bracket at 1000 mm c/c. Inverted triangle shaped Spring Tee having height of 24 mm and width of 34 mm made of GI steel 0.45 mm thick is then fixed to the main C carrier and in direction perpendicular to it at 600 mm centers with help of suspension brackets. Wherever the main C carrier and spring T have to join, C carrier and spring T connectors have to be used. All sections to be galvanized @ 120 gms/sqm (both side inclusive), fixing with clip in tiles into spring T with GI Metal Ceiling Clip in plain Beveled edge global white color tiles of size 600x600 and 0.5 mm thick with 25 mm height. made of GI sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 63.24 | Per Square metre | | | |
| 7 | Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 166.94 | Per Square metre | | | |
| 8 | Providing and Fixing ECO- 5000 series mesh shutter should be provided with stainless steel 32 gauge fly mesh of 304 grades with 144 holes per square inch complete. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7.20 | Per Square metre | | | |
| 9 | Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (Best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.00 | Each | | | |
| 10 | Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150x10 mm. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 48.00 | Each | | | |

| | | | | | | |
|----------------|--|-------|--------|--|--|------------------|
| 11 | Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 6.00 | Each | | | |
| ii | Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 mm. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 24.00 | Each | | | |
| 12 | Providing and fixing bright finished brass hard drawn hooks and eyes : 100 mm. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 24.00 | Each | | | |
| 13 | Providing and fixing machine moulded aluminium covering of approved pattern & design, made out of machine cut aluminium sheet and machine holed for receiving dash fastener, over expansion joints on vertical surfaces/ceiling floors, the fixing on plate in one row on one side of joint only shall be done with stainless steel dash fasteners of 8 mm dia and 75 mm long bolt including providing aluminium washers 2 mm thick & 15 mm dia, at a staggered pitch of 200mm centre to centre including drilling holes in the receiving surface and providing expandable plastic sleeves in holes etc. complete as per direction of Engineer-in-charge. Powder coated aluminium sheet 2.5mm thick (minimum thickness of powder coating 50 micron) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 42.00 | Per KG | | | |
| Total:- | | | | | | 398187.00 |



 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- R / R of rain damages on Sanour Patta Karyalag H/Basti Churan Gugga Temple km 0/00 to 6/095 (SH:- C/O B/wall at RD 3/381 to 3/392.50

Estimated Cost:- Rs. 3,54,150.00
 Earnest Money:- Rs. 7,100.00
 Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|----------------|---|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soils as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same | 23.46 | Per cubic metre | | | |
| 2 | Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 39.10 | Per square metre | | | |
| 3 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimeter) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 64.23 | Per cubic metre | | | |
| 4 | Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre), dia PVC pipe extending through the full width of the structures with slope of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614.709.1204.3.7. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 21.00 | Each | | | |
| 5 | Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification clause 1204.3.8 with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 16.56 | Per cubic metre | | | |
| Total:- | | | | | | |


Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Name of Work: Construction of Veterinary Hospital at Bharat, Tehsil Chumarwin District Bhalaspur HP (SH: Construction of building portion and WS & SD.

Estimated Cost: Rs. 4,29,569.00
 Earnest Money: Rs. 9,000.00
 Time: Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------|--|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Centering and shuttering including strutting, propping etc. and removal of form for suspended floors, roofs, landings, balconies and access platform all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 54.01 | Per cubic metre | | | |
| ii | Edges of slabs and breaks in floors and walls under 20 cm wide all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 27.38 | Per cubic metre | | | |
| ii | Reinforced cement concrete work in walls (any thickness), including attached pillars, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement 1:1.5:3 (1 cement, 1.5 coarse sand) 3 graded stone aggregate 20 mm nominal size all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7.35 | Per cubic metre | | | |
| 2 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 715.30 | Per KG | | | |
| 3 | Providing and fixing panelled or panelled and glazed shutters for doors, windows and de-roostery windows fixing with butt hinges of required size with necessary screws, excluding paneling which will be paid for separately, all complete as per direction of Engineer-in-charge. Second class Deodar wood all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 12.36 | Per Square Metre | | | |
| 4 | Providing and fixing wire gauge shutters using galvanized MS wire gauge of average width of aperture 14 mm in both directions with wire of dia 0.63 mm, for doors, windows and de-roostery windows with hinges and necessary screws. Second class Deodar wood all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 10.56 | Per Square Metre | | | |
| 5 | Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete. 300 x 16 all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | Each | | | |
| 6 | Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed to required colour or shade, with necessary screws etc. complete. 250 x 10 all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Each | | | |
| 7 | Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed to required colour or shade, with necessary screws etc. complete. 125 mm all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 52.00 | Each | | | |
| 8 | Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed to required colour or shade, with necessary screws etc. complete. 125 mm all leads and lifts and other incidentals. The rate includes, octroi, Malikhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 6.00 | Each | | | |

| | | | | | | |
|----|---|--|--------|------------------|--|--|
| ii | 100 mm (Hundred millimetre) | | 34.00 | Each | | |
| 9 | Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Single Rubber stopper all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 2.00 | Each | | |
| 10 | Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings / wooden frames with rawl plugs screws etc. all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 181.15 | Per KG | | |
| 11 | 6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand) all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 43.77 | Per Square Metre | | |
| 12 | 15 mm cement plaster on the ruff side of single or half brick wall of mix cement mortar:1:6 (1 cement: 6 fine sand) all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 65.98 | Per Square Metre | | |
| 13 | 15 mm cement plaster on the ruff side of single or half brick wall of mix cement mortar:1:4 (1 cement : 4 fine sand) all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 47.47 | Per Square Metre | | |
| 14 | Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 2.63 | Per Square Metre | | |
| 15 | Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc. complete all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 40.17 | Per Square Metre | | |
| 16 | Providing and laying Ceramic glazed floor tiles IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 10.97 | Per Square Metre | | |
| 17 | Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes, 110 mm dia. all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 12.00 | Per RMT | | |
| 18 | Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, 100 mm all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 4.00 | Each | | |
| 19 | White washing with lime to give an even shade New work (three or more coats) all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | 43.77 | Per Square Metre | | |

| | | | | | |
|----|--|---------|------------------|--|--|
| 20 | Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 113.45 | Per Square Metre | | |
| 21 | Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 9.97 | Per Square Metre | | |
| 22 | Applying priming coat. With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 45.76 | Per Square Metre | | |
| 23 | Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 45.76 | Per Square Metre | | |
| 24 | Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required. White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Each | | |
| 25 | Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required. White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | Each | | |
| 26 | Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) 32 mm nominal bore. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Each | | |
| 27 | Providing and fixing toilet paper holder. C.P. brass. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Each | | |
| 28 | Providing and fixing charonium plated brass soap dish with brackets fixed to wooden cleats with C.P. Brass screws including all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Each | | |
| 29 | Providing and fixing brass bib cock of approved quality. 15 mm nominal bore. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Each | | |
| 30 | Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS: 12701, marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1000.00 | Per | | |
| 31 | | | | | |

| | | | | | | |
|----------------|---|-------|------------------|--|--|-------------|
| 32 | Providing and fixing G.I. pipes complete with G.I. fittings and clamps, 1/c cutting and making good the walls etc:15 mm dia nominal bore. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 15.00 | Per RMT | | | |
| 33 | Providing and fixing unplasticised PVC connection pipe with brass unions 30 cm length 15 mm dia nominal bore. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Each | | | |
| 34 | Providing and fixing 15mm galvanised iron M1 union or following size complete 25 mm nominal size. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.00 | Each | | | |
| 35 | Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement:4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), 1/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick, finished with a floating coat of neat cement complete as per standard design With common burnt clay F.P.S.(non modular) bricks of class designation 7.5. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 19.38 | Per Square metre | | | |
| 36 | and Government shall not entertain any claim whatsoever in this respect of the same. Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone - II) : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | | | |
| Total:- | | | | | | 0.00 |



Executive Engineer
 Ghumarwin Division
 HPPVWD, Ghumarwin

Schedule of Quantity

Name of Work:- R/R damages on link road to village Bhagtheru km 0/0 to 1/00 (SH-C/o B/wall in km 0/185 to 0/210 and U-shape drain in km 0/155 to 0/220)


| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---|---|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| Estimated Cost:- Rs. 1,23,257.00 Earnest Money:- Rs. 2,500.00 Time :- One Month | | | | | | |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 21.22 | Per cubic metre | | | |
| 2 | Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillers, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 45.00 | Per square metre | | | |
| 3 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work up to plinth level 1:3:6 (1 cement :3 course sand) 6 graded stone aggregate 20 mm nominal size including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 4.72 | Per cubic metre | | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 13.75 | Per cubic metre | | | |

| | | | | | | |
|----------------|--|-------|------|--|--|--|
| 5 | Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614.709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 23.00 | Each | | | |
| Total:- | | | | | | |


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

CERTIFICATE.

Certified that the tenders called vide this office NIT No.PW/GHD/CB/EA-I/tender/2023-1103-07 dated 08-5-2023 are of urgent nature and in the large interest of public.


Executive Engineer,
Ghumarwin Division,
H.P.P.W.D. Ghumarwin.