



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 08/05/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 06/05/2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Repair and Maintenance of various Govt. Non-Residential building under HPPWD Division NO. II HPPWD Bilaspur (HP) (SH:- Providing and fixing internet wiring in Bilaspur Division No. II Bilaspur (HP))	Rs. 79,075/-	Rs. 1,600/-	Rs. 350/-	One Month
2	Restoration of Rain damages on CMM NH-205 (Old NH-21) in Km. 86/0 to 127/0 (SH:- Hiring of Excavator cum loader/JCB and tractor with trolley for removal of slips, clearing of road side drain and dressing of berms at RD 105/0 to 116/0) for the year 2023-24 Job No. 1	Rs. 99,616/-	Rs. 2,000/-	Rs. 350/-	One Month
3	Restoration of Rain damages on CMM NH-205 (Old NH-21) in Km. 86/0 to 127/0 (SH:- Hiring of Excavator cum loader/JCB and tractor with trolley for removal of slips, clearing of road side drain and dressing of berms at RD 116/0 to 127/0) for the year 2023-24 Job No. 2	Rs. 99,616/-	Rs. 2,000/-	Rs. 350/-	One Month
4	Restoration of Road damages on Kutehla Kairyan Bagchhal road Km. 0/0 to 10/815 (SH:- Road widening from RD 10/675 to 10/765 on Swarghat side approach of Bagchhal Bridge) Deposit work	Rs. 4,04,802/-	Rs. 8,100/-	Rs. 350/-	Three Month
5	Restoration of Road damages on Kutehla Kairyan Bagchhal road Km. 0/0 to 10/815 (SH:- Road widening from RD 10/765 to 10/775 on Swarghat side approach of Bagchhal Bridge) Deposit work	Rs. 4,34,634/-	Rs. 8,700/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.

5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

**Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.**

No.PW/NBT/CB/Tender-State/EA-1/2023- 655-61

Dated:- 29/04/2023

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

**Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.**

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs.79075/-only

Earnest Money:Rs 1600/-only

Time allowed:-One Month

Name of work: :-Repair & Maintenance of various Govt Non-Residential building under HPPWD Division No II HPPWD Bilaspur(HP)(SH):- Providing and fixing Internet wiring in Bilaspur Division NO.II Bilaspur(HP).

Sr. No	Description of item	Quantity	Unit	Rate in		Amount
				figures	Word.	
1	Supplying and Drawing UTP 4pair Cat 6 lan cable in the existing surface /recessed,steel /PVC conduit as required of make ISI Marked /D -Link or its equivalent as approved by Engineer-In Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	375.00	per Meter			
2	Supplying and Fixing Switch 8 port Gigabyte 10/1000 MBPS connect up to 5 devices to extend office Net work as required of make ISI Marked /D -Link or its equivalent as approved by Engineer-In Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	No			
3	Supplying and Fixing Switch 4port Gigabyte 10/1000 MBPS connect up to 8 devices as required of make ISI Marked /D -Link or its equivalent as approved by Engineer-In Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	No			
4	Supplying and fixing AIO Box Cat 6 size of make ISI Marked /D -Link or its equivalent as approved by Engineer-In Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	No			
5	Supplying and fixing Rack 9U with power switch make ISI Marked /D -Link or its equivalent as approved by Engineer-In Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	No			
6	Providing Installing & fitting charges including (Switch/Aio Box,Rack/pipe screw etc. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	1 Job			
Total:-						

Executive Engineer,
Bilaspur Division No. II
HPPWD, Bilaspur

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=99,616 /-Only.	
						Earnest Money:- Rs.= 2,000/-	
						Time:- one Months.	
Name of work :- Restoration of Rain Damages on CMM road NH-205 (old NH-21) in km 86/00 to 127/00 (SH:-Hiring of Excavator cum loader/JCB and tractor with trolley for removal of slips , clearing of road side drain and dressing of berms at Rd 105/00 to 116/00)For the Year 2023-24 Job No.-1							
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
		4		5			6
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	88.00	Hours			Per Hours	
2	Providing one number tractor with trolley in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge .The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	88.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer,
Bilaspur Division No. 8
H.P. P.O., Bilaspur (P.)
Bh

SCHEDULE OF QUANTITY.			Estimated Cost:- Rs.=99,616 /-Only.			
			Earnest Money:- Rs.= 2,000/-			
			Time:- one Months.			
Name of work :- Restoration of Rain Damages on CMM road NH-205 (old NH-21) in km 86/00 to 127/00 (SH:-Hiring of Excavator cum loader/JCB and tractor with trolley for removal of slips , clearing of road side drain and dressing of berms at Rd 116/00 to 127/00)For the Year 2023-24 Job No.-2						
Sr No.	Description of items.	Quantity		Rate In	Unit	Amount
				In Figure	In words.	
1	3	4		5		6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	88.00	Hours		Per Hours	
2	Providing one number tractor with trolley in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge . The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	88.00	Hours		Per Hours	
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
i)	The tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Bilaspur Division No. H
HPPWD, Bilaspur(H.P.)
BK

SCHEDULE OF QUANTITY.

Name of Work:-Restoration of Road damages on Kutehla Kariyan Bagchhal Road Km 0/0 to 10/815 (SH:- Road widening from RD 10/675 to 10/765 on swarghat side approach of Bagchhal Bridge) Deposit Work.				Estimated Cost:-		404802.00
				Earnest Money:- Rs.		8100.00
				Time:-		One Month.
Sr. No	Description of Item	Quantity	Rates in		Unit	Amount
			Figure	words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification,2014 Clause 300, 302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all useful /surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and execution shall be absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-Charges including carriage of materials within all leads and lifts.The rate including octori,royalty , Malkana , toll tax, sale tax,Goods services tax or other taxes imposed by the Govt. A recovery of useful stone for 161.25 Cum (one hundred sixty one point two five). Cubic metre at the rate of Rs.300/- (Rs. Three hundred) only shall be done on pro-rate basis in each running bill for this item including carriage of materials in all leads lifts as per the direction of the Engineer-in-Charge.	483.75			Per cubic metre	
Total:-						

Executive Engineer,
 Bilaspur Division No. 11
 B.P.O., Bilaspur P.

SCHEDULE OF QUANTITY.

Name of Work:-Restoration of Road damages on Kutehla Kariyan Bagchhal Road Km 0/0 to 10/815 (SH:- Road widening from RD 10/765 to 10/775 on swarghat side approach of Bagchhal Bridge) Deposit Work.			Estimated Cost:-		434634.00	
			Earnest Money:- Rs.		8700.00	
			Time:-		One Month.	
Sr. No	Description of Item	Quantity	Rates in		Unit	Amount
			Figure	words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification, 2014 Clause 300, 302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all useful /surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and execution shall be absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-Charges including carriage of materials within all leads and lifts.The rate including octroi,royalty , Malkana , toll tax, sale tax,Goods services tax or other taxes imposed by the Govt. A recovery of useful stone for 173.13 Cum (one hundred seventy three point one three). Cubic metre at the rate of Rs.300/- (Rs. Three hundred) only shall be done on pro-rate basis in each running bill for this item including carriage of materials in all leads lifts as per the direction of the Engineer-in-Charge.	519.40			Per cubic metre	
		Total:-				

Executive Engineer,
Mazapur Division No. 11
P. P. D., Balespuri P.