

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/KB/CB/Tender/2023-24
To

251-53


Dated: 01-05-2023

The Executive Engineer (IT Cell)
Nigam Bihar Shimla- 2

Subject:- **Publication of tender Notice.**

Enclosed please find herewith the tender Notice of works as given in the Notice inviting tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3) 1/2020 dated: Shimla -2 the 16th July 2021 as the works mentioned in the tender notice are urgent in nature and public interest.

DA/As above


Executive Engineer,
HP PWD Division,
Kotla Behar.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. The Computer Cell O/o Executive Engineer , (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
HP PWD Division,
Kotla Behar.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated **12.05.2023 up to 10.30AM** and the same will be opened on the same day at **11.30 AM** in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to **2.00 PM** on dated **10.05.2023** and tender forms can be obtained from this office against cash payment (nonrefundable) on **11.05.2023** from **10.00 AM** to **5.00 PM** and no tender form shall be issued by the post. The amount of earnest money in shape of **FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar**

The conditional tender and tender received without **earnest money** (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 0/740 to 0/754, 0/850 to 0/858) (Deposit work).	371335.00	80000.00	Two Month	350/-	6&8
2	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/100 to 1/114 & 1/190 to 1/198) (Deposit work).	495526.00	10000.00	Three Month	350/-	6&8
3	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/810 to 2/843 & 2/940 to 2/956) (Deposit work).	498482.00	10000.00	Three Month	350/-	6&8
4	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/300 to 2/320 & 2/800 to 2/810) (Deposit work).	422447.00	9000.00	Three Month	350/-	6&8
5	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/060 to 2/095 & 2/860 to 2/872) (Deposit work).	315706.00	7000.00	Two Month	350/-	6&8
6	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/010 to 1/020 to 1/910 to 1/930) (Deposit work).	411127.00	9000.00	Three Month	350/-	6&8
7	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/200 to 2/220) (Deposit work).	352550.00	7000.00	Two Month	350/-	6&8
8	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 0/390 to 0/418.50) (Deposit work).	496429.00	10000.00	Three Month	350/-	6&8
9	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/510 to 1/525 & 1/470 to 1/480) (Deposit work).	327762.00	7000.00	Two Month	350/-	6&8
10	Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/410 to 1/419 & 1/450 to 1/465) (Deposit work).	330343.00	7000.00	Two Month	350/-	6&8
11	Periodic renewal on Kaloha Dhaliara Dadasiba Sansarpur Terrace road road Km. 22/200 to 60/920 (SH:- Providing and Laying Interlocking Paver Block at RD. 27/500 to 27/556).	497679.00	10000.00	Three Month	350/-	6&8
12	Periodic renewal on Kaloha Dhaliara Dadasiba Sansarpur Terrace road road Km. 22/200 to 60/920 (SH:- Construction of Drain, Parapet, Catch pit & CC at Various RD's).	334968.00	7000.00	Two Month	350/-	6&8
13	Restoration of Rain damage on Baldhar Chatwal Landiara road Km 0/0 to 3/750 (SH:- R/wall at RD. 0/330 TO 0/342).	116888.00	3000.00	Two Month	350/-	6&8
14	C/o Chaplah to Sard Dogri via Ladoa road Km.. 0/0 to 7/00 (SH:- C/o CC Pavement at RD. 3/630 to 3/710).	493520.00	10000.00	Three Month	350/-	6&8
15	C/o Chaplah to Sard Dogri via Ladoa road Km.. 0/0 to 7/00 (SH:- C/o CC Pavement at RD. 4/00 to 4/080).	499620.00	10000.00	Three Month	350/-	6&8
16	C/o Sehri to Kabirpanthi Basti Sehri Km. 0/0 to 1/00 (SH:- C/o CC Pavement at RD. 0/120 to 0/252).	496570.00	10000.00	Three Month	350/-	6&8
17	C/o Baliana to Lohara Basti Ward No. 5 in GP Baliana Km. 0/0 to 1/00 (SH:- C/o CC Pavement at RD. 0/610 to 0/690).	499620.00	10000.00	Three Month	350/-	6&8

18	C/o Link road main road to Rana Basti via lotus International Convent School Rakker at Kaloha Km. 0/0 to 1/00 (SH:- Formation cutting & P/L Interlocking Paver Block at RD. 0/650 to 0/750).	484211.00	10000.00	Three Month	350/-	6&8
19	Periodic renewal on Bharwain Chintpurni Kandrori Damtal Km. 17/0 to 23/0 (SH:- Construction of Drain , Parapet & CC at Various RD's).	334968.00	7000.00	Two Month	350/-	6&8
20	C/o Link road from Upper Darb to lower Darb (SH:- C/o Retaining wall at Various RD's) (Under OTMNP).	496429.00	10000.00	Three Month	350/-	6&8
21	C/o link road from Nichla Swana (Pardhan Nali) to Rajput Basti Near Kul Mandir Dehria Km. 0/0 to 0/900 (SH:- Const. of 600 mm dia Hume pipe culvert & C/o Retaining wall) (Under OTMNP).	457017.00	10000.00	Three Month	350/-	6&8
22	Imrpovement & widening of Dehra Ghatti to village Bari road Km. 0/0 to 2/495 (SH:- Const. of Retaining wall at Various RD's).	362415.00	8000.00	Two Month	350/-	6&8
23	Balance work construcion of Health Institution Level-III Building at Dadasiba, Tehsil Dadasiba, Distt. Kangra HP (SH:- Providing and fixing Cupboard work Etcetra)	480297.00	10000.00	Three Month	350/-	6&8
24	C/o Link road from Upper Darb to lower Darb (SH:- Const. of 900 mm dia Hume pipe culvert i/c approaches) (Under OTMNP)..	462017.00	10000.00	Three Month	350/-	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER/ 2023

254 - 57

DATED 01-05-2023

information please.

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar.

Estimate Cost :- Rs. 371335.00

Earnest Money :- Rs. 8000.00

Time Limit :- Two Month.

SCHEDULE OF QUANTITY

Const. of R/wall at RD. 0/740 to 0/754, 0/850 to 0/858) (Deposit

Name of work:- Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:-

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	44.74 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical Specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	97.40 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	60.00 Number			Each	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.					
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPRWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 2

Estimate Cost :- Rs. 495526.00

Earnest Money :- Rs. 10000.00

Time Limit :- Three Month.

Name of work:- Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/100 to 1/114 & 1/190 to 1/198) (Deposit work).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	63.14 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	130.02 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	29.04 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3, 7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	84.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- Restoration of damages due to OFC on Didian Guralia road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/810 to 2/843 & 2/940 to 2/956) (Deposit work).

JOB NO. 3

Estimate Cost :- Rs. 498482.00

Earnest Money :- Rs. 10000.00

Time Limit :- Three Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	60.15 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	133.13 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	31.14 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3, 7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	44.00 Number			Each	
TOTAL						


Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/300 to 2/320 & 2/800 to 2/810) (Deposit work).

JOB NO. 4
Estimate Cost :- Rs. 422447.00
Earnest Money :- Rs. 9000.00
Time Limit :- Three Month.

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	51.10 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	111.10 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	28.80 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	53.00 Number			Each	
TOTAL						


Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

JOB NO. 5

Estimate Cost :- Rs. 315706.00

Earnest Money :-Rs. 7000.00

Time Limit :- Two Month.

Name of work:- Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/060 to 2/095 & 2/860 to 2/872) (Depos work).

SCHEDULE OF QUANTITY

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	37.85 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement is to five sand is to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical Specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	83.19 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	22.56 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical is to twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709.1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	33.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 6

Estimate Cost :- Rs. 411127.00

Earnest Money :-Rs. 9000.00

Time Limit :- Three Month.

work).

Name of work:- Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/010 to 1/020 to 1/910 to 1/930) (Deposit

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	53.70 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical Specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	107.40 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	27.00 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	63.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 7

Estimate Cost :- Rs. 352550.00

Earnest Money :-Rs. 7000.00

Time Limit :- Two Month.

Name of work:- Restoration of damages due to OFC on Didian Guralia road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 2/200 to 2/220) (Deposit work).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	48.00 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	93.40 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	21.60 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.7/09,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	39.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD, Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 0/390 to 0/418.50) (Deposit work).

JOB NO. 8

Estimate Cost :- Rs. 496429.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	60.27 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	130.00 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	34.20 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	69.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 9

Estimate Cost :- Rs. 327762.00

Earnest Money :- Rs. 7000.00

Time Limit :- Two Month.

Name of work:- Restoration of damages due to OFC on Didian Guralia road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/510 to 1/525 & 1/470 to 1/480) (Deposit work).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	42.60 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	86.00 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	21.00 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	47.00 Number			Each	
TOTAL						

Executive Engineer,
Kota Behar Division,
HPPWD Kota Behar.

SCHEDULE OF QUANTITY

Name of work:- Restoration of damages due to OFC on Didian Guralla road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 1/410 to 1/419 & 1/450 to 1/465) (Deposit work).

JOB NO. 10
Estimate Cost :- Rs. 330343.00
Earnest Money :- Rs. 7000.00
Time Limit :- Two Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	42.96 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	85.92 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	21.60 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	57.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

Estimate Cost :- Rs.4,97,679.00
Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

SCHEDULE OF QUANTITY

Name of work:- Periodic renewal on Kaloha Dhaliara Dadasiba Sansarpur Terrace road road Km. 22/200 to 60/920 (SH:- Providing and Laying Interlocking Paver Block at RD. 27/500 to 27/556).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Scarifying the existing bituminous road surface by mechanical means upto 150mm (One hundred fifty millimetre) depth and disposal of scarified material within all leads and lifts as per MORD specification clause 301.4 complete in all respect and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	291.20 Square metre			Per square metre	
2	Earth work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction and entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during dewatering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.02 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	11.02 Cubic metre			Per Cubic metre	
4	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	28.81 Cubic metre			Per Cubic metre	

5	Providing and laying of inter locking concrete paver blocks make of NTC/NTCO/HPPWD approved having thickness 80mm (eighty millimeter) Grade M-40 IS Code-15658:2006 and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	288.08 Square metre				Per square metre	
TOTAL							


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- Periodic renewal on Kaloha Dhaliara Dadasiba Sansarpur Terrace road road Km. 22/200 to 60/920 (SH:- Construction of Drain , Parapet , Catch pit & CC at Various RD's).

JOB NO. 12
Estimate Cost :- Rs. 3,34,968.00
Earnest Money :-Rs. 7000.00
Time Limit :- Two Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction and entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during dewatering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	103.52 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundations for all Type of structure, such as Drains and the like including pumping or bailing out water/ dewatering removal of the slush which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	55.58 Cubic metre			Per Cubic metre	
	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.00 Cubic metre			Per Cubic metre	
TOTAL						

Executive Engineer,
Kotla Behar Division ,
HPPWD Kotla Behar.

Estimate Cost :- Rs. 116888.00

Earnest Money :- Rs. 3000.00

Time Limit :- Two Month.

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Baldhar Chatwal Landiara road Km 0/0 to 3/750 (SH:- R/wall at RD. 0/330 TO 0/342).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	28.26 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical Specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	31.46 Cubic metre			Per cubic metre	
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick Masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	24.00 Number			Each	
	TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB No. 14

Estimate Cost :- Rs. 4,93,520/-

Earnest Money :- Rs. 10000/-

Time Limit :- Three Months.

Name of work:- C/o Chaplah to Sard Dogri via Ladoa road Km. 0/0 to 7/00 (SH:- C/o CC Pavement at RD. 3/630 to 3/710).

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps, and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	31.00 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	31.00 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty-five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	62.00 Cubic metre			Per Cubic metre	
TOTAL						


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- C/o Chaplah to Sard Dogri via Ladoa road Km. 0/0 to 7/00 (SH:- C/o CC Pavement at RD. 4/00 to 4/080).

JOB No. 15
Estimate Cost :- Rs. 4,99,620/-
Earnest Money :-Rs. 10000/-
Time Limit :-Three Months.

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	31.00 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Melkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	31.00 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	63.00 Cubic metre			Per Cubic metre	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- C/o Sehri to Kabirpantahi Basti Sehri Km. 0/0 to 1/00 (SH:- C/o CC Pavement at RD. 0/120 to 0/252).

JOB No. 16
Estimate Cost :- Rs. 4,96,570/-
Earnest Money :-Rs. 10000/-
Time Limit :-Three Months.

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	31.00 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	31.00 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	62.50 Cubic metre			Per Cubic metre	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- C/o Baliana to Lohara Basti Ward No. 5 in GP Baliana Km. 0/0 to 1/00 (SH:- C/o CC Pavement at RD. 0/610 to 0/690).

JOB No. 17
Estimate Cost :- Rs. 4,99,620/-
Earnest Money :-Rs. 10000/-
Time Limit :-Three Months.

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto all leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	31.00 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	31.00 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	63.00 Cubic metre			Per Cubic metre	
TOTAL						


Executive Engineer,
Kotla Behar Division,
HBPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- C/O Link road main road to Rana Basti via lotus International Convent School Rakker at Kaloha Km. 0/0 to 1/00 (SH):- Formation cutting & P/L Interlocking Paver Block at RD. 0/650 to 0/750).

JOB No. 18
Estimate Cost :-Rs.4,84,211.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, width, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in-Charge complete in accordance to MORD Technical Specification section 300 & 1600 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 20.00 cubic metre quantity at the rate of Rs. 300/- only (Rupees three hundred only) per cubic meter shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	200.25 Cubic metre			Per Cubic metre	
2	Earth work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction and entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during dewatering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including Octroi, Royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	39.10 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	15.30 Cubic metre			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	23.80 Cubic metre				Per Cubic metre	
5	Providing and laying of inter locking concrete paver blocks make of NTC/NITCO/HPPWD approved having thickness 80mm (eighty millimeter) Grade M-40 IS Code-15658:2006 and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	238.00 Square metre				Per square metre	
TOTAL							



 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

Estimate Cost :- Rs. 3,34,968.00
 Earnest Money :- Rs. 7000.00
 Time Limit :- Two Month.
 at Various RD's).

SCHEDULE OF QUANTITY

Name of work:- Periodic renewal on Bharwain Chintpurni Kandrori Dantal Km. 17/0 to 23/0 (SH:- Construction of Drain , Parapet & CC at Various RD's).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction and entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during dewatering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	103.52 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundations for all Type of structure, such as Drains and the like including pumping or bailing out water/ dewatering removal of the slush which may arise at the time of laying concrete, for all heights/depts, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, GST or any other taxes imposed by the Government.	55.58 Cubic metre			Per Cubic metre	
	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty-five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.00 Cubic metre			Per Cubic metre	
	TOTAL					


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from Upper Darb to lower Darb (SH:- C/o Retaining wall at Various RD's) (Under OTMNP).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	60.27 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	130.00 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	34.20 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	69.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HARD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- C/O link road from Nichla Swana (Pardhan Nali) to Rajput Basti Near Kul Mandir Dehria Km. 0/0 to 0/900 (SH:- Const. of 600 mm dia Hume pipe culvert & C/O Retaining wall) (Under OTMNP).

JOB NO. 21

Estimate Cost :- Rs. 457017.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	63.88 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40mm (forty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (Surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	1.89 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) with minimum Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate 40mm (forty millimeter) nominal size) in Cradle bedding and toe wall etc or under water, including pumping or bailing out water/ dewatering (Surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, for foundation and plinth and concrete cradle bedding Type-A under pipe and the like, etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 clauses 1101.5 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	0.77 Cubic metre			Per Cubic metre	
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in open foundation or under water, including pumping or bailing out water/ dewatering (Surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in open foundation etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	13.88 Cubic metre			Per Cubic metre	

5	Providing and laying (to level or slope) 600mm dia (Six hundred millimeter) diameter reinforced cement concrete light duty non pressure pipes IS Class NP-2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1:2 (One cement isto two sand) but excluding the cost of excavation, protection works, back filling, pipe bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101.5 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST, toll tax, sale tax or other taxes imposed by the Government.	5.00 Running metre			Per running metre	
6	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	0.22 Cubic metre			Per Cubic metre	
7	Earth filling (for marshy soil) in foundation, trenches and the like for Earth cushion over Hume pipe culverts etcetera with Earth obtained from Approved quarry approved by Engineer-in-Charge including thoroughly watering ramming/ compacting with suitable equipment, in layers not exceeding 150mm (One Hundred fifty millimeter) in thickness complete as per MORD technical specification as per clause 305.3.9 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	4.62 Cubic metre			Per Cubic metre	
8	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in all heights/depths, in or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete, as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	102.50 Cubic metre			Per Cubic metre	
9	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	18.00 Cubic metre			Per Cubic metre	
10	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	36.00 Number			Each	
TOTAL						


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- Improvement & widening of Dehra Ghatti to village Bari road Km. 0/0 to 2/495 (SH:- Const. of Retaining wall at Various RD's).

JOB NO. 22
Estimate Cost :- Rs. 362415.00
Earnest Money :- Rs. 8000.00
Time Limit :- Two Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	40.74 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	95.00 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	23.16 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plant/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	60.00 Number			Each	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

Name of work:- Balance work construction of Health Institution Level-III Building at Dadasiba, Tehsil Dadasiba, Distt. Kangra HP (SH:- Providing and fixing Cupboard work Etcetra)

JOB NO. 23

Estimate Cost :- Rs. 480297.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and Fixing Cabinet work made of 19 mm (Nineteen milimetre) thick water proof termite proof commercial board with shutters of 19 mm (Nineteen milimetre) thick commercial board including fixing with nickle plated piano hinges with screws etc. complete as per HPPWD specifications or as per the directions of the Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	47.26			Per Square Metre	
2	Providing and fixing oxidized 100x10 mm (One Hundred into ten milimetre) MS (Mild steel) Tower Bolts (Barrel type) with the necessary screws etc. complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage or materials within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	158.00			Number	
3	Providing and laying mechanically mixed and vibrated reinforced concrete work Grade M-20 (M-twenty) design mix to obtain the minimum compressive strength of 20 N/mm ² (twenty newton) per square millimeter with minimum cement content of 320 Kg (Three hundred twenty) Kilogramme per cubic meter and curing complete including the cost of form work and reinforcement for reinforced concrete work in String courses, copings, bed plates, anchor blocks, plain windows, sills and the like complete as per HPPWD specifications or as directed By the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.99			Per Cubic Metre	
TOTAL						

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

Name of work:- C/O Link road from Upper Darb to lower Darb (SH:- Const. of 900 mm dia Hume pipe culvert i/c approaches) (Under OTMNP). (Under OTMNP).

SCHEDULE OF QUANTITY

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	63.88 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40mm (forty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depts and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	1.89 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) with minimum Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate 40mm (forty millimeter) nominal size) in Cradle bedding and toe wall etc or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depts and any quantum of water, for foundation and plinth and concrete cradle bedding Type-A under pipe and the like, etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 clauses 1101.5 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	0.77 Cubic metre			Per Cubic metre	
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in open foundation or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depts and any quantum of water, in open foundation etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	13.88 Cubic metre			Per Cubic metre	

5	Providing and laying (to level or slope) 900mm dia (Nine hundred millimeter) diameter reinforced cement concrete light duty non pressure pipes IS Class NP-2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1:2 (One cement isto two sand) but excluding the cost of excavation, protection works, back filling, pipe bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101.5 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST, toll tax, sale tax or other taxes imposed by the Government.	5.00 Running metre	Per running metre	
6	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depts and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	0.22 Cubic metre	Per Cubic metre	
7	Earth filling (for marshy soil) in foundation, trenches and the like for Earth cushion over Hume pipe culverts etcetera with Earth obtained from Approved quarry approved by Engineer-in-Charge including thoroughly watering ramming/ compacting with suitable equipment, in layers not exceeding 150mm (One Hundred fifty millimeter) in thickness complete as per MORD technical specification as per clause 305.3.9 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	4.62 Cubic metre	Per Cubic metre	
8	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in all heights/depts, in or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depts and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete, as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	102.50 Cubic metre	Per Cubic metre	
9	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	18.00 Cubic metre	Per Cubic metre	
10	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	36.00 Number	Each	
TOTAL				


 Executive Engineer,
 Kotla Behar Division,
 HBPWD Kotla Behar.

Certificate

Cetified that the tenders called vide this office letter No. PWD/KB/CB/ TENDER/
2023 251 - 53 Dated: 01-05-23 is emergent nature and in public interest.

Executive Engineer,
HP PWD Division,
Kotla Behar.