



E-Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 05/06/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 03/06/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Periodical renewal on various road under Namhol Sub Division (SH:- Providing and laying Bituminous concrete 30mm thick on link road Namhol to HPPWD Rest House Km. 0/0 to 0/315)	Rs. 4,82,156/-	Rs. 9,700/-	Rs. 350/-	Three Month
2	Periodical renewal on various road under Namhol Sub Division (SH:- Providing and laying Bituminous concrete 30mm thick on link road Namhol to HPPWD Rest House Km. 0/315 to 0/360)	Rs. 1,64,599/-	Rs. 3,300/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2023-

1483-91

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

Dated:- 27/05/2023

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs. 4,82,156/-Only.						
Earnest Money :- Rs. 9,700 /- only						
Time:- Three Months.						
NAME OF WORK:- Periodical Renewal on various road under Namhol Sub Division (SH:- Providing and Laying Bituminous concrete 30 mm thick on link road Namhol to HPPWD Rest House km 0/00 to 0/315)						
Sr No.	Description of items.	Quantity		Rates in		Amount
				Figure.	Words.	
1	2	3	4	5	6	7
1	Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting bitumen emulsion. On W.B.M / W.M.M. @ 0.4kg/sqm(zero point four kilogramme per square metre including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1159.05	Square metre.		Per Square metre.	
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and key aggregates and rolling with a three wheel 80-100 KN static roller to achieve the desired degree of compaction as per Technical Specification,2004Clause 506, 50 mm (Fifty millimetre) thick with bitumen V.G-10)(Viscosity grade ten).including carriage of materials, within all leads , lifts and other incidentals as per direction of Engineer-in-charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.95	Square metre.		Per Square metre.	
3	Providing and laying Dense Graded Bituminous Macadam using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm (Fifty to one hundred millimetre) average compacted thickness with bitumen of grade VG-30 (thirty) @ 5% (Five percent)(percentage by weight of total mix) and lime filler @ 2% (two percentage by weight of Aggregate) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.77	Cubic Metre		Per Cubic metre	
Total:-						

Executive Engineer,
Bilaspur Division No. 16
H.P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							
Estimated cost:- Rs. 1,64,599/-Only.							
Earnest Money :- Rs. 3,300 /- only							
Time:- Three Months.							
NAME OF WORK:- Periodical Renewal on various road under Namhol Sub Division (SH:- Providing and Laying Bituminous concrete 30 mm thick on link road Namhol to HPPWD Rest House km 0/315 to 0/360)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting bitumen emulsion. On W.B.M / W.M.M. @ 0.4kg/sqm(zero point four kilogramme per square metre including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	395.65	Square metre.			Per Square metre.	
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and key aggregates and rolling with a three wheel 80-100 KN static roller to achieve the desired degree of compaction as per Technical Specification,2004Clause 506, 50 mm (Fifty millimetre) thick with bitumen V.G-10(Viscosity grade ten).including carriage of materials, within all leads , lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.78	Square metre.			Per Square metre.	
3	Providing and laying Dense Graded Bituminous Macadam using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm (Fifty to one hundred millimetre) average compacted thickness with bitumen of grade VG-30 (thirty) @ 5% (Five percent)(percentage by weight of total mix) and lime filler @ 2% (two percentage by weight of Aggregate) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.87	Cubic Metre			Per Cubic metre	
Total:-							

Executive Engineer,
Bilaspur Division No. II
H.P.W.D., Bilaspur (M.P.)