

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NO:-PW/SD/CB/TA/NIT /2023- 24-

980 - 10

Dated- 18-05-2023

To

The Executive Engineer (IT Cell)  
Nigam Vihar, Shimla-2,


Subject:- Tender Notice.

Dear Sir,

Enclosed Please find herewith the notice work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP. Letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender and sechdule of quantity.

  
Executive Engineer  
B&R Division Shillai  
HP PWD Shillai

CERTIFICATE

Certified that the tenders of works, as called vide this office letter No.PW-SD-  
CB-TA 2022-23- 981-1005 dated 18-05-2023 are of urgent nature.

  
Executive Engineer  
B&R Division Shillai  
HP PWD Shillai

**Himachal Pradesh  
Public Works Department  
Notice inviting Tender**

Sealed percentage rate tender on form PWD 6 & 8 are invited by the Executive Engineer Shillai, Division HP, PWD on behalf of governor of himachal Pradesh for the following works from the approved and illgble contractors enlisted in HP PWD. So as to reach in this office as per time schedule given below.

1. **Date of receipt of application of tenders forms.:- 30-05-2023 at 10:00 AM, Up To 4:00 PM**
2. **Date of issue/ sale of tender Forms.:- 31-05-2023 at 10:00 AM, Up To 5:00 PM**
3. **Date of receipt of tender 01-06-2023 at 10:00 AM, up to 11:30 AM**
4. **Date of opening of tender:- 01-06-2023 at 12:00 PM,**

Sr. NO	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender Form	Eligible of class of Contractor
1	Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Provoding and laying 80mm thick Interlocking Concrete block from RD 28/165 to 28/265	490875.00	9900.00	One Month	350/-	C & D Class
2	Repair & Maintanance of G. S. S.S. Kaffota Teh. Kamrau Distt. Sirmour ( SH:- Repair of Placter pateche & painting etc.)	363057.00	7300.00	One Month	350/-	C & D Class
3	A/R & M/O Under Rajpur Section ( SH:-Repair of Pot holes with 20 mm PMC with seal coat on PBAT road from Km 27/00 to 34/00	497668.00	10000/-	One Month	350/-	C & D Class
4	Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Provoding and laying 80mm thick Interlocking Concrete block from RD 28/365 to 28/465	489976.00	9800.00	One Month	350/-	C & D Class
5	A/R & M/O PWD Rest Hous at Kaffota ( SH:- Construction of R/wall in Rest House Premises)	403326.00	8100.00	One Month	350/-	C & D Class
6	A/R & M/O Nagheta to Killor road Km 0/0 to 16/670 ( SH:-Repair of Pot holes with 20 mm PMC with seal coat on PDPA road from Km 3/00 to 7/00	491699.00	9900.00	One Month	350/-	C & D Class
7	Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Provoding and laying 80mm thick Interlocking Concrete block from RD 28/465 to 28/565)	494430.00	9900.00	One Month	350/	C & D Class
8	A/R & M/O Under Rajpur Section (SH:-Repair of Pot holes with 20 mm PMC with seal coat on PDPA road from Km 0/00 to 5/00 & PBAT road 23/0 to 27/00)	491014.00	9900.00	One Month	350/	C & D Class
9	Repair & Maintanance of G. S. S.S. Jamna Teh. Kamrau Distt. Sirmour ( SH:- Construction of Boundary wall, plastering , painting & P/L flooring tiles etc.)	322858.00	6500.00	One Month	350/	C & D Class

10	Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Provoding and laying 80mm thick Interlocking Concrete block from RD 28/265 to 28/365)	490173.00	9900.00	One Month	350/	C & D Class
----	---	-----------	---------	-----------	------	-------------

Terms and conditions :- The tender documents shall be issued only to these contractors firms who fulfill the following criteria and submit the following documents with the application.

1. The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
2. The contractors should quoted the rates of all the items in the tenders both in figures and words.
3. Income Tax and GST No. latest clearance certificate.
4. The contractors/firms shall accompany his enlistment /renewal and EPF submit before the award of tender.
5. The contractor should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reason.


PW-SD-CB-TA-2023-24- 981-1005

Copy forwarded for information and wide publicity to:-

1. The Superintending Engineer in 12<sup>th</sup> HP PWD in Nahan.
2. All the Assistant Engineer working under this Division.
3. A/B and D/B in this office.
- 4 Notice Board.

Executive Engineer  
B&R Division Shillai  
HP PWD Shillai

dated- 18-05-2023


  
Executive Engineer  
B&R Division Shillai  
HP PWD Shillai

SCHEDULE OF QUANTITY				Job.- 1	Estimated Cost:-490875/- Only.	
Name of work:-Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Providing and laying 80mm thick Interlocking Concrete block from RD 28/165 to 28/265				Earnest Money:- 9900/- Only Time Limit: - One Month		
Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	20.00	Per cubic metre	280.95	Rs. Two hundred eight & Ninety five paise only.	5619.00
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203.P.C.C. Grade M-10 ( Nominal mix 1:3:6 ( One cement: three sand:six graded stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	7.25	Per cubic metre	4845.80	Rs. Four thousand Eight hundred forty five & Eighty paise only.	35132.00
3	Providing Laying,spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405. W B M Grade III 53 mm(Fifty three milimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	27.00	Per cubic metre	2196.93	Rs. Two thousand One hundred ninety six & Ninety three paise only.	59317.00
4	Providing Laying,factory made chamfered edge cement concrete pever block in footpath, Parks lawns, Driver ways or light traffic parking etc, of require strength, thickness and Size and Zig Zag shape made by table vibratory method using PU mould, laind in required colour & Zig Zag pattern over 50milimetre thick compectid bed of sand, compecting by proper embedding/ laying of interlocking pever block into the sand bedding layer through vibratory compection by using plate vibrator, filling the joints with sand and cutting ogf Paver blocks as per require size and pettern finnishng and sweeping extra sand. complete all as per direction of Engineer-in-charge 80milimetre thick cement concrete paver block of M-40 grade with approved colour design and ZigZag pattern including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	310.00	Per square metre	890.80	Rs. Eight hunderd ninety & Eighty paise only.	276148.00

5	Providing concrete for Plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803, 1202 and 1203 for height upto RCC Grade M-25 (1:1.5:3) One cement :one and half sand:three crushed stone aggregate 20mm nominal size) as per the direction of Engineer Incharge.	7.02	Per cubic metre	6541.42	Rs.Six thousand Five hundred forty one & Forty two paise only.	45921.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position & binding all complete upto all floor level Thermo-Mechanically Treated bars of grade Fe-500 D or more, including all leads,lifts & carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	933.30	Per Kilogram	73.65	Rs.Seventy three & Sixty Five paise only.	68738.00
			Select:-	Plus(+)	Total	490875.00
				Minus(-)	( .....%)	
					( .....%)	

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-


  
Executive Engineer  
Shillai Division  
HP PWD Shillai

SCHEDULE OF QUANTITY					Job.- 3	Estimated Cost:-4,97,668/- Only.
Name of work:-A/R & M/O Under Rajpur Section ( SH:-Repair of Pot holes with 20 mm PMC with seal coat on PBAT road from Km 27/00 to 34/00)						Earnest Money:-10000/- Only Time Limit: - One Month
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Providing Laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 . W B M Grade III 53 mm(Fifty three milimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	51.86	Per cubic metre	2231.55	Rs. Two hundred eight & Ninety five paise only.	115728.00
2	Repair of pot holes and removal of loose material, Trimming of sides cleaning of surface by providing of tack coat 20mm ( twenty millimetre) thick primix carpet and seal coat type B specification close 1904.20including cost of bituminous 20mm (twenty millimetre) thick primix carpet and seal coat coat materials and paid for separately including all accidental Charge as per direction and entair satisfattion of the Engineer-in-Charge. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1154.77	Per cubic metre	330.75	Rs. Four thousand Eight hundred forty five & Eighty paise only.	381940.00
					Total	497668.00

Select-	Plus(+)	( .....%)
	Minus(-)	( .....%)

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

Name of work- A/R & MO PWD Rest Hous at Kattoa ( SH:-Construction of R/wall in Rest House Premises)

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Words	Figures	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	60.40	Per cubic metre	Rs. Two hundred eight & Ninety five paise only.	280.95	16969.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203.(FCC 1:6-12 nominal size) within all leads lifts, and carriage of material as per the direction of the Engineer in-charge. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.57	Per cubic metre	Rs. Three thousand eight hundred eighty two & seventy paise only.	3082.70	35667.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand: eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer in-charge.	4.70	Per cubic metre	Rs. Four thousand one hundred eighty five & thirty paise only.	4185.30	19671.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specifications Clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	53.83	Per cubic metre	Rs. Three thousand three hundred fifty five & forty five paise only.	3355.45	180624.00
5	Construction of dry rubble masonry for retaining walls, breast walls, parapets etc. for sub structure and superstructure complete as per drawing and technical specifications clause 704.6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	62.64	Per cubic metre	Rs. Two thousand one hundred fifteen & eighty five paise only.	2119.85	132787.00
6	With 100 mm dia AC pipe extending through the full width of the structures with slope of (1V):20(H) towards drawing face complete as per drawing and technical specifications Clauses 614, 709, 1204.3,7, including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	26.00	Each	Rs. Two hundred twenty five & seventy five paise only.	225.75	5870.00
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer incharge.	12.69	Per cubic metre	Rs. Nine hundred twenty five & nill paise only.	925.00	11738.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	
				Total:-		403326.00

Note:-The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-

Executive Engineer  
Shillai Division



## SCHEDULE OF QUANTITY

Sr. No.		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
Name of work:-Repair & Maintenance of G. S. S. Jamna Teh. Kamrau Distt. Sirmour (SH:- Construction of Boundary wall, plastering, painting & P/L flooring tiles etc.)							
							Estimated Cost:-3,22,858/- Only, Earnest Money:- 6500/- Only Time Limit: - One Month
1		Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	20.16	Per cubic metre	282.65	Rs. Two hundred eight two & Sixty five paise only.	5698.00
2		Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	11.34	Per cubic metre	4260.60	Rs. Four thousand Two hundred sixty & Sixty paise only.	48315.00
3		Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:3(1 cement : 3 coarse sand) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	156.90	Per cubic metre	811.10	Rs. Eight hundred eleven & ten paise only.	127262.00
4		Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4(1 cement : 4 coarse sand) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.73	Per square metre	6313.45	Rs. Six thousand three hundred thirteen & Forty five paise only.	17236.00
5		15 mm ( Fifteen millimetre) cement plaster on the rough side of single or half brick wall of mix: 1:4 (1 cement: 4 fine sand)including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	241.20	Per Square metre	190.6	Rs. One hundred ninety & Sixty paise only.	45973.00
6		Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including all leads, lifts & carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	271.20	Per Square metre	109.5	Rs. One hundred six nine & fifty paise only.	29696.00
7		Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 500x500 mm, including all leads, lifts & carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	42.25	Per Kilogram	1152.15	Rs. One thousand one hundred fifty two & fifteen paise only.	48678.00
					Total		322858.00
					Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)	

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and Name and full address of the contractor:-

*Neel*  
Executive Engineer  
Shillai Division

## SCHEDULE OF QUANTITY


Name of work:-Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Providing and laying 80mm thick Interlocking Concrete block from RD 28/365 to 28/465)		Job - 4		Estimated Cost:-490875/- Only. Earnest Money:- 9900/- Only Time Limit: - One Month		
Sr.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	16.80	Per cubic metre	280.95	Rs. Two hundred eight & Ninety five paise only.	4720.00
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203.P.C.C. Grade M-10 ( Nominal mix 1:3:6 ( One cement: three sand:six graded stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	7.25	Per cubic metre	4845.80	Rs. Four thousand Eight hundred forty five & Eighty paise only.	35132.00
3	Providing Laying,spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 . W B M Grade III 53 mm(Fifty three millimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	27.00	Per cubic metre	2196.93	Rs. Two thousand One hundred ninety six & Ninety three paise only.	59317.00

4	Providing Laying, factory made chamfered edge cement concrete paver block in footpath, Parks lawns, Driver ways or light traffic parking etc, of require strength, thickness and Size and Zig Zag shape made by table vibratory method using PU mould, laind in required colour & Zig Zag pattern over 50milimetre thick compacted bed of sand, compacting by proper embedding/ laying of interlocking paver block into the sand bedding layer through vibratory compection by using plate vibrator, filling the joints with sand and cutting ogf Paver blocks as per require size and pattern finnishng and sweeping extra sand. complete all as per direction of Engineer-in-charge 80milimetre thick cement concrete paver block of M-40 grade with approved colour design and ZigZag pattern including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	310.00	Per square metre	890.80	Rs. Eight hunder ninety & Eighty paise only.	276148.00
5	Providing concrete for Plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803, 1202 and 1203 for height upto RCC Grade M-25 (1:1.5:3) One cement :one and half sand:three crushed stone aggregate 20mm nominal size) as per the direction of Engineer Incharge.	7.02	Per cubic metre	6541.42	Rs.Six thousand Five hunder forty one & Forty two paise only.	45921.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position & binding all complete upto all floor level Thermo-Mechanically Treated bars of grade Fe-500 D or more, including all leads, lifts & carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	933.30	Per Kilogram	73.65	Rs.Seventy three & Sixty Five paise only.	68738.00
					Total	489976.00

Select:-	Plus(+)	( .....%)
	Minus(-)	( .....%)

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-


  
Executive Engineer  
Shillai Division  
HP PWD Shillai

SCHEDULE OF QUANTITY					Job.-6	Estimated Cost:- 4,91,699/- Only.
Name of work:-A/R & M/O Nagheta to Killor road Km 0/0 to 16/670 ( SH:-Repair of Pot holes with 20 mm PMC with seal coat on PDPA road from Km 3/00 to 7/00						Earnest Money:-9900/- Only Time Limit: - One Month
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Providing Laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405. W B M Grade III 53 mm(Fifty three millimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	37.99	Per cubic metre	2231.55	Rs. Two hundred eight & Ninety five paise only.	84777.00
2	Repair of pot holes and removal of loose material, Trimming of sides cleaning of surface by providing of tack coat 20mm ( twenty millimetre) thick primix carpet and seal coat type B specification close 1904.20 including cost of bituminous 20mm (twenty millimetre) thick primix carpet and seal coat coat materials and paid for separately including all accidental Charge as per direction and entair satisfattion of the Engineer-in-Charge. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1230.30	Per cubic metre	330.75	Rs. Four thousand Eight hunderd forty five & Eighty paise only.	406922.00
					Total	491699.00

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-

Select:-	Plus(+)	( .....%)
	Minus(-)	( .....%)

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - 10 Estimated Cost:-490173/- Only

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	17.50	Per cubic metre	280.95	Rs. Two hundred eight & Ninety five paise only.	4917.00
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203.P.C.C. Grade M-10 (Nominal mix 1:3:5) (One cement three sand:six graded stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	7.25	Per cubic metre	4845.80	Rs. Four thousand Eight hundred forty five & Eighty paise only.	35132.00
3	Providing Laying,spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405. W B M Grade III 53 mm(Fifty three millimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	27.00	Per cubic metre	2196.93	Rs. Two thousand One hundred ninety six & Ninety three paise only.	59317.00
4	Providing Laying,Factory made chamfered edge cement concrete paver block in footpath, Parks lawns, Driver ways or light traffic parking etc, of require strength, thickness and Size and Zig Zag pattern over 50millimetre thick compacted bed of sand, compacting by proper embedding/ laying of interlocking paver block into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting off Paver blocks as per require size and pattern finishing and sweeping extra sand. complete all as per direction of Engineer-in-charge 80millimetre thick cement concrete paver block of M-40 grade with approved colour design and Zigzag pattern including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	310.00	Per square metre	890.80	Rs. Eight hundred ninety & Eighty paise only.	276148.00

Name of work:-Special Repair of Kattoota Kot road Km 0/0 to 29/750(Sh:- Providing and laying 80mm thick interlocking Concrete block from RD 28/265 to 28/365)

Earnest Money:- 9900/- Only  
Time Limit:- One Month




**SCHEDULE OF QUANTITY**

Name of work:-A/R & M/O Under Rajpur Section (SH:-Repair of Pot holes with 20 mm PMC with seal coat on PDPA road from Km 0/00 to 5/00 & PBAT road 23/0 to 27/00)		Job:-8	Estimated Cost:-4,91,014/- Only.
		Earnest Money:-9900/- Only	Time Limit:- One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Providing Laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 . W B M Grade III 53 mm(Fifty three millimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	27.39	Per cubic metre	2231.55	Rs. Two hundred eight & Ninety five paise only.	61122.00
2	Repair of pot holes and removal of loose material, Trimming of sides cleaning of surface by providing of tack coat 20mm ( twenty millimetre) thick primix carpet and seal coat type B specification close 1904.20including cost of bituminous 20mm (twenty millimetre) thick primix carpet and seal coat coat materials and paid for separately including all accidental Charge as per direction and entair satisfation of the Engineer-in-Charge. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1299.75	Per cubic metre	330.75	Rs. Four thousand Eight hundred forty five & Eighty paise only.	429892.00
				<b>Total</b>		<b>491014.00</b>

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.


Name and full address of the contractor:-

  
**Executive Engineer**  
 Shillal Division  
 HP PWD Shillal

5	Providing concrete for Plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803, 1202 and 1203 for height upto RCC Grade M-25 (1:1.5:3) One cement :one and half sand:three crushed stone aggregate 20mm nominal size) as per the direction of Engineer Incharge.	7.02	Per cubic metre	6541.42	Rs.Six thousand Five hundred forty one & Forty two paise only.	45921.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position & binding all complete upto all floor level Thermo-Mechanically Treated bars of grade Fe-500 D or more, including all leads,lifts & carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	933.30	Per Kilogram	73.65	Rs.Seventy three & Sixty Five paise only.	68738.00
					Total	494430.00
			Select:-	Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai



SCHEDULE OF QUANTITY						Job.- 7	Estimated Cost:-4,94,430/- Only.
Name of work:-Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Providing and laying 80mm thick Interlocking Concrete block from RD 28/465 to 28/565)							Earnest Money:- 9900/- Only Time Limit: - One Month
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	16.80	Per cubic metre	280.95	Rs. Two hundred eight & Ninety five paise only.	4720.00	
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203.P.C.C. Grade M-10 ( Nominal mix 1:3:6 ( One cement: three sand:six graded stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	7.25	Per cubic metre	4845.80	Rs. Four thousand Eight hundred forty five & Eighty paise only.	35132.00	
3	Providing Laying,spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 . W B M Grade III 53 mm(Fifty three millimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	27.00	Per cubic metre	2196.93	Rs. Two thousand One hundred ninety six & Ninety three paise only.	59317.00	
4	Providing Laying,factory made chamfered edge cement concrete pever block in footpath, Parks lawns, Driver ways or light traffic parking etc, of require strength, thickness and Size and Zig Zag shape made by table vibratory method using PU mould, laid in required colour & Zig Zag pattern over 50millimetre thick compacted bed of sand, compacting by proper embedding/ laying of interlocking pever block into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting ogf Paver blocks as per require size and patten finishing and sweeping extra sand. complete all as per direction of Engineer-in-charge 80millimetre thick cement concrete paver block of M-40 grade with approved colour design and ZigZag pattern including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	315.00	Per square metre	890.80	Rs. Eight hundred ninety & Eighty paise only.	280502.00	


SCHEDULE OF QUANTITY				Job.- 7	Estimated Cost:-4,94,430/- Only.	
Name of work:-Special Repair of Kaffota Koti road Km 0/0 to 29/750(Sh:- Providing and laying 80mm thick Interlocking Concrete block from RD 28/465 to 28/565)				Earnest Money:- 9900/- Only		Time Limit: - One Month
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	16.80	Per cubic metre	280.95	Rs. Two hundred eight & Ninety five paise only.	4720.00
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203.P.C.C. Grade M-10 ( Nominal mix 1:3:6 ( One cement: three sand:six graded stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	7.25	Per cubic metre	4845.80	Rs. Four thousand Eight hundred forty five & Eighty paise only.	35132.00
3	Providing Laying,spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheeled 80-100 KN static roller in stages to proper grade and camber, applying and brooming, crushable, screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 . W B M Grade III 53 mm(Fifty three milimetre) to 22.5 mm(Twenty two point five) size ( By manual means) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	27.00	Per cubic metre	2196.93	Rs. Two thousand One hundred ninety six & Ninety three paise only.	59317.00
4	Providing Laying, factory made chamfered edge cement concrete paver block in footpath, Parks lawns, Driver ways or light traffic parking etc, of require strength, thickness and Size and Zig Zag shape made by table vibratory method using PU mould, laid in required colour & Zig Zag pattern over 50millimetre thick compacted bed of sand, compacting by proper embedding/ laying of interlocking paver block into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of Paver blocks as per require size and pattern finishing and sweeping extra sand. complete all as per direction of Engineer-in-charge 80millimetre thick cement concrete paver block of M-40 grade with approved colour design and ZigZag pattern including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	315.00	Per square metre	890.80	Rs. Eight hundred ninety & Eighty paise only.	280602.00

5	Providing concrete for Plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803, 1202 and 1203 for height upto RCC Grade M-25 (1:1.5:3) One cement :one and half sand:three crushed stone aggregate 20mm nominal size) as per the direction of Engineer Incharge.	7.02	Per cubic metre	6541.42	Rs.Six thousand Five hundred forty one & Forty two paise only.	45921.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position & binding all complete upto all floor level Thermo-Mechanically Treated bars of grade Fe-500 D or more, including all leads,lifts & carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	933.30	Per Kilogram	73.65	Rs.Seventy three & Sixty Five paise only.	68738.00
					Total	494430.00

Select:-	Plus(+)	( .....%)
	Minus(-)	( .....%)

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

SCHEDULE OF QUANTITY				Job:- 3	Estimated Cost:-363057/- Only.	
Name of work:-Repair & Maintanance of G. S. S.S. Kaffota Teh. Kamrau Dist. Sirmour ( SH:- Repair of Placter pateche & painting etc.)					Earnest Money:- 7300/- Only Time Limit: - One Month	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	15 mm ( Fifteen millimetre)cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	439.26	Per Square metre	194.10	Rs. One hundred ninety four & Ten paise only.	85260.00
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	575.52	Per cubic metre	95.75	Rs. Nine five & Seventy five paise only.	55106.00
3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	646.06	Per cubic metre	99.65	Rs. Ninety neine & Sixty five paise only.	64380.00
3	Finishing wall with water proffing cement paint of required shade . including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2212.90	Per cubic metre	71.54	Rs. Seventy one & Fifty four paise only.	158311.00
					<b>Total</b>	<b>363057.00</b>
				<b>Select:-</b>	Plus(+)	( .....%)
					Minus(-)	( .....%)

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name and full address of the contractor:-

*Narep*  
Executive Engineer  
Shillai Division  
HP PWD Shillai