



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

01899-240618, 292000

Fax No 01899-240618

E-mail- ce-dal-hp@nic.in

No. PWD-Dal/TA/Tender /2023-24- **1342-44** Dated: - **11-05-2023**

To

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.**

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie**



☎ 01899-240618, 292000
Fax No. 01899-240618
E-mail- ee-dal-hp@nic.in

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Scaled percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- | | |
|--|------------|
| 1. Date of receipt of application for the tender
Form a/w requisite documents:- | 17.05.2023 |
| 2. Date of issued/sale of tender form against
Cash payment (non refundable). | 18.05.2023 |

The tender shall be received upto 3:00 PM on 18.05.2023 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 17.05.2023.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of Rain damage on Dalhousie Jandrihat Chamba via Kohlari road km. 0/0 to 11/040 (SH: Hiring of excavator cum loader for removal of slips at various RD'S)	193483/-	3900/-	Rs. 350/-	Six Months	Class-D & C
2	Restoration of Rain damage on Banikhet Dalhousie Khajjiar road km. 15/600 to 27/0 (SH: Hiring of excavator cum loader for removal of slips at various RD'S)	148881/-	3000/-	Rs. 350/-	Six Months	...do...
3	A/R & M/O to link road to Special Research unit office Moti Tibba (SH: Providing and laying Cement Concrete pavement km. 0/0 to 0/115).	303293/-	6100/-	Rs. 350/-	Six Months	...do...
4	Repair of Veterinary Dispensary at Ruliyani Tehsil Dalhousie District Chamba H.P. (SH: Providing and Fixing vertified tiles, Ceiling and painting work).	270123/-	5500/-	Rs. 350/-	Three Months	...do...

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

[Signature]
Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Dated: - 01.05.2023

No. PWD/TA/Tender /2023-24-

Copy forwarded to the following for information and necessary action please:-

Copy forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HPPWD, Shimla.
2. All the Chief Engineer in HPPWD.
3. All SEs/EE in HPPWD.
4. All AEs/Contractor under this Division.
5. Deputy Commissioner, Chamba
6. BDO Bhattiyat.
7. Sub Divisional Magistrate/Tehsildar Dalhousie.
8. Notice Board of this office.

[Signature]
Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2023-24:- 1342-44 dated. 11-05-2023 is emergent nature and in Public interest.

4-1
Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

D.N.I.T

Estimated Cost: - Rs. 193483.00

Earnest Money :- Rs. 3900.00

Time Limit :- Six Month

(SH:- Hiring of

Name of work: - Restoration of rain damage on Dalhousie Jandrihat Chamba via Kohhari road Km. 0/0 to 11/040 (SH:- Hiring of Excavator cum Loader for removal of Slips at various RD's)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	1549.10			Per Cubic Meter	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

Executive Engineer
Dalhousie Division
H.P.P.W.D. Dalhousie

D.N.I.T

Job No. TS No. 4

Estimated Cost :- Rs.	148881.00
Earnest Money :- Rs.	3000.00
Time Limit :-	Six Month

Name of work :- Restoration of rain damage on Banikhet Dalhouse Khajir road Km. 15/600 to 27/0 (SH:- Hiring of Excavator cum Loader for removal of Slips at various RD's)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including cartage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	1192.00			Per Cubic meter	0.00
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.
 Note - 2) No deviation shall be allowed in any case.
 Note -3) Subject of availbity of funds


 Executive Engineer
 Dalhouse Division
 H.P.P.W.D. Dalhouse

DNIT

Estimated Cost :- Rs.3,03,293/-
 Earnest money :- Rs.6100/-
 Time:- Six Month

Name of Work:- A/R & M/O to link road to Special Research Unit office Moti Tibba (SH:- Providing and laying Cement Concrete Pavement km 0/0 to 0/115)

Sr No	Description of items	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification section 300 and 1600 as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring, strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/ excavation work to the disposable/ dumping site to be selected by the contractor in private lands. The rate is inclusive of octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	32.55	Per cubic metre			

2	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 (forty three) grade cement or any other type as per Clause 1501.2.2 M 30 (thirty) (grade) coarse and fine aggregates conforming to IS: 383 (three hundred eighty three) maximum size of coarse aggregate not exceeding 25 mm, (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved design mix , laid in approved fixed side form work (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge / culvert and construction joints, admixtures as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and Technical specification Section 1500 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	31.50	Per Cubic metre			
	Quoted Rate in Figure (%)				To be quoted by contractor	
	Quoted Rate in Words%				To be quoted by contractor	
					Total:-	


 Executive Engineer
 Dalhousie Division
 H.P.P.W.D. Dalhousie

BILL OF QUANTITY

Estimate Cost :- Rs.2,70,123/-

Earnest Money Rs.5500/-

Time Limit :- Three Month

Name of Work:- Repair of veterinary Dispensary at Ruliyani Tehsil Dalhousie Distt Chamba H.P. (SH:- Providing & Fixing vetrified tiles, Ceiling and Painting work)

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
		Figures	Words				
1	Civil work Providing and laying cement concrete 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 20mm (twenty millimetre) nominal size) and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in Suspended floor, roofs, landing, shelves and their support balconies, beams, girders, bressumers and cantilever upto floor all level within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals and as per HPPWD specifications and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax , GST or any taxes imposed by the Government.	0.21	Cubic meter			Per Cubic meter	
2	Providing and laying Double Charges 10mm (ten millimeter) thick anti skid water proof stain and impact resistant heavy duty vetrified tiles of Kajaria, Orient, bell Rak, Nisco 600X600 mm size (six hundred into six hundred millimetre) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm (twelve millimeter) thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required up to all floor level, complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts, and other incidental. The rate including Royalty, Malkhana, Octroi, toll tax . GST Sales tax or any other taxes imposed by the Government.	34.22	Square meter			Per Square meter	

3	Providing and laying ceramic tiles of non slippery Kajaria, Nisco, Orient Bell Rak 5.5mm (five decimal five millimetres) thick tiles in flooring 300mmX300mm (three hundred into three hundred millimeter) laid on bed of 12mm (twelve millimeter) thick cement mortar 1:3 (one cement isto three sand) finishing with flush pointing in white cement slurry mixed with pigment to match the shade of tiles as required up to all floor level, complete as per HPPWD specifications and as directed by the Engineer,- in-Charge, including carriage of materials within all leads, lifts, and other incidental. The rate including Royalty, Malkhana, Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	13.44	Square meter				Per Square meter	
4	Providing and fixing position collapsible steel shutters with vertical channels 20mm X 10mm X2mm (twenty millimeter into ten millimeter into two millimeter) and braced with flat iron diagonals 20mm X 5mm (twenty millimeter into five millimeter) size with top and bottom rail of T iron 40mm X 40mm X6mm (forty millimeter into forty millimeter into six millimeter) with 38mm (thirty eight millimeter) dia steel pully complete with bolts and nuts locking arrangement, stoppers, handles including applying a priming coat of red lead paint within all leads and lifts as per the direction of the engineer-in-charge and other incidentals and as per HPPWD specifications including carriage of materials within all leads, lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax , GST or any taxes imposed by the Government.	7.56	Square meter				Per Square meter	
5	Providing and fixing Natural colour insulating board 12 mm (Twelve millimeter) thick ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately) within all leads and lifts as per the direction of the engineer-in-charge and other incidentals and as per HPPWD specifications including carriage of materials within all leads, lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax , GST or any taxes imposed by the Government.	4.00	Square meter				Per Square meter	

6	Providing and fixing plain M.S. grills of required patterns in steel frames of window etc. with M.S grill made of 10 x 10 mm (ten millimeter in to ten millimetre) in M.S square bar welded to 20mmx4mm (Twenty millimeter into four millimeter) M.S. flat, round headed bolts and nuts or screws complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including of toll tax , GST Sales tax or any other taxes imposed by the Government.	41.40	Per Kg					
7	Providing and laying Polished Granite stone Polished Granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.as per HPPWD specifications , including carriage of materials within all leads, lifts and other incidental. The rate including of toll tax , GST Sales tax or any other taxes imposed by the Government.	2.75	Square meter				Per Square meter	
8	15mm (fifteen millimetre) thick cement plaster in single coat on fair side of brick / concrete / stone walls for interior plastering upto floor all levels including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth with cement mortar 1:4 (One Cement isto four sand) within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals.The rate inclusive of Royalty, Malkhana, Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	125.44	Square meter				Per Square meter	

9	Providing and applying Birla white cement based putty of average thickness 1 mm.(One millimeter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	125.44	Square meter				Per Square meter	
10	Finishing walls with .New work (Two or more coats applied @ 1.43 litre/10 sqm. (One point four three liter per ten square meter)Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm .100% Premium acrylic emulsion paint having VOC less than 50 gm (Fifty grame) /litre and UV resistance as per IS 15489:2004. Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives complete as specified and as directed by the Engineer-in-Charge as per HPPWD specifications . including carriage of materials within all leads, lifts and other incidental. The rate including of toll tax , GST Sales tax or any other taxes imposed by the Government.	125.44	Square meter				Per Square meter	
11	Painting with synthetic enamel paint Two or more coats new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture of required colour to give an even shade on : and as directed by the Engineer-in-Charge as per HPPWD specifications . including carriage of materials within all leads, lifts and other incidental. The rate including of toll tax , GST Sales tax or any other taxes imposed by the Government.	28.58	Square meter				Per Square meter	

12	Demolishing cement concrete manually by mechanical means including disposal of material within 50 (Fifty) metres lead as per direction of Engineer - in - charge as per HPPWD specifications, including carriage of materials within all leads, lifts and other incidental. The rate including of toll tax, GST Sales tax or any other taxes imposed by the Government.	3.85	Cubic meter				Per Cubic meter	
13	Providing and laying cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size) and curing complete, in or under water, including pumping or bailing out water/dewatering, removal of slush which may arise at the time of laying under water complete excluding the cost of form work in foundation and plinth in all depths/heights as per HPPWD specifications and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax, GST or any taxes imposed by the Government.	2.89	Cubic meter				Per Cubic meter	
14	Providing and laying 40 mm (Forty millimetre) thick heavy duty precast cement concrete inter locking paver blocks vibration technology compacted upto M-50 grade of NTC including border or kurb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	48.40	Square meter				Per Square meter	

15	Providing and fixing on wall faces PVC (D-plast) or equivalent 150mm dia (one hundred fifty millimetre diameter) rain water pipes working pressure not less than 4.6 Kg (four point six) kilogram per square centimetre of finolex/relpipe/vectul including filling the joints with approved adhesive complete including carriage of material within all leads and lifts and as per the direction of the Engineer-in-Charge and other incidentals. The rate including Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	2.00	Rmt				Per Running meter	
16	Providing and fixing 150 mm (One hundred fifty millimetre) dia PVC plain bend on wall faces PVC (D-Plast) supreme or equivalent accessories for rain water pipes including filling the joints with approved adhesives complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	1.00	Nos				Per Running meter	
Total:-								


 Executive Engineer
 Dalhousie Division
 H.P.W.D. Dalhousie