

HPPWD TENDER

Sealed item rate tenders are hereby invited by the Executive Engineer, Sundernagar Division, H.P.P.W.D. Sundernagar on behalf of Governor of H.P. for the below noted works from eligible contractors registered in HPPWD in appropriate class so as to reach in this office on or before **25.05.2023** upto 11:00 AM and the same will be opened on the same day at 11:30 AM in the presence of the contractors or their authorized representatives who may be present. The applications for issue of tender form shall be received upto **12:00 Noon on 23.05.2023** and tender forms will be issued on **24.05.2023**.

The tender shall accompany with earnest money which should be in shape of NSC/ Time deposit/ saving bank account in the post office/ Bank in HP duly pledged in favour of the Executive Engineer, Sundernagar Division, H.P.P.W.D. Sundernagar. Conditional tenders, telegraphic tenders and tenders without earnest money will not be entertained. The executive Engineer reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of tenders.

Sr. No.	Name of work	Estimated cost (Rs.)	Earnest Money (Rs.)	Tender Cost (Rs.)	Time
1 ✓	A/R & M/O on Kateru Slapper vai Paurakothi road Km 0/0 to 16/0 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 4/0 to 7/0).	4,89,519/-	10,000/-	350/-	Two Month
2 ✓	A/R & M/O on Janoul Jaral road Km 0/0 to 6/855 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 0/0 to 6/855)	4,93,990/-	10,000/-	350/-	Two Month
3 ✓	A/R & M/O on Chandigarh Mandi Manali road KM 156/750 to 165/300 and Khurahal to Suin road KM 0/0 to 2/0 (SH: P/L Gr-II for correction layer and repair of pot holes)	4,98,542/-	10,000/-	350/-	Two Month
4 ✓	A/R & M/O on Chanol to Samon road Km 0/0 to 8/300 (SH: P/L Gr-II for correction layer and repair of pot holes in KM 0/0 to 8/300)	4,93,644/-	10,000	350/-	Two Month
5 ✓	A/R & M/O Sundernagar Circular road KM 0/0 to 7/630, Link road from BBMB Lake KM 0/0 to 1/0, Pungh Tamroh road KM 0/0 to 1/380 and Link road Nahungi Saghi KM 0/0 to 2/640 (SH: P/L Gr-II for correction layer and repair of pot holes).	4,99,291/-	10,000/-	350/-	Two Month
6 ✓	A/R & M/O Pungh Ghangoo road Km 0/0 to 19/0 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 0/0 to 9/0)	4,97,276/-	10,000/-	350/-	Two Month
7 ✓	A/R & M/O Salwana to Chah Ka Dohra via Masog road Km 0/0 to 0/900 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 0/0 to 0/900).	2,54,973/-	5100/-	350/-	Two Month
8 ✓	A/R & M/O Alsu Jambla road Km 0/0 to 8/900 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 0/0 to 8/900)	4,98,581/-	10,000/-	350/-	Two Month
9 ✓	A/R & M/O Jarol Behna road KM 0/0 to 7/0 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 0/0 to 7/0).	4,99,065/-	10,000/-	350/-	Two Month

10 ✓	A/R & M/O on Kateru Slapper vai Paurakothi road Km 0/0 to 16/0 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 0/0 to 4/0)	4,93,719	10,000/-	350/-	Two Month
11 ✓	A/R & M/O Bangalu Luhanu road KM 0/0 to 7/600 (SH: P/L Gr-II for correction layer and repair of pot holes in KM 0/0 to 4/0).	4,99,633/-	10,000/-	350/-	Two Month
12 ✓	A/R & M/O Pungh Kapahi vis Patsal road KM 0/0 to 9/300 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 0/0 to 9/330).	4,99,965/-	10,000/-	350/-	Two Month
13 ✓	A/R & M/O Ghangnoo Khanokhar road KM 0/0 to 4/650 (SH: P/L Gr-II for correction layer and repair of pot holes in KM 0/0 to 4/650).	4,94,359/-	10,000/-	350/-	Two Month
14 ✓	A/R & M/O Pungh Ghangnoo road Km 0/0 to 19/0 (SH: P/L Gr-II for correction layer and repair of pot holes in Km 9/0 to 19/0)	4,98,748/-	10,000/-	350/-	Two Month
15 ✓	A/R & M/O Sundernagar Maloh road Km 0/0 to 5/565 (SH: P/L G-II for correction layer and repair of pot holes at various RDs).	4,92,040/-	10,000/-	350/-	Two Month
16 ✓	A/R & M/O link road to village Bhanwar KM 0/0 to 3/0 (SH: P/L Gr-II for correction layer and repair of pot holes at various RDs).	4,68,258/-	9,400/-	350/-	Two Month

Certified that the above works are of urgent nature and require to be executed immediately in the larger public interest.

**Executive Engineer,
Sundernagar Division,
H.P.P.W.D. Sundernagar.**

No: - PW/SNR-E-Tender/Giriraj/2023- 1335-50

Dated: 11 .05.2023

Copy forwarded to the following for information and publicity:

1. The Superintending Engineer, 1st Circle H.P.P.W.D. Mandi.
2. The Executive Engineer (I.T) O/o Engineer-in-Chief, HPPWD Shimla (HP) eeict-pwd-shi@hp.gov.in for uploading the NIT on departmental website please.
3. All the Assistant Engineers working under this Division.
4. Various Contractors working under Sundernagar Division.
5. Notice Board.


**Executive Engineer,
Sundernagar Division,
H.P.P.W.D. Sundernagar.**

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,89,519/- only
 Earnest Money Rs.10,000/- Only
 Time : Two Months

Name of work :- A/R & M/O on Kateru Slapper via Pourakothi road km 0/0 to 16/00 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 4/0 to 7/00)

S.No	Description of Items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads , lifts of material and other incidentals .	35.36 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads , lifts of material and other incidentals .	1879.25 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


 Executive Engineer,
 Sunder Nagar Division,
 HPPWD Sunder Nagar.
 SR

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Janoul Jaral road km 0/0 to 6/855 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/0 to 6/855)

Estimated cost Rs. 4,93,990/- only
Earnest Money Rs.10,000/- Only
Time : Two Months

S.No	Description of items	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	37.00 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including all leads, lifts of material and other incidentals.	1880.00 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


Executive Engineer,
Sunder Nagar-Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,98,542/- only
Earnest Money Rs.10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on CMM road km 156/70 to 165/300 And Khurahal to Suin road km 0/0 to 2/000 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals .	35.00 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals .	1926.50 sqm			Per Square metre	
	Term & condition :- The bitumen will be provided by the department free of cost to the contractor .				Total	


Executive Engineer,
Sunder Nagar Division,
M.P.P.W.D. Sunder Nagar

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,93,644/- only
Earnest Money Rs. 10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on Chanol to Samon road km 0/0 to 8/300 (Sh:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/0 to 8/300)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	30.45 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals.	1960.00 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


Executive Engineer,
Sunder Nagar Division,
M.P.A.W.D. Sunder Nagar

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,99,291/- only
Earnest Money Rs. 10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on circular road km 0/0 to 7/630, Link road from BBMB Lake km 0/0 to 1/0 , Pungth Tamroh road km 0/0 to 1/380 And Link road Nounghi Saghi km 0/0 to 2/640 (SH:- P/L Gr-II for correction layer and Repair of the potholes)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405, including all leads, lifts of material and other incidentals.	44.11 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1, including all leads, lifts of material and other incidentals.	1816.50 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	

Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,97,276/- only
Earnest Money Rs.10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on Pungh Ghangu road km 0/0 to 19/00 (SH:- P/L Gr-II for correction layer and Repair of the pot holes in km 0/00 to 9/000)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	34.88 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including all leads, lifts of material and other incidentals.	1922.00 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Salwana Chah ka Dohra via Masog road km 0/0 to 0/900 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/00 to 0/900)

Estimated cost Rs. 2,54,973/- only
Earnest Money Rs.6,000/- Only
Time : Two Months

S.No	Description of Items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	30.88 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals.	823.50 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor.					Total	


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,98,581/- only
Earnest Money Rs.10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on Alsu Jambla road km 0/0 to 8/900 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/0 to 8/900)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	40.35 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals.	1860.00 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


Executive Engineer,
Sunder Nagar Division,
H.P.W.D. Sunder Nagesh

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,99,065/- only
Earnest Money Rs.10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on Jarol Behna road km 0/0 to 7/00 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/00 to 7/00)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	35.60 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals.	1921.50 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	

[Signature]
Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Estimated cost Rs. 4,93,719/- only
Earnest Money Rs.10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on Kateru Slapper via Pourakothi road km 0/0 to 16/00 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/0 to 4/00)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	36.11 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including all leads, lifts of material and other incidentals.	1889.81 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


Executive Engineer,
Sunder Nagar Division,
HPPVT Sunder Nagar.


SCHEDULE OF QUANTITY

Estimated cost Rs. 4,99,633/- only
Earnest Money Rs.10,000/- Only

Time : Two Months

Name of work :- A/R & M/O on Bangalu Luhnu road km 0/0 to 7/600 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/00 to 4/00)

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	40.75 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals.	1860.00 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


Executive Engineer,
Sunder Nagar Division,
MPPWD Sunder Nagar

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Pungh Kapahi via Patsal road km 0/0 to 9/300 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/00 to 9/330)

Estimated cost Rs. 4,99,965/- only
Earnest Money Rs.10,000/- Only
Time : Two Months

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	40.82 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including all leads, lifts of material and other incidentals.	1860.70 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .						Total


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Changanu Khanokhar road km 0/0 to 4/650 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 0/0 to 4/650)

Estimated cost Rs. 4,99,065/- only
Earnest Money Rs.10,000/- Only
Time : Two Months

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	45.74 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including all leads, lifts of material and other incidentals.	1772.81 sqm			Per Square metre	
	Term & condition :- The bitumen will be provided by the department free of cost to the contractor .				Total	


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Pungh Ghangu road km 0/0 to 19/00 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes in km 9/00 to 19/000)

Estimated cost Rs. 4,98,748/- only
Earnest Money Rs.10,000/- Only
Time : Two Months

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals .	35.60 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals .	1920.00 sqm			Per Square metre	
	Term & condition :- The bitumen will be provided by the department free of cost to the contractor .				Total	


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Sundernagar Maloh road km 0/0 to 6/565 (SH:- P/L Gr-II for correction layer and Repair of the pot holes at various RDs)

Estimated cost Rs. 4,92,048/- only
Earnest Money Rs.10,000/- Only
Time : Two Months

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) two water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	14.60 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals.	2150.00 sqm			Per Square metre	
Term & condition :- The bitumen will be provided by the department free of cost to the contractor .					Total	


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Link road to village Bhanwar km 0/0 to 3/0 (SH:- P/L Gr.-II for correction layer and Repair of the pot holes at various RDs)

Estimated cost Rs. 4,68,258/- only
Earnest Money Rs.10,000/- Only
Time : Two Months

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes 63 to 45 mm (sixty three to forty five millimeter) too water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading II as per technical specification clause 405. including all leads, lifts of material and other incidentals.	21.60 cum			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads, lifts of material and other incidentals.	1950.00 sqm			Per Square metre	
	Term & condition :- The bitumen will be provided by the department free of cost to the contractor .				Total	


Executive Engineer,
Sunder Nagar Division
HPPWD Sunder Nagar