

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NO.PW.ED.II.GA.TENDER/23-24-  
To

DATED:-

1566-88

16/6/23


The Executive Engineer (IT)  
Nirman Bhawan HPPWD  
Shimla-2

Subject: - Publication of Tender Notice.

Sir,


Jai Hind

Please find herewith the tender notice of works as given in the notice inviting tender for uploading on department website as per Notification vide Pr.Secy.(PW) to the Govt.of Himachal Pradesh letter No.PBW(B)1/2020 dated 27<sup>th</sup> May,2021 and PBW(B)A(3)1/2020 dated 16<sup>th</sup> July,2021 and even file dated 12.01.2023 as the works mentioned in the tender notice is (are) urgent in nature and in public interest.

  
Executive Engineer,  
Elect. Division No.II  
HP PWD, Shimla-1

Copy forwarded for further necessary action to the:-

- 1.The Superintending Engineer, Electrical Circle, HP PWD, Shimla-9 for information please.
2. Computer Cell O/O the Executive Engineer (IT Cell) Nigam Vihar Shimla-2

  
Executive Engineer,  
Elect. Division No.II  
HP PWD, Shimla-1



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
Office of Executive Engineer Electrical Division No-II HPPWD Shimla -171 001  
Website: [www.hppwd.gov.in](http://www.hppwd.gov.in) e-mail: [ee-eled2-hp@nic.in](mailto:ee-eled2-hp@nic.in) Tel/Fax: 0177-2990187**

**No.PW.ED.II.GA.Tender/2023-2024-**

1569-1600

**Dated:-**

16/6/23

**NOTICE INVITING TENDER**

Sealed percentage tenders are hereby invited by the Executive Engineer, Electrical Division NO II HPPWD Shimla-1 in form No.6&8 on behalf of Governor of H.P.for the following works from the contractors of appropriate class enlisted with HPPWD (Electrical). The tenders shall be opened in the presence of contractors/firms or their authorized representative who wish to be present.

**TIME SCHEDULE OF TENDER**

(i) Last date of receipt of application:	23.06.2023 Up to 1.00 P.M
(ii) Date of sale of tenders	23.06.2023 Up to 2 PM to 5.00 PM
(iii) Last date of receipt of bids: -	24.06.2023 Upto 10.30 A.M
(iv) Date of bid opening: -	24.06.2023 AT 11.30 A.M

The tender form will be issued to only those contractors who qualify the criteria after the scrutiny of application forms by the committee constituted for the purpose.

Work No. (1) Renovation and conversion of special ward No.634 into VIP patient room block-B at IGMC Shimla(SH:Supply and installation of VRV system for 633,634,635) Estimated cost Rs.4,04,010/-Earnest money Rs.8100/- Time: 1 month. Cost of form Rs.350/NR

Work No. (2)Providing CCTV camera in 1st.&2nd floors of block-A occupied by students of HPGDC Shimla at Blessington Girls hostel Lakkar Bazar,Shimla.Estimated cost Rs. 1,46,557/-Earnest money Rs.3000/-Time: 3 month. Cost of Form Rs.350/NR

Work No.(3)C/O Trauma centre at New OPD at IGMC Shimla(SH:Prov.additiional LAN cabling,IO,switches,power cable for CCTV and telephone points at attic floor, new OPD etc.).Estimated cost Rs.,1,64,430/-Earnest money Rs. 3300/-Time:1 month. Cost of form Rs.350/only

Work No. (4)Replacement of damaged essential accessories and other parts including security of 2No.medical air compressor of ATLAS COLCO make with duplex dryer system installed at HP Govt.Dental College Shimla. Estimated cost Rs 2,23,000/-Earnest money Rs.6500/-Time: 1 Year. Cost of form Rs.350/NR

Work No. (5)Providing staff for day to day maintenance at civil hospital Rohru Distt.Shimla(w.e.f.01.07.2023 to 31.12.2023) Estimated cost Rs.1,97,100/-Earnest money Rs.4000/-Time:6 month. Cost of form Rs.350/NR.

**TERMS AND CONDITIONS:-**


1. The earnest money in the shape of National Saving certificate. Time deposit account in any of the post office in HP/FDR or any Bank duly pledged in favour of Executive Engineer, Elect Division No II HPPWD Shimla-1 accompanied with the application for receipt of tender form along with cost of form.
2. The contractor/firm should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents.
  - a) Latest enlistment/renewal orders with application.
  - b) GST Number issued by the Sale Tax Department.
  - c) PAN (Permanent Account Number) issued by the Income Tax Department and copy of EPF issued from competent authority.
3. The Executive Engineer, Electrical Division No.II, HPPWD Shimla-1 reserves the right to reject any tender without assigning any reason(s)
4. The Cess charges @ 1% will be deducted from the gross amount of work done of the contractor. Contd..P.TO...



5. The work will be completed by the contractor within the stipulated period.
6. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.
7. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience which shall be duly evaluated by the technical evaluation committee.
8. The contractor /firm having necessary documents and past adequate experience shall be preferred.
9. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
10. A contractor enlisted in a particular class be eligible to tender for his own class and one step below
11. Only two number tender forms will be issued to the eligible contractor.
12. If any kind of holiday to be happened, the tender shall be opened on the next working day at 11.30 a.m.
13. GST will be deducted as per rates fixed by the Government.


**CERTIFICATE:-**

It is to certify that tender for the above works are urgently required please.

  
Executive Engineer,  
Elect. Division No.II,  
HPPWD Shimla-1

Copy forwarded for information to the:-

1. Chief Engineer (SZ) HPPWD Simla-2
2. The Superintending Engineer, 1st Electrical Circle, HPPWD Shimla-9.
3. Deputy Commissioner Shimla.
4. All the Assistant Engineers working under this Division.
5. All the intending contractors in HPPWD
9. Notice Board.

  
Executive Engineer,  
Elect. Division No.II,  
HPPWD Shimla-1



## DRAFT SCHEDULE OF QUANTITY

Name of work:- **Renovation and conversion of special ward no. 634 into VIP patient room block-B at IGMC Shimla. (SH:-Supply and installation of VRV System for 633, 634, 635.)**

Estimated Cost:- Rs.4,04,010/- only  
 Earnest Money:- Rs.8100/- only  
 Time:- One month

EE

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In words	
1.00	Supply, Installation, Testing & Commissioning of factory fitted microprocessor based self diagnostic auto check VRV/VRF system outdoor unit equipped with PCBs, accumulator, oil separator, brushless DC inverter fan motor, OEM technology for longer life with integrated IPM & PWM to ensure effective operation even at low pressure shell for better efficiencies. Compressor shall be fixed in metallic chamber for lower noise with enhanced fire safety protection. Outdoor unit shall be equipped with highly efficient induction type heater using eliminated wasted heat. VRT/VET system shall be based on advanced & automatically modulation evaporating refrigerant temperature between 0°C to 11°C for instant cooling and better energy efficiency as per user's demand. Outdoor units shall be essentially equipped with safety devices like fuse, noise filter PCB, low pressure switch, high pressure switch, pulse based LEV for optimized refrigerant flow control, isolating valve, protective corrosion resistant polyester coating on panels, hydrophilic coating on Aluminium fins, protective polyurethane coating on PCB, OEM provided Inbuilt automatic reverse phase detector & sequencer/corrector to avoid any kind of failure due to phase sequence reversal which makes system reliable and redundant. Heat exchanger must be essentially equipped with internally grooved copper tubes for better heat exchange performance and operate in extreme conditions i.e. even at ambient temperature of 52°C or more. Outdoor units shall be pre-charged with R401A gas, pump down function and shall also be equipped with charging valve/ports for additional charge of refrigerant as per site requirement. All outdoor unit shall be able to perform in duty cycle mode to optimize wear and tear of system when more than one outdoor unit is connected to a circuit. Outdoor units must also be equipped with four way valve for necessary provision of heating during winters. All outdoor shall have approximately following as per OEM standards rated capacities at ARI conditions and, with the criteria of delivering 95% capacity at 43 °C being most likely temperature to occur during summers. (All Unit shall confirm the detailed specification of tender document and providing power/ control cabling/earthing of indoor unit complete with supplying of all material in all respect as per specifications and any other items required to make the system complete as required) The manufacturer of ODU and compressor shall be same. i.e. the make of compressor shall be identical of the ODU. (Make: Voltas, O General, Trane)					
1.01	Outdoor Unit 4.3 HP	1.00	Nos.	110132.00	Rs. One Hundred Ten Thousand One Hundred Thirty Two only	110132.00



2.00	<b>Indoor Units: Round Flow Cassette Type :-</b> Supply, Installation, Testing and Commissioning of VRV/VRF indoor units with factory fitted electronic expansion valve, multi speed fan motors, dynamically balanced blowers, synthetic washable plasma media filter with hydrophobic coating on cooling coil. Electronic components like PCBs must be essentially enclosed in a metal box compartment being integrated part of indoor unit to ensure enhanced fire protection with auto by pass technology allowing uninterrupted operation of indoor units connected to a circuit in event of break down in any indoor connected to same circuit. All indoor units shall have individual fan speed and temperature control mechanism to be operated from corded/cordless remote. In addition to all indoor units can also be operated from central remote control. <b>(All Unit shall confirm the detailed specification of tender document and providing power/ control cabling/earthing of indoor unit complete with supplying of all material in all respect as per specifications and any other items required to make the system complete as required) (Make : Voltas, O General, Trane)</b>					
2.01	Cassette Type Indoor Unit - 1.6 TR	3.00	Nos.	38216.00	Rs. Thirty Eight Thousand Two Hundred Sixteen only	114648.00
3.00	Refrigerant Charges For the complete system-R410A. Its a member of hydrofluorocarbon (HFC) Class of Refrigerants and is Composed of equal parts R-32 and R-125.					
4.00	SITC of PVC (Minimum 15 Kg/Sqcm pressure rated) Drain Water Piping complete with fittings interl insulation (elbows, tees, reducers, sockets etc.), supports, jointing and any other item required to make the system complete. Nominal Diameters of Pipes in mm as indicated below:	3.00	Kg	1450.00	Rs. One Thousand Four Hundred Fifty only	4350.00
4.01	25 mm ( with 6 mm Class- O XLPE)					
5.00	SITC of Copper Refrigerant piping for VRV / VRF System complete with fittings, supports, jointing, insulation with class O -XLPE , gas charging & commissioning as per specifications, all accessories as per specifications and any other item required to make the system complete. Nominal Dia in mm OD as indicated below : <b>Make : Rajco/Maxflow/Mandev/Jobu/MTL</b>	40.00	Rmt.	210.00	Rs. Two Hundred Ten only	8400.00
5.01	12.7 ( with 13 mm insulation )					
5.02	6.3 (with 13 mm insulation)	40.00	Rmt.	1160.00	Rs. One Thousand One Hundred Sixty	46400.00
6.00	Providing & fixing control cum transmission wiring of 2 core x 2.5 sqmm copper shield cable in suitable conduits between indoor units and outdoor units and remote controllers.	40.00	Rmt.	990.00	Rs. Nine Hundred Ninety only	39600.00
7.00	Providing & fixing of 25 MM Dia of medium class PVC Conduit Along with the accessories in Surface/ recess including cutting the wall and making goods the same in case of recessed conduit.	80.00	Rmt.	180.00	Rs. One Hundred Eighty only	14400.00
8.00	Supply and fixing of perforated of indicated thick CRCA GI perforated cable tray , of following sizes complete with bends/tee joints, coupling plate & nuts bolts etc. including Supporting structure as per specification complete as required.	40.00	Rmt.	107.00	Rs. One Hundred Seven only	4280.00
8.01	150mm wide & 60mm deep x 1.6mm thickness	40.00	Rmt.	720.00	Rs. Seven Hundred Twenty only	28800.00

EE



9.00	Supply of MS fabricated Stand and cage for the Outdoor Units duly painted with Black paint and satisfaction of Engineer-In-Charge.	150.00	Kg	220.00	Rs. Two Hundred Twenty only	33000.00
	<b>Total:-</b>					<b>404010.00</b>

*Self Schedule of Quantity approved  
for Rs. 404010/- only. (Rs. Four Lakh. four  
Thousand & Ten only)*

*Sharma*  
Executive Engineer,  
Electrical Division No.-II,  
HP PWD (U.S. Club) Shimla-1



**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost:- Rs.1,46,557/- only  
 Earnest Money:- Rs. 3000/- only  
 Time:- 3 months



**Name of work:- Providing CCTV cameras in 1st & 2nd floors of block-A occupied by students of H.P. Govt. Dental College Shimla at Blessington Girls Hostel Lakkar Bazar, Shimla. (H.P.)**

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In words	
1.00	Supply, Installation, Testing and Commissioning of outdoor <b>Bullet Camera</b> with 1/2.7" 5MP Progressive CMOS Image Sensor Max. Output 5 MP (2592 × 1944)@20fps, 4 MP (2688 × 1520)@25/30fps, Instastream, Smart H.264, Dual stream encoding, WDR(120dB), Day/Night(ICR), 3D-NR, ROI, AWB, AGC,BLC, 2.7mm-13.5mm Motorized Lens, IR Range of 60 Mtrs IP 67 complete in all respect up to the entire satisfaction of Engineer-in-Charge. <b>Make:CP Plus/Hikvision /Honeywell.</b>	1.00	Each	14750.00	Rs. Fourteen Thousand Seven Hundred Fifty only	14750.00
2.00	Supply, Installation, Testing and Commissioning of indoor <b>Dome Camera</b> with 1/2.7" 5MP Progressive CMOS Image Sensor,Max. Output 5MP(2592 × 1944)@20 fps, and supports 4MP(2688×1520)@25/30 fps, Instastream, Smart H.264, Dual stream encoding, WDR(120dB), Day/Night(ICR), 3D-DNR, ROI, AWB, AGC, BLC,2.7mm-13.5mm Motorized Lens,2.7mm-13.5mm Motorized Lens,IR Range of 40 Mtrs,IP67,complete in all respect up to the entire satisfaction of Engineer-in-Charge. <b>Make:CP Plus/Hikvision /Honeywell</b>	4.00	Each	14030.00	Rs. Fourteen Thousand Thirty only	56120.00



3.00	Supply, Installation, Testing, and commissioning of <b>8 Port PoE Switch</b> with 8,1000Mbps; RJ45 ports; Max. 30W Output of Single PoE Port, 2 x 1000Mbps RJ45 ports 2 x 1000Mbps SFP Port, supports IEEE802.3i/802.3u/802.3x/802.3af/802.3ab/IEEE 802.3z, Transmission Distance: default: 0-100m, 24Gbps Full duplex Full duplex switch capacity, Built-in Power Supply, Input: 100-264V AC, 50/60Hz complete in all respects up to the entire satisfaction of Engineer-in-Charge <b>Make:CP Plus/Cisco Brocade / Juniper/Xtreme</b>	1.00	Each	10030.00	Rs. Ten Thousand Thirty only	10030.00
4.00	Supply Installation testing and Commissioning of surveillance hard disk of <b>2 TB HDD</b> 3.5 Inch SATA 6Gb/s 256MB Cache for DVR /NVR Security Camera System complete in all respects up to the entire satisfaction of Engineer-in-Charge. <b>Make:WD / Toshiba/Seagate</b>	1.00	Each	5788.00	Rs. Five Thousand Seven Hundred Eighty Eight only	11576.00
5.00	Supply, Installation, Testing, and commissioning 32 " LED Monitor, Full HD, HDMI Port, Component Video Inputs, 1 Digital Audio Out, <b>Make: Panasonic / LG / Samsung</b>	1.00	Each	20357.00	Rs. Twenty Thousand Three Hundred Fifty Seven only	20357.00
6.00	Supply and Laying of Cat6, 4Pair UTP Cable. <b>Make: Molex / R&amp;M.</b>	1.00	Meter	40.00	Rs. Forty only	6000.00
7.00	Supply and Laying of <b>HDMI Cable</b> with length 5 mtrs. <b>Make: Molex / R&amp;M.</b>	1.00	Meter	848.00	Rs. Eight Hundred Forty Eight only	848.00



8.00	Supply, installation, testing and commissioning of NVR 8 Channel with support up to 1ch@8MP/4ch@1080P decoding, Instastream/H.265/H.264 /H.264 codec decoding, Up to 8MP Resolution Preview and Playback, Max 80Mbps incoming bandwidth, support 2 SATA HDDs up to 10TB Each, 2 USB Ports, VGA/HDMI simultaneous video output, ONVIF Version 2.4 conformance, complete in all respects up to the entire satisfaction of Engineer-in-Charge. <b>Make:-CP Plus/Xtreme/CISCO / Brocade / JUNIPER.</b>					
9.00	Supply, installation, testing and commissioning of 6U rack for switch mounting with fan and power strip, PDU, Hardware mounting Kit. <b>Make:- Camrack / APW / Netrack / Perfect Rack.</b>	1.00	Each	9006.00	Rs. Nine Thousand Six only	9006.00
10.00	Supply and erection of PVC pipe 25mm dia ISI marked (medium) recessed in wall. Ceiling etc. including the cost of PVC bends, inspection boxes, iron hooks, cement concrete etc. complete in all respect up to the entire satisfaction of Engineer-in-Charge of work. <b>Make:- CUSTOM.</b>	1.00	Each	6754.00	Rs. Six Thousand Seven Hundred Fifty Four only	6754.00
11.00	Supply, installation, testing & commissioning of 1 KVA UPS offline with 1 hour backup. <b>Make:-Microtek/ APC/ Emerson/ NUMERIC/.</b>	100.00	Meter	30.00	Rs. Thirty only	3000.00
	<b>Total:-</b>	1.00	No.	8116.00	Rs. Eight Thousand One Hundred Sixteen only	8116.00
						146557.00

*Draft Schedule of Quantity approved*

*for Rs. 146,557/- only (Rs. one lakh, forty six thousand, five hundred & fifty seven only.)*

**Executive Engineer**  
Electrical Division No-II,  
HP PWD (S. Circle) Shimla-1



## DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- Rs.1,64,430/- only

Earnest Money:- Rs.3300/- only

Time:- One month

Name of work:- C/O Trauma Centre at new OPD at IGMC Shimla. (SH:- Providing additional LAN cabling, IO switches, power cable for CCTV and telephone points at attic floor, new OPD etc.)

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In words	
1.00	Supply Installation Testing & Commissioning of 3 Core Power Cable 1.5 sqmm. Make: Finolex / R.R. Kable / Havells.					
2.00	Supplying and drawing of CAT 6 Cable in the existing surface / recessed Steel/ PVC conduit as required.	150.00	Per/Meter	61.00	Rs. Sixty One only	9150.00
	i) 1 run of cable					
3.00	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	1500.00	Per/Meter	54.00	Rs. Fifty Four only	81000.00
3.01	25mm	200.00	Per/Meter	99.00	Rs. Ninety Nine only	19800.00
3.02	Supply, installation, testing and commissioning of Tiffin Box	6.00	No.	1855.00	Rs. One Thousand Eight Hundred Fifty Five only	11130.00
4.00	Supply. Istallation,commissioning of Cat-6 utp Pach cord 3 mtr. Grey, Category 6 Unshielded Twisted Pair 4 pair 100W cable shall be compliant with ANSI/TIA/EIA-568-C.2 Additional Category 6 UTP cables shall extend between the work area location and its associated telecommunications closet and consist of 4 pair, 23 AWG, UTP. Make: Molex/AMP/Panduit/D-Link	6.00	No.	1250.00	Rs. One Thousand Two Hundred Fifty only	7500.00

EE



5.00	Supply, Installation, Testing and Commissioning of Cat6 IO Box, 1x Keystone Jack + 1x Gang Box + 1x Single Socket Face Plate Suitable for : CAT6 / CAT6e Color - Off White / White / Ivory <b>Make: Molex/AMP/Panduit/D-Link</b>	30.00	No.	750.00	Rs. Seven Hundred Fifty only	22500.00
6.00	Supply Installation testing and Commissioning of OFC Armored outdoor SINGLE MODE 6/12 CORE - OS2. Should be ISO.IEC 11801 - 2nd Edition, type OS2 and ITU-T REC G 652D. Tube Identification :Single tube/Multiple tube. Fibre protection (Tube) : Polybutylene Terephthalate (PBT). Water Blocking :Thixotropic Gel (Tube) and Petroleum Jelly (Interstices). Core Wrapping : Polyethylene Terephthalate. Armouring : Corrugated Steel Tape Armour (ECCS Tape). Strength Member: Two Steel wires on periphery/Two FRP rods on periphery /Central Strength Member FRP. Sheath : UV Stabilized Polyethylene (HDPE). Maximum. Tensile Strength- Short Term : 1500N or better. Mass (Nominal) : minimum 95 kg/km <b>Make (R&amp;M, Siemon, Systimax, Molex)</b>	150.00	Meter	89.00	Rs. Eighty Nine only	13350.00
	<b>Total:-</b>					<b>164430.00</b>

*Draft Schedule of Quantity approved  
for Rs. 1,64,430/- only. (Rs one lakh, sixty  
four Thousand, four hundred, & thirty only.)*

**Executive Engineer,**  
Electrical Division No.-II,  
HP PWD (ULB, Club) Shimla



## DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- Rs.3,23,000/- only ✓

Earnest Money:- Rs.6500/- only ✓

Time:- One month Year

Name of work:- Replacement of damaged essential accessories and other parts including security of 2 No. of medical air compressor of ATLAS COLCO make with duplex dryer system installed at H.P. Govt. Dental College Shimla. ✓

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In words	
1.00	Supplying, installation, testing & commissioning of consumable essentially required for the servicing of 2 No. Medical Air Compressor (Make:- ATLAS COPCO type: GA-MED) with duplex dryer system installed at H.P. Dental College Shimla complete in all respects and as per the satisfaction of Engineer-in-charge.					
1.01	Servicing of air compressor blockage line & severely choked radiator.	2.00	Job	15000.00	Rs. fifteen Thousand only	30000.00
1.02	Air filters	2.00	Each	9500.00	Rs. Nine Thousand Five Hundred only	19000.00
1.03	Oil filters	2.00	Each	9500.00	Rs. Nine Thousand Five Hundred only	19000.00
1.04	Oil for compressors	10.00	Litre	2000.00	Rs. Two Thousand only	20000.00
1.05	Unblocker kit	2.00	No.	18000.00	Rs. Eighteen Thousand only	36000.00
1.06	Servicing of screw type compressor having oil leakage	2.00	Each	6000.00	Rs. Six Thousand only	12000.00
1.07	Oil splitter / separator	2.00	Each	15000.00	Rs. fifteen Thousand only	30000.00
1.08	Compressor Rubber belt	2.00	Each	7000.00	Rs. Seven Thousand only	14000.00
1.09	Activated Carbon	25.00	Kg	700.00	Rs. Seven Hundred only	17500.00
1.1	Activated Alumina	25.00	Kg	700.00	Rs. Seven Hundred only	17500.00
1.11	DD 32 Filter	3.00	Each	18000.00	Rs. Eighteen Thousand only	54000.00
1.12	PD 32 Filter	3.00	Each	18000.00	Rs. Eighteen Thousand only	54000.00
<b>Total:-</b>						<b>323000.00</b>

Draft schedule of quantity approved

for Rs. 323000/- only (Rs. Three Lakh, &amp;

Twenty Three Thousand only) ✓

Executive Engineer,  
Electrical Division No-II,  
HP PWD (S. Club) Shimla-1



**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost:- Rs.1,97,100/- only ✓

Earnest Money:- Rs.4000/- only

Time:- 6 months

**Name of work:- Providing staff for day to day maintainance at Civil Hospital Rohru District Shimla. (w.e.f. 01-07-2023 to 31-12-2023)**

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In words	
1.00	Providing services of one No. Electrician Gr.-II for electrical enquiry for carrying out the repair and maintainance of electrical system including replacement of petty materials as per condition at per requirement at site satisfaction of Engineer-in-Charge.					
1.01	Providing services of one No.T.Mate for electrical enquiry for carrying out the repair and maintainance of electrical system including replacement of petty materials as per condition at per requirement at site satisfaction of Engineer-in-Charge.					
1.02	Electrician Gr.II	6.00	P/Month	17430.00	Rs. Seventeen Thousand Four Hundred Thirty only	104580.00
1.03	T-Mate	6.00	P/Month	15420.00	Rs. fifteen Thousand Four Hundred Twenty only	92520.00
	<b>Total:-</b>					<b>197100.00</b>

*Draft schedule of Quantity approved for Rs.197100/- only (Rs. One lakh ninety seven thousand one hundred only)*

*Executive Engineer,*  
Electrical Division No.-II,  
HP PWD (D.S. Club) Shimla-1