



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
HP.PWD Division Ghumarwin, Distt. Bilaspur(H.P)-174021
Tel:- 01978-255281, e-mail id;- ee-ghu-hp@nic.in**

NOTICE INVITING TENDERS

Sealed item rates tenders on PWD form 6 & 7/8 are hereby invited by the Executive Engineer H.P.P.W.D. Division Ghumarwin on behalf of Governor of Himachal Pradesh from the eligible contractors/firms of appropriate class for the following works as per detail given below. The important dates of tenders are as under:-

1. Date of receipt of application for the tenders 01-7-2023
3. Date of issue/sale of tender forms 3-7-2023

The tender which will received on **4-7-2023 up to 11.00 AM** shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on 3-7-2023.

The Earnest Money in the shape of NSC/Deposit at call/Time Deposit/Account in any of the Post Office/Nationalized Bank in H.P. duly pledged of undersigned must accompany with each application. The conditional tenders and tenders received without earnest money will be rejected. The office of the tender will be kept open for 60 days. The undersigned reserved the right to accept or reject the tenders without assigning any reason.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Cost of Tender Form.
1	R/R damages on Ghumarwin Dabla Morsingh road Km. 0/0 to 8/0 (SH;-R/Wall at R.D. 5/170 to 5/179)	99988	2000	One Month	
2	Special repair to Office Building of Police Station Bharari Tehsil Ghumarwin Distt. Bilaspur H.P. (SH;-Repair work of truss, door, window, flooring distempering and painting etc.)	498494	10000	One Month	350/-
3	Restoration of rain damages Kandrou Panoh Takrehra Ghumarwin road 0/00 to 8/300(SH;-P/L Cross Drainages at Km. 6/835)	156320	3200	One month	350/-
4	Repair and maintenance of Vijaypur Amarapur Dhad Jamman Ghumarwin road Km. 0/00 to 7/500(SH. P/I GSB, G-III & Tarring at R.D. 7/380 to 7/500)	168217	3500	One Month	350/-
5	C/o Govt. Sr. SSS at Amarapur, Tehsil Ghumarwin Distt. Bilaspur H.P.(SH;-C/ of RWall for Channelization of Nallah).	452783	9500	Two Month.	350/-
6	C/o Footwall Stadium and playground at Govt. Primary School at Dakhiut G.P. Dangar, Tehsil Ghumarwin Distt. Bilaspur H.P.(Deposit)	494727	9900	Three Months	350/-

1.The undersigned reserves the right to accept or reject the tenders without assigning any reasons.

2.The tender form will not be issued to those contractors whose performance is not found satisfactory.


3. G.S.T, EPF, Earnest Money, Cost of Tender & copy of enlistment should be accompanied with the application.

4. Application without documents will not be entertained.

5. Proxy application will not be entertained.

6. The Contractors should have executed two similar types of works 1/3 of each amount put to tender.

7. Tender form shall not be issued to those Contractors who have two or more works in hand.

 Executive Engineer,
Ghumarwin Division,
H.P.P.W.D. Ghumarwin.

Dated- 21/6/2023

No/PW/GHD//CB/EA-I/Tender/2023- 2917-24

Copy alongwith Schedule of quantity is forwarded to :-

1. The Engineer-in-chief HPPWD Shimla-2. for information please.

2. The Chief Engineer (HZ) HPPWD Hamirpur for information please.


3. The Superintending Engineer, 10th Circle, HPPWD Bilaspur H.P. for information please

4. All the Assistant Engineers working under this Division for information

5. Drawing Branch.

6. Account Branch.

7. Notice Board..

 Executive Engineer,
Ghumarwin Division,
H.P.P.W.D. Ghumarwin.

Schedule of Quantity

Name of Work:- Restoration of Rain damages on Ghumarwin Dabla Morshingi toad km 0/00 to 8/00 (SH:- Construction of B/wall at RD 5/170 to 5/179)

Estimated Cost:- Rs. 99,988.00
Earnest Money:- Rs. 2,000.00
Time :- One Month

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto all leads and lift. dressing of sides and bottom and back filling in trenches with excavated suitable material as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.46	Per cubic metre			
2	Providing and Laying concrete 1:5:10 (one cement: five sand:ten crushed stone aggregate) 40 mm (forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.24	Per cubic metre			
3	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.48	Per Square metre			
4	Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe extending through the full width of the structures with slope of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each			
Total:-						

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Special repair to office Building of police station at Bharari Tehsil Ghumarwin Distt. Bilaspur (HP). (SH:- Repair work of truss, door, window, flooring distempering & painting etc).

Estimated Cost:- Rs.	4,98,494.00
Earnest Money:- Rs.	10,000.00
Time :-	Three month

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Dismantling roofing including ridges, hips, valleys, gutters etc. stacking the serviceable materials and disposal of un-serviceable materials within all lead. G.I. Sheet roofing including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	72.54	Per square metre			
2	Dismantling wooden ballies in posts and struts including stacking within 50 metres lead. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	103.00	Per Rmt			
3	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of un-serviceable materials within 50 metres lead. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	96.88	Per square metre			
4	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead. Of area 3 sq. metres and below. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	Each			
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (1/c equivalent design mix). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.56	Per cubic metre			
6	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	Each			
7	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.13	Per cubic metre			
8	Providing and fixing panelled or paneled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding paneling which will be paid for separately. all complete as per direction of Engineer-in-charge. Second class teak wood 35 mm thick shutters. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.81	Per square metre			

	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Sal wood. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.72	Per cubic metre			
10	Providing and fixing plain lining with necessary screws/nuts & bolts/nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete as per direction of Engineer-in-charge (Frame work shall be paid for separately). 12mm thick commercial ply conforming to IS : 1328 BWR type. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	96.88	Per square metre			
11	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250 X 16mm.	1.00	Each			
12	(i) Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : Door : 300 X 10 mm. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Each			
(ii)	Window: 200 x 100 mm	16.00	Each			
13	(i) Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Each			
(ii)	Window: 100 mm	8.00	Each			
14	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm/m ²	72.54	Per square metre			
15	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ² The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.60	Per Rmt.			
16	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	51.24	Per square metre			
17	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete size of tile 600 x 600 mm. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.20	Per square metre			

18	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes, 75 mm diameter. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	37.20	Each				
19	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 75 mm bend.	12.00	Each				
20	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	81.67	Per square metre				
21	Applying printing coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.45	Per square metre				
22	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications. Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	327.44	Per square metre				
23	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade. New work (two or more coats) over and including water thinnable priming coat with cement primer. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	404.66	Per square metre				
Total:-							

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Restoration of Rain Damages to Kandaur Panoh Takrehra Ghumarwin road 0/00 to 8/300(SH:-Providing and Laying Cross drainage at km 6/835).

Estimated Cost:- Rs.	1,56,320.00
Earnest Money:- Rs.	3,200.00
Time :-	Three Month

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.13	Per cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to all level 1:4:8 (One Cement : four coarse sand : eight graded stone aggregate 40 mm nominal size)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.83	Per cubic metre			
3	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.31	Per square metre			

✓

4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work up to plinth level 1:3:6 (1 cement :3 course sand) 6 graded stone aggregate 20 mm nominal size.including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.45	Per cubic metre				
5	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108.as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals.900 mm dia (nine hundred milimetre).dia The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Per running metre				
Total:-							

Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 1,68,217.00
Earnest Money:- Rs. 3,500.00

Time :- Two Month

Name of Work:- Repair and maintainance on Vijaypur Amarpur Dhad Jamman Ghumarwin road km 0/00 to 7/500 (SH:- P/I GSB, G-III and tarring work at RD 7/380 to 7/500)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to an average of 72.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per cubic metre			
2	Construction of granular sub- base by providing close graded material confirming to specifications, mixing in amechanical mix plant at OMC, carriage of mixed material by tippers to work site for all leads & lifts spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density complete to grade - I (Size range 75 mm to 0.075 mm) Having CBR value -30 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.00	Per cubic metre			
3	Supplying and stacking at site G-III 53 mm to 22.4 mm size stone aggregate with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.50	Per cubic metre			
4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.50	Per cubic metre			
5	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 technical specification clause 502. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre			

6	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. On W.B.M / W.M.M. @ 0.4kg/sqm with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre				
7	2 cm premix carpet surfacing with 1.8 cum and 0.90 cum of stone chippings of 13.2 mm size and 11.2 mm size respectively per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 30 with no solvent with in all leads and lifts and other incidentals. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre				
8	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre				
Total:-							

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 4,52,783.00
Earnest Money:- Rs. 9,500.00

Time :- Two Month

Name of Work:- Construction of Govt Sen. Sec. School Amarpur Teh. Ghumarwin Dist. Bilaspur (HP) (SH:- C/o R/wall for Channelization of Nallah).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead .All kinds of soils as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	53.20	Per cubic metre			
3	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached plasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	184.10	Per square metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	83.65	Per cubic metre			
4	Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.00	Each			
Total:-						

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Name of Work:- Construction of Football stadium and playground at Govt. Primary School Dakhuit G.P. Dangar Tehsil Ghumarwin District Bilaspur HP (SH:- construction of R/wall at RD 0/034 to 0/046).

Estimated Cost:- Rs.	4,94,727.00
Earnest Money:- Rs.	9,900.00
Time :-	Three Month

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.20	Per cubic metre			
2	P/L cement concrete - all works upto plinth level- All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 grade dstone aggregate 40 mm nominal size) within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	69.60	Per cubic metre			
3	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached plasters, buttresses, plinth and string courses fillets, kerbs and steps etc within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	106.20	Per square metre			
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	105.60	Per cubic metre			
5	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614.709.1204.3.7 as per direction of Engineer-In-Charge within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Each			

3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification clause 1204.3.8 within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.20	Per cubic metre
Total:-			

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin