

**Himachal Pradesh
Public works Department**

NO-PW-JDT-EA-I Tender NIT/2023-24:-

Dated:-

3096-98

23/06/23

To,

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject:-

Publishing of Tender notice

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Pr. Sec.(PW)to the Govt.of HP letter No-PBW(B)A9(3)1/2020dated Shilma -2the 16th july 2021 as the work mentioned in the tender notice are urgent in nature and public interest

DA:- Notice Inviting Tender

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Copy forwarded the Superintending Engineer 10th Circle
Bilaspur HP PWD Bilaspur for information please

Copy forwarded to the Computer Cell O/O Executive Engineer
(IT Cell) Nigam Bihar Shimla -2 for information and further necessary action action.

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"**

Sealed percentage / item rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender

Form a/w requisite documents: -

03/07/2023 up to 02:00 PM

2. Date of issue/sale of Tender forms against

Cash payment (Non-refundable):-

04/07/2023 up to 03:00 PM

The tender shall be received up to **11:00A.M. on 05/07/2023** and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on **05/07/2023.**

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta. must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

S.No.	Name of work	Estimate d cost	Earnest Money	Cost of form	Time limit	D cla ss
1.	C/O link road G.S.S.School at Jaddu km 0/0 to 1/0 (SH:- C/O PCC Pavement at RD 0/360 to 0/382, Edge wall RD 0/680 to 0/690 & R/Wall at RD 0/705 to 0/725)	459021/-	9200/-	350/-	Two month	D
2.	C/O link road from Dahad to village Dehlwin road km 0/0 to 3/0 (SH:- Formation cutting in km 1/915 to 2/165)	232115/-	4650/-	350/-	Two month	D
3.	A/R & M/O on Jhabola to Goacher road and MDR-116 Ghumarwin Berthin Talai Road (SH:- Repair of pot holes Jhabola to Goacher road in km 4/0 to 6/0 and MDR-116 road Ghumarwin Berthin Talai road in km 16/0 to 18/00)	394590/-	7900/-	350/-	One month	D
4.	A/R & M/O on various roads under Kalol Section (SH:- Repair of pot holes Theh to Buhad road in km 18/0 to 20/0 and Marotan to Dhani road in km 6/0 to 7/500)	495812/-	9900/-	350/-	One month	D
5.	A/R & M/O on Various roads Under Kalol Section (SH:- Repair of pot holes Thatal Jangle Chounta road in km 0/0 to 3/0)	493852/-	9900/-	350/-	One month	D
6.	A/R & M/O on Various roads Under Kalol Section (SH:- Repair of pot holes Theh to Buhad road in km 14/0 to 18/0)	436513/-	8700/-	350/-	One month	D
7.	A/R & M/O on various roads under Kalol section (SH:- Repair of pot holes Bhadoli Kallan Jejwin Salwar Marotan road in km 1/0 to 3/0, 4/0 to 5/0, 7/0 to 8/0, 10/0 to 11/0 and 17/0 to 18/0)	498505/-	10000/-	350/-	One month	D
8.	R/R damages in Badgoun Ree Randoh road km 0/0 to 4/0 (SH:- Maintenance Of Earthen Shoulders RD 0/0 to 2/0)	99874/-	2000/-	350/-	One month	D
9.	A/R & M/O on link road village Ghandeer, link road village kuthera and link road Balhseena to Tarelu road (SH:- Repair of pot holes on link road village Ghandeer km 0/0 to 1/0, link road village Kuthera km 0/0 to 2/0 and link road Balhseena to Tarelu road in km 1/0 to 2/020)	389912/-	7800/-	350/-	One month	D
10.	A/R & M/O on various roads under Jhandutta Sub-Division (SH:- C/O Penetration macadam Between various RDs (i) Link road Chatyal Balh to Dabar road km 0/0 to 2/600 (ii) link road Jhandutta to Behran road in km 0/0 to 1/0 (iii) Link road Jhandutta to Behna Brahmana road in km 0/0 to 2/00)	499200/-	10000/-	350/-	Two month	D
11.	R/R damages on Bukhar to Dhameera road km 0/0 to 4/375 (SH:- C/O R/Wall at RD 3/515 to 3/533)	498694/-	10000/-	350/-	Two month	D
12.	C/O Balance work in Court Yard CC Paver interlocking blocks & Protection/ R Wall at Samshan Ghat (Moxdham) Berri-Darola in G.P. Behna- Jattan Tehsil Jhandutta Distt Bilaspur (HP)	149889/-	3000/-	350/-	Three month	D
13.	Repair of School Building at GPS Kot (Repair of Pillar and flooring etc.)	126347/-	2500/-	350	Nine month	D
14.	Special Repair to the building of Rest house at Berthin Distt. Bilaspur (HP) (SH:- Painting distemping and repair to the door windows and cupboard)	282709/-	6000/-	350/-	Three month	D
15.	A/R & M/O on various roads under Jhandutta Sub-Division (SH:- Hiring of Tractor with Trolly including Labour Hiring)	147390/-	3000/-	350/-	Two month	D
16.	A/R & M/O on various roads under Jhandutta Sub-Division (SH:- Hiring of Excavator cum loader /JCB for removal of slips at Various roads)	156250/-	3100/-	350/-	Three month	D
17.	R/R damages on link road Nakhlehra to Lulhar via Pasol km 0/00 to 5/225 (SH:- C/O R/Wall at RD 4/180 to 4/192)	381065/-	8000/-	350/-	Three month	D

18.	C/O GSS School Building Dhani (SH:- C/O R/wall at RD 0/00 to 0/012)	168824/-	3500/-	350/-	Three month	D
19.	R/R damages on Bukhar to Dhameera road km 0/0 to 4/375 (SH:- C/O R/Wall at RD 3/570 to 3/585)	499768/-	10000/-	350/-	Two month	D
20.	R/R on Ghumawin Berthin Talai (MDR-116) road km 0/0 to 31/0 (SH:- Maintenance of Earthen Shoulder at km 18/0 to 20/500)	193830/-	3900/-	350/-	One month	D
21.	R/R damages on various roads under Sub-Division Kalol (SH:- Hiring of Tractor With Trolly)	98400/-	2000/-	350/-	Two month	D
22.	A/R & M/O on Bhagatpur to Peerthan pump House road km 0/0 to 1/500 (SH:- Maintenance of pot holes and WBM in km 0/0 to 1/0)	499690/-	10000/-	350/-	Three month	D
23.	C/O link road from Main road Barsar Shahtalai to Rada km 0/00 to 1/700 (SH:- C/O 900 mm Hume pipe culvert at RD 0/015 i/c wing wall) OTMNP	489518/-	10000/-	350/-	Two month	D
24.	Repair of Science block Govt. SS School Building at Kalol Tehsil Jhandutta Distt. Bilaspur (HP) (SH:- Repair of Ridge Valley hips gutter etc) Deposit Work	307949/-	6200/-	350/-	Two month	D
25.	C/O link road PHC Gugga Mandir to Gah km 0/0 to 3/00 (SH:- C/O PCC R/Wall at RD 0/0 to 0/010 & PCC Causeway at RD 1/500 to 1/250) Deposit Work	322149/-	6400/-	350/-	Three month	D
26.	A/R & M/O various roads under Buhad section (SH:- Repair of pot holes Koshrian to Jaddu via Brahmni Kallan km 5/00 to 9/00 & Dholag to Malroun road km 0/00 to 5/00)	499931/-	10000/-	350/-	One month	D
27.	C/O Drain & Protection wall in division Campus HPPWD Jhandutta (SH:- C/O PCC B/Wall at RD 0/00 to 0/016 and Drain at RD 0/0 to 0/075)	367829/-	7400/-	350/-	Two month	D
28.	R/R on MDR-116 (Ghumarwin Berthin Talai) road km 14/00 to 25/00 (SH:- C/O PCC R/Wall from km 14/755 for Protection of Abutment of Bhailu Bridge Talai Side)	176194/-	4000/-	350/-	Three month	D
29.	C/O Circular road in Tehsil Jhandutta Distt. Bilaspur HP (SH:- P/L interlocking paver Block at RD 1/420 to 1/475 Near BDO Office)	486920/-	9700/-	350/-	Three month	D
30.	A/R & M/O Non Residential Building under Sub-Division Jhandutta (SH:- C/O R/Wall & Boundary Wall at RD 0/072 to 0/0930 Under NR Building)	484799/-	9200/-	350/-	Three month	D
31.	C/O link road Bothu to Pump House Paploa km 0/00 to 4/00 (SH:- C/O 900 mm dia HPC at RD 0/600 with wing wall both side) DC Deposit	211695/-	4600/-	350/-	Two month	D
32.	C/O new Toilet Block for Boys Govt. S S School at Malroun.	413863/-	8300/-	350/-	Two month	D
33.	C/O Manan to Murthal road in GP Sunhani km 0/0 to 1/00 (SH:- P/L Wearing and tarring at RD 0/500 to 0/750)	490827/-	10000/-	350/-	Two month	D
34.	Balance work of Health Sub- Center Building at Hirapur Tehsil Jhandutta Distt. Bilaspur HP (SH:- C/O R/Wall, Boundary Wall & Courtyard interlocking concrete paver blocks) Deposit Work	499885/-	10000/-	350/-	Three month	D
35.	C/O link road Govt. Sr.Sec. School at Jaddu Tehsil Jhandutta Distt. Bilaspur HP (SH:- C/O Cement Concrete Pavement at RD 0/300 to 0/315 & 0/600 to 0/0665) Deposit Work	498719/-	10000/-	350/-	Three month	D
36.	R/R Damages on road to Baloh via rapper km 0/00 to 2/00 (SH:- P/L Pavement at RD 1/400 to 1/500)	394129/-	8000/-	350/-	Two month	D
37.	Balance work of Govt. Primary School Buhar Tehsil Jhandutta Distt. Bilaspur HP (SH:- C/O Mumty over stair hall 1 st floor & Protection wall Right side of Building at RD 0/00 to 0/09.70) Deposit Work	283100/-	5800/-	350/-	Two month	D
38.	C/O Circular road at Jhandutta km 0/0 to 4/904 (SH:- P/L GSB, CC 1:3:6, CC 1:2:4 and interlocking Paver Block at RD 1/675 to 1/730 near Police Thana)	497021/-	10000/-	350/-	Two month	D
39.	C/O link road from Dabber to Thurān road km 0/0 to 0/600 (SH:- P/L M-30 CC Pavement at RD 0/345 to 0/415)	294576/-	6500/-	350/-	Three month	D
40.	C/O Gangloh to Malroun road km 0/0 to 18/00 (SH:- C/O 600 mm dia HPC at RD 14/595 & U-shape drain at RD 14/565 to 14/595)	237649/-	4800/-	350/-	Two month	D
41.	A/R & M/O non Residential Building Under Sub-Division Jhandutta (SH:- C/O R/Wall at Division and Sub-Division Complex at Jhandutta)	494997/-	10000/-	350/-	One month	D
42.	C/O Manan to Morthal road in GP Sunhani km 0/0 to 1/00 (SH:- P/L wearing and Tarring at RD 0/250 to 0/500)	490827/-	10000/-	350/-	Two month	D
43.	C/O Admin block at Polytechnic college Kalol Tehsil Jhandutta Distt. Bilaspur HP (SH:- P/L Paver block in Court Yard RHS)	497544/-	10000/-	350/-	Two month	D
44.	C/O Admin block at Polytechnic College Kalol Tehsil Jhandutta Distt. Bilaspur HP (SH:- P/L Paver block in court Yard RHS)	481664/-	10000/-	350/-	Two month	D
45.	C/O circular road at Jhandutta km 0/0 to 4/904 (SH:- P/L GSB, CC 1:3:6, CC 1:2:4 and interlocking paver block at RD 1/300 to 1/355 Near Nawn)	481252/-	9600/-	350/-	Three month	D
46.	A/R & M/O Non Residential building under Sub-Division Jhandutta (SH:- C/O PCC R/Wall at Sub-Division and Division Complex at Jhandutta)	494367/-	9900/-	350/-	Two month	D

47.	R/R damages on Gehrwin to Behna jattan road km 0/00 to 7/500 (SH:- C/O R/Wall at RD 4/750 to 4/757.75)	499914/-	10000/-	350/-	Three month	D
48.	Repair of Ayurvedic Health Center Duhak GP Badgoun Gallu Tehsil Jhandutta Distt. Bilaspur HP (SH:- Balance work of Windows, Handles Paints, Interlocking pavers etc.)	115392/-	2500/-	350/-	Three month	D
49.	Repair of Health Center Kot GP Paploha Tehsil Jhandutta Distt. Bilaspur HP (SH:- P/F anti skid Tile & Distempring etc Deposit work	371150/-	7500/-	350/-	Three month	D
50.	A.R & M/O on Berthin Chhat Dabhiri road km 0/0 to 1/0 & link road GPS Jhareri to Balh km 0/0 to 1/0 (SH:- Repair to pot holes)	499902/-	10000/-	350/-	One month	D
51.	C/O Chounta to Dhani Pukhar road km 16/00 to 27/00 (SH:- C/O PCC Causeway at RD 23/205 to 23/215 & 23/330 to 23/340)	493840/-	10000/-	350/-	Two month	D
52.	R/R damage on Chounta to Dhani Pukhar road km 16/00 to 27/00 (SH:- C/O PCC R/Wall at RD 26/070 to 26/082)	499158/-	10000/-	350/-	Two month	D
53.	R/R damages on Chounta to Dhani Pukhar road km 16/00 to 27/00 (SH:- C/O PCC Causeway at RD 25/800 to 25/810 & V-shape drain at RD 25/810 to 25/905)	494332/-	10000/-	350/-	Two month	D
54.	R/R Vijaypur to Rahiyan via Auhar (SH:- C/O R/Wall at RD 0/850 to 0/862) Near Kaseh road Junction)	499517/-	10000/-	350/-	Two month	D
55.	C/O link road Galliyan to Bala road km 0/0 to 5/00 (SH:- C/O R/Wall at RD 0/050 to 0/076)	486960/-	9700/-	350/-	One month	D

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.
2. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy Application will not be entertained.
6. Payment for the works under N.I.T shall be made as & when sufficient funds are available with the Department.

Executive Engineer
Jhandutta Division
HPPWD Jhandutta

No-PW-JDT-CB-Tender NIT/2023-24:-

3085-95

Dated:-

23/06/23


Copy forwarded to the following for information and necessary action Please:-

1. The Engineer -in-Chief HP PWD Nirman Bhawan Shimla
2. All the Chief Engineer in HP PWD
3. The Superintending Engineer 10th Circle HP PWD Bilaspur
4. All the Assistant Engineer Working under this Division
5. The B.D.O Jhandutta
6. A/B & D/B in this office
7. Various Contractors working under this office
8. Notice Board

Executive Engineer
Jhandutta Division
HPPWD Jhandutta

Certificate

Certified that the tenders called vide this office letter
No. PW-JDT EA-I-Tender /2023-24- 3085-95 dated
23/06/23 is emergent nature and in Public interest.


Executive Engineer
Jhandutta Division
HPPWD Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- Construction of Link Road G.S.S.School at jaddu Km 0/0 to 1/0 (SH:- C/o P.C.C. Pavement at RD 0/360 to 0/382 , Edge wall Rd 0/680 to 0/690 & R/wall at RD 0/705 to 0/725) .		Estimated cost:- ₹ 459021.00		Only	
		Earnest Money:- ₹ 9200.00		Only	
		Time allowed:- Two Months			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
		Figures	words		
1	Excavation in cutting in soil by manual means with any lead excavation for roadway in soil using manual means for carrying of cut earth to embankment site with any lead and lead as per technical specification clause 302.3 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto any lead and left dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in Charge. including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. and other tax	45.76	212.70 INR Two hundred Twelve and Paise seven zero Only	Per Cubic Meter	9733.00
2	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octri. and other tax	10.06	1531.30 INR one Thousand Five hundred thirty one & Paise three zero Only	Per Cubic Meter	15405.00
3	Providing and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement into four sand into eight graded stone aggregate 40mm.(twenty five millimetre nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.03	5368.30 INR five thousand three hundred sixty eight and paise three zero only	Per cubic metre	27003.00

	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded/ crushed stone aggregate 20mm (forty millimetre) nominal mix curing complete including cost of form work within all leads & lifts carriage of material and other incidentals as per direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	6.71	6874.90	INR six thousand eight hundred seventy four and paise nine zero only	Per cubic metre	46131.00
5	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	73.35	4732.80	INR Four thousand seven hundred thirty two and paise eight zero only	Per cubic metre	347151.00
6	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	40.00	339.95	INR Three hundred thirty nine and Paise ninety five Only	Each	13598.00
Total:-						459021.00

Quoted Rate in Figures
Quoted Rate in Words

%age +/-

Executive Engineer,
Jharkhand Division,
HPPWD, Jharkhand

SCHEDULE OF QUANTITY

Name of work :- C.O link road from Dahad to village Dehlwin road km. 0/0 to 3/0
(SH:- Formation Cutting in km. 1/915 to 2/165)

Name of work :- C./O link road from Dahad to village Dehlwin road Km. 0/0 to 3/0						
(SH:- Formation Cutting in Km. 1/915 to 2/165)						
Sr. No.	Description of items	Quantity	Estimated cost:- ₹ 232115.00		Only	
			Earned Money:- ₹ 4650.00		Only	
			Time allowed:- Two Month			
			Figures	Rate	Unit	
			words			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 51.09 Cubic metre @ Rs.600/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	1021.86	227.15	INR Two Hundred Twenty seven and Paise Fifteen Only	Per Cubic Meter	232115
Total:-						232115
Quoted Rate in Figures:-						%age +/-
Quoted Rate in Words :-						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O on Jhabola to Goacher road and MDR-116 Chumarwin Berthin talai road (SH:-Repair of potholes Jhabola to Goacher road in km 4/0 to 6/0 and MDR -116 road Chumarwin Berthin talai Road in Km 16/0 to 18/00)		Estimated cost:- ₹ 394590.00		Only		
		Earnest Money:- ₹ 7900.00		Only		
		Time allowed:- One Month				
Sr. No.	Description of items	Quantity	Rate	Unit	Amount	
		Figures	words			
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method as per MORD Technical Specification for rural road (1st Revision 2014) Clause Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per MORD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 501,502 and 503.The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or out put by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	932.00	423.38	INR Four Hundred Twenty- Three and paise thirty- eight only	Sqm	394590.00
Total:-						394590.00
Quoted Rate in Figures				%age +/-		
Quoted Rate in Words						

Executive Engineer,
Jhandaulla Division
HPPWD, Jhandaulla

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O on Various Roads Under Kalol section (SH:-Repair of potholes Teh to Bhoad Road in km 18/0 to 20/0 and Marotan to Dhani Road in Km 6/0 to 7/500)		Estimated cost:- ₹ 495812.00		Only
		Earnest Money:- ₹ 9900.00		Only
Sr. No.	Description of items	Quantity	Time allowed:- One Month	
			Rate	Unit
		Figures	words	Amount
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method as per MORD Technical Specification for rural road (1st Revision 2014) Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per MORD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications. Clauses 501, 502 and 503. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or out put by this contract shall be payable by	1171.08	INR Four Hundred Twenty-Three and paise thirty-eight only	Sqm
Quoted Rate in figures		Total:-		495812.00
Quoted Rate in words		%		

Executive Engineer,
Jhanda Division
HPWD, Jhanda

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O on Various Roads Under Kalol section (SH:-Repair of potholes Thatal Jangle Chomta Road in km 0/0 to 3/0)

Name of Work:-A/R & M/O on Various Roads Under Kalol section (SH:-Repair of potholes Thatal Jangle Chonta Road in km 0/0 to 3/0)		Estimated cost:- ₹ 493852.00		Only		
		Earnest Money:- ₹ 9900.00		Only		
		Time allowed:- One Month				
Sr. No.	Description of items	Quantity	Rate	Unit	Amount	
			Figures			words
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method as per MORD Technical Specification for rural road (1st Revision 2014) Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per MORD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 501,502 and 503. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or out put by this contract shall be payable by	1166.45	423.38	INR Four Hundred Twenty- Three and paise thirty- eight only	Sqm	493852.00
Total:-						493852.00
Quoted Rate in figures		%age				
Quoted Rate in words						

Executive Engineer,
Jhanduta Division
HPPWD, Jhanduta


SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O various roads under Kalol Section (SH:- Repair of Potholes they to buhad road Km 14/00 to 18/00)		Estimated cost:- ₹ 436513.00		Only		
		Earnest Money:- ₹ 8700.00		Only		
Sr. No.	Description of items	Quantity	Time allowed:- One Month		Amount	
			Figures	Rate words		Unit
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and leveling the bottom, cleaning the same with compressed air or any appropriate method as per MORD Technical Specification for rural road (1st Revision 2014) Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per MORD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 501, 502 and 503. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or out put by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1031.02	423.38	INR Four Hundred Twenty-Three and paise thirty-eight only	Sqm	436513.00
Total:-						436513.00
Quoted Rate in Figures:-		%age +/-				
Quoted Rate in Words :-						

Executive Engineer,
 Jhanda Division
 HPPWD, Jhanda

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O on Various Roads Under Kalol section (SH:-Repair of potholes Bhadoli Kallan Jeivin Salwar Marotan road in km 1/0 to 3/0, 4/0 to 5/0, 7/0 to 8/0,10/0 to 11/0 and 17/0 to 18/0)		Estimated cost:- ₹		498505.00	Only	
		Earnest Money:- ₹		10000.00	Only	
		Time allowed:- One Month				
Sl. No.	Description of items	Quantity	Rate	Unit	Amount	
			Figures	words		
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method as per MORD Technical Specification for rural road (1st Revision 2014) Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per MORD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 501,502 and 503. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or out put by this contract shall be payable by	1177.44	423.38	INR Four Hundred Twenty- Three and paise thirty- eight only	Sqm	498505.00
Total:-						498505.00
Quoted Rate in figures		%		age		
Quoted Rate in words						


 Executive Engineer,
 Jhandutta Division
 HPPVWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- Restoration of Rain damages in Badgoun Ree Radoh Road km 0/0 to 4/0 (Sh :- Maintenance of Earthen Shoulders Rd 0/0 to 2/0)

Sr. No.	Description of Items	Quantity	Estimated cost:- ₹ 99874.00		Only
			Earnest Money:- ₹ 2000.00	Time allowed:- One Month	Only
			Rate	Unit	Amount
		Figures	words		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/ Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a head of 1000 m. as per technical specification Clause 1903 complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1898.75	52.60 INR Fifty two and Paise sixty Only	Per square Meter	99874.00
Total:-					99874.00
Quoted Rate in Figures					%age +/-
Quoted Rate in Words					

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O on Link road Village Chandeer , Link road village Kuthera and link road Balhseena to tareru road (SH:-Repair of potholes on Link road Village Chandeer km 0/0 to 1/0, Link road village Kuthera km 0/0 to 2/0 and link road Balhseena to tareru road in km 1/0 to 2/020)		Estimated cost:- ₹ 389912.00		Only		
		Earnest Money:- ₹ 7800.00		Only		
		Time allowed:- One Month				
Sr. No.	Description of items	Quantity	Rate	Unit	Amount	
		Figures	words			
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method as per MORD Technical Specification for rural road (1st Revision 2014) Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per MORD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 501,502 and 503.The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or out put by this contract shall be payable by the contractor and Government shall not	920.95	423.38	INR Four Hundred Twenty- Three and paise thirty- eight only	Sqm	389912.00
Total:-						389912.00
Quoted Rate in Figures		%		age +/-		
Quoted Rate in Words						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY.

Name of Work :-A/R & M/O on Various Roads Under Jhandutta Sub -division (SH:- Construction of Penetration macadam between Various RDs (i) Link Road Chatyal Balh to Dabar Road Km 0/0 to 2/600 (ii) Link Road Jhandutta to Behran Road in Km 0/0 to 1/0 (iii) Link Road Jhandutta to Behna Brahmana road in Km 0/0 to 2/00)		Estimated cost:- ₹ 499200.00		Only	
		Earnest Money:- ₹ 10000.00		Only	
		Time allowed:- Two Months			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
1	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and key aggregates and rolling with a three wheel 80-100 kN static roller to achieve the desired degree of compaction as per Technical Specification Clause 506. 50 mm thick The rate including of Goods, Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1920.00	260.00 INR Two hundred sixty and Paise Zero Only	Per Square meter	499200.00
Total:-					499200.00
Quated Rate in Figures		%age +/-			
Quated Rate in Words					

Executive Engineer,
Jhandutta Division,
HPPWD Jhandutta.

SCHEDULE OF QUANTITY.


Name of Work :- R/R damages on Bukhar to Dhameera Road Km 0/0 to 4/375 (SH:- C/O R/wall at RD 3/515 to 3/533).

Sr. No.	Description of items	Estimated cost:- ₹ 498694.00 Only			
		Earnest Money:- ₹ 10000.00 Only		Time allowed:- Two Months	
		Quantity	Figures	Rate	Unit
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	58.68	212.70	INR Two Hundred Twelve and Paise Seven zero Only	Per Cubic Meter
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm nominal size) and curing complete including the cost of form work in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	84.92	5428.30	INR Five Thousand four Hundred Twenty eight and Paise three zero Only	Per Cubic Meter
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.18	1308.10	INR One Thousand Three Hundred eight and Paise one zero Only	Per Cubic Meter
4	Providing weep holes in brick masonry / stone masonry, plain / reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	42.00	315.10	INR Three Hundred fifteen and Paise one zero Only	Each
Total:-				%age +/-	498694.00
Quoted Rate in Figures					
Quoted Rate in Figures					

Executive Engineer,
Jhanda Division,
HPPWD, Jhanda

SCHEDULE OF QUANTITY.

Name of Work :- C/O Balance work in Court Yard C.C.Paver interlocking blocks & Protection/R/wall at Samshan Ghat (Moxdham) Berri-Darola in G.P Behna - Jattan Teh, Jhandutta Distt Bilaspur (H.P).		Estimated cost:- ₹ 149889.00		Only		
		Earnest Money:- ₹ 3000.00		Only		
		Time allowed:- Three Month				
Sr. No.	Description of Items	Quantity	Rate	Unit	Amount	
		Figures	words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10sqm on plan), including dressing of sides and ramming excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All Kind Of Soil. Including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi, and other tax	24.50	212.70	INR Two hundred twelve and Paise seventy Only	Per Cubic Meter	5211.00
2	Providing and laying Stone soling properly handpacked filling interstices with and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per H.P.PWD specification. 100 mm spread thickness (finished work including materials and labour) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	8.10	1440.50	INR one Thousand Four Hundred forty and Paise Fifty Only	Per Cubic Meter	11668.00
3	Providing and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement isto four sand isto eight graded stone aggregate 25 mm.(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge.	17.01	5368.30	INR Five Thousand three Hundred sixty eight and Paise thirty Only	Per Cubic Meter	91315.00
4	Providing & laying of Interlocking concrete block pavement having thickness 60 mm as per drawing and technical specification clause 1504. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	49.72	838.60	INR eight Hundred thirty eight and Paise sixty Only	Per Sqm Meter	41695.00
Quoted Rate in Figures		Total				
Quoted Rate in words		%				
		age +/-				
		Total				
		149889.00				


 Engineer
 Jhandutta Division
 Biliaspur

SCHEDULE OF QUANTITY.

Name of Work :- Repair of School Building at G.P.S kot (SH:- Repair of Pillar and flooring etc)		Estimated cost:- ₹ 126347.00		Only
		Earnest Money:- ₹ 2500.00		Only
		Time allowed:- Nine Months		
Sr. No.	Description of items	Quantity	Rate	Amount
		Figures	words	
1	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	77.36	INR Two Hundred and Paise Ten Only	15480.00
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	84.08	INR One Hundred Twenty One and Paise Sixty Only	10224.00
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	0.54	INR Two Hundred Twelve and Paise Seventy Only	115.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	0.14	INR Five Thousand One Hundred Sixty One and Paise Eighty Only	723.00
5	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	0.79	INR six Thousand Nine Hundred eighty one and Paise thirty Only	5515.00
6	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	29.76	INR Four Hundred twenty eight and Paise fifty Only	12752.00

7	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 600x600 mm. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	47.60	1626.90	INR One Thousand Six Hundred Twenty Six and Paise Ninety Only	Per square metre	77440.00
8	Providing and fixing M.S. BP Sheet 1.66mm to 20mm thick in eaves board/facia/soffit/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.27	1805.30	INR One thousand Eight hundred five and Paise thirty Only	Per square metre	4098.00
TOTAL:-						126347.00
	Quoted Rate in Figures		%age +/-			
	Quoted Rate in Words					

Executive Engineer,
Jhantuta Division
HPPWD Jhantuta

SCHEDULE OF QUANTITY

Name of Work :- Special repair to the building of Rest House at berhin distt. Bilaspur (HP)		Estimated cost:- ₹		282709.00	Only
) (SH:- Painting distempering and repair to the door windows and cup board)		Earnest Money:- ₹		6000.00	Only
		Time allowed:- Three Month			
Sr. No.	Description of Items	Quantity	Rate	Unit	Amount
			Figures words		
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 q.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge With cement mortar 1:4 (1 cement : 4 fine sand)technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental	92.64	264.35 INR twelve paise seventy only	Per square metre	24489.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	591.22	11.15 INR Rupees eleven and paise fifteen only	Per square metre	5992.00
3	Distempering with dry distemper of approved brand and manufacture (two or more coats) of required shade on new work, over and including water thinnable priming coat to give an even shade.	591.22	72.45 INR Rupees seventy two and paise forty five only	Per square metre	42834.00
4	French spirit polishing :Two or more coats on new works including a coat of wood filler	50.74	208.55 INR Two hundred eight and paise fifty five only	Per square metre	10582.00
5	Finishing walls with water proofing cement paint of required shade :Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 ltrs/10 sqm complete including cost of Priming coat.	89.77	59.20 INR fifty nine and paise twenty only	Per square metre	5314.00
6	Painting wood work with Deluxe Multi Surface Paint of required shade: Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	362.56	94.30 INR ninety four and paise thirty only	Per square metre	34189.00
7	Painting Steel work with Deluxe Multi Surface Paint to give an even shade: Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	117.87	89.90 INR eighty nine and paise ninety only	Per square metre	10597.00
8	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Old work (one or more coats)	448.17	45.00 INR forty five and paise zero only	Per square metre	20168.00
9	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.For thickness of tiles 10 mm to 25 mm	31.94	31.20 INR thirty one and paise twenty only	Per square metre	997.00

10	P/L ceramic glazed floor tiles laid on 20 mm thick Cement Mortar (1:4) with grey cement slurry @ 3.3 kg/ sqm	31.94	787.05	INR seven hundred eighty seven and paise five only	Per square metre	25138.00
11	Providing and fixing white vitreous china pedestal type water closet European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	2	4330.2	INR four thousand three hundred thirty and paise twenty only	Each	8660
12	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	2.00	2643.75	INR two thousand six hundred forty three and paise seventy five only	Each	5288.00
13	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms 15 mm nominal bore	4.00	618.80	INR six hundred eighteen and paise eighty only	Each	2475.00
14	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall :15 mm dia nominal bore	12.40	329.10	INR three hundred twenty nine and paise eighty only	Per metre	4081.00
15	Providing and fixing cup board shutters with 25 mm thick veneered particle board IS : 3097 marked, exterior grade (Grade II), of approved make, including IInd class teak wood lipping of 25 mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of Engineer-in With non decorative veneering on both sides	38.66	1384.65	INR one thousand three hundred eighty four three and paise sixty five only	Per square metre	53531.00
16	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with :4.0 mm thick glass panes	5.01	847.55	INR eight hundred forty seven and paise fifty five only	Per square metre	4246.00
17	Providing and fixing ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc. complete:100x75x4 mm	12.00	97.15	INR ninety seven and paise fifteen only	Each	1166.00
18	Providing and fixing aluminium pull bolt lock, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws bolts, nut and washers etc. complete.	6.00	75.80	INR seventy five and paise eighty only	Each	455.00
19	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :100 mm	6.00	50.75	INR fifty and paise seventy five only	Each	305.00

20	Providing and fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete. 40 mm	8.00	191.60	INR one hundred ninety one and paise sixty only	Each	1533.00
21	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purins, rafters and trusses and including cutting to size and shape wherever required. 0.80 mm thick with zinc coating not less than 275 gm/m ²	11.52	984.10	INR nine hundred eighty four and paise ten only	Per square metre	11337.00
22	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete.	15.00	622.15	INR six hundred twenty two and paise fifteen only	Per running metre	9332.00
Total						282709.00
Quoted Rate in Figure:-		%age +/-				
Quoted Rate in Words:-						

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O on various roads under Jhandutta Sub- Division (SH:- Hiring of Tractor with Trolly including Labour Hiring)

Estimated cost:- ₹ 147390.00 Only
Earnest Money:- ₹ 3000.00 Only
Time allowed:- Two Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	Words		
1	Hiring of tractor with trolly for Shifting of materials carriage/ shifting of excavated material or any type of materials as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer- in- Charge.	40.00	2050.00	Rupees thousand fifty only	two Per day	82000.00
2	Hiring of labour for loading and unloading of material from tractor trolly and cleaning of road surface making ready the road surface to repair of pot holes etc as per the direction of Engineer- in- Charge.	130	503	Rupees hundred three only	Five Per day	65390.00
Total:-						147390.00
Quoted Rate in Figures						
Quoted Rate in Words						
%						

Estimate No.
DNIT No.
Head of Account
Available Fund :-

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O on various roads under Jhandutta Sub-Division (Sl:- Hiring of Excavator cum loader /JCB for removal of slips at Various roads)		Estimated cost:- ₹ 156250.00		Only	
		Earnest Money:- ₹ 3100.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of items	Quantity	Rate		Amount
			in Figures	in words	Unit
1	Providing one number Excavator cum loader / JCB in good Condition on hire bases at site of work for removal of slips including Cost of P.O.L.Establishment and other repair charges of the side machinery and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in- Charge. The contractor will be fully responsible for any loss/damages to any private/ Govt property during the execution of work. And No extra charge will be payable to the contractor for anytype of loss/repair of machinery during corresponding period.	125.00	1250.00	INR one thousand two hundred fifty and paise nil only	Per Hour
Total:-					
	Quated Rte in Figures	%			156250.00
	Quated Rte in Words				

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damages on link Road Nahlehura to Indhar via Pasol Km. 0/00 to 5/225. (SH:- C/O R/Wall at Rd. 4/180 to 4/192.)

Name of Work :- Restoration of rain damages on link Road Naklehtra to Jaluhar via Pasol Km. 0/00 to 5/225. (SH:- C/O R/Wall at Rd. 4/180 to 4/192.)					Estimated cost:- ₹ 381065.00		Only
					Earnest Money:- ₹ 8000.00		Only
					Time allowed:- Three Month		
Sr. No.	Description of Items	Quantity	Figures	Rate	Unit	Amount	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3,5 and 1611 and as per the entire satisfaction and direction of Engineer-in-Charge.	1234.71	132.40	INR one Hundred & Thirty two and Paise forty Only		163476	
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i.e setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	22.20	212.70	INR two Hundred & Twelve and Paise seventy Only	Per Cubic Meter	4722.00	
3	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth : including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	37.85	5328.80	INR Five Thousand three Hundred & Twenty eight and Paise eighty Only	Per Cubic Meter	201695.00	
4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	10.00	315.30	INR Three Hundred & thirty nine and Paise fifty five Only	Per Cubic Meter	3153.00	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	6.12	1310.30	INR One Thousand Three Hundred & ten and Paise thirty Only	Each	8019.00	
Total:-					381065.00		
Quoted Rate in Figure:-					%age +/-		
Quoted Rate in Words:-							

Executive Engineer,
Jharkhand Division
HPPWD, Ranchi

SCHEDULE OF QUANTITY

Name of Work :- C/O G S School Building Dhani (SH:-C/O R/wall at Rd. 0/00 to 0/012.)

Estimated cost :- ₹ 168824.00
Earnest Money :- ₹ 13500.00
Time allowed :- Three Month

Only
Only

Sr. No.	Description of Items	Quantity	Figures	Rate	Unit	Amount
				Words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	19.68	212.70	Two Hundred Twelve and Paise seventy Only	Per Cubic Meter	4186
2	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone agg. 40 mm. nominal size) and curing complete including the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	29.56	5428.30	Five thousand four Hundred twenty eight & Paise thirty only	Per Cubic Meter	160461.00
3	Providing weep holes in brick masonry / stone masonry, plain / reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	10.00	315.10	Three Hundred & fifteen and Paise ten Only	Each	3151.00
4	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammer, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. All kinds of soil. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	3.00	342.00	Three hundred forty two and Paise zero only	Per Cubic Meter	1026.00
Total:-						168824.00

Quoted Rate in Figure:-

Quoted Rate in Words:-

%age +/-

Executive Engineer,
Jhanda Division
HPPWD Jhanda

SCHEDULE OF QUANTITY.

Name of Work :- R/R damages on Bukhar to Dhameera Road Km 0/0 to 4/375 (SH:- C/O R/wall at RD 3/570 to 3/585).

Name of Work :- R/R damages on Bukhar to Dhameera Road Km 0/0 to 4/375 (SH:- C/O R/wall at RD 3/570 to 3/585).		Estimated cost :- ₹ 499768.00		Only	
		Earnest Money:- ₹ 10000.00		Only	
		Time allowed:- Two Months			
Sr. No.	Description of Items	Quantity	Rate	Unit	Amount
		Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	62.40	212.70 INR Two Hundred Twelve and Paise Seven zero Only	Per Cubic Meter	13272.00
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete including the cost of form work in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	83.79	5428.30 INR Five Thousand four Hundred Twenty eight and Paise three zero Only	Per Cubic Meter	454837.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	15.53	1308.10 INR One Thousand Three Hundred eight and Paise one zero Only	Per Cubic Meter	20315.00
4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	36.00	315.10 INR Three Hundred fifteen and Paise one zero Only	Each	11344.00
Total:-					499768.00
Quoted Rate in Figures		%		age +/-	
Quoted Rate in Figures					

Executive Engineer
Jharkhand Division
HPPWD, Jharkhand

SCHEDULE OF QUANTITY

Name of Work :- R/R on Ghumarwin Berthin Talai (MDR-116) Road Km 0/0 to 31/0 (SH:- Maintenance of earthen Shoulder at km 18/0 to 20/500)	Estimated cost:- ₹ 193830.00		Only
	Earnest Money:- ₹ 3900.00		Only
	Time allowed :- One Month		

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other leaves / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	4200.00	46.15	INR Forty Six and Paise fifteen Only	Per square Meter	193830.00
Total:-						193830.00
Quoted Rate in Figures		%age +/-				
Quoted Rate in Words						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damages on various roads under Sub- Division Kalol (SH:- Hiring of Tractor with Trolley .)		Estimated cost:- ₹ 98400.00				Only
		Earnest Money:- ₹ 2000.00				Only
		Time allowed:- Two Month				
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount
1	Hiring of tractor with trolley for Shifting of materials carriage/ shifting of excavated material or any type of materials as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in- Charge.	48.00	2050.00	Ruppes thousand fifty and paise nil only	Two Per day	98400.00
		Total:-				98400.00
Quated Rate in Figures						
Quated Rate in Words						

Executive Engineer,
Jhandutta Division
HPPVMD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O on Bhagatpur to peethan pump House road km.0/0 to 1/500 (Maintenance of Pot holes and WBM in km 0/0 to 1/0)		Estimated cost:- ₹ 499690.00		Only
		Earnest Money:- ₹ 10000.00		Only
Sr. No.	Description of items	Quantity	Time allowed:- Three Months	
			Rate	Unit
		Figures	words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1077.75	INR Three Hundred Eighty three and Paise four zero Only	Per Square Meter 413209.00
2	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and travelling as per technical specification Clause 1906.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	327.79	INR Two Hundred sixty three and Paise eighty three Only	Per Square Meter 86481.00
Total:-				499690.00
Quoted Rate in Figures:-		%age +/-		
Quoted Rate in Words :-				

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work:- C/O of Link Road from main road Barsar Shah Talai to Rada Km. 0/00 to 1/700. (SH:- C/O 900 mm dia Humc pipe culvert at RD. 0/015 i/c wing wall) OTMNP									
Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures	Estimated Cost:		AMOUNT Rs. P		
					Time Limit:	Words			
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	39.92	Per cubic metre	212.70	Two Hundred Twelve and Paise seventy Only	10000.00	8491.00		
2	Providing and laying cement concrete work 1:4:8 (one cement: four sand: eight graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.82	Per cubic metre	5368.30	Five thousand three hundred sixty eight and paise thirty only	15139.00			
3	Providing and laying cement concrete work 1:3:6 (one cement: three sand: six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.86	Per cubic metre	5897.80	Five thousand eight hundred ninty seven and paise eighty only	182006.00			
4	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete including the cost of form work in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	34.46	Per cubic metre	4732.80	Four thousand seven Hundred thirty two & Paise eighty only	163092.00			

5	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.00	Each	339.95	Three Hundred & Thirty nine and Paise fifty five Only	6799.00
6	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Per cubic metre	1345.70	One thousand three hundred forty five and Paise seven zero only	16148.00
7	Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1106, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.00	Per running metre	4020.50	Four thousand twenty Paise five zero only	60308.00
8	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	109.40	Per running metre	343.10	Three hundred forty three Paise one zero only	37535.00
Total in Figures						489518.00
Quoted Rate in Figure:-		%		age +/-		
Quoted Rate in Words:-						

Executive Engineer,
Jharkhuta Division
HPPWD, Jharkhuta

SCHEDULE OF QUANTITY.

Name of Work :- Repair of science block Govt. Sr.Sec.School Building at Kalol Teh.Jhanda Dutt Distt		Estimated cost:- ₹ 307949.00 Only			
Bilaspur (H.P) (SH :- Repair of Ridge Valley hips gutter etc) Deposit Work		Earnest Money:- ₹ 6200.00 Only			
		Time allowed:- Two Months			
Sr. No.	Description of Items	Quantity	Rate	Unit	Amount
			Figures words		
1	Steel work welded in built up sections/ framed work,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder,railings, brackets, gates and similar works,including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	101.70	INR one Hundred Five and nine paise zero only	Per Kilogramme	10770.00
2	Providing and fixing M.S. BP Sheet 1.66 mm to 2mm thick in eaves board/facade/sofite/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	13.50	INR One Thousand Six Hundred Ninety Eight and One Paise zero only	Per Square meter	22924.00
3	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately). 6 mm thick Cement fiber board as per IS: 14862 The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	25.00	INR Six Hundred Twelve and six paise zero only	Per Square meter	15315.00
4	Providing and fixing 15 cm wide, 45 cm overall semi circular plain G.S. sheet gutter with iron brackets 40X3mm size, bolts, nuts and washers etc., including making necessary connections with rain water pipes complete 0.63 mm thick with zinc coating not less than 275 gm/m ² The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	71.40	INR Five Hundred Ninety Five and Nine Paise zero only	Per Running Meter	42547.00
5	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	179.27	INR Eight Hundred Sixty one and five paise zero only	Per Square meter	154441.00
6	Providing ridges or hips of width 60 cm overall with plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete 0.63 mm thick with zinc coating not less than 275 gm/m ² The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	14.40	INR Seven Hundred two and five paise zero only	Per Running Meter	10116.00

7	Providing valleys of 90 cm wide overall in plain G.S. sheet fixed with polymer coated J, or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete : 1.60 mm thick with zinc coating not less than 350 gm/m ² The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1.00	1147.95	INR one thousand one hundred forty-seven and ninety five paise only	Per Running Meter	1148.00
8	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110 mm diameter The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	27.00	426.30	INR Four Hundred twenty six and three paise zero only	Per Running Meter	11510.00
9	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter With white enamel paint including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	260.13	41.40	INR Forty-one and four paise zero only	Per Square meter	11654.00
10	Painting with acid proof paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	260.13	67.50	INR Sixty Seven and five paise Zero only	Per Square meter	17559.00
11	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	25.00	87.40	INR Eighty-Seven and four paise zero only	Per Square meter	2185.00
12	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: Asbestos cement sheet The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	189.29	41.10	INR Forty-One and one paise zero only	Per Square meter	7780.00
Total:-						307949.00
Quoted Rate in Figures		%age +/-				
Quoted Rate in Figures						

Executive Engineer,
Jhantutta Division,
H.P.F.W.D., Jhantutta.

SCHEDULE OF QUANTITY

Name of Work :- C/O link road PHC Gugga Mandir to Gah Km 0/0 to 3/00 (SH:- C/O PCC R/wall at RD 0/0 to 0/010 & PCC Causeway at RD 1/500 to 1/250). Deposit Work		Estimated cost:- ₹ 322149.00	Only			
		Earnest Money:- ₹ 6400.00	Only			
		Time allowed:- Three Months				
Sr. No.	Description of Items	Quantity	Figures	Rate	Unit	Amount
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	66.60	212.70	INR two Hundred Twelve and Paise seven zero Only	Per Cubic Meter	14166.00
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm nominal size) and curing complete including the cost of form work in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	23.60	5428.30	INR five thousand four Hundred twenty eight and Paise Three zero Only	Per cubic metre	128108.00
3	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. All kinds of soil The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	3.30	343.00	INR three Hundred forthree and Paise zero Only	Per Cubic Meter	1132.00
4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.00	315.13	INR Three Hundred fifteen and Paise one three Only	Each	2836.00

5	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP PWD specification. 100 mm spread thickness (finished work including materials and labour) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octri.	15.00	1531.30	INR one thousand five Hundred thirty one and Paise three zero Only	Per Cubic	22970.00
6	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement into four sand into eight graded stone aggregate 25mm, twenty five millimetre nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	12.25	5130.40	INR five thousand one Hundred thirty and Paise four zero Only	Per Cubic Meter	62847.00
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded/ crushed stone aggregate 40mm (forty millimetre) nominal mix curing complete within all leads & lifts carriage of material and other incidentals as per direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	15.00	6006.00	INR Six thousand six and Paise zero Only	Per Cubic Meter	90090.00
Total:-						322149.00
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O various roads under Buhad Section (SH:-Repair of Pot holes Koshrian to Jaddu via Brahmi Kallan Km 5/00 to 9/00 & Dholag to Malroun road km 0/00 to 5/00)						
St. No.	Description of Items	Quantity	Estimated cost:- ₹ 499931.00		Only	
			Earnest Money:- ₹ 10000.00		Only	
St. No.	Description of Items	Quantity	Rate		Time allowed:- One Month	
			Figures	words	Unit	Amount
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method as per MORD Technical Specification for rural road (1st Revision 2014) Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel B-10 kN static roller and finishing to required level and grades as per MORD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 501, 502 and 503. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, bunding and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or out put by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1180.81	423.38	INR Four Hundred Twenty-Three and paise thirty-eight only	Sqm	499931.00
Total:-						499931.00
Quoted Rate in Figures:-			%age +/-			
Quoted Rate in Words :-						

Executive Engineer,
Jhandutta Division
HPPWD Jhandutta

SCHEDULE OF QUANTITY

Name of Work:- Construction of Drain & Protection wall in division campus HP PWD Jhandauda (SH- C/O PCC B wall at Rd. 0/00 to 0/016 and Drain at Rd.0/0 to 0/075.)

Estimated Cost: 367829.00
Earnest Money: 7400.00

Time Limit:

Two month

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs. p
				Figures	Words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	39.74	Per cubic metre	212.70	Two Hundred Twelve and Paise seventy Only	8453.00
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete including the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	23.51	Per cubic metre	5328.30	Five thousand three Hundred twenty eight & Paise thirty only	125268.00
3	Providing and laying cement concrete work 1:3:6 (one cement: three sand six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge. including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.50	Per cubic metre	5897.80	Five thousand eight hundred ninty seven and paise eighty only	185781.00
4	Structural steel work in single section fixed with or without connecting plate, including cutting hoisting fixing in position and applying a priming coat of approved steel primer all complete, including carriage of material in all leads and lifts as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	505.80	Per cubic metre	86.20	Eighty six Rupees and Paise twenty Only	43600.00
5	Providing weep holes in brick masonry Stone masonry: plain reinforced concrete abutment wing wall (curb wall with 100 mm dia PVC pipe extending through full of width of the structure with slope of V) 20/117 towards drawing face complete as per HPPWD specification including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	15.00	Each	315.10	Three Hundred & fifteen and Paise ten Only	4727.00
Total in Figures						367829.00
Quoted Rate in Figures:-						
Quoted Rate in Words:-						

Executive Engineer,
Jhandauda Division
HPPWD, Jhandauda

SEHEDULE OF QUENTITY

Name of Work :- R/R on MDR-116 (Ghumarwin Berthin Talai) Road
KM. 14/00 to 25/00. (SH:-C/O PCC retaining wall from Km. 14/755 for
Protection of Abutment of Bhalu Bridge Talai Side.)

Estimated cost:- ₹	176194	Only
Earnest Money:- ₹	4000.00	Only
Time allowed:- Three Month		

Sr. No.	Description of Items	Quantity	Rate	Unit	Amount	
		Figures	Words			
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	15.86	212.70	Two Hundred Twelve and Paise seveny Only	Per Cubic Meter	3373
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete including the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	30.56	5428.30	Five thousand four Hundred twenty eight & Paise thirty only	Per Cubic Meter	165889.00
3	Providing weep holes in brick masonry/stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	22.00	315.10	Three Hundred & fifteen and Paise ten Only	Each	6932.00
Total:-						176194
Quated Rate in Figure:-		%				
Quated Rate in Words:-						


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work:- C/O of Link Road Bothu to Pump House Paploa Km. 0/00 to 4/00. (SH:- C/O 900 mm dia HPC at RD. 0/600 with wing wall both side)

Deposit

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		Amount
				Figures	Words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mts. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	42.13	Per cubic metre	212.70	Two Hundred Twelve and Paise seventy Only	8961.00
2	Providing and laying cement concrete work 1:4:8 (one cement: four sand: eight graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.60	Per cubic metre	5041.50	Five thousand forty one and paise fifty only	8066.00
3	Providing and laying cement concrete work 1:3:6 (one cement: three sand: six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.84	Per cubic metre	5897.80	Five thousand eight hundred ninty seven and paise eighty only	52137.00
4	Providing and laying (to level or slope) 900mm dia (nine hundred millimetre) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1106, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	7.50	Per running metre	3882.55	Three thousand eight hundred eighty two Paise fifty five only	29119.00
5	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete including the cost of form work, in foundation and plinth excluding the cost of centring & shoring in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.32	Per cubic metre	5328.30	Five thousand three Hundred twenty eight & Paise thirty only	108271.00

6.	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to bear for the performance of this contract.	6.72	Each	343	INR Three Hundred forty three & Paise zero Only	2345 INR
7	Providing weep holes in brick masonry / stone masonry, plain / reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.00	Each	315.10	Three Hundred & fifteen and Paise ten Only	2836.00
Total in Figures						
Quoted Rate in Figure:-		%				
Quoted Rate in Words:-		%				
		211695.00				

Executive Engineer,
Jhاندута Division
HPPWD, Jhاندута

SCHEDULE OF QUANTITY.

Name of Work :- Construction of New Toilet Block For Boys Govt Sr. Sec. School at Malroun.

Name of Work :- Construction of New Toilet Block For Boys Govt Sr. Sec. School at Malroun.		Estimated cost :- ₹ 413863.00		Only	
		Earnest Money :- ₹ 8300.00		Only	
		Time allowed :- Two Months			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
		Figures	Words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302.1603.1, 1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling time dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 2.88 Cubic metre @ Rs.600/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	28.75	296.00 INR Two Hundred ninety six and Paise Zero Only	Per Cubic meter	8510.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil, the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	25.92	212.70 INR Two Hundred Twelve and Paise seventy Only	Per Cubic meter	5513.00
3(i)	Centering and shuttering including strutting, propping etc. and removal of form for lintels, beams, plinth beams, girders, breasters and cantilevers the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	10.88	512.00 INR five Hundred Twelve and Paise Zero Only	Per square metre	5571.00
(ii)	Suspended floors, roofs, landings, balconies and access platform	22.58	594.60 INR five Hundred ninety four and Paise Sixty Only	Per square metre	13426.00
(iii)	Edges of slabs and breaks in floors and walls Under 20 cm wide	29.92	155.00 INR One Hundred & Fifty Five and Paise zero Only	Per Running metre	4638.00
4	Stone soling under flooring complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1.08	1345.79 INR One Thousand Three Hundred Forty Five and Paise Seventy Only	Per cubic metre	1453.00

5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.55	5161.80	INR Five Thousand One Hundred & Sixty Only	Per cubic metre	8001.00
6	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.08	4941.50	INR Four Thousand nine Hundred forty one and Paise fifty Only	Per cubic metre	20161.00
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (1 cement : 6 coarse sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	13.29	7877.20	INR seven Thousand Eight Hundred seventy seven and Paise twenty Only	Per cubic metre	104688.00
8	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement : 4 coarse sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	9.28	855.40	INR eight Hundred fifty five and Paise forty Only	Per square metre	7938.00
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajals, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.43	8796.00	INR Eight Thousand Seven Hundred ninety six and Paise zero Only	Per cubic metre	38966.00
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	443.00	104.10	INR Two Hundred Eleven and Paise ten Only	Per Kilogramme	46116.00
11	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 1.60 mm thickness, including hinges, jamb, lock jamb, head and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 1.60 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge. Fixing with adjustable lugs with split end tail to each jamb Profile B. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	30.80	428.40	INR Four Hundred twenty Eight and Paise forty Only	Per Running meter	13195.00

12	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-Charge. Butt hinges and necessary screws shall be paid separately 35 mm thick shutters kiln seasoned and chemically treated hollock wood. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.95	2923.50	INR Two Thousand nine Hundred Twenty three and Paise fifty Only	Per square metre	17395.00
13	Providing and fixing oxidized M.S sliding door bolts with nuts and screws etc. complete. 250x16 mm (Two hundred fifty into sixteen millimeter) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.00	173.00	INR one hundred Seventy three and Paise zero Only	Each	692.00
14	Providing and fixing oxidized M.S. tower bolts (barrel type) with necessary screws etc. complete. Including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same 200x10mm (Two hundred fifty into ten millimeter)	4.00	67.30	INR sixty one and Paise thirty Only	Each	245.00
15	Providing and fixing oxidized M.S. tower bolts (barrel type) with necessary screws etc. complete. Including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same 100x10mm (Two hundred fifty into ten millimeter)	8.00	38.50	INR Fifty Two and Paise Eighty Only	Each	308.00
16	Providing and fixing oxidized M.S. handles with the necessary screws etc. complete. Including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same 125 mm (one hundred twenty five millimeter)	12.00	35.20	INR Thirty Five and Paise Twenty Only	Each	422.00
17	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	22.58	200.10	INR Two Hundred and Paise Ten Only	Per square metre	4518.00
18	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement : 6 fine sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	124.53	296.30	INR Two Hundred ninety six and Paise thirty Only	Per square metre	36898.00
19	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level vented P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	4330.20	INR Four Thousand Three hundred Thirty and Paise twenty Only	Each	8660.00
20	Providing and fixing 15 mm C.P. angle cock with capstan head The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	3.00	354.90	INR Three Hundred fifty four and Paise thirty Only	Each	1065.00

21	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm dia nominal bore. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	35.00	262.60	INR Two Hundred sixty Two and Paise sixty Only	Running Meter	9191.00
22	Providing and fixing G.I./M.I Union of size: 15mm for Making Connection to the storage Tank. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	75.00	INR seventy Five and Paise Zero Only	Each	75.00
23	Providing and fixing Wheel valve of sizes 15mm. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	275.00	INR Two Hundred seventy five and Paise Zero Only	Each	275.00
24	Providing and fixing Flot valve of sizes 15mm. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	150.00	INR one Hundred Fifty and Paise Zero Only	Each	150.00
25	Providing and fixing PVC water storage tank of ISI : 12701 marked, G.I. inlet and outlet connection, 15mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting up to all heights above ground level : 1000 litres net capacity tank. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1000.00	9.40	INR nine and Paise forty Only	Liter	9400.00
26	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm or 340x410x255 mm sizes respectively. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	3.00	1045.95	INR one Thousand forty five and Paise fifty five Only	Each	3138.00
27	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes, 110 mm diameter. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	19.00	403.30	INR Four Hundred three and Paise thirty Only	Per Running metre	7663.00
28	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	11.90	46.40	INR forty six and Paise Forty Only	Per Square Metre	552.00
29	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	11.90	62.20	INR Sixty Two and Paise Twenty Only	Per Square Metre	740.00

30	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinable priming coat with cement primer. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	60.27	121.60	INR one Hundred Twenty one and Paise sixty Only	Per Square Meter	7329.00
31	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS-15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement & matching pigments etc., complete Size of Tile 600x600 mm. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	7.20	1526.60	INR one thousand five Hundred Twenty six and Paise sixty Only	Per Square Meter	10992.00
32	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to IS-15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc., complete Size of Tile 600x600 mm. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	10.44	1530.60	INR one thousand five Hundred Thirty and Paise sixty Only	Per Square Meter	15979.00
Total:-						
	Quoted Rate in figures		%age+/-			413863.00
	Quoted Rate in Words					

Executive Engineer,
Jhanda Division,
HPPWD Jhanda

SCHEDULE OF QUANTITY.

Name of Work :-C/O Manan to Morthal Road in G.P Sunhami Km 0/0 to 1/00 (SH:- P/L Wearing and larring at RD 0/500 to 0/750)


Name of Work :-C/O Manan to Morthal Road in G.P Surhahi Km 0/0 to 1/00 (SH:-P/L Wearing and tarring at RD 0/500 to 0/750)		Estimated cost:- ₹ 490827.00		Only		
		Earnest Money:- ₹ 10000.00		Only		
		Time allowed:- Two Months				
Sr No.	Description of Items	Quantity	Rate	Unit	Amount	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty - one hundred kilonewtons) in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density grading, -III as per Technical Specification Clause 405 (a) Mech Means (50 mm to 25 mm size) including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	60.05	2503.90	INR Two thousand five hundred three and paise ninety only	Per Cubic Meter	150359.00
2	Providing and applying primer coat with bitumen emulsion (S-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502 of MORTH including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	63.35	INR sixty three and paise thirty five only	Per Square Meter	50720.00
3	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503 of MORTH including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	29.50	INR Twenty nine and paise Five Zero only	Per Square Meter	23619.00
4	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508 By Manual Means VISCOSITY GRADE_30 including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	228.55	INR Two hundred twenty eight and Paise fifty five Only	Per Square Meter	182984.00
5	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510 of MORTH including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	103.85	INR one hundred three and paise eighty five only	Per Square Meter	83145.00
Total:-						490827.00
Quoted Rate in Figures		%				
Quoted Rate in Words						

Executive Engineer,
Jhandauta Division,
HPPWDD, Jhandauta

SCHEDULE OF QUANTITY

Name of work:- Balance work of Health Sub- Center Building at Hirapur Tehsil Jhandutta District Bilaspur HP. SH:- (Construction of R/Wall, Boundary wall & Courtyard interlocking concrete paver Blocks) (Deposit Work).				Estimated cost:- ₹	499885.00	Only
				Earnest Money:- ₹	10000.00	Only
				Time allowed:- Three month		
Sr. No.	Item Description	Quantity	Rate		Unit	AMOUNT
			Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	37.35	212.70	INR Two hundred and Paise one zero only	Per cubic metre	7944.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.57	5048.70	INR five thousand forty eight and Paise seven zero only	Per cubic metre	28121.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	31.58	5328.30	INR four thousand four hundred fifty one and paise zero only	Per cubic metre	168268.00
4	Providing weep holes in brick masonry / stone masonry, plain / reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe, entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	24.00	315.10	INR Three hundred sixteen and paise six five only	Nos	7562.00
5	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	55.69	343.10	INR Three hundred forty three and paise one zero only	Per cubic metre	19107.00
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	15.48	7136.50	INR seven thousand one hundred thirty six and paise five zero only	Per cubic metre	110473.00

	Providing and laying Stone soling properly handpacked filling interstices with Kharranja stone and consolidating with power road roller to the requested gradient and comber including spreading, watering and rolling of binding materials (moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	13.36	1440.50	INR one thousand four hundred forty and paise five, zero only	Per cubic metre	19245.00
8	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	8.91	5645.30	INR five thousand three hundred thirty three and Paise four zero only	Per cubic metre	50300.00
9	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in- 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	89.10	885.60	INR Eight hundred eighty five and paise six zero only	Per square metre	78907.00
10	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1.67	5962.70	INR five thousand nine hundred sixty two and Paise seven zero only	Per cubic metre	9958.00
		Total :-				
	Quoted Rate in Figures		%age +/-			499885.00
	Quoted Rate in Words					


 Executive Engineer,
 Jhanda Dutta Division,
 HPPWD, Jhanda Dutta.

SCHEDULE OF QUANTITY

Name of Work :- C/o link road Govt. Sr. Sec. School at Jagan Iehsil Jhandutta Dist. Bilaspur HP
(SH:- C/o Cement Concrete Pavement at RD 0/300 to 0/315 & 0/600 to 0/665) Deposit Work.

Estimated cost:- ₹ 498719.00	Only
Earnest Money:- ₹ 10960.00	Only

Time Allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	110.47	212.70	INR Two Hundred twelve and Paise seven zero Only	Per Cubic Meter	23497.00
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer in-Charge. With material conforming to Grade-1 (size range 75 mm to 0.075 mm) having CBR Value-30 including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.87	2401.00	INR two thousand four hundred one and paise zero zero only	Per cubic metre	62114.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement into four coarse sand into eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts, shoring and shuttering and curing complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material, tools equipment safety measures and other including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	47.75	5368.30	INR five thousand three Hundred sixty eight and Paise three zero Only	Per Cubic Meter	256336.00

Providing and laying design mix concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joint with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Cement content considered in M-30 is @ 340 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete prepared with batch mixing machine including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Good Service Tax but including labour cess, other levies/taxes, duties, royalties, sale tax, octroy, Toll, taxes of local bodies and	19.90	78,78.00	INR seven thousand eight hundred seventy eight and paise zero zero Only	Per Cubic Meter	156,772.00
Total :- 498719.00					

Quoted Rate in Figure:-
Quoted Rate in Words:-

%age +/-

Executive Engineer
Jhandutta Division
H.P.P.W.D. Jhandutta

SCHEDULE OF QUANTITY

Name of Work:- RRD on Road to Baloh via rapper KM. 0/00 to 2/00 (SH:- P/L CC Pavement at Rd. 1/400 to 1/500.)

						Estimated Cost	394129.00
						Earnest Money	5000.00
						Time Limit	Two month
Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs. p	
				Figures	Words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	99.00	Per cubic metre	212.70	Two Hundred Twelve and Paise seventy Only	21057.00	
2	Stone soling properly handpacked filling interstices with Khatarania stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP PWD specification, 100 mm spread thickness finished work including materials and labour) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi.	49.50	Per cubic metre	1530.80	One thousand five hundred thirty and paise eighty only	75775.00	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level: 2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	49.50	Per cubic metre	6006.00	Six thousand six only	297297.00	
Total in Figures							394129.00
Quoted Rate in Figure:-						%age +/-	
Quoted Rate in Words:-							

Executive Engineer,
Jhanda Division
HPPWD Jhanda

SCHEDULE OF QUANTITY

Name of Work :- Balance wor of Govt. Primary School Bahar The Jhandutta Dist. Bilaspur (H.P.) (Sl:- C/6 Mummy over stair hall 1st floor & Protection wall Right side of Building at RD 0/00 to 0/09,70) Deposit work.

Sr. No.	Description of Items	Quantity	Estimated cost:- ₹			Only
			Earnest Money:- ₹			Only
			Time allowed:- Two Months			Only
		Figures	Rate words	Per unit	Amount	
1	(Centering and shuttering including strutting, propping etc. and removal of form for all heights : Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc. including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.12	512.05	INR five hundred twelve and paise zero five only	Per square metre	4670.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:1½:3 (1 cement : 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size), including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.60	7600.00	INR seven thousand six hundred and paise zero only	Per cubic metre	4560.00
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level, Mild steel and Medium Tensile steel bars including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.00	105.35	INR one hundred five and paise three five only	Per kilo gram	6953.00
4	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) : With E.P.S. (non modular) bricks including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.32	7628.05	INR seven thousand six hundred twenty eight and paise zero five only	Per cubic metre	55837.00
5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	233.24	105.30	INR one hundred five and paise three zero only	Per kilo gram	24560.00

6	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purfins, rafters and trusses and including cutting to size and shape wherever required, including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.01	987.30	INR nine hundred eighty seven and paise three zero only	Per square metre	23705.60
7	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) Kin seasoned and chemically treated hollock wood 35 mm thick shutters including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	2869.70	INR two thousand eight hundred sixty nine and paise seven zero only	Per square metre	8609.00
8	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 300x16 mm including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	187.20	INR one hundred eighty seven and paise two zero only	Each	187.00
9	Providing and fixing ISI marked oxidised M.S. tower bolt black finish. (Barrel type) with necessary screws etc. complete : 25x10 mm including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	75.75	INR seventy five and paise seven five only	Each	76.00
10	Providing and fixing ISI marked oxidised M.S. handles conforming to IS-4992 with necessary screws etc. complete : 125 mm including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	35.20	INR thirty five and paise two zero only	Each	141.00
11	15 mm cement plaster on rough side of single or half brick wall of mix : 1:6 (1 cement: 6 coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.62	239.70	INR two hundred thirty nine and paise seven zero only	Per square metre	16928.00
12	Applying priming coat. With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	47.60	INR forty seven and paise six zero only	Per square metre	286.00

	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specification. Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.				paise five five only	metre	
14	Dispersing with 1st quality acrylic dispenser (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.62	64.90		INR seventy four and paise nine zero only	Per square metre	4583.00
15	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	13.48	212.70		INR two hundred twelve and paise seven zero only	Per cubic metre	2867.00
16	Providing and laying in position cement concrete of specified grade including, excluding the cost, of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand); 10 graded stone aggregate 40 mm nominal size) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.89	5328.30		INR five thousand three hundred twenty eight and paise three zero only	Per cubic metre	121965.00
17	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Circular material, including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.36	1308.10		INR one thousand three hundred eight and paise one zero only	Per cubic metre	5703.00
18	Providing weep holes in brick masonry / stone masonry, plain reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	315.10		INR three hundred fifteen and paise one zero only	Each	945.00
Total:-							285100.00
Quoted Rate in Figures					%age +/-		
Quoted Rate in Words							

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

SCHEDULE OF QUANTITY

Name of Work :- C/O Circular road at Jhandutta km 0/0 to 4/904 (SH:-P/L G.S.B, CC 1:3:6, CC 1:2:4 and Interlocking Paver block at RD 1/6/5 to 1/7/30 near Police thana)

Name of Work :- C/o Circular Road at Jhandutta km 0/0 to 4/904 (SH:-P/L G.S.B, CC 1:3:6 , CC 1:2:4 and Interlocking Paver block at RD 1/675 to 1/730 near Police thana)						Estimated cost:- ₹ 497021.00		Only
						Earnest Money:- ₹ 10000.00		Only
						Time allowed:- Two Months		
Sr. No.	Description of Items	Quantity	Figures	Rate	Unit	Amount		
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor Grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	35.06	1981.50	INR one Thousand nine Hundred eighty one and Paise fifty Only	Per Cubic Meter	69471.00		
2	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	17.53	5897.60	INR five Thousand eight Hundred ninety seven and Paise sixty Only	Per Cubic Meter	103385.00		
3	Providing and laying factory made chamfered edgeCement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by tablevibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engine including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	233.75	1257.30	INR one thousand two hundred fifty seven and paise thirty only	Per square metre	293894.00		
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve within all leads & lifts carriage of material and other incidentals as per direction of Engineer-in-Chargeincluding carriage of materials ,1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.04	6006.20	INR six thousand six and paise two twenty only	Per cubic metre	30271.00		
		Total:-				497021.00		
Quated Rate in Figures				%age +/-				
Quated Rate in Words								

Executive Engineer,
Jhandutta Division
UNDAWA, BHOJAPUR

SCHEDULE OF QUANTITY.

ne of work :- Construction of link road from Dabber to Thuram road km. 0/0 to 0/600(SH.- Providing and Laying M- 30 C.C. Pavement at RD 0/345 to 0/415) *02 April 17*

ne of work :- Construction of link road from Dabber to Thurran road km. 0/0 to 0/600(SH)- Providing and Laying M- 30 C.C. Pavement at RD 0/345 to 0/415) 02 April 2021		Estimated cost:- ₹		294576.00		Only	
		Earnest Money:- ₹		6500.00		Only	
		Time allowed:- Three Months					
Sr. No.	Description of items	Quantity	In Figure	Rate In Words	Unit	Amount	
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.60	2141.50	INR two Thousand one hundred forty one and Paise Five Zero only	Per Cubic Metre	11992.00	
2	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14days using curing compound (where specified) and water finishing lines and grade as per drawing and Technical specification clause 1501Note:- Cement content considered in M-30 is @ 340 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete prepared with batch mixing machine with in all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	35.87	7878.00	INR Seven Thousand Eight hundred seventy Eight and Paise zero only	Per Cubic Metre	282584.00	
Total						294576.00	
Quoted Rate in Figures		%		age +/-			
Quoted Rate in Words							

Executive Engineer,
Jhandauta Division,
HPPWD, Jhandauta

SCHEDULE OF QUANTITY

Name of Work :- C/O Ganglooh to Malroun road Km 0/0 to 18/00 (SH:- C/O 600 mm dia Hume Pipe Culvert at RD 14/595 & U-Shape Drain at RD 14/565 to 14/595).

Name of Work :- C/O Ganglo to Malroun road Km 0/0 to 18/00 (SH:- C/O 600 mm dia Hume Pipe Culvert at RD 14/595 & U-Shape Drain at RD 14/565 to 14/595).						Estimated cost:- ₹ 237649.00	Only
						Earnest Money:- ₹ 4800.00	Only
						Time allowed:- Two Months	
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	62.90	212.70	INR Two Hundred Twelve and Paise seventy Only	Per Cubic Meter	13379.00	
2	Providing and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement isto four sand isto eight graded stone aggregate 25 mm (twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	3.50	5140.60	INR Five thousand one hundred forty and paise sixty only	Per cubic metre	17992.00	
3	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	31.74	5885.90	INR Five thousand Eight hundred Eighty five and paise ninety only	Per Cubic Meter	186818.00	
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 600 mm The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	7.50	1989.70	INR one Thousand nine hundred eighty nine and Paise seventy Only	Per Running Meter	14923.00	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	0.66	6874.90	INR six Thousand eight hundred seventy four and Paise ninety Only	Per cubic metre	4557.00	
Total:-						237649.00	
Quoted Rate in figures						%age +/-	
Quoted Rate in Words							

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

Schedule of Quantity

Name of work :- A/R & M/O non Residential Building Under Sub Division Jhandutta (SH:- C/O R/wall at Division and Sub Division Complex at Jhandutta)					Estimated cost:- ₹ 494997.00	Only
					Earnest Money:- ₹ 10000.00	Only
					Time allowed:- one Month	
Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
		Figures	In Words			
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs.-dressing of sides-and bottom-and back-filling-in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	36.75	212.70	INR Two Hundred Twelve and Paise seventy Only	Per Cubic Meter	7817.00
2	Providing and laying cement concrete 1:5:10 (one cement, five sand, ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	84.00	5428.30	INR Four Thousand seven hundred Thirty two and Paise Eighty Only	Per Cubic Meter	455977.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	14.70	1308.10	INR one Thousand Three hundred Forty five and Paise seventy Only	Per Cubic Meter	19229.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall return wall with 100 mm. dia PVC pipe extending through full of width of the structure with slope of (V) : 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	38.00	315.10	INR Three Hundred Thirty nine and Paise ninety five Only	Each	11974.00
Total						494997.00
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY.

Name of Work :- C/O Manan to Morthal Road in G.P Sunhani Km 0/0 to 1/00 (SH:- P/L Wearing and tarring at RD 0/250 to 0/500)

Name of Work :- C/O Manan to Morthal Road in G.P Sunhani Km 0/0 to 1/00 (SH:- P/L Wearing and tarring at RD 0/250 to 0/500)						Estimated cost:- ₹ 490827.00		Only
						Earnest Money:- ₹ 9500.00		Only
						Time allowed:- Two Months		
Sr. No.	Description of Items	Quantity	Figures	Rate	Unit	Amount		
			Words					
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN (lightly - one hundred kilonewtons) in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III as per Technical Specification Clause 405.(a) Mech Means (50 mm to 25 mm size) including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	60.05	2503.90	INR Two thousand five hundred three and paise ninety only	Per Cubic Meter	150359.00		
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502 of MORTH including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	63.35	INR sixty three and paise thirty five only	Per Square Meter	50720.00		
3	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503. of MORTH including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	29.50	INR Twenty nine and paise Five Zero only	Per Square Meter	23619.00		
4	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508 By Manual Means VISCOSITY GRADE. 30 including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	228.55	INR Two hundred twenty eight and Paise fifty five Only	Per Square Meter	182984.00		
5	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510 of MORTH including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	800.63	103.85	INR one hundred three and paise eighty five only	Per Square Meter	83145.00		
Total:-						490827.00		
Quoted Rate in Figures								
Quoted Rate in Words								

Executive Engineer,
Jhandaulla Division,
HPPWD, Jhandaulla.

SCHEDULE OF QUANTITY

Name of Work:- C/o Admin block at Polytechnic collage kalol tehsil Jhandutta Distt Bilaspur (HP) (SH:- P/L Paver block in court yard RHS)

Estimated Cost: 497544.00
 Earnest Money: 10000.00
 Time Limit: Two month

Sr. No.	Description of work	No.or Qty.	Unit	RATE in Figures and Words		AMOUNT Rs. p
				Figures	Words	
1	Providing and laying factory made chartered edge Cement Concrete paver blocks nootpath parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-60 mm thick C.C. paver block of M-30 grade with approved color design and pattern. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	311.75	Per cubic metre	955.00	One thousand two hundred ninety four and paise forty only	297721.00
2	Providing and laying cement concrete work 1:3:6 (one cement three sand six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.18	Per cubic metre	5897.80	Five thousand eight hundred ninety seven and paise eighty only	183895.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level 1:2.4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.65	Per cubic metre	6006.00	Six thousand six only	15928.00
Total in Figures						497544.00


 Engineer
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work:- C/O Admin block at Polytechnic collage, kalol tehsil Jhandutta Distt Bilaspur (HP) (SH:- P/L Paver block in court yard RHS)

Estimated Cost: 481664.00
Earrest Money: 10000.00
Time Limit: Two month

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks nootpath parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extrasand, complete all as per direction of Engineer-in-60 mm thick C.C. paver block of M-30 grade with approved color design and pattern. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	305.25	Per cubic metre	955.00	One thousand two hundred ninty four and paise forty only	291514.00
2	Providing and laying cement concrete work 1:3:6 (one cement: three sand: six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or hauling out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.53	Per cubic metre	5897.80	Five thousand eight hundred ninty seven and paise eighty only	180860.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 Graded stone aggregate 20 mm nominal size) as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.68	Per cubic metre	6006.00	Six thousand six only	10090.00
Total in Figures						481664.00
Quoted Rate in Figure:-				%age +/-		
Quoted Rate in Words:-						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- C/o Circular road at Jhandutta km 0/0 to 4/904 (SH-P/L G.S.B, CC 1:3:6, CC 1:2:4 and Interlocking Paver block at RD 1/300 to 1/355 Near Nawn)

Sr. No.	Description of items	Estimated cost :- ₹ 481252.00 Only			
		Earnest Money :- ₹ 9700.00 Only			
		Time allowed :- Two Months			
Sr. No.	Description of items	Quantity	Rate		Amount
			Figures	words	
1	Stone soling properly handpacked filling interstices with Kharia stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP-PWD specification. 100 mm spread thickness (finished work including materials and labour) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octri.	35.06	1531.60	INR one thousand five hundred thirty one and paise six zero only	Per Cubic Meter 53698.00
2	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octri, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	17.53	5897.85	INR five Thousand eight Hundred ninety seven and Paise eight Five Only	Per Cubic Meter 103389.00
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge of materials, within all leads and lifts as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	233.75	1257.30	INR one thousand two hundred fifty seven and paise three zero only	Per square metre 293894.00
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level within all leads & lifts carriage of material and other incidentals as per direction of Engineer-in-Charge including carriage of materials, 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.04	6006.20	INR six thousand six and paise two zero only	Per cubic metre 30271.00
Total:-				%age +/-	481252.00
Quoted Rate in Figures					
Quoted Rate in Words					

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O Non Residential building under Sub-division Jhandutta
(SH:- C/O P.C.C R/Wall at Sub- Division and Division Complex at Jhandutta)

Sr. No.	Description of Items	Quantity	Figures	Rate	Unit	Amount
				Words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	36.75	212.70	INR Two Hundred Twelve and Paise Seventy Only	Per Cubic Meter	7817.00
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	84.00	5428.30	INR Five Thousand four hundred twenty eight and Paise Thirty Only	Per Cubic Meter	455977.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	14.70	1308.10	INR One Thousand three Hundred Eight and Paise ten Only	Per Cubic Meter	19229.02
4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	36.00	315.10	INR Three Hundred fifteen and Paise ten Only	Each	11344.00
Total:-						494367
Quoted Rate in Figures				%age +/-		
Quoted Rate in Words						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damage on Gehrwain to Behnajtatan Road Km. 0/00 to 7/500. (SH:- C/O Retaining wall at RD. 4/750 to 4/757.75).

Name of Work :-R/R damage on Gehrwain to Behrajaitan Road Km. 0/00 to 7/500. (SH:- C/O Retaining wall at RD. 4/750 to 4/757.75).						Estimated cost :- ₹ 499914.00		Only
						Earned Money :- ₹ 100000.00		Only
						Time allowed:- Three Month		
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	47.66	212.70	INR two Hundred & Twelve and Paise seventy Only	Per Cubic Meter	10137		
2	Providing and laying cement concrete work 1:4:8 (one cement: four sand eight graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.89	5368.3	Five thousand three hundred sixty eight and paise thirty only	Per Cubic Meter	465163.00		
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe extending through full of width of the structure with slope of (V). 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	23.00	1345.70	INR One Thousand Three Hundred & Forty five and Paise Seventy Only	Each	16794.00		
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	12.48	339.95	INR Three Hundred & thirty nine and Paise ninty five Only	Per Cubic Meter	7819.00		
Total:-						499913.00		
Quoted Rate in Figure:-						%age +/-		
Quoted Rate in Figure:-								


 Exec. Engineer,
 Jhandata Prasad
 HPPWD Jhandata

SCHEDULE OF QUANTITY

Name of Work :- Repair of Ayurvedic Health Center Duhak GP Badgaon Gallu Teh, Jhandutta
Distt Bilaspur (H.P) (SH:- Balance work of Windows, handles, Paints, interlocking Pavers etc)

Estimated cost:- ₹ 115392.00 **Only**
Earnest Money:- ₹ 2500.00 **Only**

Time allowed:- Three Months

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	56.20	212.70	INR Two Hundred Twelve and Paise Seventy Only	Per cubic metre	11954.00
2	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	0.54	5385.60	INR Five thousand Three hundred eighty five and paise sixty only	Per Cubic Meter	2908.00
3	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-Charge- Butt hinges and necessary screws shall be paid separately) 35 mm thick shutters Kiln seasoned and chemically treated hollock wood The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.70	2869.70	INR Two thousand Eight hundred sixty nine and paise seventy only	Per square metre	27836.00
4	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws Kiln seasoned and chemically treated hollock wood 35 mm thick The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	5.26	3160.70	INR three Thousand one hundred sixty and Paise seventy Only	Per square metre	16625.00
5	Providing and fixing oxidized M.S. handles with the necessary screws etc. complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same					0.00
i	125 mm (one hundred twenty five millimeter)	4.00	35.20	INR Thirty five and Paise twenty Only	Each	141.00
ii	100 mm (one hundred millimeter)	26.00	27.90	INR Twenty seven and Paise	Each	725.00

	Providing and fixing oxidised M.S. tower bolts (barrel type) with necessary screws etc. complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same					U.V.U
i	150x10mm (Two hundred into ten millimeter)	4.00	52.80	INR Fifty two and Paise eighty Only	Each	211.00
ii	100x10mm (Two hundred into ten millimeter)	52.00	38.70	INR thirty eight and Paise seventy Only	Each	2012.00
7	Providing and fixing oxidized M.S sliding door bolts with nuts and screws etc. complete. 300x16 mm (Three hundred into sixteen millimeter) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	187.20	INR one Hundred eighty seven and Paise twenty Only	Each	374.00
8	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :Painting wood work with Deluxe Multi Surface Paint of required shade. Two armore coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10sqm of approved brand and manufactureThe rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	38.99	87.60	INR Eighty seven and Paise Sixty Only	Per square metre	3416.00
9	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	38.99	47.60	INR Forty seven and Paise Sixty Only	Per square metre	1856.00
10	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge..The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	48.82	794.60	INR seven hundred ninety four and Paise sixty Only	Per square metre	38792.00
11	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Angle back washbasin size 400 x 400 mm with single 15 mmC.P. brass pillar tapThe rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	1929.10	INR one thousand nine hundred twenty nine and paise ten only	Each	1929.00

	Providing and fixing uplasticised PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore as per direction of Engineer-in-Charge The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	77.45	INR seventy seven and Paise forty five Only	Each	77.00
13	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Semi rigid pipe 32 mm dia The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	93.30	INR ninety three and Paise thirty Only	Each	93.00
14	Renewing glass panes, with wooden fillets wherever necessary. Float glass panes of nominal thickness 4mm (weight not less than 10kg/sqm) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	0.14	951.70	INR nine Hundred fifty one and Paise Seventy Only	Per square metre	133.00
15	Finishing walls with water proofing cement paint of required shade. New work (Two or more coats applied @ 3.84 kg/10 sqm) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	35.48	74.90	INR Seventy four and Paise ninety Only	Per square metre	2657.00
16	Providing and Fixing fly proof wire gauze to windows, & doors With M.S Flat 15X3 mm and nuts & bolts complete. Galvanised M.S. Wire gauze with 0.63 mm dia wire and 1.4 mm aperture on both sides The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	5.39	677.70	INR Six Hundred seventy seven and Paise Seventy Only	Per square metre	3653.00
			Total :-			115392.00
	Quoted Rate in Figures	%age +/-				
	Quoted Rate in Words					

Executive Engineer,
Jhanda Division
HPPWD, Jhanda


SCHEDULE OF QUANTITY

Name of Work :- Repair of Health center Kot G.P Paploha Teh, Jhandutta Distt, Bilaspur. (H.P) (SH.- P/F anti skid Tile & Distempriy etc)		Estimated cost:- ₹ 371150.00		Only	
		Earnest Money:- ₹ 7500.00		Only	
		Time allowed:- Three Months			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
1	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer, the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.80	7521.10 INR seven Thousand six hundred twenty one and Paise ten Only	Per Squire Merer	36581.00
2	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	38.71	145.70 INR one hundred forty five and Paise seventy Only	Per Squire Merer	5640.00
3	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete Size of Tile 600x600 mm The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	46.34	1530.60 INR one thousand five Hundred Thirty and Paise sixty Only	Per Squire Merer	70928.00
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead, the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	31.50	30.00 INR Thirty and paise zero only	Per Squire Merer	945.00
5	15 mm cement plaster on the rough side of single or half brick wall of mix 1:1:6 (1 cement: 6 fine sand) The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	31.50	224.20 INR Two Hundred twenty four and Paise twenty Only	Per square metre	7062.00
6	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinable priming coat with cement primer The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	265.84	121.60 INR One Hundred & Twenty One and Paise Sixty Only	Per square metre	32326.00

	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old work the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	47.57	62.20	INR Sixty two and paise two zero only	Per Square Meter	2959.00
8	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid the rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	4330.20	INR Four Thousand Three hundred Thirty and Paise twenty Only	Each	8660.00
9	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White vitreous China Angle back wash basin size 600 x 480 mm with single 15mm C.P. brass pillar tap The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	2330.55	INR Two Thousand three hundred thirty and Paise fifty five Only	Each	4661.00
10	Providing and fixing toilet paper holder : C.P. Brass. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	504.90	INR Five Hundred Four and Paise ninety Only	Each	1010.00
11	Providing and fixing 600 x 450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	1050.60	INR one Thousand Fifty and Paise sixty Only	Each	2101.00
12	Providing and fixing C.P. brass towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	455.30	INR Four Hundred fifty five and Paise thirty Only	Each	911.00
13	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm dia nominal bore The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	18.00	262.60	INR Two Hundred sixty Two and Paise sixty Only	Running Meter	4727.00
14	Providing and fixing Wheel valve of sizes 15mm The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	245.00	INR Two Hundred forty five and Paise Zero Only	Each	245.00

	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	19.90	212.70	INR Two Hundred twelve and Paise seventy Only	Per Cubic Meter	4233.00
16	Providing weep holes in brick masonry/stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in Charge. Including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	10.00	315.10	INR Three Hundred fifteen and Paise ten Only	Each	3151.00
17	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.08	5690.80	INR fiveThousand six Hundred ninety and Paise eighty Only	Per Cubic Meter	51672.00
18	Providing and laying factory made chamfered edgeCement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of requiredstrength, thickness & size/ shape, made by tablevibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engine including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge.80 mm thick C.C. paver block of M-30 grade with approved color design and pattern. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	60.50	850.40	INR eight hundred fifty and paise forty only	Per square metre	51449.00
19	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1.2:2.4 (one cement : two sand : four graded/crushed stone aggregate 20 mm (twenty millimetre) nominal mix. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	2.76	6006.20	INR three thousand six and paise twenty only	Per cubic metre	16577.00
20	Providing and laying concrete for plain/reinforced cement concrete 1.4:8 (One cement isto four sand isto eight Graded stone aggregate 40 mm.(forty millimetre nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	10.80	5040.60	INR five thousand three hundred forty and paise sixty only	Per cubic metre	54438.00

Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone - III) : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.04	542.60	INR Five Hundred Forty two and Paise sixty Only	per square metre	10874.00
Total :-					
Quoted rate in figures			%age +/-		371150.00
Quoted rate in Words					


 Executive Engineer,
 Jhanda Division
 HPPWD, Jhanda

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O on Berthim Chhat dabhiri road Km 0/0 to 1/0 & link road GPS Jhareri to bath Km 0/0 to 1/0 (SH :- Repair to Pot holes)		Estimated cost:- ₹ 499902.00		Only		
		Earnest Money:- ₹ 10000.00		Only		
		Time allowed:- One Month				
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method as per MCRD Technical Specification for rural road (1st Revision 2014) Clause 1900 and filled with Mix Seal Surfacing by providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per MCRD Technical Specification for rural road (1st Revision 2014) Clause 507 applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 501, 502 and 503. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1180.74	423.38	INR Four Hundred Twenty- Three and paise thirty- eight only	Sqm	499902.00
Quoted Rate in Figures		Total:-				499902.00
Quoted Rate in Words				%age +/-		


Executive Engineer,
Jharkhand Division
HPPWD, Jharkhand

SCHEDULE OF QUANTITY

Name of Work:- C/O Chounta to Dhani Pubher Road Km. KM. 16/00 to 27/00 (SH:- C/O P.C.C Causeway at Rd. 23/205 to 23/215 N 23/330 to 23/340.)

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures	Estimated Cost	Two month AMOUNT Rs. p
					Earned Money:	
					Time Limit:	
					Figures and words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	46.86	Per cubic metre	212.70	Two Hundred Twelve and Paise seventy Only	9967.00
2	Providing and laying cement concrete work 1:4:8 (one cement, four sand eight graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.42	Per cubic metre	5140.00	Five thousand one hundred forty and paise zero only	84399.00
3	Providing and laying cement concrete work 1:3:6 (one cement, three sand six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	49.99	Per cubic metre	5785.30	Five thousand seven hundred eighty five and paise thirty only	289207.00
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. up to floor five level, excluding the cost of centering, shuttering and finishing 1:1½:3 (1 cement : 1½ coarse sand:3) graded stone aggregate 20 mm nominal size) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.55	Per cubic metre	7450.00	Five thousand four hundred fifty only	71148.00
5	Providing weep holes in brick masonry / stone masonry, plain reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extending through full of width of the structure with slope of (1/V) 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	50.00	Each	315.10	Three Hundred & fifteen and Paise ten Only	15755.00

6	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP PWD specification 100 mm spread thickness (finished work including materials and labour) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi.	14.32	Per cubic metre	1631.40	One thousand six hundred thirty one and paise eighty only	23362.00
Total in Figures						493840.00
Quoted Rate in Figure:-		%age +/-				
Quoted Rate in Words:-						


 Executive Engineer,
 Jharkhand Division
 HPPWD, Jharkhand

SCHEDULE OF QUANTITY

Name of Work :- R/R Damage on Chounta to Dhani Pulher Road Km. KAL. 16/00
to 27/00 (SI:- C/O P.C.C R/wall at Rd. 26/070 to 26/082.)

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	49.08	212.70	INR. two Hundred & Twelve and Paise seventy Only	Per Cubic Meter	10439.00
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	90.00	5328.30	INR. Five Thousand three Hundred & Twenty eight and Paise thirty Only	Per Cubic Meter	479547.00
3	Providing weep holes in brick masonry, stone masonry, plain reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	15.00	315.10	INR. Three Hundred & fifteen and Paise ten Only	Per Cubic Meter	4727.00
4	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	12.96	343.00	INR. Three Hundred forty three & Paise zero Only	Each	4445.00
Total:-						499158.00

Quoted Rate in Figure:-
Quoted Rate in Words:-

Engineer,
 Himadri Division
 HPPWD Chounta


SCHEDULE OF QUANTITY

Name of Work:- R/R Damage on Chhota to Dhani Pukher Road Km. KM. 16/00 to 27/00 (SH- C/O P.C.C Causeway at Rd. 25/800 to 25/810 & v-shape drain at Rd. 25/810 to 25/905.)

Estimated Cost: 494332.00
Earned Money: 10000.00
Time Limit: Two month

Sr. No.		Description of work	No. or Qy.	Unit	RATE in Figures and words		AMOUNT Rs. p
					Figures	Words	
1		Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	115.59	Per cubic metre	212.70	Two Hundred Twelve and Paise seventy Only	24586.00
2		Providing and laying cement concrete work 1:4:8 (one cement, four sand eight graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	8.45	Per cubic metre	5140.00	Five thousand one hundred forty and paise zero only	43433.00
3		Providing and laying cement concrete work 1:3:6 (one cement, three sand six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	67.85	Per cubic metre	5785.30	Five thousand seven hundred eighty five and paise thirty only	389061.00
4		Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing 1:1½:3 (1 cement : 1½ coarse sand : 3) graded stone aggregate 20 mm nominal size) The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.00	Per cubic metre	7450.40	Five thousand four hundred fifty & Paise forty only	37252.00
6		Total in Figures				194332.00	
Quoted Rate in Figure:-				%age +/-			
Quoted Rate in Words:-							

Executive Engineer,
Jharkhand Division
HPPW, Jharkhand

SCHEDULE OF QUANTITY

Name of Work :- R/R Vijaypur to rahiyen Via Auhar (SH:- C/O R/Wall at RD 0/850 to 0/862) Near Kaseh road Junction

Sr. No.	Description of items	Quantity	Figures	Rate	Unit	Amount
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	34.20	212.70	INR Two Hundred Twelve and Paise Seventy Only	Per Cubic Meter	7274.00
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete including the cost of form work in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	89.52	5428.30	INR Five Thousand four hundred twenty eight and Paise thirty Only	Per Cubic Meter	485941.00
3	Providing weep holes in brick masonry/stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.00	315.10	INR Three Hundred fifteen and Paise ten Only	Each	6302.00
Total:-						499517.00
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Jhanda Division
HPPWD, Jhanda