

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **19.06.2023** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **17.06.2023** up to **4:00 P.M** and the application for issue of tender form shall be received on **16.06.2023** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of link road GPS Kawari to village Ranhun in District Kangra (HP)(SH:-Providing and laying cement concrete pavement at RD 0/270 to 0/330).	177037/-	3550/-	Two months
2	Construction of link road to village Bhadrehar in District Kangra (HP) (SH:-Providing and laying cement concrete pavement at RD 0/000 to 0/160).	499419/-	10000/-	Two months
3	Construction of road from Baroh Chowk Dehrian Jandrah Talli Tikka Dolla Kharaina Khundian Nahlian MDR-93 road Km 0/000 to 49/400 in Distt Kangra (HP) (SH:-Improvement of curve by providing retaining wall at RD 5/705 to 5/720, 5/900 to 5/915 and C/o parapets at various reaches),	499783/-	10000/-	Two months
4	Restoration of rain damages on Ambari to Kawari road Km 0/000 to 6/500 in District Kangra (HP) (SH:-Construction of Edge wall & providing and laying cement concrete pavement in extended portion between Km 5/500 to 6/000).	320413/-	6450/-	Three months
5	Restoration of rain damages on Ambari to Kawari road Km 0/000 to 6/500 in District Kangra (HP) (SH:-Construction of Edge wall & providing cement concrete pavement in extended portion between km 5/000 to 5/450 and construction of culvert at RD 4/550).	340127/-	6850/-	Three months
6	Restoration of rain damages on Nagrota Massal Rajhoon road Km 0/000 to 8/000 in District Kangra (HP) (SH:-Construction of retaining wall at RD 3/140 to 3/156 & 3/170 to 3/175 and cement concrete flooring for culvert).	328545/-	6600/-	Two months
7	Special repair of Govt. Girls Sen. Sec School at Nagrota Bagwan in District Kangra (HP) Deposit work (SH:-Repair of plastered surface painting work & other civil work etcetera).	193636/-	3900/-	Two months
8	Construction of link road Bhorni to Dhiman Basti Samloti in District Kangra (HP) (SH:-Construction of retaining wall at RD 0/250 to 0/265).	270691/-	5450/-	Two months
9.	Restoration of rain damages on Nagrota Bhatti Bhadrehar road km 0/000 to 2/030 in Distt Kangra (HP) (SH:-Construction of 1.00 mtr span RCC slab culvert at RD 2/030 along with wall at RD 2/014 to 2/029(Under Telecom deposit)	485274/-	9750/-	Three months

10	Construction of various roads under Baroh Sub-Division HP PWD Baroh in District Kangra (HP) (SH:-Painting & writing Kilometre stones and boards etcetera in various roads)	202990/-	4100/-	Three months
11	Construction of Bridge over Chor Nallah on link road Nagrota Bagwan ti Dauladhar Colony in Distt Kangra (HP) (SH:-Balance work of 10.37 mtrs span RCC Bridge over Chor Nallah)	499975/-	10000/-	Three months
12.	Construction of Thana Bargran Busal road Km 0/000 to 4/300 in Distt Kangra (HP) (SH:-Balance work of earthen shoulders filling)	406350/-	8150/-	Three months
13.	Repair and maintenance of OBC Bhawan at Hatwas (Nagrota Bagwan) in Distt Kangra (HP) (SH:-Repair to plaster painting flooring and roofing work etc;)	499286/-	10000/-	Two months

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2023-24-

2598- 2627

Dated/ 31-5-2023

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla
5. The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Principal, Dr. RPGMC, Tanda.
8. The Deputy Commissioner, Kangra at Dharamshala.
9. All the S.E.s/E.E.s under North Zone.
10. The Sub-Divisional Officer(C) Nagrota Bagwan.
11. The Block Development Office Nagrota Bagwan
12. All the Assistant Engineer under this Division.
13. The Drawing /Accounts Branch in this office.
14. The Contractors concerned.
15. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 177037.00
 EARNEST MONEY :- Rs. 3550.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road GPS Kawari to village Ranhun in District Kangra, (H.P.).

SUB-HEAD :- Providing & laying cement concrete pavement at RD 0/270 to 0/330.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidental.	16.99 Cubic metres			Per Cubic metres	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	25.47 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.


SCHEDULE OF QUANTITY

ESTIMATED COST: -	Rs.	499419.00
EARNEST MONEY :-	Rs.	10000.00
TIME LIMIT :		TWO MONTHS

NAME OF WORK :- Construction of link road to village Bhadrehar in District Kangra, (H.P.).

SUB-HEAD :- Providing & laying cement concrete pavement at RD 0/000 to 0/160.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidental.	47.75 Cubic metres			Per Cubic metres	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	72.04 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 499783.00
 EARNEST MONEY :- Rs. 10000.00
 TIME LIMIT :- TWO MONTHS
 NAME OF WORK :- Construction of road from Baroh Chowk Dehrian Jandrah Talli Tikka Dolla Kharaina Khundian Nahlian MDR-93 road Km 0/000 to 49/400 in Distt. Kangra (H.P.).
 SUB-HEAD :- Improvement of curve by providing Retaining wall at RD 5/705 to 5/720, 5/900 to 5/915 and C/O parapets at various reaches.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	54.21 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	116.90 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	44.59 Running metres			Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	35.90 Cubic metres			Per cubic metre	
5	Providing concrete for plain/reinforced concrete in substructure complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 in 1:2.5:5 (One cement : Two and half sand : five graded) broken/crushed stone aggregate 20mm (Twenty millimeters) nominal size PCC grade M-15 (M-Fifteen), as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	3.18 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrola Bagwan.

SCHEDULE OF QUANTITY


ESTIMATED COST: - Rs. 320413.00
EARNEST MONEY :- Rs. 6450.00
TIME LIMIT : THREE MONTHS

NAME OF WORK :- Restoration of rain damages on Ambari road Km 0/000 to 6/500 in District Kangra, (H.P.).

SUB-HEAD :- Construction of Edge wall & Providing & laying Cement Concrete Pavement in extended portion between Km 5/500 to 6/000.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	37.59 Cubic metres	4	5	Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:3:6 (One cement; three sand; six graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	15.60 Cubic metres			Per cubic metre	
3	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two milimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidental.	20.96 Cubic metres			Per Cubic metres	

4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	35.25 Cubic metres		Per cubic metre
TOTAL :-				


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY


ESTIMATED COST :- Rs. 340127.00
 EARNEST MONEY :- Rs. 6850.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Restoration of rain damages on Ambari road Km 0/000 to 6/500 in District Kangra, (H.P.).

SUB-HEAD :- Construction of Edge wall & Providing & laying Cement Concrete Pavement in extended portion between Km 5/000 to 5/450 and Construction of culvert at RD 4/550.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	22.59 Cubic metres			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:3:6 (One cement; three sand; six graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	12.57 Cubic metres			Per cubic metre	
3	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two milimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidental.	21.50 Cubic metres			Per Cubic metres	

4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	34.13 Cubic metres			Per cubic metre
5	Structural steel work of Tata / Sail / Reliance / Jindal riveted, bolted or welded in built up sections, trusses and framed work, poles for Badminton/Volleyball court etcetra including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	405.00 Kilogramme			Per Kilogramme
TOTAL :-					


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 328545.00
 EARNEST MONEY :- Rs. 6600.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on Nagrota Massal Rajhoon road Km 0/000 to 8/000 in District Kangra, (H.P.).

SUB-HEAD :- Construction of Retaining wall at RD 3/140 to 3/156 & 3/170 to 3/175 and Cement concrete flooring for culvert. (Under Telecom Deposit)

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	31.53 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	68.61 Cubic metres			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	7.86 Cubic metres			Per cubic metre	

4	Providing and fixing 100 mm (One hundred millimetres) diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetres) gap for thermal expansion, Single socketed pipes complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	41.00 Running metre			Per Running metre
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	13.76 Cubic metres			Per cubic metre
TOTAL :-					


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 193636.00
 EARNEST MONEY :- Rs. 3900.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Special repair of Govt. Girls Sen. Sec. School at Nagrota Bagwan in District Kangra, (H.P.). Deposit Work

SUB-HEAD :- Repair of Plastered surface, Painting work & other civil work etcetra.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	15mm (Fifteen millimetre) thick cement plasters in single coat on rough side of single or half brick/concrete/stone walls for interior/exterior plastering upto all floor level including arises, internal rounded angles, chamfers or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement : six sand) above plinth level to floor all level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	479.94 Square metres			Per square metre	
2	Finishing walls with 100% (One hundred percent) Premium acrylic emulsion paint of Asian/Dulux/Berger/Nerolac Suraksha paints of approved shade having VOC less than 50 gm/litre (Fifty grams per liter) and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior/interior paint of required shade (Company Depot Tinted) with silicon additives New work (Two or more coats applied @ 1.43 litre/ 10 sqm (One point forty three litre per ten square metre) over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point ninety litre per ten square metre) upto all floor level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	479.94 Square metres			Per square metre	
3	Providing and fixing 0.60 mm (Zero point sixty millimetres) thick preprinted steel sheet of Tata Durashine / Sail / Reliance / Jindals steels in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with preprinted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameter with preprinted limpet and rubber washers complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.80 Square metres			Per Square metre	

4	Structural steel work of Tata / Sail / Reliance / Jindal riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer in grating, grames, guard bar, ladder, railing, brackets, gates and similar works complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	118.32 Kilograms		Per kilo-gram
5	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 25x25mm (Twenty five into twenty five millimetre) made of G.I. wire of dia 3mm (Three millimetre) including strengthening with 2mm (Two millimetre) dia wire or nuts, bolts and washers as required complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	4.16 Square metres		Per Square metre
6	Painting two or more coats (excluding priming coat) with Nerolac/ Asian or equivalent on new steel and other metal surfaces under coat with enamel paint other than white of approved brand brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	88.48 Square metres		Per square metre
7	Painting wood work (including priming coat) with enamel paint of Nerolac/ Asian Paint of required shade two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre per ten square metre) over an under coat of primer applied @ 0.75 ltr/10 sqm (Zero point seven five litre per ten square metre) of approved brand and manufacture including cleaning the surfaces of all dirt, dust and other foreign matter complete as per specifications, drawing and design including carriage of material within all leads, lifts and other incidentals and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	88.48 Square metres		Per square metre
TOTAL :-				


 Executive Engineer,
 H.P.P. W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :-	Rs.	270691.00
EARNEST MONEY :-	Rs.	5450.00
TIME LIMIT :		TWO MONTHS

NAME OF WORK :- Construction of link road Bhorni to Dhiman Basti Samloti in District Kangra, (H.P.).

SUB-HEAD :- Construction of Retaining wall at RD 0/250 to 0/265.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	26.62 Cubic metres			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	63.89 Cubic metres			Per cubic metre	
3	Providing and fixing 100 mm (One hundred millimetres) diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetres) gap for thermal expansion, Single socketed pipes complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	29.90 Running metre			Per Running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	21.96 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 485274.00
EARNEST MONEY :- ₹ 9750.00
TIME LIMIT : THREE MONTHS

NAME OF WORK : Restoration of rain damages on Nagrota Bhatti Bhadrehar road Km 0/000 to 2/030 in Distt Kangra (HP)

SUB HEAD : Construction of 1.00mt span RCC slab culvert at RD 2/030 alongwith wing wall at RD 2/014 to 2/029 (Under Telecom Deposit)

S. No.	Description of Items	Qty	Rate		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metres) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50m (fifty meters), dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-In-Charge, including carriage of materials within all leads lifts and other incidentals.	3 55.80 Cubic metres		5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals.	70.45 Cubic metres			Per cubic metre	
3	Providing concrete for plain/reinforced concrete in substructure complete including the cost of centering and shuttering as per drawings and technical specifications Clause 802, 803, 1202 & 1203 in 1:2.5:5 (One cement : Two and half sand : five graded) broken/crushed stone aggregate 20mm (Twenty millimeters) nominal size PCC grade M-15 (M-Fifteen) as directed by the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals.	18.36 Cubic metres			Per cubic metre	
4	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : One and Half coarse sand: Three graded stone aggregate 20 mm (Twenty millimetre) nominal size complete as per HPPWD technical specification and as directed by the Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	1.44 Cubic metres			Per cubic metre	
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level : Thermo-Mechanically Treated bars of grade Fe-500D or more as per HPPWD technical specification and as directed by the Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	252.00 Kilogram			Per kilo gram	
7	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals.	42.50 Running metres			Per running metre	
8	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, as directed by the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals.	27.00 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- 202990.00
EARNEST MONEY :- 4100.00
TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of various roads under Baroh Sub-Division, HP PWD Baroh in District Kangra, (H.P.).

SUB-HEAD :- Painting & Writing Kilometre stones and boards etcetra in various roads.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Painting two coats (excluding priming coat) on new concrete / masonry/plastered surfaces with readymixed paint of approved brand and manufacture for use on floors to give an even shade, including cleaning of all dirt, dust and other foreign matter and sand papering as required complete including carriage of material within all leads, lifts and other incidentals as per approved specification drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	17.50 Square metres			Per square metre	
2	Painting Steel work (including priming coat) with Deluxe multi surface paint of Nerolac / Asian to give an even shade two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eighty litre per ten square metre) of approved brand and manufacture including cleaning the surfaces of all dirt, dust and other foreign matter complete as per Architectural drawing, design and specification including entire carriage of materials within all leads, lifts and other incidentals and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	67.50 Square metres			Per square metre	
3	Writing letters or figures on any surface with synthetic enamel paint other than white (stops, comas, hyphens and the like not to be measured and paid separately) Block letters/ figures complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	60000.00 Centi meters height			Per Centi meters height	
4	Writing letters or figures on any surface with synthetic enamel paint (stops, comas, hyphens and the like not to be measured and paid separately) Indian letters/ figures complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	60000.00 Centi meters height			Per Centi meters height	
TOTAL :-						


Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹. 499975.00
 EARNEST MONEY :- ₹. 10000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Bridge over Chor Nallah on link road Nagrota Bagwan to Dauladhar Colony in Distt. Kangra (H.P.)
SUB HEAD :- Balance work of 10.37 mtrs span RCC Bridge over Chor Nallah.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	80.62 Cubic metres			Per cubic metre	
2	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	14.00 Cubic metres			Per cubic metre	
3	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 20mm (Twenty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	21.00 Cubic meters			Per cubic metre	
4	Construction of embankment with approved materials obtained from borrow pits with a lift upto 1.5m (One point five meters) transport to sill spreading grading to required slope and compacted to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m (One thousand meters) as per Technical Specification Clause 301.5, including entire carriage of materials within all leads, lifts and other incidentals.	235.00 Cubic metres			Per cubic metre	
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- Rs. 406350.00
 EARNEST MONEY :- Rs. 8150.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Thana Bargran Busal road Km 0/000 to 4/300 in Distt. Kangra (H.P.).

SUB HEAD :- Balance work of earthen shoulders

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Construction of embankment with approved materials obtained from borrow pits with a lift upto 1.5m (One point five meters) transport to sill spreading grading to required slope and compacted to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m (One thousand meters) as per Technical Specification Clause 301.5, as directed by the Engineer-in-Charge, including entire carriage of materials within all leads, lifts and other incidentals.	2709.00 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 499286.00
 EARNEST MONEY :- ₹ 10000.00
 TIME LIMIT :- TWO MONTHS


NAME OF WORK :- Repair and maintenance of O.B.C. Bhawan at Hatwas (Nagrota Bagwan) in Distt. Kangra (H.P.)
 SUB-HEAD :- Repair to plaster, painting, flooring and roofing work etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Repair to plaster with cement mortar 1:3 (One cement : Three sand) in patches of 2.50 sqm (Two decimal five zero) square metres upto any thickness including cutting the patches in proper shape and re-plastering the surfacing to the wall including disposal of rubbish to the dumping ground complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	65.30 Square metres			Per square metre	
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	505.60 Square metres			Per square metre	
3	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives complete New work (Two or more coats applied @ 1.43 litre/ 10 sqm (Zero point forty three liter / Ten square metre). Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point ninety liter / Ten square metre) including entire carriage of materials within all leads, lifts and other incidentals	505.60 Square metres			Per square metre	
4	Painting wall with Terracotta Paint of required shade. One coat on old work applied @ 0.60 ltr/10 Sqm of approved brand and manufacture complete and as per direction of Engineer- Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	300.40 Square metres			Per square metre	
5	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface complete and as per direction of Engineer- Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	450.95 Square metres			Per square metre	

6	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats complete and as per direction of Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	950.88 Square metres			Per square metre	
7	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 600x600 mm complete and as per direction of Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	1.80 Square metres			Per square metre	
8	Providing and laying Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick complete and as per direction of Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	5.10 Square metres			Per square metre	
9	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete and as per direction of Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	5.50 Square metres			Per square metre	
10	Providing and fixing 150x10 mm aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :complete and as per direction of Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	8 Numbers			Each	
11	Providing & fixing 4.0 mm thick glass panes glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : complete and as per direction of Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	3.50 Square metres			Per square metre	
12	Providing and fixing 4mm (Four millimetre) thick plain asbestos cement sheet ceiling of approved quality with butt jointing and wood screws (frame work and cover fillets to be measured and paid for separately)complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	49.65 Square metres			Per square metre	

13	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required and as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	201.50 Square metres			Per square metre	
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) complete as per direction of Engineer-In-Charge including entire carriage of materials within all leads, lifts and other incidentals.	2.75 Cubic metres			Per cubic metre	
15	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	42.30 Kilograms			Per kilo gram	
16	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.					
i	Coupler 110 mm	8 Numbers			Each	
ii	Bend 87.5° 110 mm bend	6 Numbers			Each	
iii	Shoe (Plain) 110 mm Shoe	6 Numbers			Each	

17	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work complete and as per direction of Engineer-Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	115.00				Per square meter	
							TOTAL :-


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.