

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
**NOTICE INVITING TENDER**

Sealed **percentage rate** tender on form No. 6 and 8 are hereby invited by the Executive Engineer (NH) Division HPPWD Nahan on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **13.06.2023** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to **12.06.2023 04:00 PM**


The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 120 days.

| Sr. No. | Name of works                                                                                                                                                                                                                   | Estimated Cost | Earnest Money | Time Limit | Cost of Form |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|---------------|------------|--------------|
| 1       | Ordinary repair to Kala Amb Paonta Sahib Dehradun road on NH-72 (New NH 07) Km 46/00 to 103/00 (SH:- Dismantling steel Railing and providing and fixing MS steel railing in Bohliyon Bridge at RD 72/760 to 72/793)             | 2,46,489/-     | 4950/-        | 01 Month   | 350/-        |
| 2       | Ordinary repair to Kala Amb Paonta Sahib Dehradun road NH 72 (New NH 07) Km 46/00 to 103/00 (SH:- Dismantling of old roundabout badripur chowk at Paonta Sahib on NH 07 at RD 99/600 & C/o of new roundabout chowk at RD 99/600 | 3,90,195/-     | 7900/-        | 2 Month    | 350/-        |

**CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.**

**Terms & Conditions:-**


1. The Contractors/Bidders must quoted their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 120 days.
10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22<sup>nd</sup> July, 2020 and 07.10.2021 regarding adoption of CPWD work manual 2019 & other publication of CPWD in HPPWD Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.

  
Executive Engineer  
NH Division HPPWD  
Nahan

No. PW/NHD-NHN/TA-Tender Notice/ 2022-23: 1031-61 dated:- 31-05-23

Copy along with NIT is forwarded to the following for kind information and necessary action please:-


- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.
- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla.
- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib/Pachhad please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.

  
Executive Engineer  
NH Division HPPWD  
Nahan

Job No. 1

| SCHEDULE OF QUANTITY                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|--------------------------------------------------------------------|-------------------|-------------------|--------|-----------------|--|
| Name of Work:- Ordinary repair to Kala Amb Paonta Sahib Dehradun road on NH-72 (New NH-07) Km 46/00 to 103/00 (SH):- Dismantling steel railing and providing and fixing MS steel railing in Bohliyon Bridge at RD 72/760 to 72/793) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   | Estimated cost :- |        | Rs.246489/-only |  |
|                                                                                                                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   | Earnest Money :-  |        | RS.4950/-only   |  |
|                                                                                                                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   | Time Limit :-     |        | 1 Months        |  |
| Sr.No                                                                                                                                                                                                                               | Description of item/Sub Head                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity | In Figure | Rates<br>In words                                                  | Unit              | Amount            |        |                 |  |
| 1                                                                                                                                                                                                                                   | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 3        | 4         | 5                                                                  | 6                 | 7                 |        |                 |  |
| 1                                                                                                                                                                                                                                   | Dismantling guard rails/ steel railing by manual means and disposal of dismantled material with all lifts and lead, stacking serviceable material and unserviceable material separately including all leads and lifts with all modes of transportation and equipment required to complete the work as per satisfaction of the Engineer in Charge.                                                                                                                                                                                                                                                                                                                                                                                                                    | 58.00    | 236.60    | Rupees two hundred thirty six and paise sixty only                 | Per Running meter | 13722.8           |        |                 |  |
| 2                                                                                                                                                                                                                                   | Providing and fixing in position pipe railing consisting of IS Rolled steel joist posts designation IS MB 100 (100x75) (One Hundred is to seventy five millimeter) at 1.5m rows of 50 mm (Fifty millimeter) dia steel pipes (Medium) including fixing in position on bridge deck complete as per drawing and technical specification clause 1208.2 including carriage of all material within all leads and lifts with all modes of transportation and equipment and cost of MS Bolts, nuts and washer, painting one shop coat with red oxide primer and three coats of synthetic enamel paint and electricity charges, welding and drilling equipment, electrodes and other consumables required to complete the work as per satisfaction of the Engineer-in-Charge. | 66.00    | 2924.90   | Rupees two thousand nine hundred twenty four and paise ninety only | Per Running meter | 193043.4          |        |                 |  |
|                                                                                                                                                                                                                                     | Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depths as per drawing and technical specification in foundation of retaining wall complete as per MORTH specification No. 1500, 1700 & 2100 including carriage of all material within all leads and lifts with all modes of transportation and equipment and cost of form work required to complete the work to the satisfaction of the Engineer-in-Charge for Parapet work                                                                                                                                                                                                                                  | 2.25     | 6011.90   | Rupees Six thousand eleven and paise ninety only                   | Per Cubic Meter   | 13526.775         |        |                 |  |
|                                                                                                                                                                                                                                     | Providing concrete for plain/reinforced (PCC M-20 (Twenty) containing minimum contents of cement is 6.60 bags per cubic meter nominal mix 1:2:4 (one cement: two sand: four crushed stone aggregate twenty millimeters nominal size) in open foundations complete as per drawings and technical specification Clause 802, 1202, and 1203 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of form work required to complete the work as per satisfaction of the Engineer-in-Charge.                                                                                                                                                                                                            | 3.96     | 6615.25   | Rupees six thousand six hundred fifteen and paise twenty five only | Per Cubic Meter   | 26196.39          |        |                 |  |
|                                                                                                                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   | 246489 |                 |  |
| Note :-                                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |
| 1 The payment will be made only for working hours.                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |
| 2 Machinery must be made available within one hour on emergency call by the Engineer-in-Charge.                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |
| 3 In case of emergency, the contractor is bound to make available JCB/Tractor in further 20 kms.both ends.                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |
| Draft schedule of quantity recommended for approval please.                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |
| Rate quoted by contractor +/-                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   | Percent           |        |                 |  |
| Quoted rate in figure                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |
| Quoted rate in words                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                                                    |                   |                   |        |                 |  |

Note :- 1 The payment will be made only for working hours.  
 2 Machinery must be made available within one hour on emergency call by the Engineer-in-Charge.  
 3 In case of emergency, the contractor is bound to make available JCB/Tractor in further 20 kms both ends.  
 Draft schedule of quantity recommended for approval please.

  
 Executive Engineer,  
 NH. Division Nahan,  
 HP.PWD., Division,

Feb. No. 2

| SCHEDULE OF QUANTITY                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |         |                   |                                                                        |        |                  |           |  |
|-------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------|-------------------|------------------------------------------------------------------------|--------|------------------|-----------|--|
| Name of work :- Ordinary repair to Kala Amb Paonta sahib Dehradun road NH 72 (New Nh No.07) km 48/0 to 103/0 (SH : RD 96/600. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |         |                   |                                                                        |        |                  |           |  |
| Sr.No                                                                                                                         | Description of Item/Sub Head                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Unit    | Estimated cost :- |                                                                        | Amount | Rs.390195/- only |           |  |
|                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |         | In Figure         | In words                                                               |        | RS.7900/- only   | 2 months. |  |
| 1                                                                                                                             | Demolition above GL upto floor two level including stacking of serviceable material and disposal of un-serviceable material within a lead of 50 mtrs and including cutting the necessary reinforcement and reparting from RCC/RB work. : RCC work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 3        | 4       | 5                 | 6                                                                      | 7      |                  |           |  |
| 1                                                                                                                             | Demolition of stone masonry above G.L. up to floor two level including stacking the serviceable material and disposal of un-serviceable material within 50 metres lead. Rubble masonry in cement mortar.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 3.53     | per cum |                   | Rupees One Thousand four hundred sixty five and paise thirty five only | 5173   |                  |           |  |
| 2                                                                                                                             | Demolition of brick work above G.L. up to floor two level including stacking the serviceable material and disposal of un-serviceable material within 20 metres lead. in cement mortar.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 11.78    | per cum |                   | Rupees one Thousand Eleven and paise seventy five only                 | 11918  |                  |           |  |
| 3                                                                                                                             | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:3:6                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 7.18     | per cum |                   | Rupees eight hundred forty seven and paise ninety five only            | 6088   |                  |           |  |
| 4                                                                                                                             | Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 4.17     | per cum |                   | Rupees One thousand four and paise forty five only                     | 4189   |                  |           |  |
| 5                                                                                                                             | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.                                                                                                                                                                                                                                                                                                                                                                                                       | 27.31    | per sqm |                   | Rupees thirty one and paise twenty only                                | 852    |                  |           |  |
| 6                                                                                                                             | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 86.10    | per cum |                   | Rupees one hundred seventy one and paise forty only                    | 14757  |                  |           |  |
| 7                                                                                                                             | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 in P.C.C. Grade M 10 (nominal mix 1 : 3 : 6)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 29.30    | per cum |                   | Rupees seven thousand four hundred thirteen and paise sixty only       | 217218 |                  |           |  |
| 8                                                                                                                             | Providing and fixing pavement marker ( Cat eyes ) made out of ABS 3M Plastic size 100*90*19mm (One hundred into ninety into nineteen point five millimeter) without nails having 50mm stem of ABS fixed . The pavement marker shall be installed with epoxy Abs including carriage of materials and equipment in all leads and lifts with all mode of transportation and as per MORTH Specification and the direction of Engineer-in-charge                                                                                                                                                                                                                                                                                                                        | 11.68    | Per cum |                   | Rupees six Thousand one hundred seventy three and paise ten only       | 72101  |                  |           |  |
| 9                                                                                                                             | Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm high above ground level, painted black and white in 15 cm wide strips, fitted with 80 x 100 mm rectangular or 75 mm dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 and the drawings.                                                                                                                                                                                                                                                                                                                                                                                                          | 100.00   | Each    |                   | Rupees four hundred sixty and paise ninety only                        | 46090  |                  |           |  |
| 10                                                                                                                            | P/F of Retro-reflecterised informatory/cautionary sign boards as per IRC:67 made of encapsulated lens type reflective sheeting vide clause 1701.2.3 fixed over aluminium sheeting . 1.5mm thick supported on mild steel angle iron post 75 x 75 x 6mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450mm x 600mm below ground level as per drawing and technical specifications clause 801:- 600mm Equilateral triangle in including carriage all labour material & equipment to various locations through all modes of transportation as per HPPWD Specifications & as per the direction & specifications of the Engineer -in - charge. (800 x 600 mm rectangular each) i.e cautionary sign boards | 20.00    | Nos     |                   | Rupees six hundred sixty two and paise sixty only                      | 13252  |                  |           |  |
| 11                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 4.00     | Each    |                   | Rupees one thousand nine hundred thirty and paise seventy five only    | 7723   |                  |           |  |
| Total (A)                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |         |                   |                                                                        | 399361 |                  |           |  |

| Details of serviceable material to be received from dismantling |                               |  |         |         |                                                    |      |
|-----------------------------------------------------------------|-------------------------------|--|---------|---------|----------------------------------------------------|------|
| 1                                                               | Serviceable stones (Ordinary) |  | 3.18    | per cum | Rupees seven hundred and paise zero only<br>700.00 | 2226 |
| 2                                                               | Serviceable bricks            |  | 1226.00 | each    | Rupees three and paise zero only<br>3.00           | 3678 |
| 3                                                               | Tor steel (scrap)             |  | 148.26  | per kg. | Rupees Twenty two and paise zero only<br>22.00     | 3262 |
| TOTAL (B)                                                       |                               |  |         |         |                                                    | 9166 |

# REMARKS

- The rates for dismantling are as per HPSR 2020
- The rates for useful / old material are prevailing market rates

NET AMOUNT = A-B  
399361 - 9166 = Rs 390195

|  |                               |         |  |
|--|-------------------------------|---------|--|
|  | Rate quoted by contractor +/- | Percent |  |
|  | Quoted rate in figure         |         |  |
|  | Quoted rate in words          |         |  |
|  |                               |         |  |

Executive Engineer  
NH Division  
HPPWD Nahan