



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



HP.PWD. Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Office of the Executive Engineer, Outer Seraj Division,

Phone No.-01904-255140

Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2022-23 2558-68
To

Dated 09-06-23

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Supdt. of C Branch.
6. Notice Board.


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

NOTICE INVITING TENDER

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on **17.06.2023** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on **16.06.2023** between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **16.06.2023** between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost	Earnest Money	Time	Cost of tender form
1	C/o Toilet Block at Neether (SH:- Construction of B/Wall at RD.14/322.50 to 14/330 of Road from Jn. of LDCK to Jn. of NAS road)	424373.00	9000.00	Two months	350/-
2	Improvement of black spots by providing corrective measures on Wazir Bowali to Mohali road km. 0/0 to 26/00 (SH:- Improvement of curve at RD 11/255 to 11/315)	187505.00	4000.00	One month	350/-
3	Improvement of black spots by providing corrective measures on Wazir Bowali to Mohali road km. 0/0 to 26/00 (SH:- Improvement of curve at RD 10/780 to 10/840)	199711.00	4000.00	One month	350/-
4	R/R Damage on Nagan Chheora Chhatttri road km 0/0 to 12/240(SH-Repair of abutment and pier of damages RCC Slab Culvert at RD 1/200 to 1/232)	311657.00	7000.00	Two months	350/-

5	Restoration of rain damages on Sinvi Muhan road 0/00 to 3/075 (SH:-Repair of abutment and pier of damages RCC Slab Culvert at RD 1/150 to 1/157 and 1/980 to 1/987)	216058.00	5000.00	Two months	350/-
6	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/150 to 24/156.50)	411777.00	10000.00	One month	350/-
7	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/156.50 to 24/160)	222025.00	6000.00	One month	350/-
8	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O R/Walls at RD. 25/284.80 to 25/296)	445839.00	10000.00	One month	350/-
9	A/R & M/O link road to Villge Sarapara km. 0/00 to 1/420 (SH:- Providing wing walls of RCC Slab Culvert at RD 0/420)	478740.00	10000.00	One month	350/-
10	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- C/O wire crate R/Wall at RD 0/260 to 0/268 and 0/280 to 0/288)	449871.00	10000.00	One month	350/-
11	Restoration of rain damages on Dalash Rewari road km. 0/00 to 1/300. (SH:- C/O PCC breast wall at RD. 0/810 to 0/820).	185171.00	4000.00	One month	350/-
12	Construction of link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435 under MNP (Sub Head:- Construction of B/Wall at RD. 1/370 to 1/390)	329463.00	8000.00	Two months	350/-
13	Restoration of rain damages on Nore to Wazir Bowali road (MDR-28) road km. 0/00 to 37/00. (SH:-C/O PCC retaining Walls at RD. 12/612 to 12/622 and 12/635 to 12/641.70)	322893.00	4000.00	Two months	350/-
14	A/R & M/O Showad Karana road km. 0/00 to 15/900.(SH:- Providing M/T works in km. 15/600 to 15/750 at Bus Stand Karana)	399800.00	8000.00	Two months	350/-
15	A/R & M/O Showad Karana road km. 0/00 to 15/900.(SH:- Providing M/T works in km. 15/750 to 15/900 at Bus Stand Karana)	399800.00	8000.00	Two months	350/-
16	Restoration of rain damages on Khanag Shush Takrasi road km. 0/00 to 12/420. (Sub Head:- Providing and laying soling in slushy reaches between km. 4/00 to 6/00)	242342.00	5000.00	One month	350/-
17	Restoration of rain damages on Nore to Luhri road (MDR-120) km. 0/00 to 65/765 (Sub Head:- Construction of R/Wall at RD 33/145 to 33/160) under BASP.	314046.00	8000.00	Two months	350/-

It is certified that the above tenders i.e Sr. No 1 to 17 are very urgent nature, So may be uploaded on department website in public interest.


 Executive Engineer
 Outer Seraj Division
 H.P PWD, Nirmand
 on behalf of Governor of Himachal Pradesh

Schedule of quantity									
Name of Work:- Construction of Toilet Block at Neether. (SH:- Construction of B/Wall at RD.14/322.50 to 14/330 of Road from Jn. of LDCK to Jn. of NAS road)				Estimated cost:-		424373.00			
				Earnest Money		9000.00			
				Time		Two months			
				RATE		AMOUNT			
Sl. No.	Description of work	Qty.	Unit	Figures	Words				
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.75	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	8660.00			
2	Providing and Laying cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP PWD technical specifications including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	84.62	Cubic Metre	4802.10	Rupees Four Thousand Eight Hundred & Two - Paise Ten Only	406354.00			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	30.00	Each	311.95	Rupees Three Hundred & Eleven - Paise Ninety Five Only	9359.00			
Total in Figures						424373.00			
Rate quoted by contractor +/-				Percent					
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nizamand.

Schedule of quantity

Name of Work: Improvement of black spots by providing corrective measures on Wazir Bowali to Mohali road km. 0/0 to 26/00 (SH:- Improvement of curve at RD 11/255 to 11/315)					Estimated cost:-		187505.00
					Earnest Money		4000
					Time		One month
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT	
				Figures	Words		
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 124.92 cum. In all cases, @ Rs. 300/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	416.4	Cubic Metre	450.30	Rupees Four Hundred & Fifty - Paise Thirty Only	187505.00	
Total in Figures							187505.00
Rate quoted by contractor +/-					Percent		
quoted rate in figure							
Quoted rate in workds							


 Executive Engineer
 Outer Saraj Division

3

Schedule of quantity						
Name of Work: Improvement of black spots by providing corrective measures on Wazir Bowali to Mohali road km.				Estimated cost:-		199711.00
0/0 to 26/00 (SH:- Improvement of curve at RD 10/780 to 10/840)				Earnest Money		4000
				Time		One month
				RATE		AMOUNT
Sl. No.	Description of work	Qty.	Unit	Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 137.00 cum. In all cases, @ Rs. 300/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	410.00	Cubic Metre	487.10	Rupees Four Hundred & Eighty Seven - Paise Ten Only	199711.00
Total in Figures						199711.00
Rate quoted by contractor +/-					Percent	
Quoted rate in figure						
Quoted rate in workds						

Schedule of quantity

Name of Work: Restoration of rain damages on Nagan Chheora Chhattari road km. 0/00 to 12/240 . (SH:-Repair of abutment and pier of damages RCC Slab Culvert at RD 1/200 to 1/232)				Estimated cost:- Earnest Money Time		311657.00 7000 Two months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	12.16	Cubic Metre	371.00	Rupees Three Hundred & Seventy One Only	4511.00
2	Providing and Laying plain cement concrete 1:3:6 (one cement : three sand : six graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.85	Cubic Metre	5150.00	Rupees Five Thousand One Hundred & Fifty Only	9528.00
3	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C. grade M-25 nominal mix 1:1.5:3 (one cement: one point five snad: three graded stone aggregates twenty millimetre nominal size) complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	21.66	Cubic Metre	6600.00	Rupees Six Thousand Six Hundred Only	142956.00
4	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C. 1:2.4 (one cement: two snad: four graded stone aggregates twenty millimetre nominal size) complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	19.00	Cubic Metre	5800.00	Rupees Five Thousand Eight Hundred Only	110200.00
5	Fitting, and placing TMT bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 complete as per drawing and technical specifications including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete (Tore steel will be provided by the department free of cost)	3659.40	KG	12.15	Rupees Twelve - Paise Fifteen Only	44462.00
Total in Figures						311657.00
Rate quoted by contractor +/-			Percent			
quoted rate in figure						
Quoted rate in workds						


 Executive Engineer
 Outer Soraj Division
 HPPWD, Nirmand

Schedule of quantity

Name of Work: Restoration of rain damages on Sinvi Muhan road km. 0/00 to 3/075 . (SH:-Repair of abutment and pier of damages RCC Slab Culvert at RD 1/150 to 1/157 and 1/980 to 1/987)										Estimated cost:- Earnest Money		216058.00
										Time		5000
										Two months		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT					
					Words							
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.39	Cubic Metre	290.00	Rupees Two Hundred & Ninety Only		6203.00					
2	Providing and Laying plain cement concrete 1:3:6 (one cement : three sand : six graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.40	Cubic Metre	5150.00	Rupees Five Thousand One Hundred & Fifty Only		12360.00					
3	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C. grade M-25 nominal mix 1:1.5:3 (one cement: one point five snad: three graded stone aggregates twenty millimetre nominal size) complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	16.54	Cubic Metre	6600.00	Rupees Six Thousand Six Hundred Only		109164.00					
4	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C. 1:2.4 (one cement: two snad: four graded stone aggregates twenty millimetre nominal size) complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	10.80	Cubic Metre	5800.00	Rupees Five Thousand Eight Hundred Only		62640.00					
5	Fitting, and placing TMT bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 complete as per drawing and technical specifications including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete (Tore steel will be provided by the department free of cost)	1640.40	KG	12.15	Rupees Twelve - Paise Fifteen Only		19931.00					
	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	18.00	Each	320.00	Rupees Three Hundred & Twenty Only		5760.00					
Total in Figures								216058.00				
Rate quoted by contractor +/-							Percent					
quoted rate in figure												
Quoted rate in workds												


 Executive Engineer
 Outer Sanjay Division
 HPPWD, Nirmaland

Schedule of quantity	
Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/150 to 24/156.50)	

~~Executive Engineer
Outer Security Division~~

Signature of Tenderer with seal

Schedule of quantity

Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/156.50 to 24/160)									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
								Earnest Money	222025.00
								Time	6000
								AMOUNT	One month
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	10.68	Cubic Metre	186.00	Rupees One Hundred & Eighty Six Only				1986.00
	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	11.83	Cubic Metre	365.00	Rupees Three Hundred & Sixty Five Only				4318.00
2	Providing and Laying plain cement concrete 1:3:6 (one cement : three sand : six graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	40.29	Cubic Metre	5200.00	Rupees Five Thousand Two Hundred Only				209508.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.25	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only				5591.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.00	Each	311.00	Rupees Three Hundred & Eleven Only				622.00
Total in Figures									222025.00
Rate quoted by contractor +/-								Percent	
quoted rate in figure									
Quoted rate in workds									

8

Schedule of quantity									
Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O R/Walls at RD. 25/284.80 to 25/296)									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
								Earnest Money	One month
								Time	AMOUNT
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	16.80	Cubic Metre	186.00		186.00	Rupees One Hundred & Eighty Six Only		3125.00
	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	19.71	Cubic Metre			365.00	Rupees Three Hundred & Sixty Five Only		7194.00
2	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.05	Cubic Metre			4313.00	Rupees Four Thousand Three Hundred & Thirteen Only		26094.00
	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	71.46	Cubic Metre			5570.00	Rupees Five Thousand Five Hundred & Seventy Only		398032.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.61	Cubic Metre			1065.00	Rupees One Thousand & Sixty Five Only		7040.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	14.00	Each			311.00	Rupees Three Hundred & Eleven Only		4354.00
Total in Figures									445839.00
Rate quoted by contractor +/-						Percent			
quoted rate in figure									
Quoted rate in words									

Executive Engineer
Outer Sanj Division
Approved, Nirmand

9

Schedule of quantity

Schedule of quantity									
Name of Work:- A/R & M/O link road to villge Sarapara km. 0/00 to 1/420 (SH:- Providing wing walls of RCC Slab Culvert at RD 0/420)									
					Estimated cost:-		478740.00		
					Earnest Money		10000		
					Time		One month		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	15.00	Cubic Metre	327.60	Rupees Three Hundred & Twenty Seven - Paise Sixty Only		4914.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	17.60	Cubic Metre	524.10	Rupees Five Hundred & Twenty Four - Paise Ten Only		9224.00		
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.40	Cubic Metre	5338.25	Rupees Five Thousand Three Hundred & Thirty Eight - Paise Twenty Five Only		28827.00		
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	63.80	Cubic Metre	6590.60	Rupees Six Thousand Five Hundred & Ninety - Paise Sixty Only		420480.00		
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.90	Cubic Metre	1953.40	Rupees One Thousand Nine Hundred & Fifty Three - Paise Fourtyv Only		11525.00		
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.00	Each	377.00	Rupees Three Hundred & Seventy Seven Only		3770.00		
							478740.00		
					Percent				
	quoted rate in figure								
	Quoted rate in works								

(10)

Schedule of quantity									
Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (SH:- C/O wire crate R/Wall at RD 0/260 to 0/268 and 0/280 to 0/288)					Estimated cost:-		449871.00		
					Earnest Money		10000		
					Time		One month		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	53.76	Cubic Metre	178.15	Rupees One Hundred & Seventy Eight - Paise Fifteen Only		9577.00		
2	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	299.52	Cubic Metre	1470.00	Rupees One Thousand Four Hundred & Seventy Only		440294.00		
Total in Figures									449871.00
Rate quoted by contractor +/-					Percent				
Quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Mirmand.

Schedule of quantity

Name of Work:- Restoration of rain damages on Dalash Rewari road km. 0/00 to 1/300. (SH:- C/O PCC breast wall at RD. 0/810 to 0/820).					Estimated cost:- Earnest Money	185171.00
					Time	4000
					One month	
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	4.90	Cubic Metre	179.70	Rupees One Hundred & Seventy Nine - Paise Seventy Only	881.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	17.50	Cubic Metre	365.00	Rupees Three Hundred & Sixty Five Only	6388.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.10	Cubic Metre	4366.50	Rupees Four Thousand Three Hundred & Sixty Six - Paise Fifty Only	17903.00
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	34.30	Cubic Metre	4563.40	Rupees Four Thousand Five Hundred & Sixty Three - Paise Fourty Only	156525.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	9.00	Each	386.00	Rupees Three Hundred & Eighty Six Only	3474.00
Total in Figures						185171.00
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in workds						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Armand.

Schedule of quantity							
Name of Work: Conastruction of link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435 under MNP (Sub Head:- Construction of B/Wall at RD. 1/370 to 1/390)							
Sl. No.		Description of work	Qty.	Unit	RATE		AMOUNT
					Figures	Words	
1		Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	25.20	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	10033.00
2		Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.20	Cubic Metre	4278.50	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only	30805.00
3		Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	66.20	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	288625.00
Total in Figures							329463.00
Rate quoted by contractor +/-					Percent		
quoted rate in figure							
Quoted rate in workds							


 Executive Engineer,
 Outer Seraj Division,
 HPPWD Nirmand.

(13)

Schedule of quantity							Estimated cost:-	322893.00
Name of Work: Restoration of rain damages on Nore to Wazir Bowali road (MDR-28) road km. 0/00 to 37/00. (SH:-C/O PCC retaining Walls at RD. 12/612 to 12/622 and 12/635 to 12/641.70) under deposit of Telecom Deptt.							Earnest Money	8000
							Time	Two months
							RATE	AMOUNT
Sl. No.	Description of work	Qty.	Unit	Figures	Words			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	6.82	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only			1217.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	17.14	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only			6824.00
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	63.40	Cubic Metre	4733.40	Rupees Four Thousand Seven Hundred & Thirty Three - Paise Forty Only			300098.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only			6234.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	8.00	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only			8520.00
Total in Figures						Percent		322893.00
Rate quoted by contractor +/-								
quoted rate in figure								
Quoted rate in words								


 Executive Engineer,
 Outer Sewer Division,
 HPPWD, Nirmand.

Draft Schedule of quantity

Name of work:- A/R & M/O Showad Karana road km. 0/00 to 15/900.(SH:- Providing M/T works in km. 15/600 to 15/750 at Bus Stand Karana)									
Estimated cost:-					399800.00				
Earnest Money					8000				
Time					Two months				
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT			
				Figures	Words				
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	10.46	Per Cubic Metre	2,165.00	Rupees two Thousand one Hundred sixty five and paise sixty five Only	22646.00			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	44.61	Per Cubic Metre	2,525.90	Rupees two Thousand five Hundred twenty five and paise ninety Only	112680.00			
3	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 405, Grade-III A. By mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	44.61	Per Cubic Metre	2,689.25	Rupees two Thousand six Hundred eighty nine and paise twenty five Only	119967.00			
4	Providing and applying priming coat with bitumen emulsion (SS-I) using bitumen distributor at the rate of 0.85 kg. (Zero point eight five Kilogramme) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications clause of 502 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	654.23	Per Square Metre	68.68	Rupees sixty eight and paise sixty eight only.	44933.00			
5	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion pressure distributor @ 0.275 kg (Zero point two seven five Kilogramme) per square metre of the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications of clause 503 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Bitumen emulsion (RS-I) will be supplied by the department free of cost)	654.23	Per Square Metre	2.80	Rupees two and paise eighty only	1832.00			

Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
6	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508, including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Bitumen VG-10 will be supplied by the department free of cost)	654.23	Per Square Metre	121.80	Rupees one hundred twenty one and paise eighty only.	79685.00
7	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type B as per Technical Specification Clause 510 Case - II : including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Bitumen VG-10 will be supplied by the department free of cost)	654.23	Per Square Metre	27.60	Rupees twenty seven and paise sixty only.	18057.00
Total in Figures						399800.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Himachal Pradesh.

15

Draft Schedule of quantity									
Name of work:- A/R & M/O Showad Karana road km. 0/00 to 15/900.(SH:- Providing M/T works in km. 15/750 to 15/900 at Bus Stand Karana)					Estimated cost:-		399800.00		
					Earnest Money		8000		
					Time		Two months		
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	AMOUNT	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	10.46	Per Cubic Metre	2,165.00			Rupees two Thousand one Hundred sixty five and paise sixty five Only	22646.00	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	44.61	Per Cubic Metre	2,525.90			Rupees two Thousand five Hundred twenty five and paise ninety Only	112680.00	
3	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 405, Grade-III A. By mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	44.61	Per Cubic Metre	2,689.25			Rupees two Thousand six Hundred eighty nine and paise twenty five Only	119967.00	
4	Providing and applying priming coat with bitumen emulsion (SS-I) using bitumen distributor at the rate of 0.85 kg. (Zero point eight five Kilogramme) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications clause of 502 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	654.23	Per Square Metre	68.68			Rupees sixty eight and paise sixty eight only.	44933.00	
5	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion pressure distributor @ 0.275 kg (Zero point two seven five Kilogramme) per square metre of the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications of clause 503 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Bitumen emulsion (RS-I) will be supplied by the department free of cost)	654.23	Per Square Metre	2.80			Rupees two and paise eighty only	1832.00	

Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
6	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen VG-10 will be supplied by the department free of cost)	654.23	Per Square Metre	121.80	Rupees one hundred twenty one and paise eighty only.	79685.00
7	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type B as per Technical Specification Clause 510 Case - II : including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen VG-10 will be supplied by the department free of cost)	654.23	Per Square Metre	27.60	Rupees twenty seven and paise sixty only.	18057.00
Total in Figures						399800.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Noida.

Schedule of quantity							Estimated cost:- Rs.242342.00	
name of work:- Restoration of rain damages on Khanag Shush Takrasi road km. 0/00 to 12/420. (Sub Head:- Providing and laying soling in slushy reaches between km. 4/00 to 6/00)							Earnest Money:- Rs. 5000.00	
							Time :- One month.	
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT		
				Figures	Words			
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	993.00	Square metre	4.00	Rupees Four Only	3972.00		
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub grade including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	993.00	Square metre	2.00	Rupees Two Only	1986.00		
3	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 150mm spread thickness(finished work including materials and labour) and as per directions of the Engineer-In-Charge including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	148.95	Cubic Metre	1587.00	Rupees One Thousand Five Hundred & Eighty Seven Only	236384.00		
Total in Figures						242342.00		
Rate quoted by contractor +/-				Percent				
quoted rate in figure								
Quoted rate in workds								


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nizamand.

Schedule of quantity

Name of Work: Restoration of rain damages on Nore to Luhri road (MDR-120) km. 0/00 to 65/765. (Sub Head:- Construction of R/Wall at RD.33/145 to 33/160) under BASP									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
				AMOUNT				Earnest Money	
				Two months				Time	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	9.92	Cubic Metre	178.40			Rupees One Hundred & Seventy Eight - Paise Fourty Only	1770.00	314046.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	14.88	Cubic Metre	398.15			Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	5924.00	
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.12	Cubic Metre	4278.50			Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only	21906.00	
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	40.56	Cubic Metre	4359.90			Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	176838.00	
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	33.52	Cubic Metre	5023.00			Rupees Three Thousand & Twenty Three Only	101331.00	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.96	Cubic Metre	1265.60			Rupees One Thousand Two Hundred & Sixty Five - Paise Sixty Only	6277.00	
Total in Figures									314046.00
Rate quoted by contractor +/-							Percent		
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer
 Outer Sanction Division
 Jammu & Kashmir