

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 2617-19 Dated:- 6/6/23

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


**Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar**

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

**Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 15.06.2023 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 14.06.2023 upto 1:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Padhar Nauhli road Km 0/0 to 14/500. (SH:- Construction of P.C.C. retaining wall at R.D. 4/350 to 4/360)	2,22,448/-	4,500/-	350/-	One month
2	BSP/2022/1119, C/O (Construction of) Widening of road Galu to Rulang. (SH:- Improvement of curve, re-grading of road surface R.D. 5/420 to 5/795)	2,48,586/-	5,000/-	350/-	One month
3	VKV/2022/2553, R/O (Repair of) road from Bihal to village Tarwan Km 0/0 to 1/0. (SH:- Removal of formation deficiencies at R.D. 0/240 to 0/370).	82,871/-	1,700/-	350/-	One month
4	Restoration of rain damages on Bhiuli Tung road Km 0/0 to 12/300. (SH:- Hiring of Hydraulic excavator cum loader for removal of slips etc. in Km 0/0 to 6/0).	99,000/-	2,000/-	350/-	One month
5	Restoration of rain damages on Bhiuli Tung road Km 0/0 to 12/300. (SH:- Hiring of Hydraulic excavator cum loader for removal of slips etc. in Km 6/0 to 12/300).	99,000/-	2,000/-	350/-	One month
6	Restoration of rain damages on Uhl Valley road. (SH:- Hiring of Hydraulic excavator cum loader for removal of slips, dressing of berms, clearing of drains etc. in Km 10/0 to 22/0).	1,98,000/-	4,000/-	350/-	Two months
7	Improvement of black spot on Shegli Prasher road Km 0/0 to 22/510. (SH:- Improvement of curves at R.D. 2/010 to 2/262).	71,433/-	7,700/-	350/-	One month
8	Construction of Link road Lanjnu & Bridge over Uhl river. (SH:- Formation cutting in approaches at R.D. 0/720 to 0/790).	66,964/-	1,400/-	350/-	One month
9	Construction of Link road Lanjnu & Bridge over Uhl river. (SH:- Construction of Breast wall at R.D. 0/775 to 0/780).	93,313/-	1,900/-	350/-	One month
10	Construction of Community Health Centre Building at Kataula District Mandi (H.P.) (SH:- Providing and fixing powder fire extinguishers)	4,95,000/-	9,900/-	350/-	One month

1. **Certified that tender of above works are being called of emergent nature in exigency of public interest.**

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. The intending Contractors are requested to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 222448.00

Earnest Money Rs:- 4500.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Padhar Nauhli road Km. 0/0 to 14/500. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 4/350 to 4/360.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of Items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.90	Per cubic metre	485.30	9657.00	Rupees Nine Thousand Six Hundred Fifty Seven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.00	Per cubic metre	5497.70	197917.00	Rupees One Lakh Ninety Seven Thousand Nine Hundred Seventeen Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.30	Per cubic metre	1560.10	11389.00	Rupees Eleven Thousand Three Hundred Eighty Nine Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	290.40	3485.00	Rupees Three Thousand Four Hundred Eighty Five Only
Total in figure :					222448.00	Rupees Two Lakh Twenty Two Thousand Four Hundred Forty Eight Only
Total in Words :		Rupees Two Lakh Twenty Two Thousand Four Hundred			Forty Eight Only	


 Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar.


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 248586.00

Earnest Money Rs:- 5000.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- BSP/2022/1119, C/O (Construction of) Widening of road Galu to Rulang. (Sub Head:- Improvement of curve, re-grading of road surface R.D. 5/420 to 5/795.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	1381.64	Per cubic metre	202.82	280224.00	Rupees Two Lakh Eighty Thousand Two Hundred Twenty Four Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	52.73	Per cubic metre	600.00	-31638.00	Rupees Seventy Six Lakh Seventy Six Thousand Six Hundred Thirty Eight Only
Total in figure :					248586.00	Rupees Two Lakh Forty Eight Thousand Five Hundred Eighty Six Only
Total in Words :		Rupees Two Lakh Forty Eight Thousand Five Hundred			Eighty Six	Only


Executive Engineer,
Mandi Division No-1,
HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 82871.00

Earnest Money Rs:- 1700.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- VKV/2022/2553, R/O (Repair of) road from Bihal to village Tarwan Km. 0/0 to 1/0. (Sub Head:- Removal of formation deficiencies at R.D. 0/240 to 0/370.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	453.70	Per cubic metre	221.51	100499.00	Rupees One Lakh Four Hundred Ninety Nine Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	29.38	Per cubic metre	600.00	-17628.00	Rupees Fifty Six Lakh Fifty Six Thousand Six Hundred Twenty Eight Only
Total in figure :					82871.00	Rupees Eighty Two Thousand Eight Hundred Seventy One Only
Total in Words :		Rupees Eighty Two Thousand Eight Hundred Seventy One Only				


 Executive Engineer,
 Mandi Division No-I,
 HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 99000.00
Earnest Money Rs:- 2000.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Bhiuli Tung road Km. 0/0 to 12/300. (Sub Head:- Hiring of Hydraulic excavator cum loader for removal of slips etc. in Km. 0/0 to 6/0.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes including GST in Rs. P.	TOTAL AMOUNT with all taxes including GST in words.
1	Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, clearance of drains and catch pit/ dressing of berms in all kinds of soil and trimming of side slopes and disposing of earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etcetera happened during the course of hiring period shall be absolute responsibility of the contractor. The repair and spares including watch and ward of machines shall also be born by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per hour	1100.00	99000.00	Rupees Ninety Thousand Only
Total in figure :					99000.00	Rupees Ninety Nine Thousand Only
Total in Words :		Rupees Ninety Nine Thousand Only				Rupees Ninety Nine Thousand Only


Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 99000.00
Earnest Money Rs:- 2000.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Bhiuli Tung road Km. 0/0 to 12/300. (Sub Head:- Hiring of Hydraulic excavator cum loader for removal of slips etc. in Km. 6/0 to 12/300.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes including GST in Rs. P.	TOTAL AMOUNT with all taxes including GST in words.
1	Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, clearance of drains and catch pit/ dressing of berms in all kinds of soil and trimming of side slopes and disposing of earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etcetera happened during the course of hiring period shall be absolute responsibility of the contractor. The repair and spares including watch and ward of machines shall also be born by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per hour	1100.00	99000.00	Rupees Ninety Thousand Only
Total in figure :					99000.00	Rupees Ninety Thousand Only
Total in Words :		Rupees Ninety Nine Thousand Only				Rupees Ninety Nine Thousand Only


Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 198000.00
Earnest Money Rs:- 4000.00

Time Two months

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Uhl Valley road. (Sub Head:- Hiring of Hydraulic excavator cum loader for removal of slips, dressing of berms, clearing of drains etc. in Km. 10/0 to 22/0.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes including GST in Rs. P.	TOTAL AMOUNT with all taxes including GST in words.
1	Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, clearance of drains and catch pit/ dressing of berms in all kinds of soil and trimming of side slopes and disposing of earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etcetera happened during the course of hiring period shall be absolute responsibility of the contractor. The repair and spares including watch and ward of machines shall also be born by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	180.00	Per hour	1100.00	198000.00	Rupees One Lakh Ninety Eight Thousand Only
Total in figure :					198000.00	Rupees One Lakh Ninety Eight Thousand Only
Total in Words :		Rupees One Lakh Ninety Eight Thousand Only				


Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 71433.00

Earnest Money Rs:- 7700.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Improvement of black spot on Shegli Prasher road Km. 0/0 to 22/510. (Sub Head:- Improvement of curves at R.D. 2/010 to 2/262.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	380.35	Per cubic metre	221.93	84411.00	Rupees Eighty Four Thousand Four Hundred Eleven Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	21.63	Per cubic metre	600.00	-12978.00	Rupees Fifty Six Lakh Fifty Six Thousand Nine Hundred Seventy Eight Only
Total in figure :					71433.00	Rupees Seventy One Thousand Four Hundred Thirty Three Only
Total in Words :		Rupees Seventy One Thousand Four Hundred Thirty Three Only				


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 66964.00

Earnest Money Rs:- 1400.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Construction of Link road Lanju & Bridge over Uhl river. (Sub Head:- Formation cutting in approaches at R.D. 0/720 to 0/790.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	364.51	Per cubic metre	207.71	75712.00	Rupees Seventy Five Thousand Seven Hundred Twelve Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	14.58	Per cubic metre	600.00	-8748.00	Rupees Ninety Six Thousand Seven Hundred Forty Eight Only
Total in figure :					66964.00	Rupees Sixty Six Thousand Nine Hundred Sixty Four Only
Total in Words :		Rupees Sixty Six Thousand Nine Hundred Sixty Four Only				


 Executive Engineer,
 Mandi Division No-I,
 HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 93313.00

Earnest Money Rs:- 4500.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Construction of Link road Lanjnu & Bridge over Uhl river. (Sub Head:- Construction of Breast wall at R.D. 0775 to 0780.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS


Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.55	Per cubic metre	485.30	1238.00	Rupees One Thousand Two Hundred Thirty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.50	Per cubic metre	4916.15	90949.00	Rupees Ninety Thousand Nine Hundred Forty Nine Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.00	Each	281.40	1126.00	Rupees One Thousand One Hundred Twenty Six Only
Total in figure :					93313.00	Rupees Ninety Three Hundred Thirteen Only
Total in Words :		Rupees Ninety Three Thousand Three Hundred Thirteen Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 495000.00
Earnest Money Rs:- 9900.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Construction of Community Health Centre Building at Kataula Sub District Mandi (H.P.) . (Sub Head:- Providing and fixing powder fire extinguishers.)						
Contract No. :						
Bidder Name :						
<u>SCHEDULE OF WORKS</u>						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes including GST in Rs. P.	TOTAL AMOUNT with all taxes including GST in words.
1	Providing and fixing powder fire extinguisher (stored pressure type) 9 Kg (nine kilogramme) capacity duly ISI marked conforming to ISI : 15883:2006 with IS 14609, ISI marked ABC powder complete with squeeze grip release valve, discharge pipe, locking arrangement, pressure gauge, operational manual, brackets with two screw and sleeve including carriage of material within all leads, lifts and entire satisfaction of Engineer-in-Charge.	50.00	Each	9900.00	495000.00	Rupees Four Lakh Ninety Five Thousand Only
Total in figure :					495000.00	Rupees Four Lakh Ninety Five Thousand Only
Total in Words :		Rupees Four Lakh Ninety Five Thousand Only				


Executive Engineer,
Mandi Division No-I,
HP. PWD, at Padhar.