

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2022-23/ 2397-2447 Dated/ 17-6-23

To


✓ The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of HP letter No. PBW(B) A 9(3) 1/2020 dated Shimla -26th July 2021

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above


Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 01.07.2023 up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 30.06.2023 up to 4.00 P.M and the application for issue of tender form shall be received on 28.06.2023 up to 12.00 noon.


The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Link road to Deot Basti 0/00 to 0/500 (SW:- C/o R/Wall at Km 0/250 to 0/270)	Rs. 2,99,490/-	Rs. 6000/-	Three Months
2	C/o link road Manohar House to land of Vaishali GP Molichak Km 0/00 to 1/00 (SW:- C/o Edge wall, Paver Block etc at 0/650 to 0/700)	Rs. 4,91,452/-	Rs. 9900/-	Three Months
3	NH to Govt. High School Tanda via Saheed Captain Vikram Batra College to connect SC Basti Km 0/00 to 5/00 (SW:- Providing laying of Paver block at Km 1/700 to 1/800)	Rs. 4,48,393/-	Rs. 9000/-	Three Months
4	Restoration of rain damage on saheed Sourabh Kalia road Km 0/00 to 0/585 (SW:- Providing and laying CC Pavement at Km 0/210 to 0/265 & 0/495 to 0/575)	Rs. 4,94,204/-	Rs. 9900/-	Three Months
5	A/R & M/O various roads under Gopalpur Sub Division HP.PWD Gopalpur (SW:- Repair of Potholes at various roads in Lahla Section) i) Parour to Garh Mata via Brahmtheru Km 0/00 to 7/00 ii) Parour to Dharot road Km 0/00 to 2/500 (MMSRRY)	Rs. 4,94,851/-	Rs. 9,900/-	Three Months
6	C/o link road from Chowki Patwar Khana to Rajpur Chowk Kallu-Di-Hatti Kesar Bag Colony & Govt. College Palampur i/c bridge over Bhiral Khad (SW:- P/L Cement Concrete Pavement from Km 1/195 to 1/315)	Rs. 4,94,505/-	Rs. 9900/-	Three Months
7	A/R & M/O various road under HP.PWD Sub-division Palampur (Kandwari Section) (1) Speru to Nanahar via Rachiyara (2) Sungal to Matt (3) Neelkanth to Rajehar via Rampur (4) Gadiara to MadhoNagar (SW:- Repair of Pot holes in various RD,s (MMSRRY)	Rs. 4,96,982/-	Rs. 10,000/-	Three Months

Terms & Conditions

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand. Next tender will be issued only after completion of previous works in hand.



Executive Engineer

Draft Schedule of Quantity

Work No. (1)

Name of work :- Construction of Link road to Deot Basti Km. 0/00 to 0/500

Sub work:- C/o Retaining wall at RD 0/250 to 0/270. (SCSP)

Estimate Cost :- 299498/-
Earnest Money :- 6000/-
Time Limit : Three months.

S. No	Description of Item	Quantity		Rate		Unit	Amount
			In figure	In Words			Rs.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental.	22.40 Cubic metre.				Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:5:10 (1 cement: 5 sand:10 graded crushed/ broken stone aggregate 40 mm (forty millimetre) nominal size) in parapets and filling in abutments per drawing and MORD technical specifications Section 800, 900 & 1200 including the cost of form work and curing complete, including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the government.	70.40 Cubic metres.				Per Cubic metre	
3	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials with in all leads, lifts and other incidental.	13.20 Cubic metre.				Per Cubic metre	
4	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials with in all leads, lifts and other incidental.	27.00 Numbers				Each	
Total :-							

(Signature)

Executive Engineer
Palampur Division
HP.PWD Palampur

Draft Schedule of Quantity

Name of Work :- C/O link road Manohar House to land of Vaishali GP Molchak 0/00 to 1/00.

Sub Work :- Edge wall, Paver Block etc at 0/650 to 0/742). (SCSP)

Work No. 2

Estimated Cost : Rs. 4,91,452/-
Earnest Money : Rs. 9,900/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental.	16.56 Cubic metre.			Per Cubic metre	
2	Providing Cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) Nominal Mix P.C.C. grade for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .	27.60 Cubic metre			Per Cubic metre	
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all leads and lift and other incidental .The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	240.00 Square metres			Per Square-metre	
4	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix.P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .	1.84 Cubic metre.			Per Cubic metre	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Draft Schedule of Quantity

Work No. (3)

Name of Work : - NH to Govt. High School Tanda Via Saheed Capt. Vikram Batra College to Connect SC Basti 0/00 to 5/00.

Estimated Cost : Rs. 4,48,393/-
Earnest Money : Rs. 9,000/-

Sub Work :- Providing, laying of Paver Block at km 1/700 to 1/800). (SCSP)

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size WBM Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405, as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate including of octroi,royalty,Makana,tolltax, Sale Tax or other taxes imposed by the government.	2.55 Cubic metre.			Per Cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, makana, tolltax, sale tax or other taxes imposed by the government.	340.00 Square metres			Per Square-metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .	3.00 Cubic metre.			Per Cubic metre	
Total :-						


Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Work No. 7

Name of Work : - Restoration of Rain Damages on Sahced Sourabh Kalia road Km. 0/00 to 0/585.

Estimated Cost : Rupees 4,94,204/-

Sub Work :- P/L Cement concrete pavement road at RD 0/210 to 0/265 and 0/495 to 0/575.

Earnest Money : Rupees 9,900/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals.	22.80 Cubic metre.			Per Cubic metre	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental.	75.71 Cubic metre.			Per Cubic metre	

Total :-

Executive Engineer
Palampur Division
HP.PWD Palampur

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Gopalpur Sub Division HPPWD Gopalpur. (SH:- Repair of potholes at various roads in **Lahla** section).

1) Pour to Garh Mata via Brahmantheru Km 0/00 to 7/00.
2) Pour to dharot Road Km 0/00 to 2/500. (MMRRRy)

Estimated cost Rs.	4948
Earnest Money Rs.	9900
Time Limits	Three

S. No.	Description of Item	Quantity	Rate		Unit	A
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre, Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1365.00			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.23			Per Cubic metre	
	Total					

Executive Engineer
Palampur Division
HP.PWD Palampur.

Drafts Schedule of Quantity

Name of Work :- C/O Lin k road from Chowki Patwar Khana to Rajpur Chowk Kallu-Di-Hatti Kesar Bag Colony & Govt. College Palampur i/c bridge over Bhiral Khad.
Sub Work :- P/L Cement concrete pavement road at RD 1/195 to 1/315

Work No. 6

Estimated Cost : Rupees 4,94,505/-
Earnest Money : Rupees 9,900/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate including of octroi,royalty,Makana,tolltax, Sale Tax or other taxes imposed by the government.	11.89 Cubic metre.			Per Cubic metre	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate including of octroi,royalty,Makana,tolltax, Sale Tax or other taxes imposed by the government.	79.28 Cubic metre.			Per Cubic metre	
Total :-						

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 7

Name of Work : - A/R & M/O s in various road under HPPW Sub Division Palampur (Kandwari Section.)
i) Speru to Nanahar via Rachiyara. ii) Sungal to Matt. iii) Neelkanth to Rajehar via Rampur. iv) Gadiara to Madhonagar
Sub Work :- Repair of pot holes in various RD's (under MMSRRY)

Estimated Cost : Rupees 4,96,982/-
Earnest Money : Rupees 10,000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (Twenty millimetre) thick premix carpet and seal coat type B specification clause 1904.2, 503 and 508.1 The tendered rate shall be inclusive of charge, Royalty, Malkana, taxes and all other sundry / incidental expenses.	1426.57 Sqmt.			Per square metre	
2	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying aggregate, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals.	2.14 Cubic metre.			Per Cubic metre	
Total :-						

Executive Engineer
Palampur Division
HP.PWD Palampur