

Himachal Pradesh
Public Works Department
NO.PW.THD/CB-TENDER/2023- 2270-81
To

Dated:- 5-6-2023


The Executive Engineer, (I.T. Cell),
O/O Engineer-in-Chief,
H.P.P.W.D., Nirman Bhawan,
Shimla-2

Subject:- Publication of Tender Notice
Sir,

I am enclosing herewith Notice Inviting Tenders for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW(B)A(3)1/2020 dated 16th July,2021.


As the works mentioned in the tender notice are urgent in nature and in public interest.

Encl:- As above


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- 1 The Deputy Commissioner, Shimla Distt. Shimla, HP
- 2 The Superintending Engineer, 4th Circle, H.P.P.W.D., Shimla-3 . He is requested to grant permission for awarding of tender without publication in pursuance of Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter NO. PBW(B)A(3)1/2020 dated 7th January 2021.
- 3 The Sub-Divisional Officer(C) Theog
- 4 The Municipal Council Theog
- 5 Block Development Officer, Theog Block
- 6 All the Assistant Engineers working under this division
- 7 Superintendent Gr-II (Estt.) in this division
- 8 Drawing branch in this office.
- 9 Notice Board .



Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No. PW.THD/CB-tender/2022-2270-81..... dated 5/6/2023.....are of emergent nature in exigency of public interest.

Dated: 5th June, 2023

Place: Theog


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **14/06/2023 up to 11:00 PM.** and the same shall be opened on the same day at 11:30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **13/06/2023 up to 4:00 P.M.** and the application for issue of tender form shall be received on **12/06/2023 up to 4:00 P.M.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 60 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

| Sr. No | Name of work | Estimated cost(Rs.) | Earnest money (Rs.) | Cost of form (Rs) | Time allowed for completion |
|--------|--|---------------------|---------------------|-------------------|-----------------------------|
| 1 | 2 | 4 | 5 | 6 | 7 |
| 1 | A/R & M/O Shakildhar Alloti Devban road km 0/0 to 18/390 (SH:- P/L WBM G-III for repair of pot holes in km 15/00 to 18/390 in essential reaches) | 497122 | 10000 | 350 | one Month |
| 2 | R/R damages on Court to Khanewari road km 0/0 to 4/240 (SH:- C/O PCC R/Wall at RD 0/486 to 0/495) | 478130 | 9600 | 350 | one Month |
| 3 | C/O Additional accommodation to PWD Rest House at Fagu (SH:- Prov. Furnishing item) | 299900 | 6000 | 350 | one Month |
| 4 | R/r damages on Runkali Chikher road km 0/0 to 6/180 (SH:- C/O R/Wall at RD 5/970 to 5/987) | 469318 | 10000 | 350 | One month |
| 5 | R/R of rain damages on Fagu Cheog Dhamandari road km 5/680 to 24/0 (SH:- C/O R/Wall at RD 19/15 to 19/025 & 14/940 to 14/950) | 466599 | 9400 | 350 | One month |
| 6 | R/R damages on Shakil Dhar Aloti Dev Ban road km 0/0 to 18/390 (SH:- C/O B/wall in PCC at RD 0/675 to 0/705) | 497743 | 10000 | 350 | One month |
| 7 | R/R damages on Bhakhaliti Dharech Gawach Sidhpur road km 0/0 to 6/500 (SH:- C/O PCC B/Wall at RD 6/578 to 6/601) | 494917 | 9900 | 350 | One month |
| 8 | R/R of rain damages on Fagu Cheog Tiyaali Sainj Dhamandari road km 5/680 to 24/0 (SH:- C/O B/Wall at RD 19/135 to 19/153) | 269216 | 5400 | 350 | One month |
| 9 | R/R damages on Sainj Tikkri road km 0/0 to 4/0 (SH:- C/O B/Wall at RD 3/300 to 3/320) | 222668 | 4500 | 350 | One month |
| 10 | R/R of rain damages on Runkali Chikhar road km 0/0 to 6/0 (SH:- C/O PCC R/Wall at RD 5/730 to 5/750) | 348538 | 7000 | 350 | One month |
| 11 | R/R damages on Basa Mahog to Delogarh road km 0/0 to 6/0 (SH:- C/O B/Wall at RD 1/205 to 1/232 protection of house Sh. Dayal Chand | 302604 | 6050 | 350 | One month |
| 12 | Imp. of Bhakhaliti Dharech Gawach Sidhpur road km 0/0 to 10/0 (SH:- C/O B/Wall & RCC hume pipe culvert at RD 6/100 i/c both side wing wall) | 445401 | 9000 | 350 | One month |
| 13 | R/R damage on Damandari to Jais road km 0/0 to 6/500 (SH:- C/O R/Wall at RD 2/520 to 2/538 | 495113 | 10000 | 350 | One month |
| 14 | R/R damages on TKH road km 5/0 to 8/0 (SH:- C/O PCC R/wall at RD 5/450 to 5/465) | 478130 | 9600 | 350 | One month |

| | | | | | |
|----|---|--------|-------|-----|-----------|
| 15 | R/R damages on Kufri Chair road km 0/0 to 8/00 (SH:- C/O PCC R/Wall at RD 0/330 to 0/345) SCDP | 489023 | 10000 | 350 | One month |
| 16 | R/R damages on Bhakhality Dharech Gawach Sidhpur road km 0/0 to 10/00 (SH:- C/O R/Wall in PCC at RD 2/945 to 2/954 and B/Wall in PCC at RD 0/300 to 0/315) | 498459 | 10000 | 350 | One month |
| 17 | R/R of rain damages on Tyali Mandir to Nanoo road km 0/0 to 8/210 (SH:- C/O PCC R/Wall at RD 6/335 to 6/348) | 300438 | 6100 | 350 | One month |
| 18 | R/R of rain damages on Dhamandari jais road km 0/0 to 6/500 (SH:- C/O B/Wall at RD 2/635 to 2/655) | 320790 | 6500 | 350 | One month |
| 19 | R/R of rain damages on Bhakhality to Sarog road km 0/0 to 13/060 (SH:- C/O Bwall at RD 4/095 to 4/120) | 270307 | 5500 | 350 | One month |
| 20 | Annual maintenance of Kanohar Nallah to Jahu road km 0/0 to 2/570 (SH:- P/L renewal coat 30mm thick BC & 50mm thick BM in Lower Jahu to Upper Jahu km 0/0 to 0/180) | 491499 | 10000 | 350 | One month |
| 21 | R/R of rain damages on Rahighat Kiartoo road km 0/0 to 4/00 (SH:- C/O B/Wall at RD 5/045 to 5/064.50) | 450214 | 9000 | 350 | One month |
| 22 | C/O Dhalli Chouri road km 0/0 to 6/0 (SH:- C/O PCC R/Wall at RD 2/255 to 2/240)SCCP | 393301 | 8000 | 350 | One month |

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. Following documents should accompany the application for tenders: -

- (1) The contractors are required to be produce a copy of their PAN No.Sale tax No. with sales tax clearance Certificate and should produce a copy of enlistment /renewal letter.
- (2) Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- (3) The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act 1952 (EPF number) within a month from award of work/contract. Failure to observe this condition shall render the tender of contractor liable to summary rejection.
- (4) The bidder are advised to quote rates inclusive of G.S.T. as applicable notified vide Additional Chief Secretary (PW) to the Govt. of H.P. letter No. PBW(B)C(17)2/2012 dated 07/08/2018 ,G.S.T. shall not be paid extra.
- (5) The contractor will give affidavit duly attested from the competent authority that he has not more than two works in hand for execution failing which the application shall be rejected.
- (6) The provision of notification issued vide Addl. Chief Secretary (PW) to the govt. of H.P. Notification No.PBW(B)A(3)1/2020 dated 13th April 20021 shall also be applicable.

On Behalf of Governor of Himachal Pradesh

Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

DNIT/SCHEDULE OF QUANTITY


Estimated Cost Rs.497122

Earnest Money:10000/-

Time: One months

Name of Work : A /R and M/O Shakildhar Alloti Devban road km 0/0 to 18/390 (SH:- P/L WBM G-III for repair of Pot Holes in km 15/0 to 18/390 in essential reaches.)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|---|--------|--------------|--|-----------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | WBM Grade-3 Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density-grading 3 as per Technical Specification Clause 405/c all leads and lifts and as per direction of the Engineer-in- Charge. | 216.14 | 2300.00 | Rupees two thousand three hundred only | Per cubic meter | 497122 |
| | | | | | | 497122 |


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Name of Work : - R/R damages on Court to Khnewari road km 0/0 to 4/240 (SH: C/O PCC R/wall at RD 0/486 to 0/495...)

Estimated Cost Rs.478130/
 Earnest Money:9600/
 Time: one Months

| Sr. No. | Description of Item | QTY | Rate | | | Unit | Amount |
|---------|--|--------|--------------|---|--|-------------------|--------|
| | | | Rate in fig. | Rate in words | | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 50.31 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | | per cubic meter | 10771 |
| 2 | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm | 102.55 | 4178.00 | Rupees Four Thousand One Hundred Seventy Eight Only | | Per cubic meter | 428454 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer-in -Charge. | 31.50 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | | Per running meter | 7628 |
| 4 | Stone filling behind the retaining wall,B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge. | 16.20 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only | | Per cubic metre | 20390 |
| | | | | | | | 467243 |

Signature
 Executive Engineer,
 Theog Division,
 HP.PWD. Theog


SCHEDULE OF QUANTITY

Estimated Cost Rs.299900
Earnest Money:6000/
Time: one Month

Name of Work : - C/O Additional Accomodation to PWD Rest house at Fagu in Teh- Theog Distt- Shimla HP (SH:- Providing Furnishing item)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount | |
|---------|--|-------|--------------|--|------|--------|--------|
| | | | Rate in fig. | Rate in words | | | |
| 1 | Supplying of sleepwell mattress of Size 75 "x 72"x 6" including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 6.00 | 28000.00 | Rupees Twenty Thousand Only | each | | 168000 |
| 2 | Providing and placing quilt single bed (Comforter) of high quality comfortable cotton blend microfiber in serten inside including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 8.00 | 3200.00 | Rupees Three Thousand Two Hundred Only | each | | 25600 |
| 3 | Providing and placing quilt cover single bed (Dohar cover) of high quality comfortable cotton including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 16.00 | 1700.00 | Rupees One Thousand Seven Hundred Only | each | | 27200 |
| 4 | Providing and placing blanket single bed including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 8.00 | 2800.00 | Rupees Two Thousand Eight Hundred Only | each | | 22400 |
| 5 | Providing and placing bed sheet double bed of high quality comfortable cotton including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 10.00 | 2200.00 | Rupees Two Thousand Two Hundred Only | each | | 22000 |
| 6 | Providing and placing pillow of high quality comfortable cotton blend microfiber in serten inside including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 12.00 | 600.00 | Rupees Six Hundred Only | each | | 7200 |
| 7 | Providing and placing pillow cover including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 12.00 | 125.00 | Rupees One Hundred Twenty Five Only | each | | 1500 |
| 8 | Providing and placing foot mat durasoft rubber including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 50.00 | 280.00 | Rupees Two Hundred Eighty Only | sqft | | 14000 |

| | | | | | | |
|---|---|------|---------|--------------------------|------|--------|
| 9 | Providing and placing bed Cover with pillow cover double bed of high quality comfortable cotton including carriage of material with in all lead and lifts. As per the direction of Engineer- In-charge. | 6.00 | 2000.00 | Rupees Two Thousand Only | each | 12000 |
| | | | | | | 299900 |


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.469318

Earnest Money: 10000/

Time: Two months

Name of Work : R/R damages on Runkail Chikhar road road km 0/0 to 6/180 (SH:- C/O R/wall in RR Masonary in km RD 5/970 to 5/987.)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|--------|--------------|---|-----------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 47.67 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 10206 |
| 2 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 20mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 4.62 | 4291.60 | Rupees Four Thousand Two Hundred Ninety One and Paise | Per cubic meter | 19827 |
| 3 | Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts as per direction of the Engineer-in-Charge.) | 124.95 | 3365.50 | Rupees Three Thousand Three Hundred Sixty Five and Paise Fifty Only | Per cubic meter | 420519 |
| 4 | Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer-in-Charge. | 14.91 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only | Per cubic meter | 18766 |
| | | | | | | 469318 |

Executive Engineer,
Theog Division,
HP.PWD. Theog


SCHEDULE OF QUANTITY

Estimated Cost Rs.466599
Earnest Money:9400/

Time: One months

Name of Work : R/R damages on Fagu Cheog Tiyaal Dhamandri road km 5/680 to 24/0 (SH:- C/O PCC R/wall at RD 19/015 to 19/025 and 14/940 to

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|-------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 66.05 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 14141 |
| 2 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 96.94 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 405054 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC aburnent,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge. | 67.90 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | Per running meter | 16442 |
| 4 | Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge. | 24.60 | 1258.65 | Rupees One Thousand Fifty Eight and Paise Sixty Five Only | Per cubic meter | 30963 |
| | | | | | | 466599 |


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY


Estimated Cost Rs.497743

Earnest Money:10000/-

Time: One months

Name of Work : R/R damages on Shakeel Dhar Aloit Dev Ban road Km 0/0 to 18/390 (SH:- C/O PCC B/wall at RD0/675 to 0/705.)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|--------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge. | 160.00 | 148.75 | Rupees One Hundred Forty Eight and Paise Seventy Five Only | Per cubic meter | 23800 |
| 2 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 35.84 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 7673 |
| 3 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 107.36 | 4178.40 | Rupees Four Thousand Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 448593 |
| 4 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in-Charge. | 73.00 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | Per running meter | 17677 |
| | | | | | | 497743 |


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Name of Work : R/R damages on Bhekhalti Dharech Gawech Sidhpur road km 0/0 to 6/500 (SH:- C/O PCC R/wall at RD 6/578 to 6/601.)

Estimated Cost Rs.494917

Earnest Money:9900/

Time: One months

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|--------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 27.83 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 5958 |
| 2 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 107.41 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 448802 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer-in-Charge. | 69.00 | 242.15 | Rupees Two Hundred Two and Paise Fifteen Only | Per running meter | 16708 |
| 4 | Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer-in-Charge. | 18.63 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only | Per cubic meter | 23449 |
| | | | | | | 494917 |

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY


Name of Work : R/R damages on Fagu Cheog Sainj Dhamandri road km 5/680 to 24/0 (SH:- C/O B/wall at RD 19/135 to 19/153.)

Estimated Cost Rs.269916

Earnest Money:5400/

Time: One months

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|-------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge. | 33.84 | 148.75 | Rupees One Hundred Forty Eight and Paise Seventy Five Only | Per cubic meter | 5034 |
| 2 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 20.16 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 4316 |
| 3 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 60.39 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 252334 |
| 4 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer-in-Charge. | 34.00 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | Per running meter | 8233 |
| | | | | | | 269916 |


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Name of Work : R/R damages on Sainj Tikkeri road km 0/0 to 4/0 (SH:- C/O B/wall at RD3/300 to 3/320.)

Estimated Cost Rs.222668
Earnest Money:4500/
Time: One months

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|-------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts-as per direction of Engineer-in-Charge. | 27.20 | 179.70 | Rupees One Hundred Seventy Nine and Seventy Only | Per cubic meter | 4888 |
| 2 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 19.40 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 4154 |
| 3 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 49.04 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 204909 |
| 4 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts-as per direction of the Engineer -in -Charge. | 36.00 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | Per running meter | 8717 |
| | | | | | | 222668 |

Amt.
Executive Engineer,
Theog Division,
HP.PWD. Theog

DNI/SCHEDULE OF QUANTITY

Name of Work : R/R damages on Runkali Chikhar road km 0/0 to 6/0 (SH:- C/O PCC R/wall at RD 5/730 to 5/750)

Estimated Cost Rs.348538

Earnest Money:7000/

Time: One months

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|-------|--------------|--|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 32.20 | 214.10 | Rupees Hundred Fourteen and Paise Only | Per cubic meter | 6894 |
| 2 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 71.60 | 4178.40 | Rupees Thousand Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 299173 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge. | 60.00 | 242.15 | Rupees Hundred Two and Paise Fifteen Only | Per running meter | 14529 |
| 4 | Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge. | 22.20 | 1258.65 | Rupees Thousand Hundred Eight and Paise Sixty Five Only | Per cubic meter | 27942 |
| | | | | | | 348538 |

Aut
Executive Engineer,
Theog Division,
HP.PWD. Theog

DNIT/SCHEDULE OF QUANTITY

Estimated Cost Rs.302604
Earnest Money:6050/

Time: One months

Name of Work : R/R damages on Basa Mahog Detogarth road km 0/0 to 6/0 (SH:- C/O E/wall at RD 1/205 to 1/132 Protection of House Sh. Dayal Chand)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|-------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Excavation in soil in Hilly area by Manual means including cutting and trimming of sides, lops and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification Clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge. | 54.00 | 179.70 | Rupees One Hundred Seventy and Nine Paise and Seventy Only | Per cubic meter | 9704 |
| 2 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 26.46 | 214.10 | Rupees Two Hundred Fourteen and Ten Paise Only | Per cubic meter | 5665 |
| 3 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 65.88 | 4178.40 | Rupees Four Thousand Seven Hundred Eight and Paise Forty Only | Per cubic meter | 275273 |
| 4 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge. | 49.40 | 242.15 | Rupees Two Hundred Two and Paise Fifteen Only | Per running meter | 11962 |
| | | | | | | 302604 |

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.445401

Earnest Money:9000/-

Time: Two months

Name of work:- Imp. Of Bhakality Dharech Gowech Sidhpur road km 0/0 to 10/0 (SH:- C/O B/wall & RCC Hurre pipe culvert at RD 6/100 including both side wing wall)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|---|-------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto a depth of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 97.10 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 20789 |
| 2 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 80.31 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 335567 |
| 3 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 PCC grade M-10 hand mixing including all leads and lifts as per direction of the Engineer-in-Charge. | 11.44 | 4850.00 | Rupees Four Thousand Eight Hundred Fifty Only | Per cubic meter | 55484 |
| 4 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC aburnent,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts as per direction of the Engineer -in - Charge. | 30.00 | 296.50 | Rupees Two Hundred Ninety Six and Paise Fifty Only | Per running meter | 8895 |
| 5 | Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in - Charge. | 1.26 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only | Per cubic meter | 1586 |
| 6 | Providing laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 900mm dia including all leads and lifts as per direction of the Engineer in-Charge. | 5.00 | 4615.90 | Rupees Four Thousand Six Hundred Fifteen and Paise Ninety Only | Per running meter | 23080 |
| | | | | | | 445401 |

Handwritten signature

SCHEDULE OF QUANTITY

Estimated Cost Rs.495113/
Earnest Money:10000/
Time: one Months

Name of Work : - F/R damages on Dhamandri Jais road km 0/0 to 6/500 (SH: 020 PCC R/wall at RD2/520 to 2/538.)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|--------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 24.48 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | per cubic meter | 5241 |
| 2 | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) | 106.56 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty | Per cubic meter | 445250 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC aburnent, B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts, as per direction of the Engineer -in -Charge. | 72.00 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | Per running meter | 17435 |
| 4 | Stone filling behind the retaining wall B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge. | 21.60 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only | Per cubic metre | 27187 |
| | | | | | | 495113 |

Executive Engineer
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY


Estimated Cost Rs.478130/

Earnest Money:3600/

Time: one Months

Name of Work : - R/R damages on TKH road km 5/100 to 8/0(SH: C/O PCC R/wall at RD 5/450 to 5/465.)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|--------|--------------|---|-------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.4 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 52.50 | 214.00 | Rupees Two Hundred Fourteen Only | per cubic meter | 11235 |
| 2 | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm | 104.67 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 43735 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC aburnent,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge. | 52.00 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | Per running meter | 12592 |
| 4 | Stone filling behind the retaining wall,B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge. | 13.50 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only | Per cubic metre | 16992 |
| | | | | | | 478130 |


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY


Estimated Cost Rs.489023/

Earnest Money:10000/

Time: one Months

Name of Work : - R/R damages on Kufri Chair road km 0/0 to 8/0(SH: C/O PCC R/wall at RD 0/330 to 0/345.)SCDP

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|--------|--------------|---|-----------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 56.70 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | per cubic meter | 12133 |
| 2 | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm | 101.25 | 4276.00 | Rupees Four Thousand Two Hundred Seventy Six Only | Per cubic meter | 43294 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer-in-Charge. | 64.50 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | per cubic metre | 15614 |
| 4 | Stone filling behind the retaining wall,B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer-in-Charge. | 22.50 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only | Per cubic metre | 28320 |
| | | | | | | 48902 |


Executive Engineer,
Theog Division,
HP.PWD. Theog

DNIT/Schedule of Quantity


Estimated Cost: 498459/-
Earnest Money 10000/-

Time One month

Name of Work: R/R Of Rain Damages on Bhakailly Dharech Gowech Sidhpur Road km 0/0 to 10/00 (SH:- C/O PCC R/Wall at RD

2/945 to 2/954 & C/O B/Wall at Rd 0/300 to 0/315)

| Sr. | Description of Items | QTY. | Rate | | Unit | Amount |
|-----|--|--------|---------|---|---------|-----------|
| 1 | Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge. | 21.60 | 148.75 | Rupees one hundred forty eight & seventy five Paisa only | P/cum | 3213.00 |
| 2 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 35.94 | 214.00 | Rupees two hundred fourteen & ten Paisa only | P/cum | 7691.16 |
| 3 | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 40mm nominal size) | 109.38 | 4178.40 | Rupees four thousand two hundred seventy six only | P/cum | 457033.39 |
| 4 | Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. | 25.00 | 242.15 | Rupees two hundred forty two & fifteen Paisa only | Per mtr | 6053.75 |
| 4 | Stone Back Filling behind retaining wall/ breast wall. including all leads and lifts as per direction of the Engineer-in-Charge | 19.44 | 1258.65 | Rupees one thousand two hundred fifty eight & sixty five Paisa only | P/cum | 24468.16 |
| | | | | | Total | 498459.00 |


Executive Engineer,
Theog Division,
HP.PWD, Theog.

DNIT/Schedule of Quantity

Estimated Cost:-300438/-

Earnest Money 6100/-

Time One month

PCC R/Wall at RD 6/335 to 6/348)

Name of Work:R/R Of Rain Damages on Tiyaali Mandir Nanoo Road km 0/0 to 8/120 (SH:- C/O

| Sl. | Description of Items | QTY. | Rate | Unit | Amount |
|-----|--|-------|---------|--|------------------|
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 40.93 | 214.10 | Rupees two hundred fourteen & ten Paissa only | P/cum 8763.11 |
| 2 | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203, including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 40mm nominal size) | 62.40 | 4178.40 | Rupeesfour thousand two hundred seventy six only | P/cum 260732.16 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. | 46.70 | 242.15 | Rupees two hundred forty two & fifteen Paissa only | Per mnt 11308.41 |
| 4 | Stone Back Filling behind retaining wall/ breast wall. including all leads and lifts as per direction of the Engineer-in-Charge | 15.60 | 1258.65 | Rupees one thousand two hundred fifty eight & sixty five Paissa only | P/cum 19634.94 |
| | | | | Total | 300438.00 |

A. M. L.
Executive Engineer,
Theog Division,
HP PWD, Theog.

DNIT/Schedule of Quantity


Estimated Cost:-320790/-

Earnest Money 6500/-

Time One month

Name of Work:-R/R Of Rain Damages on Dhamandri Jais Road km 0/0 to 6/500 (SH:- C/O PCC B/Wall at RD 2/635 to 2/655)

| Sr. | Description of Items | QTY. | Rate | | Unit | Amount |
|-----|--|-------|---------|--|---------|-----------|
| 1 | Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer in-Charge. | 42.80 | 148.75 | Rupeesone hundred forty eight & seventy five Paissa only | P/cum | 6366.00 |
| 2 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 26.00 | 214.10 | Rupees two hundred fourteen & ten Paissa only | P/cum | 5566.00 |
| 3 | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 40mm nominal size) | 71.60 | 4178.40 | Rupeesfour thousand two hundred seventy six only | P/cum | 299173.00 |
| 4 | Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts | 40.00 | 242.15 | Rupees two hundred forty two & fifteen Paissa only | Per mmt | 9685.00 |
| | | | | | Total | 320790.00 |


Executive Engineer,
Theog Division,
HP.PWD. Theog.


DNIT/Schedule of Quantity

Estimated Cost:-270307/-
Earnest Money 5500/-

Time One month

Name of Work: R/R Of Rain Damages on Bhakality Sarog Road km 0/0 to 13/060 (SH:- C/O PCC B/Wall at RD 4/095 to 4/120)

| Sr. | Description of Items | QTY. | Rate | Unit | Amount |
|-----|--|-------|---------|--|------------------|
| 1 | Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer in-Charge. | 24.50 | 148.75 | Rupeesone hundred forty eight & seveny five Paissa only | P/cum 3644.00 |
| 2 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 24.50 | 214.10 | Rupees two hundred fourteen & ten Paissa only | P/cum 5245.00 |
| 3 | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 40mm nominal size) | 61.00 | 4178.40 | Rupeesfour thousand one hundred seveny eight & forty Paissa only | P/cum 254882.00 |
| 4 | Providing and fixing weapholes in brick masonry/stone masnory, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts | 27.00 | 242.15 | Rupees two hundred forty two & fifteen Paissa only | Per mlt 6538.00 |
| | Total | | | | 270307.00 |


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog.

SCHEDULE OF QUANTITY


Estimated Cost Rs.491499/-

Earnest Money:-10000/-

Time: One months

Name of work:- Annual Maintenance of Kanohar Nallaha to Jahu road KM 0/0 to 2/570 (SH:- Providing and laying renewal coat of 30 mm thick BC and 50 mm thick BM in lower Jahu upper Jahu Km 0/0 to 0/180.)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|---|---------|--------------|---|------------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per Technical Specification Clause 405/c all leads and lifts and as per direction of the Engineer-in-Charge. | 8.25 | 2196.60 | Ruppes two thousand one hundred ninety six & sixty Paissa only | Per cubic meter | 18122 |
| 2 | Providing and applying tack coat using Bitumen emulsion conforming to IS :8887 using emulsion distributor including preparing the surface and cleaning the mechanical broom on bituminous surface @25 kg per sqm as per direction of the Engineer-in-Charge. | 1095.00 | 21.01 | Ruppes twenty one & one Paissa only | Per square metre | 23006 |
| 3 | Providing and laying Bitumen penetration Macadam with hard stone aggregate of quality, size and grading as specified ,with bitumen of suitable penetration grade, including required key aggregate as specified ,spreading coarse aggregate with the helps of self propelled /tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete including Consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy as per direction of the Engineer-in-Charge. | 23.25 | 9187.58 | Ruppes nine thousand one hundred eighty seven & fifty eight Paissa only | Per square metre | 213611 |
| 4 | Providing and laying bituminous concrete using crushed stone aggregate of specified grading primixed with bituminous binder and filler, transporting the hot mix to work site by tippers laying with paver finisher equipped with electronic sensor to the required grade level and alignment rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction and density as per specifications complete per direction of the Engineer-in-Charge. 30mm compacted thickness with bitumen of grade VG-10 @5.5% (percentage)by weight of tota: mix)and lime aggregate prepared in batch type Hot MIX plant of 100-120 TPH capacity. | 18.90 | 12527.00 | Ruppes twelve thousand five hundred twenty seven only | Per cubic meter | 236760 |
| | | | | | | 491499 |



 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

DNIT/SCHEDULE OF QUANTITY

Estimated Cost Rs.499630
Earnest Money: 10000/
Time: One months

Name of Work : R/R damages on Rahighat Kiartoo road km 0/0 to 4/0 (SH:- C/O PCC R/wall at RD 2/285 to 2/300)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|--------|--------------|---|-----------------|--------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 37.50 | 214.10 | Rupees Two Hundred Fourteen and Paise Ten Only | Per cubic meter | 8029 |
| 2 | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm | 109.50 | 4178.40 | Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only | Per cubic meter | 4575 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument, B/wall R/wall with 100 mm dia PVC pipe i/c all leads and lifts.as per direction of the Engineer-in-Charge. | 90.00 | 242.15 | Rupees Two Hundred Forty Two and Paise Fifteen Only | each | 2179 |
| 4 | Back filling behind the retaining wall. all leads and lifts as per direction of the Engineer-in-Charge. | 9.75 | 1258.65 | Rupees One Thousand Two Hundred Fifty Eight | Per cubic meter | 122 |
| | | | | | | 4996 |


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY


Estimated Cost Rs.393301

Earnest Money:8000/

Time: One months

Name of Work : C/O Dhali Chauri road km 0/0 to 6/0 (SH:- C/O PCC R/wall at RD 2/240 to 2/255)

| Sr. No. | Description of Item | QTY | Rate | | Unit | Amount |
|---------|--|-------|--------------|---|-------------------|---------|
| | | | Rate in fig. | Rate in words | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil) | 36.90 | 214.10 | Rupees Hundred Fourteen and Paise Only | Per cubic meter | 7900 |
| 2 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40mm N.S including all leads and lifts as per direction of the Engineer-in-Charge. | 84.66 | 4178.40 | Rupees Thousand Hundred Eight and Paise Forty Only | Per cubic meter | 353743 |
| 3 | Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer-in-Charge. | 32.50 | 242.15 | Rupees Hundred Two and Paise Fifteen Only | Per running meter | 7870 |
| 4 | Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer-in-Charge. | 18.90 | 1258.65 | Rupees Thousand Hundred Eight and Paise Sixty Five Only | Per cubic meter | 23788 |
| | | | | | | 3933301 |


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog