



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in Email:- ee-bsr-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW·BSR·E·105/2023·2024·
To

9782-90

Dated:- 05-07-23

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.

Executive Engineer
Barsar Division
HPPWD Barsar

Copy forwarded with its enclosures for information to:-

1. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
2. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Supdt of C Branch in this office.
6. Notice Board.

Executive Engineer
Barsar Division
HPPWD Barsar.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**
Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in Email:- ee_bar_hp@nic.in Phone No:- 01972-288041

NOTICE INVITING TENDER.

Scaled percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP, from the approved eligible contractors enlisted in HPPWD, for the following works: so as to reach this office on **11-07-2023 up to 10.30 A.M.** and same will be opened on the same day at **11.00 A.M.** in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **07-07-2023 upto 1:30 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **10-07-2023** during office hours till **2.00 P.M.** The application must be accompanied with earnest money in shape of NSD FDR Time deposit etc. of any post office of HP, or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained. It may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from, earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required along with latest returns, Copy of PAN Card, EPF along with latest returns failing which no tender form will be issued to him. All the required documents must be attached with the application.**

Sr. No.	Name of work	Estimated Cost	Earnest Money	Cost of Tender form	Time limit	Eligible Class
1.	Restoration of rain damage on link road H.B. Damyana km. 0/ to 0/530 (Sh:- C/O R/Wall at Rd. 0/260 to 0/270, V-shape & U-shape drain at various rds.)	4,47,634/-	9,000/-	350/-	Two Month	C & D
2	Restoration of rain damage on Mehre Jabbal Kherian road Km. 0/0 to 6/0 (Sh:- C/O wire crate R/wall at Rd. 4/200 to 4/216)	4,94,396/-	9,900/-	350/-	Two Month	C & D
3	C/O L/R from Budan Da paron to H.B. Bihru (G.P. Sakroh((Sh:- P/L 900mm dia RCC hume pipe culvert at Rd. 0/705 & 0/750) Under SCSP Head	4,76,874/-	9,600/-	350/-	Two Month	C & D
4	Restoration of rain damage on Badran Garli road Via Ghallian Jole Km. 4/0 to 13/500 (Sh:- P/L C.C. pavement at Rd. 12/836 to 12/900)	4,93,896/-	9,900/-	350/-	One Month	C & D
5	Restoration of rain damage on L/R H.B. Village Kalyana (Sh:- C/O R/wall at Rd. 0/980 to 0/999 & V-shape drain at Rd. 0/900 to 1/050)	4,50,054/-	9,000/-	350/-	One Month	C & D
6	Repair & maintenance of G.S.S. Giara Gran Distt. Hamirpur (Sh:- Distempering, painting & tiles etc.) D.W.	3,57,119/-	7,200/-	350/-	One Month	C & D
7	C/O L/R Thapper to Vill. Khansara Km. 0/0 to 1/500 (Sh:- F.C. in km. 0/735 to 0/750, R/wall at Rd. 0/060 to 0/072 & P/L 900mm dia RCC hume pipe culvert at Rd. 0/840) Under OTMNP Head	4,51,217/-	9,100/-	350/-	Three Month	C & D
8	C/O Link road from Gwaled Khad to Samella Check DPF Samella via Tajyar km. 0/0 to 1/710 (Sh:- P/L 900mm dia RCC hume pipe culvert at Rd. 0/378 i/c wing walls) Under SCSP Head	4,71,125/-	9,500/-	350/-	Two Month	C & D
9	C/O L/R from College rain shelter to H.B. W. No. 5 (Sh:- Balance work for the C/O 3.00 mtr. Saphn RCC type culvert at Rd. 0/425) Under SCSP Head	4,77,337/-	9,600/-	350/-	Two Month	C & D

10	C/O L/R from Tanger to Vill. Bhudloo (Ghori) km. 0/0 to 1/0 (Sh:- F.C. in between km. 0/0 to 0/450 & P/L 900mm dia RCC hume pipe culvert at Rd. 0/450) Under OTMNP Head	4,08,336/-	8,200/-	350/-	Three Month	C & D
11	C/O L/R to village Tiyalu (Loharara) G.P. Dhabriana Km. 0/0 to 1/200 (Sh:- C/O edge wall at Rd. 0/410 to 5/446, 0/520 to 0/555) Under OTMNP Head	4,84,097/-	9,700/-	350/-	One Month	C & D
12	Restoration of rain damage on Bani Matkar road Km. 0/0 to 6/715(Sh:- C/O B/wall at Rd. 3/750 to 3/775)	2,69,102/-	5,400/-	350/-	One Month	C & D
13	Restoration of rain damage on Harsour Garli road km. 0/0 to 8/0 (Sh:- C/O R/wall at rd. 5/030 to 5/042)	2,29,239/-	4,600/-	350/-	One Month	C & D
14	VKV/2022/337 C/O L/R from Pattian Mahila Mandal to village Tathliayan (Masalana khurd) G.P. Jhanjiani(Sh:- P/L 600mm dia RCC humepipe culvert at Rd. 0/600) Deposit Head)	1,39,769/-	2,800/-	350/-	One Month	C & D
15	C/O L/R Kohdra to Badloi via Pattian km. 0/0 to 1/800 (Sh:- C/O U-Shape drain with edge wall) Under SCSP Head	4,89,170/-	9,800/-	350/-	One Month	C & D
16	Restoration of rain damage on Bhota Bijhari road via Ropari Km. 0/0 to 14/300 (Sh:- C/O R/wall at Rd. 12/780 to 12/805)	4,30,757/-	8,700/-	350/-	One Month	C & D
17	C/O L/R from Jajri Bazar to Khil Chang km. 0/0 to 1/0 (Sh:- C/O R/wall at Rd. 0/090 to 0/100, 0/105 to 0/116 & 0/150 to 0/167) Under OTMNP Head	4,99,010/-	10,000/-	350/-	One Month	C & D
18	C/O L/R from Suglani Balhi to Joreghat Shiv Mandir via Batlahu road Km. 0/0 to 0/900 G.P. Dhangota (Sh:- F.C. in km. 0/0 to 0/250 & P/L 900mm dia RCC hume pipe culvert at Rd. 0/200) Under OTMNP Head	4,97,217/-	10,000/-	350/-	One Month	C & D
19	Restoration of rain damage on L/r to H.B. Tillu Km. 0/0 to 0/900(Sh:- C/O R/wall at Rd. 0/050 to 0/064.80)	4,51,546/-	9,100/-	350/-	One Month	C & D
20	A/R & M/O HPPWD Rest House at Barsar (Sh:- C/O vetrified tiles & sanitary work etc.)	4,91,487/-	9,900/-	350/-	One Month	C & D
21	A/R & M/O Dhabrian to Dhangota via Kharal km. 0/0 to 5/0 (Sh:- P/L C.C. pavement at rd. 0/200 to 0/285)	4,82,779/-	9,700/-	350/-	One Month	C & D
22	Repair & Maintenance of Executive Engineer Residence at Barsar (Sh:- Painting, distempering & paneled glazed shutter etc.)	3,10,281/-	6,300/-	350/-	One Month	C & D
23	C/O L/R from Magnoti to H.B. Sohari & Pandhri km. 0/0 to 1/700(Sh:- C/O R/wall at Rd. 1/610 to 1/628& P/L C.C. pavement at Rd. 1/680 to 1/700) Under SCSP Head	3,88,204/-	7,800/-	350/-	One Month	C & D

Certified that the tenders for Job No. 1 to 23 are of urgent nature and in public interest.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
Barsar Division
HPPWD Barsar.

On behalf of Governor of Himachal Pradesh

DNIT

Job No- 1

Name of Work:- Restoration of rain damages on link road Harizan Basti Damyana KM 0/00 to 0/530
(SH:- C/O R/wall at Rd 0/260 to 0/270, V shape drain and U-Shape drain at various Rds)

Estimated Cost Rs:- 4,47,634.00

Earnest Money Rs:-9,000.00

Time Limit :- Two month

Sl.No	Description of Item	65.19	Cubic metre	Figure	words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.			465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	30352.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	52.90	Cubic metre	4257.40	Rupees Four Thousand Two Hundred Fifty Seven And Paise Forty Only	Per Cubic Metre	225216.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	28.20	Cubic metre	5688.50	Rupees Five Thousand Six Hundred Eighty Eight And Paise Fifty Only	Per Cubic Metre	160416.00
4	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	14.50	Cubic metre	1436.30	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	20826.00

3) Providing sweep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall , return wall , retaining and lucast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plate/ Linolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all lands and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	27.00	Numbers	400.90	Rupees Four Hundred And Paice Ninety Only	Each	10824.00
					Total:-	447634.00

Executive Engineer
Barsar Division
HPPWD Barsar

52

DNIT

Job No - 2

Name of work:- Restoration of rain damages on Mehre Jabble Kherian road Km 0/00 to 6/00

Estimated cost Rs:- 4,94,396.00

(SH:- C/O wire crate R/Wall at Rd 4/200 to 4/216)

Earnest money Rs:- 9,900 .00

Time Limit :- Two Month

Sr.No	Discription of item	Quantity	Rate inclusive all taxes i/c G S T		Unit	Amount
			Figures	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	24.40	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	11361.00
2	Providing and laying of boulder apron laid in wire creates with 4mm (four millimeter dia G.I wire conferring to I.S. 280 and IS-4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mash WOVEN diagonally) including 10 percent extra for laps and joints laid with stone boulder weighting not less then 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301. including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax , GST or other taxes imposed by the Government .	154.70	3122.40	Rupees Three Thousand One Hundred Twenty Two And Paise Forty Only	Per Cubic Metre	483035.00
					Total:-	494396.00

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Job No- 3

Name of Work:- C/O link road from Budia Da Paron to Harizan Basti Bihru (G.P Sakroh) KM 0/00 to 1/925

(SH:- P/L 900 mm dia RCC hume pipe culvert at RD 0/705 & 0/750)

Estimated Cost Rs:- 4,76,874.00

Earnest Money Rs:- 9,600.00

Time Limit :- Two month

(under SCSP Head)

Sr.No	Description of Item	Rate inclusive all taxes i/c G S T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	80.15	Cubic metre	465.60 Rupees Four Hundred Sixty Five And Paise Sixty Only	37318.00
2	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802,803,1202&1203 as per direction of Engineer-in- Charge including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	5.13	cubic metre	4757.45 Rupees Four Thousand Seven Hundred Fifty Seven And Paise Forty Five Only	24406.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	25.36	Cubic metre	5887.51 Rupees Five Thousand Eight Hundred Eighty Seven And Paise Fifty One Only	149307.00
4	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	32.43	Cubic metre	4233.30 Rupees Four Thousand Two Hundred Thirty Three And Paise Thirty Only	137286.00

5	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.1.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.20	Cubic metre	1436.30	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	8905.00
6	Providing and laying reinforced cement concrete pipe NP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.50	Running metre	4393.13	Rupees Four Thousand Three Hundred Ninety Three And Paise Thirteen Only	Per running metre	98845.00
7	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolux/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	26.00	Numbers	400.90	Rupees Four Hundred And Paise Ninety Only	Each	10423.00
8	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of the Engineer-in-Charge including entire carriage of material upto all leads and lifts and other incidental the rate includes octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	82.61	cubic metre	125.70	Rupees One Hundred Twenty Five And Paise Seventy Only	Per Cubic Metre	10384.00
						Total:-	476874.00

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Name of Work:- restoration of rain damages on Badaran Garhi via Galliyan Jole at Km 4/00 to 13/500
(SH:- P/I. cement concrete pavement at Rd 12/836 to 12/900)

Job No-
Estimated Cost Rs:- 4,93,896.00
Earnest Money Rs:-9900.00
Time Limit :- One month

Sr No	Description of Item	Cubic metre	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during devaltering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	38.40	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	17879.00
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401. for grading -I material including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	25.60	2062.10	Rupees Two Thousand Sixty Two And Paise Ten Only	per cubic metre	52790.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, devaltering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc open foundations complete as per drawing and technical specification clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	25.60	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	150072.00
4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum cam presibe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	38.40	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	273155.00
				Total:-		493896.00

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Name of Work:- Restoration of rain damages on Harizan Basti village Kalyana
(SH:- C/O R/wall at Rd 0/980 to 0/999 & V-Shape drain at Rd 0/900 to 1/050)


Job No-

Estimated Cost Rs:- 4,50,054.00
Earnest Money Rs:-9100.00

Time Limit :- One month

Sr.No	Description of Item	Rate inclusive all taxes i/e G.S.T	Unit	Amount
		Figure	words	
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	16096.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	4233.30	Rupees Four Thousand Two Hundred Thirty Three And Paise Thirty Only	334600.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	5771.00	Rupees Five Thousand Seven Hundred Seventy One Only	60596.00
4	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	1436.30	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	32748.00

providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall , return wall , retaining and breast wall with 10mm (one hundred ten millimetre) dia PVC pipe (D-plasty) Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structure with slope of 1(V):2(H) towards drawing face complete as per drawing and technical specification clause 614, 700, 704, 704.1 / as per direction of Engineer-in-Charge including entire carriage of material within all lands and lifts and other incidentals The rates are inclusive oetroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	15.00	Numbers	400.90	Rupees Four Hundred And Paise Ninety Only	Each	6014.00
				Total:-		450054.00


 Executive Engineer
 Barsar Division
 HPPWD Barsar

DNIT

Name of work:- Repair & Maintenance of G.S.S. School Giara Gran Distt. Hamirpur

(SII:- Distemper, Painting, tile etc.)

(Deposit work)

Job No:- 6

Estimated Cost Rs:-353119.00

Earnest Money Rs:-7100.00

Time Limit :- Two Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government	615.90	Square metre	120.80	Rupees One Hundred Twenty And Paise Eighty Only	Per square metre	74401.00
2	Painting wood work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point nine zero liter/ ten square metre) over an under coat of primer applied @ 0.75 ltr/ 10 sqm(zero point seven five liter/ ten square metre) of approved brand and manufacture including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	148.50	Square metre	110.50	Rupees One Hundred Ten And Paise Fifty Only	Per square metre	16409.00
3	Providing and laying vitrified floor tiles made of Kajaria/ Nitco first class quality 600x600mm (six hundred into six hundred millimetre) in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm(twenty millimetre) thick cement mortar 1:4 (one cement : four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm(three point three kilogram / square metre) upto all floors levels including grouting the joints with white cement and matching pigments etc., including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	180.12	Square metre	1456.30	Rupees One Thousand Four Hundred Fifty Six And Paise Thirty Only	Per square metre	262309.00
					Total:-		353119.00

Executive Engineer

Barsar Division

HPPWD Barsar

DNIT

Name of Work:- C/O Link road from Thappar to village Khansara Km 0/00 to 1/500
 (S/I:- Formation cutting in Km 0/735 to 0/750, C/O R/wall at Rd 0/060 to 0/072, P/L- 900mm dia RCC Hume Pipe culvert at Rd 0/840)
 (Under O/TMNP Head)

Job No- 7

Estimated Cost Rs:- 4,51,217.00

Earnest Money Rs:- 9100.00

Time Limit :- Three month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling wedging out of rock (where blasting in prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification clause 302, 1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and other necessary to complete the work by mechanical means and/ or labour if required. Any loss to the public/ private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	75.75	182.40 Rupees One Hundred Eighty Two And Paise Forty Only	Per Cubic Metre	13817.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	56.84	465.60 Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	26465.00
3	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	63.48	4257.40 Rupees Four Thousand Two Hundred Fifty Seven And Paise Forty Only	Per Cubic Metre	270260.00
4	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.04	1436.30 Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	20166.00

6	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall , return wall , retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-Plast)/ Finolux/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614. 709. 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	Numbers	400.90	Rupees Four Hundred And Paise Ninety Only	Each	6014.00
6	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802,803, 1202&1203 as per direction of Engineer-in- Charge including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	3.95	cubic metre	4897.10	Rupees Four Thousand Eight Hundred Ninety Seven And Paise Ten Only	Per Cubic Metre	19344.00
7	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	10.36	Cubic metre	5688.50	Rupees Five Thousand Six Hundred Eighty Eight And Paise Fifty Only	Per Cubic Metre	58933.00
8	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	0.96	Cubic metre	4257.40	Rupees Four Thousand Two Hundred Fifty Seven And Paise Forty Only	Per Cubic Metre	4087.00
9	Providing and Laying reinforced cement concrete pipe NP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government .	7.50	Running metre	4284.10	Rupees Four Thousand Two Hundred Eighty Four And Paise Ten Only	Per running metre	32131.00
						Total:-	451217.00

DNIT

Name of Work:- C/O link road from Gwaled Khad to Smella Check DPF Smella via Jatt Tajyar KM 0/00 to 1/10
(SH:- P/L 900 mm dia R/C hume pipe culvert at RD 0/378 i/c wing wall)
(under SCSP Head)

Job No- 8
Estimated Cost Rs:- 4,71,126.00
Earnest Money Rs:- 9,500.00
Time Limit :- Two month

Sr.No	Description of Item			Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	61.25	Cubic metre	464.92	Rupees Four Hundred Sixty Four And Paise Ninety Two Only	Per Cubic Metre	28476.00
2	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802.803, 1202&1203 as per direction of Engineer-in- Charge . including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	2.98	cubic metre	5157.40	Rupees Five Thousand One Hundred Fifty Seven And Paise Forty Only	Per Cubic Metre	15369.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	20.68	Cubic metre	5887.50	Rupees Five Thousand Eight Hundred Eighty Seven And Paise Fifty Only	Per Cubic Metre	121754.00
4	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802.803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	48.76	Cubic metre	4303.80	Rupees Four Thousand Three Hundred Three And Paise Eighty Only	Per Cubic Metre	209853.00

5	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	13.65	Cubic metre	1444.17	Rupees One Thousand Four Hundred Forty Four And Paise Seventeen Only	Per Cubic Metre	19713.00
6	Providing and laying reinforced concrete pipe NP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	15.00	Running metre	4302.75	Rupees Four Thousand Three Hundred Two And Paise Seventy Five Only	Per running metre	64541.00
7	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment, wing wall, return wall, rounding and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00	Numbers	400.45	Rupees Four Hundred And Paise Forty Five Only	Each	8009.00
8	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of the Engineer-in- Charge including entire carriage of material upto all leads and lifts and other incidental the rate includes octroi, royalty, malkana toll tax, GST or other taxes imposed by the Government.	28.50	cubic metre	119.68	Rupees One Hundred Nineteen And Paise Sixty Eight Only	Per Cubic Metre	3411.00
						Total:-	471126.00

Executive Engineer
Barsar Division
HPPWD, Barsar

50

DNIT

Name of Work:- C/O link road from college Rain shelter to Harizan Basti Palah ward No.5 (G.P Chakmoh)
(SH:-Balance work for the C/O 3.00 mtr span RCC Slab type culvert at Rd 0/425 (Under SCSP Head)

Job No- 9

Estimated Cost Rs:- 4,77,337.00

Earnest Money Rs:-9,600.00

Time Limit :- Two month

Sr.No	Description of Item	Rate inclusive all taxes i/e G.S.T		Unit	Amount
		Figure	words		
1	Providing and laying mechanically mixed and vibrated cement concrete nominal mix M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.09	Cubic metre	Per Cubic Metre	135155.00
	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete mix design M-25 (M-Twenty five) using minimum cement concrete of 0.400(zero point four zero zero) metric tonne per cubic metre crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete super structure complete upto all heights or depths including form work with M.S plate complete as per drawing and technical specifications clause 800, 1205.4 & 1205.5 including carriage of material within all loads and lifts and other incidentals. The rate are inclusive of octroi, royalty malkhana ,toll tax, GST or other taxes imposed by the Government	5.85	Cubic metre	Per Cubic Metre	42162.00
2	Supplying, fitting and placing HYSD bar made of Tata Tisco. Sali reinforcement in sub structure in all heights including cost of bending binding wire and cost for cutting straightening bending and placing in position of bars complete as per drawings and MORTH technical specification clause 1002,1010,1202 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax ,GST or other taxes imposed by the Government.	1.053	Tonne	Per tonne	102270.00
	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	32.00	Numbers	Each	12814.00
	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802.803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	42.00	Cubic metre	Per Cubic Metre	181584.00

Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	2.25	Cubic metre	1489.90	Rupees One Thousand Four Hundred Eighty Nine And Paise Ninety Only	Per Cubic Metre	3352.00
				Total		477337.00

Executive Engineer
Barsar Division
HPPWD Barsar

60

DNIT

Job No- 10

Name of Work:- C/O link road from Tanager to Bhadloo (Ghori) Km 0/00 to 1/00

Estimated Cost Rs:- 4,08,336.00

(SH:- Formation cutting in between Km 0/00 to 0/450 & P/L 900mm dia RCC Hume Pipe culvert at Rd 0/430)

Earnest Money Rs:- 8,200.00

(Under O'MNP I lead)

Time Limit :- Three month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	Words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling wedging out of rock where blasting is prohibited and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification clause 302, 1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and other necessary to complete the work by mechanical means and/or labour if required. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	548.10	cubic metre	182.40 Rupees One Hundred Eighty Two And Paise Forty Only	Per Cubic Metre 99973.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.25	Cubic metre	465.60 Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre 20603.00
3	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.08	cubic metre	4973.20 Rupees Four Thousand Nine Hundred Seventy Three And Paise Twenty Only	Per Cubic Metre 25264.00
4	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.06	Cubic metre	5771.00 Rupees Five Thousand Seven Hundred Seventy One Only	Per Cubic Metre 86911.00

7	Providing and laying PCC (Grade M-15 (M-Fifteen) cement concrete 1:2 1/2 :5 (one cement : Two and half Sand : five graded crushed stone aggregate :thum) (Twenty millimeter) nominal size for plain/reinforced cement concrete in substructure as per drawing and technical specification clause 802.804,805,806,807,1202 & 1204 including entire carriage of material to all leads and lifts. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes	23.04	Cubic metre	5754.50	Rupees Five Thousand Seven Hundred Fifty Four And Paise Fifty Only	Per Cubic Metre	132584.00
8	Providing and laying reinforced cement concrete pipe NIP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government .	7.50	Running metre	4289.30	Rupees Four Thousand Two Hundred Eighty Nine And Paise Thirty Only	Per running metre	32170.00
9	Providing and laying flooring laid over cement concrete bedding complete as per drawings and MORTH technical specification clause 1303 and as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, malkana ,toll tax, GST, or other taxes imposed by the Government .	0.49	Cubic metre	5287.70	Rupees Five Thousand Two Hundred Eighty Seven And Paise Seventy Only	Per cubic metre	2591.00
8	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	1.55	Cubic metre	1436.30	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	2226.00
9	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	Numbers	400.90	Rupees Four Hundred And Paise Ninety Only	Each	6014.00
						Total:-	408336.00

Executive Engineer
Barsar Division
HPPWD Barsar

21

DNIT

Job No- 11

Name of Work:- C/O link road to to village Tiyalu (Loharda) Km 0/00 to 1/200

Estimated Cost Rs:- 4,54,097.00

(SH:- C/O Edge Wall at Rd 0/410 to 0/446, 0/520 to 0/555)

Earnest Money Rs:- 9100.00

(Under OTMNP Head)

Time Limit :- One month

Sr.No	Description of Item	Quantity	Rate inclusive all taxes i/c G S T	Unit	Amount
			Figure	words	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	74.55	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	34710.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	79.88	4233.30	Rupees Four Thousand Two Hundred Thirty Three And Paise Thirty Only	338156.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	42.60	1436.30	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	61186.00
4	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plasty) Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50.00	400.90	Rupees Four Hundred And Paise Ninety Only	20045.00
				Total:-	454097.00

Executive Engineer
Barsar Division
HPPWD Barsar

Name of Work:- Restoration of rain damages on Bani Matkar road Km 0/00 to 6/715
(SIT:- C/O B/wall at Rd 3/750 to 3/775)

DNIT

Job No- 12
Estimated Cost Rs:- 2,69,102.00
Earnest Money Rs:- 5,400.00
Time Limit :- one month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	20.25	Cubic metre	465.60 Rupees Four Hundred Sixty Five And Paise Sixty Only	9428.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	59.00	Cubic metre	4333.30 Rupees Four Thousand Three Hundred Thirty Three And Paise Thirty Only	255665.00
3	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.00	Numbers	400.90 Rupees Four Hundred And Paise Ninety Only	4009.00
				Total:-	269102.00

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Name of Work:- Restoration of rain damages on Harsour Gurli road Km 0/00 to 8/00
(SH:- C/O R/wall at Rd 5/030 to 5/042)

Job No- 13

Estimated Cost Rs:- 2,29,234.00

Earnest Money Rs:-4,600.00

Time Limit :- one month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	15.75	Cubic metre	Rupees Four Hundred Sixty Five Cubic Metre And Paise Sixty Only	7333.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	47.30	Cubic metre	Rupees Four Thousand Three Hundred Thirty Three And Paise Thirty Only	204965.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	9.00	Cubic metre	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	12927.00
4	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.00	Numbers	Rupees Four Hundred And Paise Ninety Only	4009.00
				Total:-	229234.00

Executive Engineer
Barsar Division
HPPWD Barsar

69

DN/11

Name of Work:- VKV/2022/337 C/O link road from Pattian Mahila Mandal to village Tathliyan (Maslana Khurd) (G.P. Ihanjiani)
(SH):- P/L 600 mm Dia RCC Hume pipe culvert at RD 0/600 (Deposit Works)

Job No- 14

Estimated Cost Rs:- 1,39,768.00

Earnest Money Rs:- 2,800.00

Time Limit :- ~~Five~~ ^{Three} month

Sr No	Description of Item		Figure	words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	42.11	465.60	Rupees Four Hundred Sixty Five Cubic And Paise Sixty Metre Only	Per Cubic Metre	19606.00
2	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802.803,1202&1203 as per direction of Engineer-in- Charge . including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	4.02	4973.20	Rupees Four Thousand Nine Hundred Seventy Three And Paise Twenty Only	Per Cubic Metre	19992.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	12.21	5771.00	Rupees Five Thousand Seven Hundred Seventy One Only	Per Cubic Metre	70464.00
4	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	4.80	1436.30	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	6894.00
5	Providing and Laying reinforced cement concrete pipe NP ² 600mm(Six hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection works back filling concrete and masonry works in head walls and parapets Clause 1108, including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	7.50 running metre	2720.90	Rupees Two Thousand Seven Hundred Twenty And Paise Ninety Only	Per running Metre	20407.00

6	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall , return wall , retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plasty/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all loads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	6.00	Numbers	400.90	Rupees Four Hundred And Paise Ninety Only	Each	2405.00
							Total:-
							139768.00

Executive Engineer
Barsar Division
HPPWD Barsar

Job No- 15
Estimated Cost Rs:- 4,89,170.00
Earnest Money Rs:-9,800.00
Time Limit :- one month

Name of Work:- C/O link road Kohdra to Badloi via Pattian Km 0/00 to 1/800
(Sft:- C/O U-Shape drain at Rd 0/420 to 0/510 with edge wall)
(under SCSP Head)

Sr.No	Description of Item	Rate inclusive all taxes % G.S.T	Unit		Amount
			Figure	words	
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	87.55	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	40763.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	77.70	5771.00	Rupees Five Thousand Seven Hundred Seventy One Only	448407.00
				Total:-	489170.00

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Name of Work:- Restoration of Bhota Bijhari road via Ropri Km 0/00 to 14/300

(SH:- C/O R/wall at Rd 12/780 to 12/805)

Job No- 16

Estimated Cost Rs:- 4,30,757.00

Earnest Money Rs:-8700.00

Time Limit :- one month

Sr No	Description of Item	Rate inclusive all taxes i/c G S T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	29.25	Cubic metre	465.50 Rupees Four Hundred Sixty Five And Paise Fifty Only	13616.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	87.75	Cubic metre	4333.30 Rupees Four Thousand Three Hundred Thirty Three And Paise Thirty Only	380247.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	21.50	Cubic metre	1436.30 Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	30880.00
4	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	Numbers	400.90 Rupees Four Hundred And Paise Ninety Only	6014.00
				Total:-	430757.00

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Name of Work:- C/O link road from Jajri Bazar to Khil Chang Km 0/00 to 1/00
(SH:- C/O R/wall at Rd 0/090 to 0/100, 0/105 to 0/116 & 0/150 to 0/167)
(Under OTMNP Ilead)

Job No- 17

Estimated Cost Rs:- 4,99,010.00

Earnest Money Rs:- 10000.00

Time Limit :- Three month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words			
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	46.27	Cubic metre	465.60 Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	21543.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802.803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	97.83	Cubic metre	4333.30 Rupees Four Thousand Three Hundred Thirty Three And Paise Thirty Only	Per Cubic Metre	423927.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	23.14	Cubic metre	1436.30 Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	33236.00
4	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	48.00	Numbers	400.90 Rupees Four Hundred And Paise Ninety Only	Each	19243.00

5	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of the Engineer-in- Charge including entire carriage of material upto all lands and lifts and other incidental the rate includes octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	8.44	cubic metre	125.70	Rupees One Hundred Twenty Five And Paise Seventy Only	Per Cubic Metre	1061.00
						Total:-	499010.00

Executive Engineer
Barsar Division
HPPWD Barsar

68

DNIT

Job No- 18

Name of Work:- C/O link road from Suglani Balhi to Joreghat (Shiv Mandir) via Batlahu (G.P Dhangota) Km 0/00 to 0/900

Estimated Cost Rs:- 4,97,217.00

(SH:- Formation cutting in Km 0/00 to 0/250 & P/L 900mm dia RCC Hume Pipe culvert at Rd 0/200)

Earnest Money Rs:- 10,000.00

(Under OTMNP Head)

Time Limit :- Three month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Unit	Amount
		Figure	words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling wedging out of rock (where blasting in prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification clause 302, 1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation for filling in road works, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and other necessary to complete the work by mechanical means and/or labour if required. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1020.00	cubic metre	186048.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.25	Cubic metre	20603.00
3	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.08	cubic metre	25264.00
4	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.06	Cubic metre	86911.00

5	Providing and laying 14(C Grade M-15 (M-Fifteen) cement concrete 1:2 1/2 :5 (one cement : Two and half Sand : five graded crushed stone aggregate 20mm (Twenty millimeter) nominal size for plain/reinforced cement concrete in substructure as per drawings and technical specification clause 802.804,805,806,807,1202 & 1204 including entire carriage of material in all leads and lifts. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.04	Cubic metre	5754.30	Rupees Five Thousand Seven Hundred Fifty Four And Paise Fifty Only	Per Cubic Metre	132584.00
6	Providing and laying reinforced cement concrete pipe NP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.50	Running metre	4289.30	Rupees Four Thousand Two Hundred Eighty Nine And Paise Thirty Only	Per running metre	32170.00
7	Providing and laying flooring laid over cement concrete bedding completed in rubble stone laid in cement mortar 1:3(one cement : three sand) as per drawing and technical specification clauses 1303 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	0.49	Cubic metre	5287.70	Rupees Five Thousand Two Hundred Eighty Seven And Paise Seventy Only	Per cubic metre	2591.00
8	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.55	Cubic metre	1436.30	Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	2226.00
9	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.00	Numbers	400.90	Rupees Four Hundred And Paise Ninety Only	Each	8820.00
						Total:-	497217.00

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Name of Work:- Restoration of rain damages on link road to Ilarizan Basti Tilla Km 0/00 to 0/900
(Sl:- C/O R/wall at Rd 0/050 to 0/064.80)

Job No- 19

Estimated Cost Rs:- 4,51,546.00

Earnest Money Rs:-9,100.00

Time Limit :- one month

Sr No	Description of Item		Rate inclusive all taxes i/c G.S.T	Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21.03	Cubic metre	Per Rupees Four Hundred Sixty Five And Paise Sixty Only	9792.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802.803, 1202 and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	97.19	Cubic metre	Per Rupees Four Thousand Two Hundred Thirty Three And Paise Thirty Only	411434.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.76	Cubic metre	Per Rupees One Thousand Four Hundred Thirty Six And Paise Thirty Only	25509.00
4	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast) / Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.00	Numbers	Each Rupees Four Hundred And Paise Ninety Only	4811.00
				Total:-	451546.00

Executive Engineer
Barsar Division
HPPWD Barsar

70

DNIT

Name of Work:- A/R & M/O HPPWD Rest House at Barsar
(SH:- C/O Vettrified Tiles, Sanitary works etc.)

Job No- 20
Estimated Cost Rs:- 491487.00
Earnest Money Rs:- 9900.00
Time Limit :- One month

Sl No	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	Words		
1	Constructing brick masonry manhole in cement mortar 1:4 (one cement : four coarse sand) with R.C.C. top slab with 1:1.5:3 mix (one cement : One & Half coarse sand (zone- III) : 3 graded stone aggregate 20 mm (twenty millimetre) nominal size), foundation concrete 1:4:8 mix (one cement : four coarse sand (zone- III) : Eight graded stone aggregate 40 mm (forty millimetre) nominal size), inside plastering 12 mm (twelve millimetre) thick with cement mortar 1:3 (one cement : three coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (one cement : Two coarse sand : four graded stone aggregate 20 mm (twenty millimetre) nominal size) finished with a floating coat of neat cement complete as per standard design. Inside size 90x80 cm (ninety into eighty centimetre) and 45cm (forty five centimetre) deep including C.I. cover with frame (light duty) 455x610 mm (four hundred fifty five into six hundred ten millimetre) internal diameter, total weight of cover and frame to be not less than 38kg (thirty eight kilogramme) (weight of cover 23 kg (twenty three kilogramme) and weight of frame 15 kg) (fifteen kilogramme); With common burnt clay F.P.S. (nonmodular) bricks of class designation 7.5 including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	19.00	Numbers	Rupees Nine Thousand Six Hundred Seventy And Paise Seventy Only	Each	183,743.00
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in Cement mortar 1:6 (one cement : six coarse sand) in super structure above plinth level up to all floors level including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	0.80	cubic metre	Rupees Eight Thousand Three Hundred Twenty One And Paise Ninety Only	Per cubic metre	6,658.00
3	Providing and laying vitrified floor tiles made of Kajaria/ Nitco first class quality 600x600mm (six hundred into six hundred millimetre) in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetre) thick cement mortar 1:4 (one cement : four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram / square metre) including grouting the joints with white cement and matching pigments etc., including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	33.50	Square metre	Rupees One Thousand Four Hundred Seventy Five And Paise Thirty Only	Per square metre	49423.00
4	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works including applying priming coat of approved steel primer mild steel tube. including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	200.00	kilogramme	Rupees One Hundred Thirty Eight And Paise Thirty Only	per kilogramme	27660.00
5	Providing and fixing 150mm (one hundred fifty millimetre) nominal size high pressure made of Paryware, Hindware, Cera/finolex of following dia PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	150.00	running metre	Rupees Eight Hundred Seventy Six And Paise Seventy Only	per running metre	131505.00

6	Providing and fixing 110mm (one hundred ten millimetre) nominal size high pressure made of Paryware , Hindware , Cera/finolex of following dia PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	72.00	running metre	516.80	Rupees Five Hundred Sixteen And Paise Eighty Only	per running metre	37210.00
7	Providing and fixing 75 mm (seventy five millimetre) Nominal size high pressure made of Paryware , Hindware , Cera/finolex of following dia PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts;and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	12.00	running metre	388.80	Rupees Three Hundred Eighty Eight And Paise Eighty Only	per running metre	4666.00
8	Providing and fixing 50mm (fifty millimetre) nominal size high pressure made of Paryware , Hindware , Cera/finolex of following dia PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	6.00	running metre	315.10	Rupees Three Hundred Fifteen And Paise Ten Only	per running metre	1891.00
9	Providing and fixing 150mm (one hundred fifty millimetre) nominal size PVC door bend with oval access door, insertion rubber washer 3mm (three millimetre) thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	6.00	numbers	982.70	Rupees Nine Hundred Eighty Two And Paise Seventy Only	each.	5896.00
10	Providing and fixing 110mm (one hundred ten millimetre) nominal size PVC door bend with oval access door, insertion rubber washer 3mm (three millimetre) thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	4.00	numbers	297.40	Rupees Two Hundred Ninety Seven And Paise Forty Only	each.	1190.00
11	Providing and fixing 75mm (seventy five millimetre) nominal size PVC door bend with oval access door, insertion rubber washer 3mm (three millimetre) thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	4.00	numbers	283.70	Rupees Two Hundred Eighty Three And Paise Seventy Only	each.	1135.00
12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc 25 mm dia nominal bore including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	24.00	running metre	430.20	Rupees Four Hundred Thirty And Paise Twenty Only	per running metre	10325.00
13	Providing and fixing 600x450 mm (six hundred into four hundred millimetre) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	4.00	numbers	1041.40	Rupees One Thousand Forty One And Paise Forty Only	each.	4166.00
14	Providing and fixing white solid plastic seat with lid for pedestal type W.C. pan complete including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	2.00	numbers	590.80	Rupees Five Hundred Ninety And Paise Eighty Only	each.	1182.00

18	Providing and fixing 15 mm (fifteen millimetre) nominal bore brass bib cock of approved quality including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	6.00	numbers	313.00	Rupees Three Hundred Thirteen Only	each.	1878.00
19	Providing and fixing 20 mm (twenty millimetre) nominal bore wheel of approved quality (screwed end) 20 mm (twenty millimetre) nominal bore including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	4.00	numbers	476.20	Rupees Four Hundred Seventy Six And Paise Twenty Only	each.	1905.00
20	Providing and fixing 15mm (fifteen millimetre) nominal bore uplasticed PVC connection pipe with brass unions (about thirty centimetre) length Finolex / Hindware/ Cera/ Jaguar make complete. including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	6.00	numbers	75.40	Rupees Seventy Five And Paise Forty Only	each.	452.00
21	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 catalogue No Jaguar Fusion- 29053 etc. 15mm (fifteen millimetre) nominal bore including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	4.00	numbers	550.40	Rupees Five Hundred Fifty And Paise Forty Only	each.	2202.00
22	Providing and fixing floor mounted white vitreous china single piece, double traps syphonic water closet of approved brand/ make Jagvar Hindware/ Cera shape size and pattern including integrated white vitreous china cistern of capacity 10liter (ten liter) with dual flushing system including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc. including making connection with the existing P or S trap. including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	1.00	numbers	18400.40	Rupees Eighteen Thousand Four Hundred And Paise Forty Only	each.	18400.00
Total:-							491487.00

11.11.2019

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT
Name of Work:- A/R & M/O Dandwin to Dhangota via Kharal KM 0/00 to 5/00
(Sl:- P/L cement concrete pavement at Rd 0/200 to 0/285)

Job No- 21
Estimated Cost Rs:- 4,82,479.00
Earnest Money Rs:-9,700.00
Time Limit :- one month

Sr.No	Description of Item	68.00	Cubic metre	Figure	words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	68.00	Cubic metre	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	31661.00
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401, for grading - I material including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34.00	Cubic metre	2062.10	Rupees Two Thousand Sixty Two And Paise Ten Only	per cubic metre	70111.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34.00	Cubic metre	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	199315.00
4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete mix design M-25 (M-Twenty five) RCC Grade using minimum cement concrete of 0.400(zero point four zero zero) metric tonne per cubic metre crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete super structure complete upto all heights or depths including form work with M.S plate complete as per drawing and technical specifications clause 800, 1205.4 & 1205.5 including carriage of material within all leads and lifts and other incidentals. The rate are inclusive of octroi, royalty malkhana ,toll tax, GST or other taxes imposed by the Government.	25.50	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	181392.00
						Total:-	482479.00

DNIT approved by Mr. V. S. ...

Executive Engineer
Barsar Division
HPPWD Bargarh

DNIT

Name of Work:- Repair & Maintenance of Executive Engineer Residence at Barsar
(SH:- Painting , Distempering & Panelled Glazed shutters etc.)

Job No- 22

Estimated Cost Rs:-310281.00

Earnest Money Rs:-6300.00

Time Limit :- 02 month

Sr. No.	Description of item	Quantity		Rate inclusive all taxes /c G.S.T		Unit	Amount
				Figure	words		
1	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/ 10 sqm over an under coat of primer applied @ 0.80 lit/ 10 sqm of approved brand and manufacture including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government.	100.42	Square metre	104.90	Rupees One Hundred Four And Paise Ninety Only	Per square metre	10,534.00
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government.	328.80	Square metre	143.65	Rupees One Hundred Forty Three And Paise Sixty Five Only	Per square metre	47,232.00
3	Finishing walls with 100% (hundred percent) Premium acrylic emulsion paint having VOC less than 50 gm/litre(fifty gram/ liter) and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives . New work (Two or more coats applied @ 1.43 litre/ 10 sqm.(one point four three liter/ ten square metre) Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm(zero point nine zero liter/ ten square metre) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government.	688.64	Square metre	124.60	Rupees One Hundred Twenty Four And Paise Sixty Only	Per square metre	85,805.00
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government.	688.64	Square metre	119.55	Rupees One Hundred Nineteen And Paise Fifty Five Only	Per square metre	82,327.00

5	Providing and fixing 19mm (Nineteen millimeter) thick HDHMR water proof anti termite resistant board confirming box including shelves and shutters, the back side of cup board / cabinet of 8mm (eight millimetre) thick ply and cut portions of shelves shall be finished with 6mm(six millimetre) hard board edging. The shutters from all the sides shall be finished with 12mm(twelve millimetre) thick hard wood edging . The shutters from out side shall be finished with 4mm (four millimetre) thick veneer ply of approved shade to match with paneling including stainless steel piano hinges and magnetic catcher with all accessories as per direction of Engineer-in- Charge. including entire carriage of materials in all leads and lifts .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	8.25	square metre	3542.75	Rupees Three Thousand Five Hundred Forty Two And Paise Seventy Five Only	per square metre	29228.00
6	French spirit polishing two or more coats on new works including a coat of wood filler including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	57.60	Square metre	264.00	Rupees Two Hundred Sixty Four Only	Per square metre	15,206.00
7	Painting (two or more coats) 100 mm (one hundred millimetre) diameter pipes on rain water, soil waste and vent pipes and fittings with black anticorrosive bitumastic paint of approved brand and manufacture, over and including a priming of ready mixed zinc chromate yellow primer on new work including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	1.80	Square metre	45.00	Rupees Forty Five Only	Per square metre	81.00
8	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	6.00	Numbers	62.80	Rupees Sixty Two And Paise Eighty Only	Each	377.00
9	Providing and fixing 18 mm (eighteen millimetre) thick, 150 mm(one hundred fifty millimetre) wide pelmet of flat pressed 3(three) layer or graded wood particle board medium density grade I, IS : 3087 marked, including top cover of 6 mm (six millimetre) commercial ply wood conforming to IS: 303 BWR grade, nickel plated M.S. pipe 20 mm (twenty millimetre dia (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm(twenty five into three millimetre) M.S. flat 10 cm(ten centimetre) long fixed to pelmet with hollock wood cleats of size 100 mm x 40 mm x 40 mm(one hundred millimetre into forty millimetre into forty millimetre) on both inner side of pelmet and rawl plugs 75 mm (seventy five millimetre) long etc. all complete.including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	12.00	Running metre	462.05	Rupees Four Hundred Sixty Two And Paise Five Only	Per running metre	5545.00

10	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). panelling for panelled or panelled glazed shutters 25mm to 40mm (twenty five millimeter to forty millimetre) thick Second class Teak wood, including entire carriage of material to all loads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	9.00	Square metre	2704.00	Rupees Two Thousand Seven Hundred Four Only	Per square metre	24336.00
11	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). panelling for panelled or panelled glazed shutters 25mm to 40mm (twenty five millimeter to forty millimetre) thick Particle Board 12 mm (twelve millimetre) thick including entire carriage of material in all loads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	9.00	Square metre	1067.75	Rupees One Thousand Sixty Seven And Paise Seventy Five Only	Per square metre	9610.00
Total:-							310281.00

DRIFT, approved - Rs 3,10,281/- (and)

Executive Engineer
Barsar Division
HPPWD Barsar

DNIT

Job No- 23

Name of Work:- C/O link road from village Mangnoli to Harizan Basti Sohari & Pandiri Km 0/00 to 1/700

Estimated Cost Rs:- 4,10,022.00

(S/L:- C/O R/wall at Rd 1/610 to 1/628 & P/L cement concrete pavement in between Km 0/00 to 0/750)

Earnest Money Rs:- 8,200.00

(Under SCSP Head)

Time Limit :- one month

Sr.No	Description of Item	Quantity	Figure	Words	Rate inclusive all taxes i/c G.S.T	
					Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	21.06	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	9806.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	63.18	4244.40	Rupees Four Thousand Two Hundred Forty Four And Paise Forty Only	Per Cubic Metre	268161.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	15.48	1409.40	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	21818.00
4	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	16.00	402.00	Rupees Four Hundred Two Only	Each	6432.00

5.	Providing, and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-Ten) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specifications clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.00	Cubic metre	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	46898.00
6.	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.00	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	56907.00
						Total:-	410022.00

Executive Engineer
Barsar Division
HPPWD Barsar