



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 31/07/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 28/07/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Construction of link road Manjher to village Panga Km. 0/0 to 2/0 (SH:- Construction of 900mm dia hume pipe culverts at RD 1/090 with wing walls)	Rs. 1,88,094/-	Rs. 3,800/-	Rs. 350/-	Three Month
2	A/R & M/O Sh. Naina Devi Ji H.P.P.W.D. Rest House (SH:- Supply of Housekeeping material).	Rs. 1,36,938/-	Rs. 2,800/-	Rs. 350/-	Three Month
3	Repair of Rain damages from SNB road to link road village Khal Tibba Km. 0/0 to 7/0 (SH:- Providing and laying Kharanja stone soling at various RDS) DC Deposit	Rs. 1,05,866/-	Rs. 2,200/-	Rs. 350/-	Three Month
4	Construction of link road Manjher to village Panga Km. 0/0 to 2/0 (SH:- Construction of 900mm dia hume pipe culverts at RD 1/520 with wing walls)	Rs. 1,92,225/-	Rs. 3,900/-	Rs. 350/-	Three Month
5	Construction of 40.00 meter span bridge over Dehni Khad on link road from Punjab Boundary Dehni Nange Thakur and Barota Dawala at RD 2/015 (SH:- Preparation of Detailed Project report Construction of 25.00 meter span Bridge)	Rs. 1,75,000/-	Rs. 3,500/-	Rs. 350/-	Three Month
6	Construction of link road from Sh. Naina Devi Ji Bhakra road to village Khal Tiba in Km. 0/0 to 7/0 under Nabard) (SH:- Preparation of detailed Project report & CBR test)	Rs. 2,94,000/-	Rs. 5,900/-	Rs. 350/-	Two Month
7	Construction of link road Laraghat to Ghamrada Km. 0/0 to 4/690 (SH:- C/o B/wall at RD 2/790 to 2/800).	Rs. 1,16,037/-	Rs. 2,400/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 22-7-2023

No.PW/NBT/CB/Tender-State/EA-1/2023-3966-71

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.1,88,094/-Only.			
				Earnest Money :- Rs.3,800/-			
				Time:- Three Months.			
NAME OF WORK:- Construction of link road Manjher to Village Panga km 0/00 to 2/00 (SH:- Construction of 900 mm dia Hume pipe culverts at RD 1/090 with wing wall)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.65	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.75	Cubic metre			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.74	Cubic Metre			Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.57	Cubic metre.			Per Cubic Metre	

	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running Meter		Per Running Meterr	
6	Providing & Laying Cement concrete flooring 1:2:4 (one cement :Two coarse sand :Four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm (Forty millimeter) thick with 20 mm (Twenty millimeter) nominal size stone aggregate including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.26	Square Meter		Per Square Meter	
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.00	Cubic metre.		Per Cubic Metre	
8	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Nos.		Each	
	Total:-					

Executive Engineer,
Bilaspur Division No. 2,
P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.1,36,938/-Only.						
Earnest Money :- Rs.2,800/-						
Time:- Three Months.						
NAME OF WORK:- A/R & M/O Sh. Naina Devi Ji HP.PWD Rest House (SH:- Supply of House keeping Material)						
Description of items.						
Sr No.	Quantity	Rates in		Unit	Amount	
		Figure.	Words.			
1	3	4	5	6	7	
1	12.00 Nos			Each		
2	12.00 Nos			Each		
3	20.00 Nos			Each		
4	18.00 Nos			Each		
5	36.00 Nos			Each		
6	18.000 Nos			Each		
7	18.000 Nos			Each		

2

1 Supplying of wholly quilted material single size 90"x60" inch (Ninety into Sixty inch) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.

2 Supplying of Blanket 6301- including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

3 Supplying of Quilt cover single including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.

4 Supplying of Double Bed sheet cover including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.

5 Supplying of pillow cover including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.


6 Supplying of Bath towel including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.

7 Supplying of Hand towel including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Supplying of Double bed cover including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10,000	Nos			Each	
Total:-						

Executive Engineer
Bilaspur Division
HP PWD., Bilaspur

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.1,05,866/- Only.						
Earnest Money :- Rs.2,200/- Only						
Time:- Three Months.						
NAME OF WORK:- Repair of Rain Damages from SNB road to link road village Khal Tibba km 0/00 to 7/00 (SH:- Providing & Laying Kharanja Stone soling at Various RDs) (D.C Deposit)						
Sr No.	Description of items.	Quantity		Rates in		Unit
				Figure.	Words.	
1	2	3	4	5	6	7
1	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc.complete as per HP.PWD specification. 100 mm (One Hundred millimeter)spread thickness (finished work including materials and labour) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other consruction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	72.86	Cubic metres			Per Cubic metre
Total						


 Executive Engineer
 Bilaspur Division No. II
 H.P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.1,92,225/-Only.		
							Earnest Money :- Rs.3,900/-		
							Time:- Three Months.		
NAME OF WORK:- Construction of link road Manjher to Village Panga km 0/00 to 2/00 (SH:- Construction of 900 mm dia Hume pipe culverts at RD 1/520 with wing wall)									
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
1	2	3	4	5	6	7			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.19	cubic metre		Per cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.75	Cubic metre		Per Cubic metre				
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.79	Cubic Metre		Per Cubic Metre				
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.18	Cubic metre.		Per Cubic Metre				
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement :Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running Meter		Per Running Meterr				

	2.26	Square Meter			Per Square Meter
Providing & Laying Cement concrete flooring 1:2:4 (one cement :Two coarse sand :Four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm (Forty millimeter) thick with 20 mm (Twenty millimeter) nominal size stone aggregate including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
7	11.50	Cubic metre.			Per Cubic Metre
Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
8	8.00	Nos.			Each
Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
Total:-					

Executive Engineer,
Bilaspur Division No. 2,
B.P.W.D., Bilaspur (H.P.).

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.1,75,000/-Only.						
Earnest Money :- Rs. 3,500/- only						
Time:- Two Months.						
NAME OF WORK:- Construction of 40.00 metre span bridge over Dehni khad on link road from Punjab Boundary to village Dehni Nange Thakur and Barota Dawala at RD 2/015 (SH:- Preparation of Detailed Project Report Construction of 25.00 mtr span Bridge)						
Sr No.	Description of items.	Quantity		Rates in		Unit
				Figure.	Words.	
1		3		4	5	6
1	Preparation of Detailed Project Report of Bridge 25.00 mtr span Bridge on subject cited road on the basis of approved General arrangement Drawing & Super Structure Drawings including submission of Hard copy & after getting approval from the competent authority the same may be fairout and supplied in six sets duly printed A-4 size with relevant drawing on A-3 size paper alongwith the soft copy of DPR & Drawings.	1,000	No			Each
Total:-						7

Conditions:- 1. 75 % payment will released after approval of Manuscript DPR from the competent authority.

2. The balance payment will be released after submission of fair DPR in required set alongwith soft copy.

Executive Engineer
Bilaspur Division No. 11
HP PWD., Bilaspur

SCHEDULE OF QUANTITY.									
NAME OF WORK:- Constrution of link road from S.N.B. road to village Khal Tibba in Km 0/0 to 7/00 under Nabard (SH:-Preparation of Detailed Project Report & CBR test)									
Sr No.									
Description of items.									
2									
1	1	Preparation of detailed proeject report for road after conducting Topographical survey plan and mark provisions on the survey plan which include the following provision as given below: (a) Topographical survey by digital total station with two second accuracy ,showing all features on survey plan like trees,culverts,bridges,electric poles,telephone poles,hand pimps ,schools, Habitant villages etc. (b) Draw cross sections at 15m (fifteen metre) intervals,L-Section and calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable. (c) Preparation of survey plan showing all provision on the topographical survey plan and preparation of Detailed project report as per MORD guidelines. Submission of draft copy & after getting approval from the competent authority the same may be fair out and be supplied in six sets duly printed A-4 size, relevant drawing on A-3 size alongwith soft copy of DPR & Drawings in CD Format will also be submitted.	3	4	Figure.	Words.	Unit	Amount	
			7.000	Km	5	6	Per Kilometre	8	
2		Conducting CBR value and pavement Design of Crust as per IRC:37-2018.	21.000	No			Each		
Total:-									

Conditions:- 1. 75 % payment will released after approval of Manuscript DPR from the competent authority.

2. The balance payment will be released after submission of fair DPR in required set alongwith soft copy.

Executive Engineer
Bilaspur Division No II
HP PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.1,16,037/-Only.	
							Earnest Money :- Rs.2,400/-	
							Time:- Three Months.	
NAME OF WORK:- Construction of link road Laraghat to Ghamrada km 0/00 to 4/690 (SH:- C/O B/wall at RD 2/790 to 2/800)								
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount	
				Figure.	Words.			
1	2	3	4	5	6	7		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.80	cubic metre			Per cubic metre		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.50	Cubic metre			Per Cubic metre		
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.			Each		
Total:-								

Executive Engineer
Bilaspur Division No. II
HP PWD., Bilaspur