



E-Mail id – ee-bil2-hp@nic.in  
Phone No. 01978-222551

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**“NOTICE INVITING TENDERS”**

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 22/07/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 21/07/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain damages on Ghyal Dabar road Km. 0/0 to 11/0 (SH:- C/o R/wall at RD 0/685 to 0/691)	Rs. 4,4,7605/-	Rs. 9,000/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on Ghyal Dabar road Km. 0/0 to 11/0 (SH:- C/o R/wall at RD 0/691 to 0/695)	Rs. 2,98,403/-	Rs. 6,000/-	Rs. 350/-	Three Month
3	Balcony work of Additional Accommodation to HPPWD Rest House at Namhol (SH:- Providing and laying C.C. and 60mm thick cobble stone flooring in courtyard)	Rs. 4,22,000/-	Rs. 8,500/-	Rs. 350/-	Three Month

**Certified that tender of above works are being called of emergent nature in exigency of Public interest.**

**Terms and Conditions:-**

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2023- 3663-70

**Copy forwarded to the following for information and necessary action to:-**

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

*[Signature]*  
Executive Engineer,  
Bilaspur Divn.No.II,  
HP.PWD., Bilaspur.  
Dated: 15/7/23

*[Signature]*  
Executive Engineer,  
Bilaspur Divn.No.II,  
HP.PWD., Bilaspur.

**Estimated cost:- Rs.4,47,605/-Only.**

#### SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.

**Earnest Money :-** Rs.9,000/-

Time:- Three Months.

001685 to 01691

**NAME OF WORK:-** Restoration of Rain Damages on Ghyl Dabbar road  
**Description of items.**

2

SCHEUDLE OF QUANTITY.		Estimated cost:- Rs.2,98,403/-Only.	
NAME OF WORK:- Restoration of Rain Damages on Ghyl Dabbar road km 0/00 to 11/00 (SH:- C/O R/wall at RD 0/691 to 0/695)		Earnest Money :- Rs.6,000/-	
Sr No.		Description of items.	
Sr No.		Quantity	Rates in Unit Amount
		Figure. 3	Figure. 4
		Words. cubic metre	Words. cubic metre
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.00	Per cubic metre
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	59.76	Per Cubic metre
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.40	Per Cubic metre.
4	Providing weepholes in brick masonry/stone masonry/plain Reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre ) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Each
Total:-			

Executive Engineer,  
Bhaisapur Division No. 2,  
M.P. PWD., Bhaispur (M.P.)  


SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,22,000/- Only.	
		Earnest Money :- Rs.8,500/- Only	
NAME OF WORK:- Balance work of Additional Accommodation to HP.PWD Rest House at Namhol (SH:- Providing and Laying C.C and 60 mm Thick cobble stone flooring in courtyard)		Time:- Three Months.	
Sr No.	Description of items.	Quantity	Rates in Unit Amount
		Quantity	Rates in Unit Amount
1	2	3	4
Figure.	Words.	Figure.	Words.
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etc in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	53.50	Cubic Metre Per Cubic Metre
2	Stone solling properly hand packed filling interstices with kharanja Stone and consolidating with power road road to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.72	Cubic metres Per Cubic metre
3	Providing and laying mechanically mixed and vibrated concrete, for plain / reinforced concrete in open foundations for all type of structure complete of plain cement concrete (Nominal mixed 1:4:8)(One Cement four sand eight graded crushed stone aggregate)40mm(Forty millimetre size)nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 802,803,1203and 1205.5 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges .The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.37	Cubic metres Per Cubic metre

Providing and Laying Heavy Duty Cobble Stone 100x100x60 mm (One Hundred into One Hundred into Sixty millimeter) of approved shade stone laid over 20 mm (twenty millimeter) average thick base of cement mortar 1:3 (one cement three coarse sand ) with joints finished flush including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	133.75	Square Meter	Per Square Meter
Total			

*H. S. D.*  
Executive Engineer,  
Blisspur Division No. 2,  
H.P.W.D., Blisspur (H.P.).