



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

cepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2023-24-

To

1944-46

Dated:- 27/06/2022

The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

**Dear Sir,**

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.  
DA/ As above.

*U. S. S.*  
**Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.**

Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

*1*  
**Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.**



Tel.01899-299219.  
cepwd-chowari@hp.gov.in

## HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

### "NOTICE INVITING TENDERS"

Sealed percentage/item rate tender (s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 5 Date of receipt of application for the tender  
Form a/w requisite documents: -
- 6 Date of issued/sale of tender form against  
Cash payment (non refundable).

10/07/2023

11/07/2023\_

The tender shall be received up to 11.00 AM on 12/07/2023 and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 12/07/2023.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	C/o Saloh Sarna Naddal Prachore (SH:- C/o HP Culvert at Rd 1/545 alongwith wing wall).	491270/-	10000/-	350/-	Three Month	Class-D
2	C/o link road from Garnota to ( Bhadela) to Pukhru via Padwal road Km 0/0 to 6/400 ( SH:- Imp. Of curves at Rd 0/500 to 3/500).	450218/-	9100/-	350/-	Three Month	Class-D
3.	C/o link road to village Dhar Km 0/0 to 1/600 (SH:- HP Culvert at Rd 0/330 alongwith Wing wall).	439932/-	9500/-	350/-	Three Month	Class-D
4	C/o link road to village Thulel to Anai Km 0/0 to 2/400 (SH:- C/o HP Culvert at Rd 0/175 alongwith wing wall).	425728/-	9500/-	350/-	Three Month	Class-D
5	C/o link road to village Thulel to Anai Km 0/0 to 2/400 (SH:- C/o HP Culvert at Rd 0/620 alongwith wing wall).	374697/-	8000/-	350/-	Three Month	Class-D
6	C/o link road to village Nahana Km 0/0 to 4/200 (SH:- P/L GSB,G-II,G-III and Bituminous concrete at Rd 3/930 to 4/077).	491467/-	10000/-	350/-	Three Month	Class-D
7	Restoration of rain damage on Nanikhed to Samlue road Km 0/0 to 3/585 ( SH:- Formation cutting at Rd 5/675 to 5/695 & 9/440 to 9/500).	249198/-	5000/-	350/-	Three Month	Class-D
8	Restoration of rain damage on Chowari Mandhiar Gaghar Baloh Fagot road Km 0/0 to 13/450 ( SH:- Hiring of excavator cum loader for removal of slips in Km 0/0 to 13/00).	468000/-	10000/-	350/-	Three Month	Class-D



9	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba road Km 14/00 to 45/00 ( SH:- C/o wire crate at Rd 49/847 to 49/872).	391153/-	6000/-	350/-	Three Month	Class-D
10	Restoration of rain damage on Jajri Gala to Bai Ka Baag road Km 0/0 to 1/500 ( SH:- C/o crate work R/wall at Rd 0/010 to 0/025).	231283/-	5000/-	350/-	Three Month	Class-D
11	Restoration of rain damage on Shahpur Sihunta Chowari road Km 40/0 to 76/00 ( SH:- C/o R/wall at Rd 46/825 to 46/837).	372830/-	6000/-	350/-	Three Month	Class-D
12	C/o Saloh Sama Naddal Parchore road Km 0/0 to 3/700 ( SH:- C/o 900 mm dia HP culvert at Rd 1/705 alongwith wing walls).	476383/-	10000/-	350/-	Three Month	Class-D
13.	Restoration of rain damage on Jolna Bhated road Km 0/0 to 2/00 ( Sh:- Hiring of excavator cum loader for removal of slips in Km 0/0 to 1/00 ).	490455/-	10000/-	350/-	Three Month	Class-D

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No. /Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
- 4 Application without all documents will not be entertained.
- 5 Proxy application will not be entertained.

*4-1-1*  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

No. PWD-CHW/Tender /2023-24-

*1947-1997*

Dated:-

*27/06/23*


Copy forwarded to the following for information and necessary action please:-

- 01/07/23*
- Engineer-in-Chief, HPPWD, Shimla.
  - All the Chief Engineer in HPPWD.
  - All SEs/EE in HPPWD.
  - All AEs/Contractor under this Division.
  - Deputy Commissioner, Chamba
  - The BDO Bhattiyat.
  - Sub Divisional Magistrate/B.D.O/Tehsildar Chowari.
  - Notice Board of this office.

Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

**Certificate**

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2023-24-~~1947-97~~.....dated..~~27/6/23~~ is emergent nature and in Public interest.

  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

(1)

**Schedule of Quantity**

**NAME OF WORK:- Construction of Saloh Sarna Naddal Parchore km 0/0 to 3/700 (Sub Head:- C/O 900 mm dia H.P. culverts at RD 1/545 along with wing walls)**

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	63.38			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	2.20			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	20.19			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 ( One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	7.50			Per running metre	

Rs. 491442/-

Estimated Cost

Rs. 10000/-

Earnest Money

Three months

Time Limit



7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	52.92			Per cubic metre	
8	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	22			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	12.15			Per cubic metre	

  
 Executive Engineer,  
 Chowari Division,  
 HP, PWD, Chowari

3

### Schedule of Quantity

Estimated Cost	Rs. 439932/-
Earnest Money	Rs. 8800/-
Time Limit	Three months

**NAME OF WORK:- Construction of Link Road to village Dhar km 0/0 to 1/600 (Sub Head:- C/O 900 mm dia H.P. culverts at RD 0/150 alongwith wing wall)**

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	58.92			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	16.81			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.00			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 ( One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	7.50			Per running metre	

7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	43.56			Per cubic metre	
8	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	14			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	9.14			Per cubic metre	

Executive Engineer,  
Chowari Division,  
HP. PWD. Chowari



## Schedule of Quantity

**Name of work:- Construction of Link road from Garnota (Bhadela) to Pukhru via Padwal km 0/0 to 6/400 (SH:- 3/500)**

Estimated Cost	Rs. 450222/-
Earnest Money	Rs. 9000/-
Time Limit	Three months

**Improvement of curves at RD 0/500 to**

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock Where blasting is prohibited and their intermediate classification of soil complete including setting out true to the require lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer -In -Charge at site, according to the MORD Technical specification section 300 and 1600 and sorting out useful material and stacking the same within all leads and lifts in acquired width of road and transportation of un-usual materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus material to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries, material, tools, equipment and safety measures and other incidental necessary to complete the work by contractor. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the Contractor, which shall have to be compensated by him in all cases. The rate are including the octroi royalty, Malkana toll tax, sales tax, GST or any other taxes imposed by the Govt.	3510.78			Per Cubic Metre	
<b>Total</b>						

**Executive Engineer**  
**Chowari Division**  
**Hppyd Chowari**

4

Three months

S.No.	Description	Quantity	Rate	Unit	Amount
		in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	62.43		Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803,1202, and 1203 (P.C.C Norminal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	2.32		Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803,1202, and 1203 (P.C.C Norminal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28		Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803,1202, and 1203 (P.C.C Norminal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37		Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803,1202, and 1203 (P.C.C Norminal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	20.41		Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 ( One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	7.50		Per running metre	



7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	52.74			Per cubic metre	
8	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	16			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	6.57			Per cubic metre	

Executive Engineer,  
Chowari Division,  
HP.PWD, Chowari



### Schedule of Quantity

**NAME OF WORK:- Construction of Link Road to village Thuliel to Anai km 0/0 to 2/400 (Sub Head:- C/O 900 mm dia H.P. culverts at RD 0/620 alongwith wing wall)**

Estimated Cost	Rs. 374697/-
Earnest Money	Rs. 7500/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	58.39			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	2.24			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	18.69			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 ( One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	7.50			Per running metre	

7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Norminal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	43.8				Per cubic metre	
8	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 asper the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	12				Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	6.39				Per cubic metre	

Executive Engineer,  
 Chowari Division,  
 H.P.W.D. Chowari



(6)

### Schedule of Quantity

Name of work:- Construction of Link Road to village Nahana km 0/0 to 4/200 (SH:- Providing and laying GSB, G-II, G-III & Bitumenous concrete at RD 3/500 to 3/645)	Estimate Cost .	491420/-
	Earnest Money	10000/-
	Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Loosening of ground upto a level of 300mm (Three hundred millimetre) below the sub grade level,watered graded and compacted in layer to meet requirement of table 300.1 and 3000.2 with power Road Roller 8-10 Tonne(Eight tonne) capacity for sub grade construction as per MORD technical specification rural roads clauses 303.5.2 including hauling of materials in all leads,lifts and other incidentals or as per the entire specifications and directions of Engineer-in-Charge.The rate including octroi,royalty, Malkana toll tax , GST or other taxes imposed by the Government.	77.56			Per cubic metre	
2	Construction of granular sub base/base by providing well graded materials of nominal maximum size 80 mm ( eighty millimeter) as per table 2.3 of IRC –SP-77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compacting with three wheel 80-100 (eighty -one hundred) kN static roller to achieve the desired density, as per Technical Specifications contained in para 2.2 ,3.6 and 3.7 of IRC-SP-77 -2008 or as directed by the Engineer-in-Charge complete , including carriage of materials within all leads, lifts and other incidentals The rate including octroi, royalty, Malkana, toll tax , GST or any other taxes imposed by the Government.	64.63			Per cubic metre	



3	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm Grading-II [75mm consolidated thick] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-B of size 11.2mm nominal size at the rate of 0.20 cum ( zero point twenty cubic metres) per ten square metres and binding material at the rate 0.06 cum to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 including carriage of materials within all leads, lifts and other incidentals The rate including octroi, royalty, Malkana, toll tax , GST or any other taxes imposed by the Government.	38.78				Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm ( fifty three millimeter to twenty two point four millimeter) Grading-III [75mm( seventy five millimeters) consolidated thick] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm ( eleven point two millimetres) nominal size at the rate of 0.18cum ( zero point two eighteen cubic metres) per ten square metres and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 including carriage of materials within all leads, lifts and other incidentals The rate including octroi, royalty, Malkana, toll tax , GST or any other taxes imposed by the Government.	38.78				Per cubic metre	
5	Providing and applying primer coat with Bitumen emulsion Bitchem (SS-1) and Silance Nano technology -Tera prime on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 1.0 kg./sqm.using mechanical means as per Technical Specification Clause 502 including carriage of materials within all leads, lifts and other incidentals The rate including octroi, royalty, Malkana, toll tax , GST or any other taxes imposed by the Government.	470.77				Per square metre	
6	Providing and applying tack coat with Bitumen emulsion (RS-1) and Silance Nano technology - Nano tac using emulsion distributor at the rate of 0.250 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.including carriage of materials within all leads, lifts and other incidentals The rate including octroi, royalty, Malkana, toll tax , GST or any other taxes imposed by the Government.	470.77				Per square metre	

Per cubic  
metre

**Executive Engineer**  
**Chowari Division**  
**Hppwd Chowari**



## Schedule of Quantity

**Name of work:- Restoration of rain damage on Nanikhad to Samluc Road km 0/0 to 30/585 ( SH - Formation cutting at RD 5/675 to 5/695 and 9/440 to 9/500)**

Schedule of Quantity				Estimated Cost . Rs. 249198/-	
				Earnest Money Rs. 5000/-	
				Time Limit Three months	
Name of work:- Restoration of rain damage on Nanikhad to Samluc Road km 0/0 to 30/585 ( SH - Formation cutting at RD 5/675 to 5/695 and 9/440 to 9/500)					
S.No.	Description	Quantity	Rate	Unit	Amount
			in Fig.	in Word	
1	Excavation in hilly area in all hieghts and depths and in all lind of soil by manual /mechanical means including saturated soil comprising of ordinary soil,ordinary rock ,soft rock,hard rock chieseling, wedging out rock Where blasting is prohibited )and their intermediate classification of soil complete including setting out true to the require lines, grades , width ,cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer -In -Charge at site, according to the MORD Technical specification section 300 and 1600 and sorting out useful material and stacking the same within all leads and lifts in acquired width of road and transportation of un-usual materials for filling in roadways camber ,embankments for grade improvements and disposal of all surplus material to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries , material , tools , equipment and safety measures and other incidental necessary to complete the work by contractor. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor, which shall have to be compensated by him in all cases. The rate are including the octroi royalty, Malkana toll tax, sales tax, GST or any other taxes imposed by the Govt.	1052.58			Per Cubic Metre
Total					

**Executive Engineer**  
**Chowari Division**  
**Hppwd Chowari**




## Schedule of Quantity

**Name of work:-** Restoration of rain damage on Chowari Mandhiar Gagahar Baloh Fagot Road km 0/0 to 13/450  
**Head:-** Hiring of Excavator cum Loader for removal of slips in km 0/0 to 13/00

Estimate Cost :- Rs.	468000/-
Earnest Money	9400/-
Time Limit	Three months
	( Sub-

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth of unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be laved to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate is including octroi, royalty, Malkhana, and Toll Tax GST or other Taxes imposed by the Government.	480.00			per hour	

  
**Executive Engineer**  
 Chowari Division  
 HPPWD, Chowari


(9)

### Schedule of Quantity

Estimated Cost	Rs. 3,91,153/-
Earnest Money	Rs. 7900/-
Time Limit	Three months

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba Road km 0/0 to 76/00 ( SH:- Construction of Breast wall in wire crate at RD 49/847 to 49/872)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leadss and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	64.00			Per cubic metre	0
3	Providing & Laying of boulder apron laid in wire crate with 4 mm dia GI wire conforming to IS : 280 and IS: 4826 in 100 mm x 100 mm mesh ( woven diagonally ) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301. as per the direction of the Engineer in Charge. Including Carriage of material within all leadss and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	117.19			Per cubic metre	0.00
Total						391153

  
Executive Engineer  
Chowari Division  
HPPYD Chowari



## Schedule of Quantity

Estimated Cost	Rs. 231283/-
Earnest Money	Rs. 4700/-
Time Limit	Three months

**Name of work:- Restoration of rain damage on Jajri Gala to Bai Ka Baag Road Km 0/00 to 1/500 ( SH:- Construction of crated retaining walls at RD 0/010 to 0/025)**

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	24.68			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Fortykilogram) each as per drawing and technical specification Clause 1301 and as per directions of including the octroi, royalty Malkana , Toll tax Sales tax, GST or any taxes imposed by the Govt.	70.31			Per cubic metre	
<b>Total</b>						


**Executive Engineer**  
 Chowari Division  
 Hppwd Chowari

## Schedule of Quantity

Name of work:- Restoration of rain damage on Patka to Dalhousie Road Km 14/00 to 45/00( SH:- Construction of Retaining walls at RD 36/775 to 36/780)

Estimated Cost	Rs 366046/-
Earnest Money	Rs. 7400/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidentals. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	29.04			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	70.56			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	27.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.28			Per cubic metre	
<b>Total</b>						

  
 Executive Engineer  
 Chowari Division  
 Hppwd Chowari



### Schedule of Quantity

**NAME OF WORK:- Construction of Saloh Sarma Naddal Parchore km 0/0 to 3/700 (Sub Head:- C/O 900 mm dia H.P. culverts at RD 1/705 alongwith wing wall)**

Schedule of Quantity		Estimated Cost		Rs.476580/-		
		Earnest Money		Rs. 9600/-		
		Time Limit		Three months		
NAME OF WORK:- Construction of Saloh Sarma Naddal Parchore km 0/0 to 3/700 (Sub Head:- C/O 900 mm dia H.P. culverts at RD 1/705 alongwith wing wall)						
S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deteriorous material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	63.09			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materilas with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	2.20			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materilas with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materilas with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materilas with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	20.19			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 ( One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	7.50			Per running metre	

7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	50.82			Per cubic metre	
8	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	20			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	9.17			Per cubic metre	

Executive Engineer,  
 Chowari Division,  
 HP.PWD, Chowari



**Schedule of Quantity**

Estimate Cost :- Rs.	490453/-
Earnest Money	10000/-
Time Limit	Three months

**Name of work:- Restoration of rain damage on Jolna to Bhaded Road Km 0/0 to 3/810 ( SH:- Removal of slips in km 0/00 to 1/00)**

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
	Removal of landslides/ slip clearance in hilly area in all kinds of soil not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any leads and lifts as per technical specifications. The rate including octroi, royalty, Malkana Toll tax sale tax , GST or other taxes imposed by the Govt.	3921.43			Per cubic metre	
Total						

Executive Engineer  
Chowari Division  
Hppwd Chowari