



Office of  
Executive Engineer B&R Division HP.PWD. Joginder Nagar  
Himachal Pradesh Public Works Department, Mandi-175015  
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

**"NOTICE INVITING TENDER"**

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **23/08/2023 up to 11:30 A.M.** and will be opened on the same day at **(12:00 noon)** in the presence of intending contractors. The tender application will be received in this office on **21/08/2023 up to 10.00 A.M. to 12:30 P.M.** and tender form can be had from this office on **22/08/2023 from 2.00 P.M. to 5.00 Pm.** The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

|   | Name of work  | Amount put to tender/<br>Estimated cost | Earnest Money | Cost of tender form | Eligible Class of Contractor | Time         |
|---|---|---|---------------|---------------------|------------------------------|--------------|
| 1 | Construction of Industrial Training Institute Joginder Nagar at Dohag (Sub Head:- Construction of sitting steps and G.I. Chain Fencing at Basket Ball ground) | Rs. 4,94,506/-                          | Rs. 9,900     | Rs. 350/-           | Class "D"                    | Three months |
| 2 | Construction of Industrial Training Institute Joginder Nagar at Dohag (Sub Head:- Construction of main gate)  | Rs. 4,09,110/-                          | Rs. 8,200/-   | Rs. 350/-           | Class "D"                    | Three months |

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

**Terms and conditions:-**

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.  
District Mandi (HP) on behalf of  
Governor of Himachal Pradesh  
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24- 10006-10055

Dated:- 27-7-2023

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.



# SCHEDULE OF QUANTITY


30540-1(5)

Name of work : Construction of Industrial Training Institute Joginder Nagar at Dohag  
(SH: Construction of Sitting Steps and G.I. Chain Fencing at Basket Ball Ground )

Estimate Cost: 4,94,500  
Earnest Money: 9,900  
Time Limit : Three Months

| Sr. No. | Description of work  | No. or Qty. | Unit             | Rate    |       | AMOUNT Rs. P |
|---------|--|-------------|------------------|---------|-------|--------------|
|         |  |             |                  | Figures | Words |              |
| 1       | Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost . | 8.10        | Per cubic metre  |         |       |              |
| 2       | Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.  | 936.00      | Per Kilogramme   |         |       |              |
| 3       | Providing and fixing G.I. chain link fabric fencing Made of G.I. wire of dia 4 mm (four millimeter) required width in mesh size 50x50 mm (fifty by fifty millimeter) including strengthening with 2 mm dia (two millimeter diameter) wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.   | 112.50      | Per square metre |         |       |              |
| 4       | Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm2 with cement contents not less than of 330kg/m3 (three hundred thirty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in foundation footing, basis of columns and the like mass concrete upto floor all level and curing complete including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction of Engineer-in-Charge.  | 13.13       | Per cubic metre  |         |       |              |

| Sr. No. | Description of work  | No. or Qty. | Unit            | Rate    |       | AMOUNT<br>Rs. |
|---------|--|-------------|-----------------|---------|-------|---------------|
|         |  |             |                 | Figures | Words |               |
| 5       | Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-1 (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.   | 8.75        | Per cubic metre |         |       |               |
| 6       | Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size ) plums and curing complete including the cost of form work in <b>Retaining walls Breast walls</b> , in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. | 40.50       | Per cubic metre |         |       |               |
|         | <b>Total</b>   |             |                 |         |       |               |

  
 Executive Engineer  
 B & R Division HP.PWD,  
 Joginder Nagar



# DNT/SCHEDULE OF QUANTITY

Job No - 2

Name of Work : Construction of Government Industrial Training Institute Joginder Nagar at Dohag  
(S.H. : Construction of Main Gate)

Estimate Cost: 4,09,11  
Earnest Money: 8,20  
Time Limit : Three Months

| Sr. No. | Description of work  | No. or Qty. | Unit            | Rate     |  | AMOUNT Rs. P |
|---------|--|-------------|-----------------|----------|--|--------------|
|         |  |             |                 | Figures  | Words  |              |
| 1       | Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST. | 2.70        | Per cubic metre | 411.90   | Rupees Four Hundred Eleven And Paise Ninety Only                     | 1,1          |
| 2       | Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm2 with cement contents not less than of 330kg/m3 (three hundred thirty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in foundation footing, basis of columns and the like mass concrete upto floor all level and curing complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.   | 2.70        | Per cubic metre | 5,765.70 | Rupees Five Thousand Seven Hundred Sixty Five And Paise Seventy Only | 15,56        |
| 3       | Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm2 with cement contents not less than of 330kg/m3 (three hundred thirty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in columns, pillars posts and struts upto floor all level and curing complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.   | 2.06        | Per cubic metre | 6,986.80 | Rupees Six Thousand Nine Hundred Eighty Six And Paise Eighty Only    | 14,3         |



| Sl. No. | Description of work  | No. or Qty. | Unit              | Rate     |  | AMOUNT<br>Rs. P |
|---------|--|-------------|-------------------|----------|--|-----------------|
|         |  |             |                   | Figures  | Words  |                 |
| 4       | Providing and fixing 0.60mm (zero point six zero millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted limpet and rubber washers complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.  | 29.42       | Per square metre  | 1,473.30 | Rupees One Thousand Four Hundred Seventy Three And Paise Thirty Only | 43,34           |
| 5       | Providing and fixing ridges or hips 60cm (sixty centimetre) overall with 0.63mm (zero point six three millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted GI limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST. | 11.25       | Per running metre | 652.40   | Rupees Six Hundred Fifty Two And Paise Forty Only                    | 7,34            |
| 6       | Providing and fixing valley 60 cm (sixty centimeter) overall 0.60mm (zero point six) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating of back coat of polyester of 5 (five) microns over 5 (five) microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia with prepainted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.  | 12.00       | Per running metre | 705.50   | Rupees Seven Hundred Five And Paise Fifty Only                       | 8,46            |
| 7       | Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams joists channels, angles, tee flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like work including cutting hoisting fixing in position & applying a priming coat of red lead paint complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.  | 2542.88     | Per Kilogramme    | 100.40   | Rupees One Hundred And Paise Forty Only                              | 2,55,30         |

| Sl. No. | Description of work   | No. or Qty. | Unit              | Rate    |   | AMOUNT<br>Rs. P |
|---------|---|-------------|-------------------|---------|---|-----------------|
|         |   |             |                   | Figures | Words   |                 |
| 8       | Providing and fixing angle iron door, window, clerestory window frame manufactured from M.S. Angle iron section of 50X50X6 mm (fifty by fifty by six millimeter), thickness including hinges jamb, lock jamb, bead and if required angle threshold of mild steel angle 50X25 mm (fifty by twenty five millimeter) welded or rigidly fixed by mechanical means, lugs with split end tails to each jamb including steel butt hinges 2.5 mm (two point five millimeter) thick with provision for locking arrangement and shock observer as specified and applying a coat of approved steel primer after pretreatment of the surface as directed by Engineer-in-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST. | 89.80       | Per running metre | 445.50  | Rupees Four Hundred Forty Five And Paise Fifty Only                 | 40,00           |
| 9       | Providing and fixing MS BP sheet 1.66mm to 2mm (one point six six millimetre to two millimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.   | 15.74       | Per square metre  | 1497.90 | Rupees One Thousand Four Hundred Ninety Seven And Paise Ninety Only | 23,57           |
|         | <b>Total</b>  |             |                   |         |   | <b>4,09,11</b>  |

*Amount of Rs. 40,000/- (Rupees Forty Thousand Only) is hereby confirmed and the same is paid to the contractor.*

*(Signature)*  
 Executive Engineer  
 B & R Division HP.PWD,  
 Joginder Nagar