



**Himachal Pradesh
Public works Department**

NO: PW- BHNR-B&R-EA-1-Tender/2022-23- 23 28-34

To,

Dated:- 23 6 023

The Executive Engineer,
IT Cell HP.PWD Shimla-2.


Subject: - Publication of Notice Inviting Tender.

Sir,

I am enclosing herewith the Notice Inviting Tender along with schedule of Qty. for favour of information and necessary action. The work attached in list is of very urgent nature. It is requested that the same may kindly be got published.

Yours Faithfully,


DA: - As above.


Executive Engineer,
Karchham Division,
HP.PWD, Bhabanagar.

Copy to following for information & necessary action.

1. All the Assistant Engineers, working under this Division.
2. Drawing Branch of this office
3. Notice Board of this office.

DA: - 1 No.


Executive Engineer,
Karchham Division,
HP.PWD, Bhabanagar.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDERS

The Executive Engineer, Karchham Division, H.P.P.W.D. Bhabanagar District Kinnaur Pin-172115 invite Item rate tenders in sealed cover on the prescribed forms from the eligible Contractors on 03.07.2023 and shall be opened on the same day at 11:00 Hrs. in the presence of intending contractors or their authorized representatives who wish to be present at the time.


Sr. No	Name of work	Estimated cost	Earnest money	Time	Cost of form
1	R/R damages on Chhitkul Dumti road Km. 0/0 to 20/750(SH:- P/L G-I at RDs 13/500 to 20/00).	430988/-	8700/-	One month	Rs. 350/-
2	R/R damages on Chhitkul Dumti road Km. 0/0 to 20/750(SH:- P/L G-II at RDs 13/500 to 20/00).	457065/-	9200/-	One month	Rs. 350/-
3	R/R damages on Chhitkul Dumti road Km. 0/0 to 20/750(SH:- P/L G-III at RDs 13/500 to 20/00).	447975/-	9000/-	One month	Rs. 350/-
4	R/R damages on Chhitkul Dumti road Km. 0/0 to 20/750(SH:- Hiring of hydraulic Excavator in working condition for removal of land slide/slips/debris at various RDs)	500000/-	10000/-	15 days	Rs. 350/-

TERMS AND CONDITIONS:-

The Earnest Money shown against each work must accompany with each tender in the shape of National Saving Certificate/Time Deposit Account/Post Office Saving Bank Account of any of the Post Offices duly pledged in the name of undersigned. The application of each tender alongwith following documents must reach in this office on 01.07.2023 upto 12:00 PM and issued on same day.

- (i) Each application alongwith attested copy of the proof of enlistment in the appropriate Class and its renewal.
- (ii) Permanent Account Number (PAN)
- (iii) EPF No and GST.
- (iv) Exemption Letter for payment of earnest money from competent authority if any.

The contractor enlisted in a particulars class shall be eligible to tender for his own class and one step below. The tender rates must be quoted in words and figures by the tenderer. The conditional tenders or the tenders without earnest money shall be rejected. The Executive Engineer reserves the right to reject any or all tenders without assigning any reason. In case there happens to be a holiday on the date of opening of the tenders the same shall be opened on the next working day. The offer of the tender shall remain valid upto 90days from the opening of the tenders.


Executive Engineer,
Karchham Division
HP:PWD:Bhabanagar

Schedule of Quantity

Estimated Cost:- 500000.00
 Earnest Money:- 10000.00
 Time:- 15 Days

Name of work:- Restoration of rain damages on Chitkul Dumti road Km 0/00 to 20/750
 Sub Head:- Hiring of Hydraulic Excavator in working condition for Removal of land slides/slips/debris at various RDS

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of one No. Hydraulic excavator (L&T 140) in working condition Hyundai/L&T make (Excavation bucket with 360 degree rotation) on hire charges basis at the site of work for removal of slips/landslide and debris in all classification of soil dressing of berms, filling of depression and filling behind R/wall etc. and their loading with free of cost including P.O.L. operation staff, repair charges of machinery etc. The actual working hour shall be counted for payment. Any damages to the private/ public property during the execution shall be the absolutely responsibility of the owner. The work shall be executed as per the entire satisfaction and direction of Engineer-in-Charge with in all leads lifts complete in all respect.	200.00			Per hour	
					Total	

Executive Engineer
 Karchham Division HP, PWD,
 Karchham at Bhadga Nagar

Schedule Of Quantity

Estimated Cost :- 447975.00
Earnest Money:- Cost :- 8960
Time:- One Month
Sub Head:-

Name of work:- R/R damages on Chhitkul Dumti road Km 0/0 to 20/750
Providing and laying G-III at Rd. 13/500 to 20/00. Job No- 1

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, spreading and compacting stone aggregate of sizes 53 -22.4 mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by Manual means as per technical Specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per direction of Engineer-In-Charge.	450.00			Per cubic metre	
					Total	

Executive Engineer,
 Karchham Division HP.PWD.,
 At Bhaba Nagar.

Schedule Of Quantity

Estimated Cost :- 457065.00
 Earnest Money:- Cost :- 9141
 Time:- One Month
 Sub Head:-

Name of work:- R/R damages on Chhitkul Dumti road Km 0/0 to 20/750
 Providing and laying G-II at Rd. 13/500 to 20/00. Job No- 1

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, spreading and compacting stone aggregate of sizes 63- 45 mm (Sixty three to point forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-II by Manual means as per technical Specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per direction of Engineer-In-Charge.	450.00			per cubic metre	
					Total	


Executive Engineer,
 Karchham Division HP.PWD.,
 At Bhaba Nagar.

Schedule Of Quantity

Estimated Cost :- 430988.00
Earnest Money:- Cost :- 8620
Time:- One Month
Sub Head:-

Name of work:- R/R damages on Chhitkul Dumti road Km 0/0 to 20/750
 Providing and laying G-I at Rd. 13/500 to 20/00. Job No- 1

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, spreading and compacting stone aggregate of sizes 90-45 mm (ninety to point forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-I by Manual means as per technical Specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per direction of Engineer-In-Charge.	450.00			per cubic metre	
					Total	


 Executive Engineer,
 Karchham Division HP.PWD.,
 At Bhaba Nagar.