

**OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**

PH: 01907-222229 Fax: 222229, e-mail : [ee-kar-hp@nic.in](mailto:ee-kar-hp@nic.in)

No.PW-KSG-E-Tenders/2023-

To

Dated:- 10.07.2023


2639  
✓ The Executive Engineer (IT) Cell,  
HPPWD, Nirman Bhawan, Nigam Vihar,  
Shimla-2.

**Subject :-**

Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 12.07.2023 as per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16<sup>th</sup> July, 2021. As the works mentioned in the Tender Notice are urgent in nature.

**Encl:- As above.**

  
Executive Engineer,  
B&R Division,  
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**  
**PH: 01907-222229 Fax: 222229 , E-mail : [ee-kar-hp@nic.in](mailto:ee-kar-hp@nic.in)**

**Notice inviting tender**

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **20.07.2023 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 19.07.2023** for which the application should reach in this office **upto 1.00 PM 19.07.2023**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.


Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	C/o Narash to Bego via Bhiru Km. 0/00 to 7/00 (SH:- Widening of road in Km. 4/300 to 4/480).	4,74,616/-	9,500/-	One months	350/-
2	C/o Narash to Bego via Bhiru Km. 0/00 to 7/00 (SH:- Widening of road in Km. 4/510 to 4/705).	4,87,374/-	9,800/-	One month	350/-
3	C/o Choridhar Kotlu road Km. 0/00 to 7/00 (SH:- Widening of road in Km. 4/805 to 4/990) Deposit Work.	4,94,569/-	9,900/-	One month	350/-
4	R/R damages on Kelodhar to Sainj road Km. 0/00 to 19/00, Chauridhar Kotlu road Km. 0/00 to 7/00 (SH:- Removal of slips, C/o unlined surface, drain maintenance earthen shoulder & maintenance of berms at various RDs).	4,27,584/-	8,600/-	One month	350/-
5	R/R damages on Rashog Deyom road Km. 0/00 to 9/00 (SH:- C/o R/wall at RD 4/170 to 4/179).	4,96,289/-	10,000/-	One month	350/-




6	R/R damages on various roads under Karsog Sub-Division(SH:- Hiring of JCB for removal of slips on various roads) Section Katanda.	3,96,000/-	7,920/-	Two months	350/-
7	R/R damages on various roads under Karsog Sub-Division(SH:- Hiring of JCB for removal of slips on various roads) Section Kotlu.	3,96,000/-	7,920/-	Two months	350/-

#### TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

  
Executive Engineer  
B&R Division  
HPPWD Karsog,  
Distt. Mandi(HP)

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1<sup>st</sup> Circle, HP,PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


  
Executive Engineer,  
B&R Division,  
HP PWD Karsog

# SCHEDULE OF QUANTITY

Estimated Cost 474616  
Earnest Money 9500  
Time One Month

Name of Work:- C/O Narash to Bego via Bhiru Km. 0/00 to 7/00 (SH:- Widening of road in Km 4/300 to 4/480).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 309.53 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.92,859/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1785.75			Per Cubic Meter	
Total Amount						

  
Executive Engineer,  
Karsog Division,  
HPBWD, Karsog.



# SCHEDULE OF QUANTITY

Name of Work:- C/O Narash to Bego via Bhiru Km. 0/00 to 7/00 (SH:- Widening of road in Km 4/510 to 4/705).

Estimated Cost  
Earnest Money  
Time

487374  
9800  
One Month

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 317.85 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.95,355/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1833.75			Per Cubic Meter	
Total Amount						

Executive Engineer,  
Karsog Division,  
HRPMD, Karsog.

# SCHEDULE OF QUANTITY

Estimated Cost 494569  
Earnest Money 9900  
Time One Month

Name of Work:- C/O Chauridhar Kotlu road Km. 0/00 to 7/00 (SH:- Widening of road in Km 4/805 to 4/990). Deposit work

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 322.54 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.96,762/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1860.89			Per Cubic Meter	
Total Amount						

  
Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# SCHEDULE OF QUANTITY

Name of work : - R/R damages on Kelodhar to Saini road Km 0/00 to 19/00, Chauridhar Kotlu road Km 0/00 to 7/00 (SH:- Removal of slips,C/O unlined surface  
drain maintenance of earthen shoulder & maintenance of berms at various RD'S ).

Estimated Cost 427584  
Earnest Money 8600  
Time One Month

Sr.No.	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1070.03			Per Cubic Meter	
2	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	5355.00			Per Running Meter	
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	5152.00			Per Square Meter	
	<b>Total Amount</b>					

  
Executive Engineer,  
Karsog Division,  
HPWD, Karsog.



# SCHEDULE OF QUANTITY

Estimated Cost 496289  
Earnest Money 10000  
Time One Month

Name of Work:- R/R Damages on Rasog Deyom road Km. 0/00 to 9/00 (SH:- C/O R/Wall at RD 4/170 to 4/179).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Earth work in excavation by mechanical means(Hydraulic) manual means in foundation trenches or drains(not exceeding 1.5 m in width or 10 Sqm on plan,including getting dressing of sides and ramming of bottoms,any lift including getting out the excavated soil and disposal of surplus excavated soil as directed upto any lead as per direction of engineer in charge with in all lead and lifts and other incidentals.	31.50			Per Cubic Meter	
2	Providing and laying concrete for pain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 in P.C.C 1:5:10 (one cement : five coarse sand : 10graded stone aggregate 40 mm nominal size).As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals..	89.82			Per Cubic Meter	
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	16.00			Each	
4	Back filling behind abutment wing wall, retaining wall , Breast Wall & Return Wall complete as per drawing & technical clause 1204.3.8 Granular materials. As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	6.48			Per Cubic Meter	
Total :-						

Executive Engineer,  
Karsog Division,  
HPRWD, Karsog.



**P.N.I.T/SCHEDULE OF QUANTITY**

Name of work :- R.R. damages on Various Road under Karsog Sub Division (SH.- Hiring of JCB for removal of slips on various roads) Section Katanda

Estimated Cost :- Rs.396000/-  
Earnest Money :- Rs. 7920/-  
Time :- Two Months

S.No.	Sub-Head and items of work.	Qty.	Rate.		Unit.	Amount.
			In Figure	In Words.		
1.	Hiring of JCB/Excavator cum Loader for cutting in earth work in all kinds of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 6 Hour daily and remove at least 25 cum. Qty. of soil per hour. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The fuel and operation staff for the machine will be provided by the owner. The repair charges of machinery during the execution of work will be borne by the contractor. While making the record entry. It may ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 Cum. Per Hour. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge.	360 Hours			Per Hours	
	Total :-					

  
Executive Engineer  
Karsog Division  
HPPWD Karsog

**D.N.I.T/SCHEDULE OF QUANTITY.**

**Name of work :-** R.R. damages on Various Road under Karsog Sub Division (SH.:- Hiring of JCB for removal of slips on various roads) Section Kotlu

**Estimated Cost :-** Rs.396000/-

**Earnest Money :-** Rs. 7920/-

**Time :-** Two Months

S.No.	Sub-Head and items of work.	Qty.	Rate.		Unit.	Amount.
			In Figure	In Words.		
1.	Hiring of JCB/Excavator cum Loader for cutting in earth work in all kinds of soil such as pick work, jumper work, blasting, work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 6 Hour daily and remove at least 25 cum. Qty. of soil per hour. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The fuel and operation staff for the machine will be provided by the owner. The repair charges of machinery during the execution of work will be borne by the contractor. While making the record entry. It may ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 Cum. Per Hour. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge.	360 Hours			Per Hours	
	<b>Total :-</b>					

  
**Executive Engineer**  
 Karsog Division  
 HPPWD Karsog