


**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated **2.8.2023** up to **10.30AM** and the same will be opened on the same day at **11.30 AM** in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to **2.00 PM** on dated **01.08.2023** and tender forms can be obtained from this office against cash payment (nonrefundable) on **01.08.2023** from **2.00 PM** to **5.00 PM** and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without **earnest money** (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons.

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Restoration of Rain Damages on Chanour Tiamal Sheetla Mandhir Road Km 2/0 to 10/495 (SH:- C/O R/wall in CC 1:5:10 and wire crate at Rd 6/915 to 6/930)	482334	10000	Three Month	350	6&8
2	Restoration of Rain Damages on on Bridge Over Lag Baliaana and Sehri Khad on Bani Pragpur Via Dangra Sidh Km 0/0 to 2/0 (SH:- P/L Distempering Painting over lag Baliaana Bridge and Sehri Khad	162133	3000	ONE Month	350	6&8
3	Restoration of Rain Damages on Chambli Swana Road Km 0/0 to 4/00 (SH:- C/O Wire crate at Rd 1/705 to 1/735)	461052	1000	Two Month	350	6&8
4	A/R & M/O of link Road from Shantla to Bhudwar via Sai Road Km 0/0 to 3/300 (SH:- Pretreatment of shoulder in slushy reaches)	184397	4000	Two Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest,


Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER /2023-24 **1889 -93**


DATED **26/7/2023**

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.


Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

SCHEDULE OF QUANTITY

Estimate Cost :- Rs.1,62,133/-
 Earnest Money :-Rs.3000/-
 Time Limit :-One Months.
 Name of work:- Restoration of Rain damage on Bridge over Lag Baliana and Sehri Khad on Bani Pragpur via Dangra Sidh road Km. 0/0 to 2/0 (SH):- P/L Distempiring ,
 Painting over Lag Baliana Bridge and Sehri Khad)

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and applying white cement based putty of average thickness over plastered surfaces after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final finish to the surface complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Malkhana, Royalty, Octroi, toll tax, Sale Tax, GST or any taxes imposed by the Government	646.70 Square meter			Per Square meter	
2	Applying acrylic primer spectrum or its equivalent over new concrete / masonry as per cement plaster surface after and including preparing the surface by thoroughly cleaning, oil, grease, dirt and other foreign matter, sand papering and knotting with ready mixed paint of approved brand and manufacture (Narolac/Asian paints) complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Malkhana, Royalty, Octroi, toll tax, Sale Tax, GST or any taxes imposed by the Government	646.70 Square meter			Per Square meter	
3	Painting two or more coats (excluding priming coat) on new concrete / masonry / plaster surface with enamel paint of approved brand and manufacture (Narolac/Asian or equivalent paints) and of approved shade brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Malkhana, Royalty, Octroi, toll tax, Sale Tax, GST or any taxes imposed by the Government	190.27 Square meter			Per Square meter	
4	Finishing wall with weather proofing exterior grade emulsion of approved brand and manufacture (Apex exterior) and of approved shade on undecorated surfaces (two or more coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, other foreign matter and sand papered smooth including applying of putty as required for making the surface smooth complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Malkhana, Royalty, Octroi, toll tax, Sale Tax, GST or any taxes imposed by the Government	439.42 Square meter			Per Square meter	
TOTAL						


 Executive Engineer,
 HPPWD Division,
 Kotla Behar.

SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 4,61,052/-
 Earnest Money :-Rs.10000/-
 Time Limit :-Three Months.
 Name of work:- Restoration of Rain damages on Chambli Swana road Km 0/0 to 4/00 (SH):- C/o wire Crate at RD. 1/705 to 1/735).

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	64.80 Cubic metre			Per Cubic metre	
2	Providing and laying of boulder apron Gabion wall laid in wire crates with 4mm (four millimeter) dia GI wire conforming to IS-280 and IS-4826 in 100mmx100mm (One hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10 (Ten) per cent extra for laps and joints laid with stone boulders weighing not less than 40kg (Forty kilogramme) each as per drawing and MORD technical specifications Clause 1301 and as per direction and the entire satisfaction of the Engineer-in-Charge including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	162.00 Cubic metre			Per Cubic metre	
	TOTAL					


 Executive Engineer,
 HPPWD Division,
 Kotla Behar.

SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 4,82,334/-
Earnest Money :- Rs. 10000/-

Time Limit :- Three Months.

Name of work:- Restoration of Rain damages on chanour Tiamal Sheetla Mandir road Km 2/0 to 10/495 (SH:- C/o R-wall in C.C 1:5:10 and wire Crate at RD. 6/915 to 6/930).

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	39.38 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement to five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	73.80 Cubic metre			Per cubic metre	
3	Providing and laying of boulder apron Gabion wall laid in wire crates with 4mm (four millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm (One hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10 (Ten) per cent extra for laps and joints laid with stone boulders weighing not less than 40kg (Forty kilogramme) each as per drawing and MORD technical specifications Clause 1301 and as per direction and the entire satisfaction of the Engineer-in-Charge including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	81.00 Cubic metre			Per Cubic metre	
	TOTAL					


Executive Engineer,
HPPWD Division,
Kotla Behar.

SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 1,84,397/-
 Earnest Money :-Rs. 4000/-
 Time Limit :- Two month

Name of work:- A/R & M/O of link road from Shantla to Bhudwar via Sai road Km. 0/0 to 3/300 (SH: Pretreatment to shoulder in slushy reaches).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	24.48 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	12.24 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.24 Cubic metre			Per Cubic metre	
4	Providing and laying of inter locking concrete paver blocks make of NTC/NITCO/HPPWD approved having thickness 80mm (eighty millimeter) Grade M-40 IS Code-15658:2006 and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	38.40 Square metre			Per square metre	

5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2.4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government	0.96 Cubic metre			Per Cubic metre
TOTAL					


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.