



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

Dated 19.07.2023

No.-PW/OSDN/ Tender-NIT/2023-24 5164.74

To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:- Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate

Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, H.P.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140

Fax No. 01904-255740

Certificate

Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2023-24 5164-74 dated
19.07.2023 is very urgent nature. So may be uploaded on Departmental
website in public interest please.

**Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh**

Schedule of quantity

Name of Work: Restoration of rain damages on link road from Nirmand to Jehad via Ambika Mata temple Nirmand km. 0/00 to 4/435 (SH:-C/O wire crated B/Wall at RD. 2/480 to 2/515)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:- Earnest Money Time	AMOUNT		
				Figures	Words				
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	27.30	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		10869.00		
2	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the deopartment free of cost)	100.80	Cubic Metre	1500.00	Rupees One Thousand Five Hundred Only		151200.00		
Total in Figures							162069.00		
Rate quoted by contractor +/-				Percent					
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

(2)

Schedule of quantity

Schedule of quantity						
Name of work:- Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP, (Sub Head:- Removal of slips and construction of unlined drain between km. 0/00 to 1/700)				Estimated cost:- Rs.205884.00 Earnest Mony:- Rs. 4500.00 Time :- One month.		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in all kinds of soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto all leads and lifts as per Technical Specification Clause 307, including carriage of materials in all leads and lifts as per entire satisfaction of the Engineer-In-Charge complete.	900.000	Per Running Metre	25.90	Rupees twenty five and paise ninety only.	23310.00
2	Removal of landslides /slip clearance. Removal of land slide in hilly area in all kinds of soil by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	1521.450	Cubic Metre	120.00	Rupees One Hundred & Twenty Only	182574.00
Total in Figures						205884.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in workds						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Noida.

3

Schedule of quantity						
Name of work:- Improvement of identified black spots by providing corrective measures on Nore to Wazir Bowali road km. 0/00 to 37/00.				Estimated cost:-		497907.00
(SH):- Improvement of narrow curves in km. 2/030 to 2/090				Earnest Money		10000
				Time		One month
Sl. No.	Description of work	Qty.	Unit	Figures	RATE Words	AMOUNT
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 272.24 cum. In all cases, @ Rs. 300/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2094.16	Cubic Metre	237.76	Rupees Two Hundred & Thirty Seven - Paise Seventy Six Only	497907.00
Total in Figures						497907.00
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD Mirmand.

Schedule of quantity

Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH:- C/O B/Wall at RD 0/930 to 0/960.									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
				Time				Earnest Money	
				Three months				AMOUNT	
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	11.60	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	4619.00			205981.00
2	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.40	Cubic Metre	4193.20	Rupees Four Thousand One Hundred & Ninety Three - Paise Twenty Only	22643.00			
3	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	37.80	Cubic Metre	4563.10	Rupees Four Thousand Five Hundred & Sixty Three - Paise Ten Only	172485.00			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	6234.00			
Total in Figures									205981.00
Rate quoted by contractor +/-									
quoted rate in figure									
Quoted rate in words									


 Executive Engineer,
 Outer Sagaj Division,
 HPPWD Nirmand.

Schedule of quantity

Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH:- C/O B/Wall at RD 1/00 to 1/025).									
Sl. No.	Description of work	Qty.	Unit	RATE i/c GST & all taxes		Estimated cost:- Earnest Money	Time	Three months	AMOUNT
				Figures	Words				
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	19.25	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only				7664.00
2	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.88	Cubic Metre	4193.20	Rupees Four Thousand One Hundred & Ninety Three - Paise Twenty Only				33042.00
3	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	90.56	Cubic Metre	4563.10	Rupees Four Thousand Five Hundred & Sixty Three - Paise Ten Only				413234.00
4	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only				6234.00
Total in Figures									460174.00
Rate quoted by contractor +/-					Percent				
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Immand.

Schedule of quantity

Schedule of quantity						
Name of Work:- Restoration of rain damages on Guhatan to Baloo Balerh road km. 0/00 to 2/500 (SH-C/O wire crated B/Wall at RD. 0/275 to 0/290)				Estimated cost:-		316289.00
				Earnest Money		7000
				Time		One month
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	16.50	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	2944.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	11.70	Cubic Metre	398.20	Rupees Three Hundred & Ninety Eight - Paise Twenty Only	4659.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and I.S.4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders of approved quality weighing not less than 25 kg each as per drawing and technical specifications Clause1301complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	113.40	Cubic Metre	2722.10	Rupees Two Thousand Seven Hundred & Twenty Two - Paise Ten Only	308686.00
Total in Figures						316289.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Sagar Division,
 HP PWD, Shimla

7

Schedule of quantity

Schedule of quantity						
name of work:- Construction of road from Kalog to Tirmidhar km. 0/00 to 1/420 under SCSP. (Sub Head:- Providing and laying kharanja stone soling in slushy reaches between km. 0/600 to 1/400)				Estimated cost:- Rs.478464.00 Earnest Mony:- Rs. 10000.00 Time :- Three months.		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	1675.00	Square metre	1.90	Rupees One - Paise Ninety Only	3183.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub grade including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	1675.00	Square metre	13.75	Rupees Thirteen - Paise Seventy Five Only	23031.00
3	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 150mm spread thickness(finished work including materials and labour) and as per directions of the Engineer-In-Charge including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	251.25	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	452250.00
Total in Figures						478464.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in workds						

Executive Engineer,
Outer Seraj Division,
HPPWD, Mirmand.

Schedule of quantity

Name of work:-Periodic Maintenance of Nore to Luhri road KM. 0/0 to 65/765 (SH:- Providing surface correction with WBM G-III in km 11/00 to 12/00 and 18/00 to 19/00) for the year 2023-24					Estimated cost:-	
					Earnest Money	8000
					Time	One month
Sl. No.	Description of work	Qty.	Unit	Figures	RATE Words	AMOUNT
1	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 405, Grade-III A. By mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	110.72	Per Cubic Metre	2788.70	Rupees Three Thousand two Hundred fifty eight and twenty six Only	308765.00
2	Providing and applying priming coat with bitumen emulsion (SS-1) using bitumen distributor at the rate of 0.85 kg. (Zero point eight five Kilogramme) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications clause of 502 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	1409.10	Per Square Metre	62.50	Rupees sixty eight and paise sixty nine only.	88069.00
Total in Figures						396834.00
	Rate quoted by contractor +/-			Percent		
	quoted rate in figure					
	Quoted rate in words					


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Harmand.

9

SCHEDULE OF QUANTITY

Name of work :- R.R. damages on various roads under Nirmand Sub-Division. (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on various roads under Urtoo Section .)

Estimated Cost Rs. 153900

Earnest Money Rs.4000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	300.00			Per Hour	
					Total	

22

Executive Engineer,
Outer Serai Division,
HP. PWD, Nirmand.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchra drain and removal of slips on various roads under Nirmand and Urtoo Section)

Estimated Cost Rs. 475000.00
Earnest Money Rs. 10000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and construction of road side kutchra drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	380.00			Per Hour	
					Total	


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Nirmand.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00. (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00. .)

Estimated Cost Rs. 102600
Earnest Money Rs.4000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	200.00			Per Hour	
					Total	


 Executive Engineer,
 Outer Seraj Division,
 HP. PW/D/Nirmand.

12

Name of work :- Restoration of rain damages on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00.)

Estimated Cost Rs. 250000.00
 Earnest Money Rs. 5000/-
 Time :- One month.

SCHEDULE OF QUANTITY

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and construction of road side kutchha drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	200.00			Per Hour	
					Total	

21

Executive Engineer,
 Outer Seraj Division,
 HP, PW, Nirmand.


73

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Arsu Section)

Estimated Cost Rs. 250000.00
Earnest Money Rs. 5000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and construction of road side kutchha drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	200.00			Per Hour	
					Total	


Executive Engineer,
Outer Seraj Division,
HPPWD, Nirmand.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Bagipul Section)

Estimated Cost Rs. 250000.00
Earnest Money Rs. 5000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and construction of road side kutchha drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	200.00			Per Hour	
					Total	

22
Executive Engineer,
Outer Seraj Division,
HPPWD, Nirmand.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Bagipul Section) Job 2

Estimated Cost Rs. 187500.00
Earnest Money Rs. 4000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and construction of road side kutchha drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	150.00			Per Hour	
					Total	


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutcha drain and removal of slips on various roads under Arsu Section) Job 2

Estimated Cost Rs. 187500.00
Earnest Money Rs. 4000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and constructionm of road side kutcha drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	150.00			Per Hour	
					Total	

20 -

Executive Engineer,
Outer Seraj Division,
HPPWD, Nirmand.

17

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Neether Sub-Division. (SH:- Deployment of JCB for construction of road side kutchra drain and removal of slips on various roads) Job 2

Estimated Cost Rs. 125000.00
Earnest Money Rs. 3000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and constructionm of road side kutchra drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	100.00			Per Hour	
					Total	


Executive Engineer,
Outer Seraj Division,
HPPWD, Mirmand.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Neether Sub-Division (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on various roads.)

Estimated Cost Rs. 102600

Earnest Money Rs.4000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	200.00			Per Hour	
					Total	


 Executive Engineer,
 Outer Seraj Division,
 HP. PWD, Noida.

Schedule of quantity

Name of work:-A/R & M/O to Judge residence at Anni. (SH:- P/L interlocking paver blocks flooring, painting and grating on U-shape drain etc)		Estimated cost:-		340348.00	
		Earnest Money		7000	
		Time		One month	
Sl. No.	Description of work	Qty.	Unit	RATE	
				Figures	Words
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	17.89	Per Cubic Metre	5424.85	Rupees Five Thousand Four Hundred & Twenty Four - Paise Eighty Five Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.02	Per Cubic Metre	5954.35	Rupees Five Thousand Nine Hundred & Fifty Four - Paise Thirty Five Only
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	175.95	Per Square Metre	774.05	Rupees Seven Hundred & Seventy Four - Paise Five Only
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	382.80	Per KG	107.45	Rupees One Hundred & Seven - Paise Forty Five Only
5	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	122.88	Per Square Metre	73.85	Rupees Seventy Three - Paise Eighty Five Only
6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	45.81	Per Square Metre	89.90	Rupees Eighty Nine - Paise Ninety Only
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade One or more coats on old work including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	96.48	Per Square Metre	53.85	Rupees Fifty Three - Paise Eighty Five Only
8	Distemping with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade Old work (one or more coats) including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	243.95	Per Square Metre	35.45	Rupees Thirty Five - Paise Forty Five Only

Signature of Tenderer with seal

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchra drain and removal of slips on various roads under Nirmand Sub-Division) Job NO. 3

Estimated Cost Rs. 437500.00
Earnest Money Rs. 10000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and construction of road side kutchra drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	350.00			Per Hour	
					Total	


Executive Engineer,
Outer Serai Division,
HPPWD, Nirmand.

21

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Nirmand Sub-Division) *Is ok*

Estimated Cost Rs. 187500.00
Earnest Money Rs. 4000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and constructionm of road side kutchha drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	150.00			Per Hour	
					Total	

22
Executive Engineer,
Outer Seraj Division,
HPPWD, Nirmand.

Schedule of quantity

Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH:- C/O R/Wall at RD 0/260 to 0/272: 97264 x 0/272)									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
								Earnest Money	Time
								Three months	AMOUNT
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	19.32	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only				473428.00
2	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	24.00	Cubic Metre	4733.40	Rupees Four Thousand Seven Hundred & Thirty Three - Paise Fourty Only				113602.00
3	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	73.02	Cubic Metre	4563.10	Rupees Four Thousand Five Hundred & Sixty Three - Paise Ten Only				333198.00
4	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	30.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only				9351.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	9.00	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only				9585.00
Total in Figures									473428.00
Rate quoted by contractor +/-						Percent			
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Demand.

Schedule of quantity

Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH- C/O R/Wall at RD)									
06/06/2023. 07250 to 07262									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
								Earnest Money	Three months
								Time	AMOUNT
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	19.32	Cubic Metre	398.15			Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		7692.00
2	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	24.00	Cubic Metre	4733.40			Rupees Four Thousand Seven Hundred & Thirty Three - Paise Fourty Only		113602.00
3	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	73.02	Cubic Metre	4563.10			Rupees Four Thousand Five Hundred & Sixty Three - Paise Ten Only		333198.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	40.00	Each	311.70			Rupees Three Hundred & Eleven - Paise Seventy Only		12468.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	9.00	Cubic Metre	1065.00			Rupees One Thousand & Sixty Five Only		9585.00
				Total in Figures					476545.00
				Rate quoted by contractor +/-		Percent			
				quoted rate in figure					
				Quoted rate in workds					


 Executive Engineer,
 Outer Social Division,
 HPPWD, Nirmaland.



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740



NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **26.07.2023** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **25.07.2023** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF** failing which no tender form will be issued to him.

Job No	Name of work	Estimated cost	Earnest Money	Time	Co ter fc
1	Restoration of rain damages on link road from Nirmand to Johad via Ambika Mata temple Nirmand km. 0/00 to 4/435 (SH:-C/O wire crated B/Wall at RD. 2/480 to 2/515)	162069.00	4000.00	Two months	Rs.
2	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP. (Sub Head:- Removal of slpis and construction of unlined drain between km. 0/00 to 1/700)	205884.00	4500.00	One month	Rs..
3	Improvement of identified black spots by providing corrective measures on Nore to Wazir Bowali road km. 0/00 to 37/00, (SH:- Improvement of narrow curves in km. 2/030 to 2/090)	497907.00	10000.00	One month	Rs.

4	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH:- C/O B/Wall at RD 0/930 to 0/960).	205981.00	5000.00	Three months	Rs.3.
5	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH:- C/O B/Wall at RD 1/00 to 1/025)	460174.00	10000.00	Three months	Rs.3.
6	Restoration of rain damages on Guhatan to Baloo Balerh road km. 0/00 to 2/500 (SH:-C/O wire crated B/Wall at RD. 0/275 to 0/290)	316289.00	7000.00	One month	Rs.3.
7	Construction of road from Kalog to Tirmidhar km. 0/00 to 1/420 under SCDP, (Sub Head:- Providing and laying kharanja stone soling in slushy reaches between km. 0/600 to 1/400)	478464.00	10000.00	Three months	Rs.3.
8	Periodic Maintenance of Nore to Lohri road KM. 0/0 to 65/765 (SH:- Providing surface correction with WBM G-III in km 11/00 to 12/00 and 18/00 to 19/00) for the year 2023-24	396834.00	8000.00	Two months	Rs.3.
9	R.R. damages on various roads under Nirmand Sub-Division. (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on various roads under Urtoo Section .)	153900.00	4000.00	One month	Rs.3.
10	Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Nirmand and Urtoo Section)	475000.00	10000.00	One month	Rs.3.
11	Restoration of rain damages on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00. (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00. .)	102600.00	4000.00	One month	Rs.3.
12	Restoration of rain damages on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on Pazenda Shamani road km. 0/00 to 5/300 and Nauni to Tirmidhar road km. 0/00 to 2/00.)	250000.00	5000.00	One month	Rs.3.
13	Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Arsu Section)	250000.00	5000.00	One month	Rs.3.
14	Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Bagipul Section)	250000.00	5000.00	One month	Rs.3.
15	Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kutchha drain and removal of slips on various roads under Bagipul Section) Job2	187500.00	4000.00	One month	Rs.3.

16	Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kuteha drain and removal of slips on various roads under Arsu Section) Job 2	187500.00	4000.00	One month	Rs.35
17	Restoration of rain damages on various roads under Neether Sub-Division. (SH:- Deployment of JCB for construction of road side kuteha drain and removal of slips on various roads) Job 2	125000.00	3000.00	One month	Rs.35
18	Restoration of rain damages on various roads under Neether Sub-Division. (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on various roads .)	102600.00	3000.00	One month	Rs.35
19	A/R & M/O to Judge residence at Anni. (SH:- P/L interlocking paver blocks flooring, painting and grating on U-shape drain etc)	3406348.00	7000.00	One month	Rs.35
20	Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kuteha drain and removal of slips on various roads under Nirmand Sub-Division) Job NO. 3	437500.00	10000.00	One month	Rs.35
21	Restoration of rain damages on various roads under Nirmand Sub-Division. (SH:- Deployment of JCB for construction of road side kuteha drain and removal of slips on various roads under Nirmand Sub-Division)	187500.00	4000.00	One month	Rs.35
22	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH:- C/O R/Wall at RD 0/264 to 0/276.	473428.00	5000.00	Three months	Rs.35
23	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCDP (SH:- C/O R/Wall at RD 0/250 to 0/262..	476545.00	5000.00	Three months	Rs.35

HIM SUCHANA AVAM JAN SAMPARK