



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

Dated 22/7/23

No.-PW/OSDN/ Tender-NIT/2023-24

5408-18

To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.


**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**

Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740



NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **28.07.2023** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **27.07.2023** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

1	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/150 to 24/156.50)	494878.00	10000.00	One month
2	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/156.50 to 24/160)	266613.00	6000.00	One month
3	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O R/Walls at RD. 25/284.80 to 25/296)	496091.00	10000.00	One month
4	A/R & M/O link road to villge Sarapara km. 0/00 to 1/420 (SH:- Earth filling behind abutments of RCC Slab Culvert at RD 0/450)	191349.00	4000.00	One month
5	Restoration of rain damages on Nore to Wazir Bowali road km. 0/00 to 37/00 (Sub Head:- Construction of R/Wall at RD. 18/780 to 18/813)	470820.00	10000.00	Two months

6	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD. 3/762 to 3/782.80. UNDER BASP	432165.00	10000.00	Two months
7	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD. 4/545 to 4/559. UNDER BASP	432165.00	10000.00	Two months
8	Construction of Link road from Moin to Gothna km 0/00 to 2/600 (SH:-Balance work of F/C 5/7 mtrs wide in km 2/240 to 2/375)	464794.00	10000.00	One month
9	Construction of Link road from Moin to Gothna km 0/00 to 2/600 (SH:-Balance work of F/C 5/7 mtrs wide in km 2/375 to 2/465)	493696.00	10000.00	One month
10	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.4/495 to 4/505). UNDER BASP	157914.00	10000.00	One month
11	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.4/597 to 4/614). UNDER BASP	413110.00	10000.00	One month
12	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.5/420 to 5/432). UNDER BASP	432619.00	10000.00	One month
13	Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/975 to 2/090)	450421.00	10000.00	Three months
14	Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 2/090 to 2/170)	494934.00	10000.00	Three months
15	Restoration of rain damages on various roads under Dalash Sub-Division. (SH:- Deployment of JCB for construction of road side kutcha drain and removal of slips on various roads under Dalash Sub-Division) Job No. 2	437500.00	10000.00	One month

HIM SUCHANA AVAM JAN SAMPARK


 Executive Engineer
 Outer Seraj Division
 H.P PWD, Nirmand
 on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140
Fax No. 01904-255740

Certificate

**Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2023-24- 5408-18 dated
22.07.2023 is very urgent nature. So may be uploaded on Departmental
website in public interest please.**


**Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh**

Schedule of quantity
Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/150 to 24/156.50)

Executive Engineer
Outer Sanjay Division

Schedule of quantity									
Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/156.50 to 24/160)									
				Estimated cost:-		266613.00			
				Earnest Money		6000			
				Time		One month			
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	AMOUNT	
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	10.68	Cubic Metre			327.60	Rupees Three Hundred & Twenty Seven - Paise Sixty Only	3499.00	
	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	11.83	Cubic Metre			524.10	Rupees Five Hundred & Twenty Four - Paise Ten Only	6200.00	
2	Providing and Laying plain cement concrete 1:3:6 (one cement : three sand : six graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	40.29	Cubic Metre			6185.60	Rupees Six Thousand One Hundred & Eighty Five - Paise Sixty Only	249218.00	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.25	Cubic Metre			1322.29	Rupees One Thousand Three Hundred & Twenty	6942.00	
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.00	Each			377.00	Rupees Three Hundred & Seventy Seven Only	754.00	
				Total in Figures					
				Rate quoted by contractor +/-					
quoted rate in figure				Percent		266613.00			
Quoted rate in workds									

Schedule of quantity

Schedule of quantity									
Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O R/Walls at RD. 25/284.80 to 25/296)									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Estimated cost:- Earnest Money	Time	One month
				Words					
				AMOUNT					
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	16.80	Cubic Metre	327.60	Rupees Three Hundred & Twenty Seven - Paise Sixty Only	5504.00			
	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	19.71	Cubic Metre	524.10	Rupees Five Hundred & Twenty Four - Paise Ten Only	10330.00			
2	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.05	Cubic Metre	5313.47	Rupees Five Thousand Three Hundred & Thirteen - Paise Forty Seven Only	32146.00			
	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	71.46	Cubic Metre	6070.70	Rupees Six Thousand & Seventy - Paise Seventy Only	433812.00			
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.61	Cubic Metre	1364.83	Rupees One Thousand Three Hundred & Sixty Four - Paise Eighty Three	9022.00			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	14.00	Each	376.90	Rupees Three Hundred & Seventy Six - Paise Ninety Only	5277.00			
	Total in Figures					496091.00			
	Rate quoted by contractor +/-				Percent				
	quoted rate in figure								
	Quoted rate in works								

Executive Engineer
Outer Saraj Division
HPPWD, Mirmand

Schedule of quantity							
Sl. No.		Description of work	Qty.	Unit	Figures	Estimated cost:-	
						Earnest Money	
						Time	
						One month	
						AMOUNT	
Name of Work:- A/R & M/O link road to villge Sarapara km. 0/00 to 1/420 (SH:- Earth filling behind abutments of RCC Slab Culvert at RD 0/450)							
1		Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	540.00	Cubic Metre	354.35	Rupees Three Hundred & Fifty Four - Paise Thirty Five Only	191349.00
							191349.00
Rate quoted by contractor +/-							
						Percent	
		quoted rate in figure					
		Quoted rate in workds					

Executive Engineer
Outer Seraj Division
Muzaffargarh, Nihmand

Schedule of quantity


Name of Work: Restoration of rain damages on Nore to Wazir Bowali road km. 0/00 to 37/00 (Sub Head:- Construction of R/Wall at RD. 18/780 to 18/813)									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
								Earnest Money	Time
								Two months	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	21.78	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only				470820.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	33.66	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only				13402.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	11.21	Cubic Metre	4278.50	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only				47962.00
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	48.77	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only				212632.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	61.78	Cubic Metre	3023.00	Rupees Three Thousand & Twenty Three Only				186761.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.80	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only				6177.00
Total in Figures									470820.00
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

Schedule of quantity									
Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD. 3/762 to 3/782.80). UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
								Earnest Money	Time
				AMOUNT					
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical.Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	14.56	Cubic Metre	178.40			Rupees One Hundred & Seventy Eight - Paise Forty Only	432165.00	10000.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	68.43	Cubic Metre	398.15			Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	27245.00	
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.78	Cubic Metre	4254.50			Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only	20337.00	
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	87.36	Cubic Metre	4359.90			Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	380881.00	
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each	311.70			Rupees Three Hundred & Eleven - Paise Seventy Only	6234.00	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.60	Cubic Metre	1265.00			Rupees One Thousand Two Hundred & Sixty Five Only	759.00	
Total in Figures								438054.00	
Rate quoted by contractor +/-				Percent					
Quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Mirmand.

Schedule of quantity									
Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD. 4/545 to 4/559.					Estimated cost:-		432165.00		
UNDER BASP					Earnest Money		10000.00		
					Time		Two months		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	30.38	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only		5420.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	56.28	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		22408.00		
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	3.22	Cubic Metre	4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only		13699.00		
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	87.80	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only		382799.00		
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	15.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only		4676.00		
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.50	Cubic Metre	1265.00	Rupees One Thousand Two Hundred & Sixty Five Only		3163.00		
Total in Figures							432165.00		
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmal.

Schedule of quantity

Name of Work: Construction of Link road from Moin to Gothna km 0/00 to 2/600 (SH:-Balance work of F/C 5/7 mtrs wide in km 2/240 to 2/375)					Estimated cost:-		464794.00
					Earnest Money		10000
					Time		One month
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT
					Words		
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 315.51 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on porta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2201.25	Cubic Metre	211.15	Rupees Two Hundred & Eleven - Paise Fifteen Only		464794.00
Total in Figures							464794.00
Rate quoted by contractor +/-						Percent	
	quoted rate in figure						
	Quoted rate in workds						


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Noida.

Schedule of quantity									
Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.4/495 to 4/505).									
UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	AMOUNT	
								Time	Two months
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	6.00	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	1070.00		Estimated cost:- Earnest Money 4000.00	157914.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	15.30	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	6092.00			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.30	Cubic Metre	4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only	9785.00			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	31.40	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	136901.00			
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	3117.00			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.75	Cubic Metre	1265.00	Rupees One Thousand Two Hundred & Sixty Five Only	949.00			
Total in Figures									157914.00
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in workds									


22

Executive Engineer,
Outer Seraji Division,
HPPW/D, Mirmand.

Schedule of quantity									
Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.4/497 to 4/614).									
UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
				Time				Earnest Money	
								Two months	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	11.90	Cubic Metre			178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only		2123.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	55.93	Cubic Metre			398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		22269.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.31	Cubic Metre			4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only		31100.00
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	80.40	Cubic Metre			4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only		350536.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each			311.70	Rupees Three Hundred & Eleven - Paise Seventy Only		6234.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.67	Cubic Metre			1265.00	Rupees One Thousand Two Hundred & Sixty Five Only		848.00
Total in Figures									413110.00
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in words									


 Executive Engineer,
 Outer Setai Division,
 HPPWD Mirmand.

Schedule of quantity									
Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.5/420 to 5/432).									
UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	26.04	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		4646.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	48.24	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		19207.00		
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.76	Cubic Metre	4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only		11742.00		
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	89.70	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only		391083.00		
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	12.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only		3740.00		
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.74	Cubic Metre	1265.00	Rupees One Thousand Two Hundred & Sixty Five Only		2201.00		
Total in Figures							432619.00		
Rate quoted by contractor +/-				Percent					
Quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Mirmand.

Schedule of quantity						
Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/975 to 2/090)				Estimated cost:- Earnest Money		450421.00
				Time		10000
				Three months		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 282.35cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1689.12	Cubic Metre	266.66	Rupees Two Hundred & Sixty Six - Paise Sixty Six Only	450421.00
Total in Figures						450421.00
Rate quoted by contractor +/-						
Quoted rate in figure				Percent		
Quoted rate in words						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Dalash Sub-Division. (SH:- Deployment of JCB for construction of road side kutchra drain and removal of slips on various roads under Dalash Sub-Division) Job No. 2

Estimated Cost Rs. 437500.00
Earnest Money Rs. 10000.00
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips, snow and construction of road side kutchra drain etc from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	350.00			Per Hour	
					Total	


Executive Engineer,
Outer Seraj Division,
HP. PWD Nirmand.