

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2023-24-

3868-70

Dated:- 4/7/23

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 19.07.2023 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 18.07.2023 upto 1:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.


Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Dharmehar Tarswan Dragar Garhgawn road Km 0/0 to 5/250. (SH:- Construction of 900mm dia metre RCC hume pipe culvert alongwith wing walls at R.D. 0/320).	3,18,341/-	6,400/-	350/-	Three months
2	Construction of Tikkar Sarni road Km 0/0 to 3/720. (SH:- Construction of 900mm dia metre RCC hume pipe culvert alongwith wing walls at R.D. 3/500)	2,85,338.14	5,700/-	350/-	Three months
3	BSP/2023/116, C/O (Construction of) and widening of road from Ropa to Kashla Hurang Mohal. (SH:- ROFD/ Widening of road at R.D. 0/180 to 0/225, 0/315 to 0/390 & 0/555 to 0/570)	1,23,869/-	2,500/-	350/-	One month
4	BSP/2023/112, Maintenance and Widening of road Baghan Nallah to village Chhuchal road Mohal. (SH:- Widening of road at R.D. 0/090 to 0/120, 0/180 to 0/210, 0/405 to 0/435, 0/675 to 0/705 & 0/825 to 0/870).	1,19,948/-	2,400/-	350/-	One month
5	BSP/2023/113, Maintenance of and Widening of road Swar to Farehar road Mohal. (SH:- ROFD/ Widening of road at R.D. 0/0 to 0/075, 0/270 to 0/300, 0/345 to 0/360, 0/495 to 0/525, 0/570 to 0/600, 0/690 to 0/720, 0/840 to 0/855 & 1/435 to 1/465)	1,20,374/-	2,400/-	350/-	One month
6	BSP/2023/120, C/O (Construction of) and widening of road Ahlang to Hurang road Mohal. (SH:- ROFD/ Widening of road at R.D. 2/0 to 2/165)	1,23,390/-	2,500/-	350/-	One month
7	VKV/2022/2452, C/O Road from Fiyun Gala Sudhar road to village Bulang. (SH:- Hiring of Hydraulic excavator cum loader for widening of road from Km 1/500 to 2/0)	99,000/-	2,000/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. The intending Contractors are requested to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 318341.00

Earnest Money Rs:- 6400.00

Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work:- Construction of Dharmehar Tarswan Dragar Gangawn road Km. 0/0 to 5/250. (Sub Head:- Construction of 900mm diameter RCC hume pipe culvert along with wing walls at R.D. 0/320.)

SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Excavation in soil in hilly area by manual means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	4.58	Per cubic metre	218.30	1000.00	Rupees One Thousand Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	42.56	Per cubic metre	485.30	20654.00	Rupees Twenty Thousand Six Hundred Fifty Four Only
3	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.28	Per cubic metre	5248.30	11966.00	Rupees Eleven Thousand Nine Hundred Sixty Six Only
4	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	28.40	Per cubic metre	5751.25	163336.00	Rupees One Lakh Sixty Three Thousand Three Hundred Thirty Six Only
5	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.79	Per cubic metre	5860.95	74962.00	Rupees Seventy Four Thousand Nine Hundred Sixty Two Only
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3671.50	25701.00	Rupees Twenty Seven Hundred One Only

Contract No.:

Name of Bidder/Bidding Firm/ Company:

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5958.65	2920.00	Rupees Nine Hundred Twenty Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	12.00	Each	291.70	3500.00	Rupees Three Thousand Five Hundred Only
9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	9.48	Per cubic metre	1508.60	14302.00	Rupees Fourteen Thousand Three Hundred Two Only
Total in Figure					318341.00	Rupees Three Lakh Eighteen Thousand Three Hundred Forty One Only
Quoted Rate in Words		Rupees Three Lakh Eighteen Thousand Three Hundred Forty One Only				


 Executive Engineer,
 Mandi Division No. 1,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 285338.14
Earnest Money Rs:- 5700.00

Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work:- Construction of Tikkar Sami road Km. 0/0 to 3/720. (Sub Head:- Construction of 900mm diameter RCC hume pipe culvert along with wing walls at R.D. 3/500.)

Contract No.:

Name of Bidder/Bidding Firm/ Company:

SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Excavation in soil in hilly area by manual means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	1.91	Per cubic metre	218.30	416.95	Rupees Four Hundred Sixteen and Paise Ninety Five Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	40.49	Per cubic metre	485.30	19649.80	Rupees Nineteen Thousand Six Hundred Forty Nine and Paise Eighty Only
3	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.94	Per cubic metre	5229.40	10145.04	Rupees Ten Thousand One Hundred Forty Five and Paise Four Only
4	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	25.41	Per cubic metre	5731.40	145634.87	Rupees One Lakh Forty Five Thousand Six Hundred Thirty Four and Paise Eighty Seven Only
5	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	11.64	Per cubic metre	5839.85	67975.85	Rupees Sixty Seven Thousand Hundred Seventy Five and Paise Eighty Five Only

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3666.70	25666.90	Rupees Twenty Five Thousand Six Hundred Sixty Six and Paise Ninety Only
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5528.80	2709.11	Rupees Two Thousand Seven Hundred Nine and Paise Eleven Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.00	Each	303.20	3032.00	Rupees Thousand Thirty Two Only
9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	6.70	Per cubic metre	1508.60	10107.62	Rupees Ten Thousand One Hundred Seven and Paise Sixty Two Only
Total in Figure					285338.14	Rupees Two Lakh Eighty Five Thousand Three Hundred Thirty Eight and Paise Fourteen Only
Quoted Rate in Words		Rupees Two Lakh Eighty Five Thousand Three Hundred Thirty Eight and Paise Fourteen Only				


 Executive Engineer,
 Mandi Division No. I,
 H.P. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 123869.00

Earnest Money Rs:- 2500.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- BSP/2023/116, C/O (Construction of) and widening of road from Ropa to Kashla Hurang Mohal. (Sub Head:- ROFD/Widening of road at R.D. 0/180 to 0/225, 0/315 to 0/390 & 0/555 to 0/570.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	675.44	Per cubic metre	217.11	146845.00	Rupees One Lakh Forty Six Thousand Six Hundred Forty Five Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	37.96	Per cubic metre	600.00	-22776.00	Rupees Fifty Two Lakh Fifty Two Thousand Seven Hundred Seventy Six Only
Total in figure :					123869.00	Rupees One Lakh Twenty Three Thousand Eight Hundred Sixty Nine Only
Total in Words :		Rupees One Lakh Twenty Three Thousand Eight Hundred Sixty Nine Only				


Executive Engineer,
Mandi Division No-I,
HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 119948.00

Earnest Money Rs:- 2400.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- BSP/2023/112, Maintenance and Widening of road Baghan nallah to village Chhuchal road Mohal. (Sub Head:- Widening of road at R.D. 0/090 to 0/120, 0/180 to 0/210, 0/405 to 0/435, 0/675 to 0/705 & 0/825 to 0/870.).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	653.70	Per cubic metre	207.18	135434.00	Rupees One Lakh Thirty Five Thousand Four Hundred Thirty Four Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	25.81	Per cubic metre	600.00	-15486.00	Rupees Seventy Two Lakh Seventy Two Thousand Four Hundred Eighty Six Only
Total in figure :					119948.00	Rupees One Lakh Nineteen Thousand Nine Hundred Forty Eight Only
Total in Words :		Rupees One Lakh Nineteen Thousand Nine Hundred Forty Eight Only				

Executive Engineer,
Mandi Division No-I,
HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 120374.00
 Earnest Money Rs:- 2400.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- BSP/2023/113, Maintenance of and Widening of road Swar to Farehar road Mohal. (Sub Head:- ROFD/Widening of road at R.D. 0/0 to 0/075, 0/270 to 0/300, 0/345 to 0/360, 0/495 to 0/525, 0/570 to 0/600, 0/690 to 0/720, 0/840 to 0/855 & 1/435 to 1/465.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	674.68	Per cubic metre	197.35	133148.00	Rupees One Lakh Thirty Three Thousand One Hundred Forty Eight Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	21.29	Per cubic metre	600.00	-12774.00	Rupees Forty Eight Lakh Forty Eight Thousand Seven Hundred Seventy Four Only
Total in figure :					120374.00	Rupees One Lakh Twenty Thousand Three Hundred Seventy Four Only
Total in Words :						Rupees One Lakh Twenty Thousand Three Hundred Seventy Four Only


 Executive Engineer,
 Mandi Division No-I,
 HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 123390.00

Earnest Money Rs:- 2500.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- BSP/2023/120, C/O (Construction of) and widening of road Ahlang to Hurang road Mohal. (Sub Head:- ROFD/Widening of road at R.D. 2/0 to 2/165.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	685.89	Per cubic metre	209.01	143358.00	Rupees One Lakh Forty Three Thousand Three Hundred Fifty Eight Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No,1	33.28	Per cubic metre	600.00	-19968.00	Rupees Thirty Six Lakh Thirty Six Thousand Nine Hundred Sixty Eight Only
Total in figure :					123390.00	Rupees One Lakh Twenty Three Thousand Three Hundred Ninety Only
Total in Words :		Rupees One Lakh Twenty Three Thousand Three Hundred Ninety Only				


 Executive Engineer,
 Mandi Division No-I,
 HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 99000.00

Earnest Money Rs:- 2000.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- VKV/2022/2452, C/O Road from Fiyun Gala Sudhar road to village Bulang. (Sub Head:- Hiring of Hydraulic excavator cum loader for widening of road from Km. 1/500 to 2/0.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes including GST in Rs. P.	TOTAL AMOUNT with all taxes including GST in words.
1	Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, clearance of drains and catch pit/ dressing of berms in all kinds of soil and trimming of side slopes and disposing of earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etcetera happened during the course of hiring period shall be absolute responsibility of the contractor. The repair and spares including watch and ward of machines shall also be born by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per hour	1100.00	99000.00	Rupees Ninety Thousand Only
Total in figure :					99000.00	Rupees Ninety Thousand Only
Total in Words :		Rupees Ninety Nine Thousand Only				


Executive Engineer,
Mandi Division No-I,
HP. PWD, at Padhar.