

Himachal Pradesh
Public Works Department
PW-RD-GA-Tender-2023-24-
To

SSoy

dated:- 21-7-20


The Executive Engineer (IT Cell)
Nigam Bihar, Shimla-2.

Subject: - Tender notice.

Enclosed please find herewith the tender notice of work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter N. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest. i8o

DA:- Notice inviting tender & schedule of quantity.


Executive Engineer,
B&R Division, HPPWD,
Rohru.

Himachal Pradesh
Public Works Department
"NOTICE INVITING TENDERS"

Sealed item rate tender on form PWD 6&8 are invited by the Executive Engineer Rohru Division HPPWD, on behalf of Governor of H.P. for the following works from the approved and eligible contractors enlisted in HPPWD, So as to reach in this office as per time schedule given below:-

- | | |
|--|----------------------------------|
| 1.Date of receipt of applications for tender forms:- | 27.07.2023 upto 1:00PM |
| 2.Date of issue/sale of tender forms:- | 27.07.2023 upto 2:00PM to 3.00PM |
| 3.Date of receipt of tender:- | 28.07.2023 upto 3:30PM |
| 4.Date of opening of tender:- | 28.07.2023 upto 4:00PM |

Sr.No.	Name of Work.	Estt.Cost.	E/Money	Time.
1	RR Damaages to Junidhar Kutu road Km. 0/0 to 5/0 (SH:- C/O B/Wall at Rd. 2/405 to 2/445)	Rs. 467629/-	Rs. 10000/-	1Month.
2	RR Damaages to Junidhar Kutu road Km. 0/0 to 5/0 (SH:- C/O B/Wall at Rd. 2/690 to 2/720)	Rs.487907/-	Rs. 10000/-	1Months
3	RR Damages to various road under Rohru Section under Rohru Sub-Division (SH:Hiring of JCB for removal of slips at various RDs , maintenance of road and dressing of road surface)	Rs. 495000/-	Rs. 10000/-	450 hours
4	RR Damages to various road under Rohru Section under Rohru Sub-Division (SH:Hiring of Tipper for carriage of muck etc).	Rs. 98000/-	Rs. 2000/-	14 days

Certified that the tender mantioned in the notice is exigencies/emergency are urgent nature and in public interest.

Terms and conditions:-The tender doucument shellbe issued only to these contractors/firms who fulfill the following criteria and submit the following doucument with the application.

1. The Earnest-money for the above works should be submitted with the application for the purchase of the tender-documents.
2. The Contractors should quoted the rates of all the items in the tenders both in figures and words.
3. Income tax & GST No latest clearance certificate.
4. The contrs / firm shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The contractors should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

Executive Engineer,
B&R Division, HPPWD, Rohru

NO.: -PW-RD-GA.-Tender/2023-24 **5404-SS03**

Copy forwarded for information and wide publicity to:-

1. The Chief-Engineer(SZ), HPPWD, Shimla-2.
3. The S E 14th Circle HPPWD, Rohru
4. All the E.E.'s under 14th Circle, HPPWD, Rohru
5. All the A.E.'s working under this Division (B&R).
6. The Sub Divisional Magistrate, Rohru.
7. The B.D.O. Rohru and Chirgaon.
8. The Tehsildhar, Rohru/Chirgaon and Tikkar.
9. The Chairman, N.A.C. Rohru.
10. A/B. and D/B. in this Office.
11. Notice-Board.

Dated:- **21-7-2023**

Executive Engineer,
B&R Division, HPPWD, Rohru

Estimated Cost:-467629/-
E/Money:-10000/-
Time:- One Month

Schedule of Quantity

Name of Work:R/R damages on Junidhar Kurtu road km 0/0 to 5/0

Sub head :-c/o B/wall at RD 2/405 to 2/445

S No.	Name of work	Quantity	Rate	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	56.25		cum	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	28.35		cum	
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	140.62		cum	
Total					


Executive Engineer
B&R HPPWD Divn. Rohru

Schedule of Quantity

Name of Work:R/R damages on Junidhar Kuttu road km 0/0 to 5/0
Sub head :-c/o B/wall at RD 2/690 to 2/720

S No.	Name of work	Quantity	Rate	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	75.00		cum	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	37.50		cum	
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 Kg each as per drawing and technical specifications Clause 1301	140.62		cum	
Total					



Executive Engineer
B&R HPPWD Divn. Rohru

Schedule of Quantity


ESTIMATED COST:RS.495000/-
Earnest Money:-100000/-
TIME :-450 Hour.

Name of work :- R/R damage to various roads under Rohru section Sub- Division Rohru (S.H:-Hiring of JCB for removal of slips at various RDs maintenance of road and dressing of road surface)

Sr No.	Sub-Head and Item of works.	Quantity.	Rate in figures.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) front end loader 1 cum bucket capacity & 45 cum/hour including P.O.L. charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450.00		Per Hour	
Total:-					


Executive Engineer,
B&R Division HPPWD,
Rohru

Schedule of Quantity					Estimate Cost:-98000/-	Earnest Money :-2000/-	Time :- 14 Days
Name of Work:- R/R Damage to Various roads under Rohru section Sub Division Rohru . (SH:- Hiring of Tipper for carriage of muck etc.)					Rate in words, Unit	Amount	
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.				
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancilliary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	14.00			Per Day		
Total							


 Executive Engineer,
 B&R Division HPPWD,
 Rohru