

Himachal Pradesh  
Public Works Department  
**NOTICE INVITING TENDER**

Sealed tenders on item rates on PWD form 6&7 are hereby invited by the Executive Engineer, Tauni Devi Division, and HPPWD Tauni Devi for the following works. The tender shall be received in this office on or before 31.07.2023 up to 11:00 AM and the same shall be opened on the same day at 11:30 AM in the presence of the contractor /firms. The application for the issue of tender document shall be received on dated 27.07.2023 up to 1:30 PM and the tender form will be sold on cash payment (Non refundable) on dated 28.07.2023 from 11:00 AM to 3:00 PM.

Sr. No.	Name of Work	Estimated Cost (Rs.)	Earnest Money	Time limit	Cost of form
1.	R/R damages on various road under Sujanpur sub-Division ( Sh:- Hiring of JCB/front end loader for removal of slips/clearing of drain due to heavy rains ) ( Section -Chouri ).	195000/-	3900/-	Two months	350/-
2.	R/R damages on various road under Sujanpur Sub-Division ( Sh:- Hiring of JCB/front end loader for removal of slips/clearing of drain due to heavy rains ) ( Section -Patlander ).	442200/-	8800/-	Two months	350/-
3.	R/R damages on link road Kakkar to Bakkar Khad via Ghodlamber 0/00 to 2/200 ( SH:- C/O Breast wall at RD 1/125 to 1/150 )	381788/-	7700/-	Two months	350/-
4.	R/R damages on Hamirpur Sujanpur road km .2/600 to 18/300.( SH:- C/O R/wall at RD 10/960 to 10/973) (Deposit work )	243573/-	4900/-	Two months	350/-
5.	R/R damages on Hamirpur Sujanpur road km .2/600 to 18/300.( SH:- C/O R/wall at RD 13/570 to 13/576.50) (Deposit work )	188995/-	3800/-	Two months	350/-
6.	C/o link road to Ayurvedic Dispensary Ree to village Kuwall in G.P .Ree km .0/0 to 1/500 ( SH:- C/o B/wall at RD .0/060 to 0/080 ) ( Under OTMNP )	287910/-	5800/-	Two months	350/-
7.	R/R damages on Hamirpur Sujanpur road km .2/600 to 18/300. ( Sh:- C/O U-shape Drain at RD 7/205 to 7/315 ) . ( Deposit work )	213940/-	4300/-	Two months	350/-
8.	R/R damages on various road under Tauni Devi Sub-Division . ( SH:- Hiring of JCB/front end Loader for removal of slips /clearing of drain due to heavy rains ) . ( Section -1 and section -II )	481000/-	9600/-	Two months	350/-
9.	R/R damages on various road under Baghera section under sub Division Kakkar . ( SH:- Hiring of excavator cum loder for removal of slips, clearance of drain )	198000/-	4000/-	Two months	350/-
10.	R/R damages on various roads in Jangal Beri Section*under Sub Division Kakkar. ( SH:- Hiring of excavator cum loader for removal of slips, clearance of drain )	191400/-	3900/-	Two months	350/-
11.	C/o link road from Baghera Bridge to Harizan Basti Jol via Samouna Goushala km .0/00 to 1/200.( SH:- C/O R/wall at RD .0/712 to 0/761).( Under SCSP )	485789/-	9700/-	Two months	350/-
12.	C/o link road Kothi to Jolly km .0/0 to 2/500. ( SH:- C/O cement concrete pavement at RD .0/038 to 0/056, 0/141 to 0/165 and 0/206.50 to 0/269.50) ( Under OTMNP )	455696/-	9100/-	Two months	350/-
13.	C/O link road to village Khanpal km .0/0 to 1/0 ( SH:- C/O C.C causeway ,hume pipe culvert with wing walls etc.km 0/200 to 0/550 ) . ( Under OTMNP )	498697/-	10000/-	Two months	350/-
14.	R/R damages on various road under Kakkar Sub-Division . ( Sh:- C/O Un-lined surface drain and dressing of berms )	480300/-	9600/-	Two months	350/-
15.	R/R damages on various road under Kakkar Sub-Division . ( Sh:- Hiring of JCB/front end Loader for removal of slips/clearing of drain due to heavy rains ) .	499200/-	10000/-	Two months	350/-



16	R/R damages on Lambri Nalahi Asthota road km 0/00 to 6/00. ( SH:- C/O PCC Brest wall at RD 3/495 to 3/525) Deposit work	359860/-	7200/-	Two months	350/-
17	C/O link road from Nalahi Kangri via Asthota Sauran Da Gran road km 0/0 to 4/500 . ( SH:- C/O 900mm dia hume pipe culvert with wing wall at km 4/120) Under OTMNP	416864/-	8400/-	Two months	350/-
18	R/R damages on Barin Dhawal via Siswan Ghalot road km .0/00 to 5/00 ( SH:- C/O R/wall at RD .4/840 to 4/852 )	292427/-	6000/-	Two months	350/-
19	R/R damages on Barin Dhawal via Siswan Ghalot road km .0/00 to 5/00 ( SH:- C/O R/wall at RD .1/710 to 1/725 )	304871/-	6100/-	Two months	350/-
20	R/R damages on Khanauli-kheri-Bhatlamber-Dudla via Mahesqual road km 0/0 to 9/460 ( SH:- P/L interlocking concrete block pavement 50m long between km at RD 4/730 to 4/760 )	346113/-	7000/-	Two months	350/-
21	C/o link road from Chamarda to Harizan Basti Kudana ( Kalyana ) km .0/0 to 0/300 ( SH:- P/L C.C pavement Breast wall in km .0/130 to 0/230) (Under SCSP)	460911/-	9200/-	Two months	350/-
22	R/R damages on various road under Tauni Devi Sub-Division , HP-PWD ,Tauni Devi .( SH:- C/O Un-lined surface drain and dressing of berms) .	180220/-	4500/-	Two months	350/-
23	R/R damages on various road under Kakkar Sub Division. ( SH:- Hiring of JCB/front end loader ,for removal of slips /clearing of drain due to heavy rains ) .	499200/-	10000/-	Two months	350/-
24	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km 15/0 to 30/915 ( SH:- C/O PCC R/wall at RD 20/880 to 20/894.50 )	482761/-	9700/-	Two months	350/-
25	A/R & M/O on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km 0/0 to 30/915 ( SH:- C/O Brest wall at Rd .10/105 to 10/125)	220874/-	4400/-	Two months	350/-
26	R/R damages of Barara to Bakkar Khad via Patnoun road km 2/00 to 8/00 ( SH:- Imp of curves at RD 2/695 to 2/730 )	108325/-	2200/-	Two months	350/-
27	Special Repair to Bai Ashram at Sujanpur Tihra Distt .Hamirpur ( HP) ( SH:- P/F dismantled doors and windows etc ) ( Deposit work )	414091/-	8300/-	Two months	350/-
28	A/R & M/O various road under Tauni Devi Division , HP-PWD , Tauni Devi ( SH:- Supplying and stacking of dual direction delineators ) Job No.2	499200/-	10000/-	Two months	350/-
29	A/R & M/O various road under Tauni Devi Division , HP-PWD , Tauni Devi ( SH:- Supplying and fixing retro-reflectorised cautionary mandatory board etc.) Job No.2	496000/-	10000/-	Two months	350/-
30	P/L of vitrified tiles in cadet dorm of Jhelum hostel Sainik school Sujanpur Thira ( SH:- Levelling /rectification of floors ) .Deposit work	122941/-	2500/-	Two months	350/-
31	A/R & M/O NIT Muthan via Khas Gran km 0/0 to 3/885 ( SH:- C/O U-shape drain at RD 1/570 to 1/586 and P/L Paver block at RD 1/670 to 1/700)	438160/-	8800/-	Two months	350/-
32	C/o Govt. ITI Building at Sujanpur Tihra Distt. Hamirpur ( HP) ( SH:-P/F collapsible gate and painting etc.) Deposit work	159886/-	3200/-	Two months	350/-
33	C/o Govt. ITI Building at Sujanpur Tihra Distt. Hamirpur ( HP) ( SH:-P/F grilling work in existing windows ) . Deposit work	416010/-	8500/-	Two months	350/-
34	C/o Ambulance Jeepable standard road Lambara to Dhangota Brahmana . Km 0/0 to 2/00 ( SH:- C/O V-shape drain at RD 0/375 to 1/300 and M.S grating at RD 0/370 and 0/660 ) ( Under OTMNP)	376589/-	7500/-	Two months	350/-
35	C/O link road from Dhar to Drug Khad via Grauru km .0/0 to 2/00. ( SH:- P/L GSB at RD .0/000 to 0/500 ) . ( Under OTMNP )	493772/-	10000/-	Two months	350/-
36	C/O link road from Dhar to Drug Khad via Grauru km .0/0 to 2/00. ( SH:- P/L GSB at RD .0/500 to 1/00 ) . ( Under OTMNP )	493772/-	10000/-	Two months	350/-

37	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km .15/0 to 30/915. ( SH:- C/O B/wall at RD.19/990 to 19/996)	132510/-	2700/-	Two months	350/-
38	R/R damages on Kakkar to Chamb road km 0/0 to 4/100.( SH:- C/O Breast wall at RD 0/78 to 0/795 )	211483/-	4200/-	Two months	350/-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit documents with the application. The valid enlistment/ registration of contractor in appropriate class. Permanent Account Number (PAN) Earnest money in the shape of National saving certificate/ Time deposit Account in any of the Post office in H.P. / F.D.R. from any Nationalized Bank (i/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer. Other special terms and condition can be seen/obtain in this office on any working day. Any ambiguous /telegraphic conditional tenders by fax shall not be entertained /considered in any case. It is also certified that tenders are urgent work and required early completion.

Executive Engineer,  
Tauni Devi Division,  
HP:PWD., Tauni Devi

No.PW/TDD/GA/N.I.T./2023-24

6169-6299

Dated:- 24.07.2023


Copy forwarded for information & necessary action please:-

1. The Engineer-in-Chief, HP:PWD, Shimla.
2. The Chief Engineer (HZ), HP:PWD, Hamirpur.
3. The Superintending Engineer, 8<sup>th</sup> Circle, HP:PWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP:PWD.
5. The Deputy Commissioner, Hamirpur.
6. ✓ **The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, HP Shimla -2 for information and necessary action.**
7. The Tehsildar, Tauni Devi.
8. The B. D. O. Tauni Devi.
9. The Municipal Committee, Hamirpur.
10. All the Assistant Engineers working under this Division.
11. Accounts Branch/ Drawing Branch/ Notice Board.
12. Lok Mitra, Tauni Devi.
13. Various Contractors/ Firms.

Executive Engineer,  
Tauni Devi Division,  
HP:PWD., Tauni Devi

CERTIFICATE

Certified that the tender for job No. 1 to 38 are called vide this office letter No. PW/TDD/GA/2023-24-6169-6229 dated 24.07.2023 are an urgent nature and in public interest.

  
Executive Engineer,  
Tauni Devi Division,  
HP: PWD., Tauni Devi.




# **Schedule of Quantity**

**NAME OF WORK:-** Restoration of rain damages on various road under Sujapur Sub-Division. (Sft:- Hiring of JCB/Front end loader for removal of slips/clearing of drain due to heavy rains).(Section-Chour).

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (Front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiseling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	150.00			Per hour	
<b>Total</b>						

## **Terms and Condition**

1. The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
2. Nothing shall be paid for idle hours
3. All bear and tear and POL charges are to be born by the contractor.

  
 Executive Engineer,  
 Tannal Devi Division,  
 HPPWD, Tannal Devi

# **Schedule of Quantity**


**NAME OF WORK:-** Restoration of rain damages on various road under Sujapur Sub-Division. (SH:- Hiring of JCB/front end loader for removal of slips/clearing of drain due to heavy rains)-(Section-Parthander).

**Estimated Cost:-** Rs. 442000.00  
**Earnest Money:-** Rs. 8800.00  
**Time:-** Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	340.00			Per hour	
<b>Total</b>						

## **Terms and Condition**

- 1 The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- 2 Nothing shall be paid for idle hours
- 3 All bear and tear and POL charges are to be born by the contractor.

  
**Anand Gire**  
 Executive Engineer,  
 Tamil Devi Division,  
 HPPWD, Tamil Devi

# Schedule of Quantity

NAME OF WORK: Restoration of rain damages on link road Kakhar to Babbar Khud via Ghodiamber 0/00 to 2/200 (SH- Construction of Breast Wall at RD 1/125 to 1/150).

NAME OF WORK:- Restoration of rain damages on link road Rakkar to Bokkar Khud via Ghodlambar 0/00 to 2/200.(SH:- Construction of Breast Wall at RD 1/125 to 1/150).							Estimated Cost:-		Rs.381788.00
							Earnest Money:-		Rs.7700.00
							Time:-		Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
20.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	139.50			Per cubic metre				
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	71.75			Per cubic metre				
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm ( one hundred ten millimeter) dia PVC pipe De phos./finoles/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty ) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	25.00			Each				
Total									

## Terms and Condition

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tamil Devel Division,  
 HPPWD- Tamil Devel



**Schedule of Q. antiy**


**NAME OF WORK:- Restoration of rain damages on Hainpur Sujapur road km. 2/600 to 18/300, (SH:- C/O R./Wall at RD. 10/960 to 10/973). (Deposit Work).**

<b>Estimated Cont:-</b>	<b>Rs. 243573.00</b>
<b>Earnest Money:-</b>	<b>Rs. 4900.00</b>
<b>Time:-</b>	<b>Two Months</b>

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (one point five metre) in width or 10 sqm (ten square metre on plan), including dressing of sides and raiming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within at leads and lifts and other incidentals.	30.16			Per cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. up to floor five level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within at leads and lifts and other incidentals.	53.84			Per cubic metre	
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia P.V.C. pipe (De-plas/flex) weepus pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V), 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within at leads and lifts and other incidentals.	26.00			Each	
	<b>Total</b>					

**Terms and Condition**

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tamsil Devt Division  
 HPPWD, Tamsil Devt




**Schedule of Quantity**

**NAME OF WORK:-** Restoration of rain damages on Namrup Sujampur road km. 2/600 to 18/200 (SH- C/O R/Wall at RD. 13/570 to 13/576.50). (Deposit Work).

NAME OF WORK:- Restoration of rain damages on Ramtampur Solanpur road km. 2/600 to 18/200 (SH- C/O R/Wall at RD. 13/570 to 13/576.50). (Deposit Work).							Estimated Cost:-	Rs. 188995.00
							Earnest Money:-	Rs. 38000.00
							Time:-	Two Months
Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount	
				In Words				
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (one point five metre) in width or 10 sqm (ten square metre on plan), including dressing of sides and ramming of bottoms, fill upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	20.80				Per cubic metre		
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, surken floor etc., up to floor five level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	42.43				Per cubic metre		
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 10mm (one hundred ten millimeter) dia PVC pipe. De-plaster/rook/ wotus pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V: 20H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and lifts and other incidentals.	15.00				Each		
Total								

**Terms and Condition**

1. Work shall be executed as per PWD specification.


  
 Executive Engineer,  
 Tamsil Development Division,  
 HPPWD, Tamsil, Dist.

**Schedule of Quantity**

NAME OF WORK:- C/O link road to Ayurvedic dispensary Rce to village Kuwall in G.P. Rce km. 0/0 to 1/500 (SH:- C/O B/Wall at RD. 0/060 to 0/080) (Under OTMNP).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Rs. 5800.00		
			Time:-	Two Months		
			Rate			
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (one foot five inches) in width or 10 sqm (ten square metres) on plan), including dressing of sides and ramming of bottom, till upto 1.5 m, (one foot five inches) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (fifty metres) as per the direction of the Engineer-in-Charge including entire cartage of material within all leads and its and other incidentals. The rates are inclusive of oil, royalty, Mahasana, toll tax, GST or other taxes imposed by the Government.	14.40			Per cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plinth, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor any level, including the cost of cementing, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimetre nominal size), as per the direction of the Engineer-in-Charge including entire cartage of material within all leads and its and other incidentals. The rates are inclusive of oil, royalty, Mahasana, toll tax, GST or other taxes imposed by the Government.	65.15			Per cubic metre	
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 150mm (one hundred and fifty millimetre) dia PVC pipe De-pist/hollow vector pipe having pressure 4kg per centimetre square (four kilogramme per centimetre square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 014, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and its and other incidentals. The rates are inclusive of oil, royalty, Mahasana, toll tax, GST or other taxes imposed by the Government.	40.00			Each	
	<b>Total</b>					

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tauni Devi Division  
 HPPWD: Tauni Devi


# **Schedule of Quantity**

**NAME OF WORK:-** Restoration of rain damages on Hamirpur Solanpur road km. 2/600 to 18/300 (SH- C/O U-shape drain at RD. 7/205 to 7/315). (Deposit Work).

Schedule of Quantity									
NAME OF WORK:- Restoration of rain damages on Hamirpur Seelampur road km. 2/600 to 18/300 (S.H. C/O U-shape drain at R.O.									
7/205 to 7/315). (Deposit Work).									
Sr No.	Description of Items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
			Estimated Cost:- Earnest Money:- Time:-	Rs. 213940.00 Rs. 4300.00 Two Months					
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m (one point five metre) in width or 10 sqm ( ten square metre on plan), including dressing of sides and raming of batters, fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a head of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all heads and fills and other incidentals.	44.55			Per cubic metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to depth level 1:3:6 (one cement, three sand, six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all heads and fills and other incidentals.	40.84			Per cubic metre				
					Total				

## **Terms and Condition**

1. Work shall be executed as per PWD specifications.

  
 Executive Engineer,  
 Tamsal Devi Division,  
 HPPWD, Tamsal Devi



# Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Tauni Devi Sub-Division. (SH:- Hiring of JCB/Tront end Loader for removal of slips/clearing of drain due to heavy rains).(Section-I and Section-II).

Estimated Cost:- Rs. 481000.00  
Earnest Money:- Rs. 9600.00  
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (Tront end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	370.00			Per hour	
<b>Total</b>						

## Terms and Condition

- 1 The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- 2 Nothing shall be paid for idle hours
- 3 All bear and tear and P.O.L. charges are to be born by the contractor.

*Arindam*  
Executive Engineer,  
Tauni Devi Division,  
HPPWD, Tauni Devi

### Schedule of Quantity

NAME OF WORK:-	Estimated Cost:-
Restoration of rain damages on various roads in Baghera Section under Sub Division Kakkar. (SH:- Hiring of excavator cum loader for removal of slips, clearance of darin)	Rs.198000.00
	Estimated Money:-
	Rs.4000.00

Sr. No.	Description of Items	Qty.	Time:-		Two Months Unit	Amount
			In Fig.	Rate		
				In Words		
1.00	Hiring of excavator cum loader for maintenance of berms, clearance of side drain, removal of slip etc. including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor on risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hours will be accounted for the payment. Earth cutting in all kinds of soils, including loading into tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	150.00			Per Hours	
					Total	

### Terms and Condition

1. Work shall be executed as per PWD specification.

*Avinash*  
Executive Engineer,  
Tanni Devi Division,  
HPPWD: Tanni Devi

00

this

Two Months

Two Months

Amount
--------

1

*Arun Chandra*  
Executive Engineer,  
Taanvi Devi Division  
HPPWD: Taanvi Devi



**Schedule of Quantity**

**NAME OF WORK:- C/O link road from Bughera bridge to Harizan Basti [ol via Sa-nouna Goushala km. 0/00 to 1/200.(SH:- C/O**  
**if wall at RD. 0/712 to 0/761). (Under SSCP).**

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m/one point five metre) in width or 10 sqm (ten square metre on plan) including dressing of sides and ramming of bottoms, fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within at leads and fits and other incidentals.	35.10			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pilars, posts, struts, buttresses, sitting or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, surfen floor etc., up to floor line level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within at leads and fits and other incidentals.	91.26			Per Cubic metre	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe. De-plasticized/ vesdus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V) : 20(H) towards drainage face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within at leads and fits and other incidentals.	76.00			Each	
4	Construction of embankment with approved material obtained from borrow pits with a fill upto 1.5mtr. (one point five meter) transporting to site, spreading, grading to required slope and compacting to meet requirement of tables 300.1 and 300.2 with a lead upto 1000mt. (one thousand meter) as per technical specification clause 301.5, as per direction of Engineer-in-charge, including entire carriage of material within at leads and fits and other incidentals.	279.30			Per Cubic metre	
<b>Total</b>						

**Terms and Condition**

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tami Devi Division,  
 HPPWD, Tami De

# Schedule of Quantity

NAME OF WORK:- C/O link road Kothai to Jolly km. 0/0 to 2/500.(SH:- C/O cement concrete pavement at RD. 0/038 to 0/056, 0/141 to 0/165 and 0/206.50 to 0/269.50).(under OTMNP).

NAME OF WORK:- C/O link road Kolthi to july km. 0/0 to 2/500 (SH:- C/O cement concrete pavement at RD. 0/038 to 0/056, 0/141 to 0/165 and 0/206-50 to 0/269-50),(under OTMNP).										ESTIMATE OF QUANTITIES	
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount					
			In Fig.	In Words							
Rate											
Time:-											
Two Months											
Earrest Money:-											
Rs. 455696.00											
Rs. 9100.00											
Per Cubic metre											
Per Cubic metre											
Per square metre											
Per Cubic metre											
Total											

## Terms and Condition

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 TAMIL DEVEL DIVISION  
 HYPOND, Tamil Devel



NAME OF WORK:- C/O link road to village Kharpal km. 0/0 to 1/0 (Sft:- C/O C.C. causeway, hume pipe culvert with wing walls etc. km. 0/200 to 0/550). (Under OTMNP).

**Schedule of Quantity**

NAME OF WORK:- C/O link road to village Khanpal km. 0/0 to 1/0 (SH:- C/O C.C. causeway, hume pipe culvert with wing walls etc. km. 0/200 to 0/550) (Under OTMNP).

estimate of quantity

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount		
				Earliest Money:-					
				Time:-	Rate				
				In Words					
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m,(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	21.60				Per cubic metre			
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached piers, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor level, excluding the cost of centering, shuttering and freshing, 1:5:10 (one cement : five coarse sand : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	45.60				Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement : three sand : six graded stone aggregate 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	24.83				Per cubic metre			
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm/ one hundred ten millimeter) dia PVC pipe. De-plasticizer/ weep pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square ) extending through the full width of the structures with slopes of (1V/ 20H) towards drainage face complete as per drawing and technical specification clauses 614, 710, 1204.3.7 as per direction of Engineer- in- Charge, including entire cartage of material within all leads and lifts and other incidentals.	20.00				Each			
5	Providing and laying reinforced cement concrete pipe No2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 900mm(nine hundred millimeters) dia as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals.	10.00				Per running metre			
6	Stone soling properly handpacked filling interstices with spalls and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. concrete as per HP-PWD, specification 100mm (one hundred millimeter) spread thickness finished work, including materials and labour as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals.	12.00				Per cubic metre			
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	12.00				Per cubic metre			



B	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire cartage of material within all loads and lifts and other incidentals	18.00			Per cubic metre	
	Total					

# **Terms and Condition**

1. Work shall be executed as per PWD specification.

*Amal Kumar*  
Executive Engineer,  
Tamil Nadu Division,  
HPPWD, Tamil Nadu

# Schedule of Quantity

**NAME OF WORK:-** Restoration of rain damages on various road under Kakkar Sub-Division (SHT - C/O Un-lined surface drain and dressing of berms).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Rate	In Words		
				Time:-			
						Two Months	
1	Construction of un-lined surface drain of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in in embankments with a lift upto 3mtr. and lead of 50mtr. (average lead 25m) as per technical specification clause 307 (a) By manual means, as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidentals.	3300.00				Per running metre	
2	Maintenance of earthen shoulder (filling with fresh selected soil). Making up loss of material/irregularities on shoulders to the design level by adding fresh approves selected soil and compacting it with appropriate equipment at OMC upto all leads and lifts as per technical specification clause 1503, as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidentals.	2000.00				Per Square metre	
						<b>Total</b>	

## **Terms and Condition**

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tauni Devi Division  
 HPPWD, Tauni Devi

# Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Kalkar Sub-Division. (SH:- Hiring of JCB/Front end loader for removal of slips/clearing of drain due to heavy rains).

Estimated Cost:- Rs. 499200.00  
Earnest Money:- Rs. 10000.00  
Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	384.00			Per hour	
Total						

## Terms and Condition

- 1 The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- 2 Nothing shall be paid for idle hours
- 3 All bear and tear and P.O. charges are to be born by the contractor.

Executive Engineer,  
Tamil Devl Division  
HPPWD, Tamil Devl



# Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Lambri Nalaji Asthatha road KM 0/00 to 6/00. (SH:- Construction of PCC Breast Wall at RD 3/495 to 3/525)(Deposit Work)

Estimated Cost:- Rs. 359860.00  
Earnest Money:- Rs. 7200.00  
Time:- Two Months

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire cartage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	74.25				Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	78.00				Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vecus having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty ) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	45.00				Each	
	<b>Total</b>						

## Terms and Condition

1. Work shall be executed as per PWD specification.

*Handwritten Signature*  
Executive Engineer,  
Tauri Devi Division  
HPWD, Jaunpur

# Schedule of Quantity


NAME OF WORK:- Construction of link road from Nalahi Kangri via Asthobha Sauran Da Gran road KM 0/0 to 4/500. (SH:- Construction of 900mm dia Hume pipe culvert with wing wall at Km 4/120)(Under OTMNP)							Estimated Cost:- Rs.416864.00
							Earrest Money:- Rs.8400.00
							Time:- Two Months
Sr. No.	Description of Items	Qty.	In Fig.	Rate	Unit	Amount	
				In Words			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,roll tax, GST or other taxes imposed by the Government.	58.91			Per cubic metre		
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,roll tax, GST or other taxes imposed by the Government.	66.32			Per cubic metre		
3.00	Providing and laying cement concrete for plain/reinforced concrete in P.C.C grade M-10(M:ten) nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,roll tax, GST or other taxes imposed by the Government.	16.11			Per cubic metre		
4.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 (granular Material) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,roll tax, GST or other taxes imposed by the Government.	11.76			Per cubic metre		
5.00	Providing and laying non-pressure NP2 class (light duty) reinforced cement concrete pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : two sand) including testing of joints etc. complete 900 mm(nine hundred millimetre) dia. R.C.C. pipe as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,roll tax, GST or other taxes imposed by the Government.	7.50			Per running metre		



6.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plant /finolex/sectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty ) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents, The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.00					Each	
<b>Total</b>								

# **Terms and Condition**

1. Work shall be executed as per PWD specifications.

  
 Executive Engineer,  
 Taunsa Devi Division,  
 HPWD, Taunsa Devi



Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in burndown trenches or drains (not exceeding 1.5m/one point five metre) to width or 10 sqm/ ten square metre on plan, including dressing of sides and ramming of bottom, at upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a limit of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all heads and its and other incidentals. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	29.38			Per cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bull blocks, anchor blocks, plain window sills, flash, surken floor etc., up to floor any level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire cartage of material within all heads and its and other incidentals. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	63.43			Per cubic metre	
3	Providing steep bodes in brick/masonry/stone reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm/ one hundred ten millimeter) dia P.V.C. pipe De-plastrified/ section pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V: 20H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.1.7 as per direction of Engineer- in -Charge, including entire cartage of material within all heads and its and other incidentals. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	17.00			Each	
4	Back filling with granular material bedded abutment, wing walls, return walls and retaining walls complete as per drawing and MOPD technical specifications clause 1204.1.8 as per direction of Engineer- in -Charge, including entire cartage of material within all heads and its and other incidentals. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	14.83			Per Cubic metre	
<b>Total</b>						

**Terms and Condition**  
 1. Work shall be executed as per MWD specification.

Executive Engineer,  
 Tamsi Devi Division,  
 HPPWD, Tamsi Devi

**Schedule of Quantity**  
**NAME OF WORK:- Restoration of rain damages on Barin Dhalwal via Siswan Gahlot road km. 0/00 to 5/00.(SH:- C/O R/Wall at RD. 1/7710 to 1/7725).**

NAME OF WORK- Restoration of rain damages on Barin Dhawal via Siswan Gahlot road km. 0/00 to 5/00 (SH- C/O R/Wall at RD. 1/710 to 1/725).
Schedule of Quantity

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
				Estimated Cost- Earnest Money-> Timer-	Rs.304671.00 Rs.6100.00 Two Months		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding upto 1.5 m, (one point five metre) in width or 10 sqm) (sq square metre on plan),including dressing of sides and ranshing of bottom, (at least of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals. The rates are inclusive octroi, royalty, Mahakama tax, GST or other taxes imposed by the Government.	10.15				Per cubic metre	
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached piers, columns, piers, abutments, plans, posts, trunks, buttresses, drying or facing courses, parapets,coping, bed blocks, anchor blocks, plain window coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals. The rates are inclusive octroi, royalty, Mahakama tax, GST or other taxes imposed by the Government.	66.31				Per cubic metre	
3	Providing weep holes in brick/stone masonry/ plain reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plestified/ wurtz pipe having pressure Alg per centimeter square (four kilograms per centimeter square) extending through the full width of the structures with slopes of (1V/ 20(H) towards drainage face complete as per drawing and technical specification clauses 514, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and its and other incidentals. The rates are inclusive octroi, royalty, Mahakama tax, GST or other taxes imposed by the Government.	23.00				Each	
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and MOPD technical specifications clause 1204.3.8 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and its and other incidentals.	16.31				Per Cubic metre	
	<b>Total</b>						

Terms and Condition
Work shall be executed as per PWD specification.

**Terms and Condition**  
 1. Work shall be executed as per PWD specification.

*Anwar*  
 Executive Engineer,  
 Tauni Devi Division,  
 HPPWD-Tauni Devi




### Schedule of Quantity

**NAME OF WORK:-** Restoration of rain damages on Kahuah-Kheri-Bhatamber-Dudla via Maheshgaur road KM 0/0 to 9/460. (SH). Providing and laying interlocking concrete block pavement 50M long between Km at RD 4/730 to 4/760)

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a load of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-Charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.00			Per cubic metre	
2.00	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials masonry or earth etc. complete as per HP-PWD, specification 101mm(one hundred millimeters) spread thickness as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.50			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimeter) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.40			Per cubic metre	
4.00	Providing and laying of interlocking concrete block pavements having thickness 80mm( Eighty millimeters) as per drawing and technical specification clause 1504 (N.T.C. 15 over marked type paver block) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	150.00			Per Square metre	
					<b>Total</b>	

#### Terms and Condition

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tauni Development Division,  
 HPPMD, Tauni Development Division



# **Schedule of Quantity**


**NAME OF WORK:- C/O link road from Channaruda to Harisan Basi Kudana (Kalyana) km. 0/0 to 0/300 (SH- P/L C.C. pavement, Breast wall in km. 0/130 to 0/230). (Under SCSP).**


<b>Estimated Cost:-</b>	<b>Rs. 460911.00</b>
<b>Earnest Money:-</b>	<b>Rs. 9200.00</b>
<b>Time:-</b>	<b>Two Months</b>

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m/one point five metre) in width or 10 sqm (ten square metre on plan),including dressing of sides and ramming of bottom, fill upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a band of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all heads and lbs and other incidentals.	16.50			Per cubic metre	
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached plasters, columns, piers, abutments, piers, posts, struts, buttresses, string or baling courses, parapets,coping, bed blocks, anchor blocks, plain window sills,floors, surface floor etc., up to floor any level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all heads and lbs and other incidentals.	25.92			Per cubic metre	
3	Providing weep holes in brickwork masonry/ply reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plex/flex/vectas pipe having pressure 4kg per centimeter square, (four kilogramme per centimeter square ) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all heads and lbs and other incidentals.	11.00			Each	
4	Stone facing properly handpacked filling interfaces with spalls and consolidating with power road roller to the required gradient and camber including spreading, watering and rolling of bedding materials masonry or earth etc. complete as per HP-PWD, specification 100mm (one hundred millimeter) spread thickness finished work including materials and labour as per direction of Engineer-in-Charge including entire carriage of material within all heads and lbs and other incidentals.	45.75			Per cubic metre	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all heads and lbs and other incidentals.	30.50			Per cubic metre	
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all heads and lbs and other incidentals.	30.50	9		Per cubic metre	
	<b>Total</b>					

## **Terms and Condition**

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tamil Devi Division,  
 HEPWD, Tamil Nadu



# **Draft Schedule of Quantity**

**NAME OF WORK:-** Restoration of rain damages on various road under Tauni Devi Sub-Division, HP-PWD, Tauni  
**Dev(SH):-** C/O Un-lined surface drain and dressing of berms).

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Construction of un-lined surface drain of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in in embankments with a lift upto 3mtr. and lead of 50mtr. (average lead 25m) as per technical specification clause 307 (a) By manual means, as per direction of Engineer-in-Charge, including cartage of materials within all leads and lifts and other incidentals.	900.00	18.30	Rupees Eighteen and paise thirty only	Per running metre	16470.00
2	Maintenance of earthen shoulder (filling with fresh selected soil). Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto all leads and lifts as per technical specification clause 1903, as per direction of Engineer-in-Charge, including cartage of materials within all leads and lifts and other incidentals.	2500.00	65.50	Rupees Sixty five and paise fifty only	Per Square metre	163750.00
<b>Total</b>						<b>180220.00</b>

## **Terms and Condition**

1. Work shall be executed as per PWD specification.

DNT No. 4 for the year 2023-24 duly approved for Rs.1,80,220/- (One lac. Eighty thousand two hundred twenty) Only.

*Arvind*  
 Executive Engineer,  
 Tauni Devi Division,  
 HP-PWD, Tauni Devi




# Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Kakkar Sub-Division. (SH:- Hiring of JCB/Front end loader for removal of slips/clearing of drain due to heavy rains).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Rs. 499200.00		
			Time:-	Rs. 10000.00		
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiseling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	384.00			Per hour	
<b>Total</b>						

## **Terms and Condition**

1. The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
2. Nothing shall be paid for idle hours
3. All bear and tear and POL charges are to be born by the contractor.

  
 Executive Engineer,  
 Tarni Devi Division,  
 HPPWD, Tarni Devi

PROJECT OF REPAIR & MAINTENANCE OF ROAD DAMAGES ON TAMIL NADU STATE HIGHWAY NO. 15/0 TO 30/915 (SHEET- C/O) Estimated Cost: Rs. 407761.00  
PCC R/W Wall as RD. 20/880 to 20/894.50). Earnest Money:- Rs. 9700.00  
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m/one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ranning of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a head of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all heads and its and other incidentals.	55.16			Per Cubic metre	
2	Providing and laying cement concrete in retaining wall,return wall, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or bacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,flags, surzen floor etc., up to floor five level, including the cost of carting, shuffling and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire cartage of material within all heads and its and other incidentals.	115.28			Per Cubic metre	
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing wall, return wall, retaining walls and breast wall with 110mm/ one hundred ten millimeter) dia PVC pipe De-gast/noise/ ventus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square ) extending through the full width of the structures with slopes of (1V/ 20H) towards drawing face complete as per drawing and technical specification clauses 614, 708, 1204.3.7 as per direction of Engineer- in -Charge, including entire cartage of material within all heads and its.	30.00			Each	
					Total	

**Terms and Condition**

Work shall be executed as per PWD specification

1. Work shall be executed as per PWD specification.

Executive Engineer,  
Tamsil Devi Division  
B.P. No. Tamsil Devi

**Schedule of Quantity**

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earliest Money:-	Time:-		
				Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means to foundation trenches or drains (not exceeding 1.5m (one foot two inches) in width or 10 sqm) ten square metre on plan) including delivery of sides and razing of bottoms, lift upto 1.5 m. (one foot two inches) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a limit of 50 m (fifty metre) as per the direction of the Engineer-in-Charge including entire carriage of material within all limits and its and other incidentals. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	24.90				Per cubic metre	
2	Providing and laying cement concrete in retaining walls, retaining walls, walls (any thickness) including attached piers, columns, piers, abutments, pillars, posts, arches, buttresses, string or leaning columns, parapets, coping, bed blocks, anchor blocks, plain window sills, floor, sunken floor etc., up to floor any level, including the cost of centering, shoring and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (four millimeters nominal size) as per the direction of the Engineer-in-Charge including entire carriage of material within all limits and its and other incidentals. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	47.40				Per cubic metre	
3	Providing weep holes in brick/stone masonry plain reinforced concrete abutment, wing walls, retaining walls and breast walls with 150mm (one hundred two millimeter) dia PVC pipe De-plastron/verbas pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structure with slopes of (1/4) 20/1 towards drainage back complete as per drawing and technical specification classes 614, 709, 1204 J.7 as per direction of Engineer-in-Charge, including entire carriage of material within all limits and its and other incidentals. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	36.00				Each	
<b>Total</b>							

**Terms and Condition**

1. Work shall be executed as per PWD specification.

*Amir*  
Executive Engineer,  
Tamil Devi Division,  
Hq. PWD, Tamil Devi




**Schedule of Quantity**

**NAME OF WORK:- Restoration of rain damages on Barara to Bakkar Khad via Patnour road km. 2/00 to 8/00.(SH:- Improvement of curves at RD. 2/695 to 2/730).**

NAME OF WORK:- Restoration of rain damages on Barara to Bakkar Khad via Patnoun road km. 2/00 to 8/00.(5H:- Improvement of curves at RD. 2/695 to 2/730).									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-						
			Time:-	Two Months					
			In Fig.	In Words					
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling (wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and/or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 44.37/-cubic metre shall be made from the contractor @ Rs. 300/-three hundred only per cubic metre) amounting to Rs. 13,311/- only.	266.22			Per cubic metre				
Total									

**Terms and Condition**

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tauni Devt Division,  
 H.P.W.D. Tauni Devt

**Draft Schedule of Quantity**

**NAME OF WORK:- Special Repair to Bal Ashram at Solapur Thira Dist. Hamirpur (HP) (SH:- Providing and fixing dismantled doors and windows etc.(Deposit Work)**

NAME OF WORK:- Special Repair to Bad Ashram at Solapur Thira Dist. Hantrapur (HP) (SH:- Providing and fixing dismantled doors and windows etc.(Deposit Work)						
		Estimated Cost:-		Rs.414091.00		
		Earnest Money:-		Rs.8300.00		
		Time:-		Two Months		
Sr.No.	Description of Items	Qty.	Rate	Unit	Amount	
			In Fig.	In Words		
1.01	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkats, architrave, hold fasts etc. complete and stacking within 50(fifty) metres lead of area 3 sqm. (three square metres) and below as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	28.00	156.25	Rupees one hundred fifty six and paise twenty five only.	Each 4375.00	
2.01	Providing sal wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1.09	95763.05	Rupees ninety five thousand seven hundred sixty three and paise zero five only.	Per cubic metre 104190.00	
3.01	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, case of black local construction with frame of 1st class hard wood and well matched ornamental 31three ply veneering with vertical grain or cross bands and face veneers on both faces of shutters 35 mm. (thirty five millimetre) thick including ISI marked Stainless Steel turn hinges with necessary screws as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	25.60	1695.50	Rupees one thousand six hundred ninety five and paise fifty only.	Per square metre 43405.00	
4.01	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm (four millimetre) thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws 30 mm(thirty millimetre) thick as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	10.77	3425.65	Rupees three thousand four hundred twenty five and paise sixty five only.	Per square metre 36894.00	
5.01	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm(one point four millimetre) in both directions with wire of dia 0.63 mm(zero point sixty three millimetre), for doors, windows and clerestory windows with hinges and necessary screws with ISI marked M.S. pressed butt hinges bright finished of required size 30 mm(thirty millimetre) thick shutters. Second class teak wood as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	10.77	3242.05	Rupees three thousand two hundred forty two and paise zero five only.	Per square metre 34917.00	
6.01	Providing and fixing aluminium sliding door bolts, ISI treated anodized (anodic coating not less than grade AC 10 as per IS : 10681), transparent or dyed to required colour or shade, with nuts and screws etc. complete 250x16 mm (two hundred fifty into sixteen millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	14.00	214.20	Rupees two hundred fourteen and paise twenty only.	Each 2999.00	



7.01	Providing and fixing 250x10 mm(two hundred fifty into ten millimetre) aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents.The rates are inclusive octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	56.00	99.20	Rupees ninety nine and paise twenty only.	Each	5555.00
8.01	Providing and fixing 125 mm( one hundred twenty five millimetre) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents. The rates are inclusive octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	28.00	57.55	Rupees fifty seven and paise fifty five only.	Each	1011.00
8.02	100 mm (one hundred millimetre)	28.00	50.75	Rupees fifty and paise seventy five only.	Each	1421.00
9.01	Providing and fixing Pre-laminated medium density fibre board exterior grade (Grade-I) IS:14587:1998 marked, to frame, backing or studding with screws etc. complete ( Frames, backing or studding to be paid separately)Pre-laminated with decorative lamination on both side exterior Grade - I MDF Board 18 mm(nineteen millimetre) thick conforming to IS:14587 as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents.The rates are inclusive octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	1.68	982.25	Rupees nine hundred eighty two and paise twenty five only.	Per square metre	1650.00
10.01	Applying priming coat with ready mixed pink or grey putty of approved brand and manufacture on wood work (hard and soft wood) as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents.The rates are inclusive octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	93.68	38.95	Rupees thirty eight and paise twenty five only.	Per square metre	3649.00
11.01	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.30 litr/10 sqm(zero point ninety litre per ten square metre) over an under coat of primer applied @0.75 litr/10 sqm(zero point seventy five litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents.The rates are inclusive octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	93.68	94.30	Rupees ninety four and paise thirty only.	Per square metre	8834.00
12.01	Demonishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead in cement mortar as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents.The rates are inclusive octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	6.80	847.95	Rupees eight hundred forty seven and paise ninety five only.	Per cubic metre	5766.00
13.01	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5(twelve point five) conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (one cement : six coarse sand) with modular bricks as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents.The rates are inclusive octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	6.80	6230.90	Rupees six thousand two hundred thirty and paise ninety only.	Per cubic metre	42370.00



14.01	Repairs to plaster of thickness 12 mm (twelve millimetre) to 20 mm (twenty millimetre) in patches of area 2.5 sqm (two point five square millimetre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground with cement mortar 1:4 (one cement four coarse sand) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	22.68	276.15	Rupees two hundred seventy six and paise fifteen only.	Per square metre	6263.00
15.01	Dastermpering with oil bound washable dastermper of approved brand and manufacture to give an even shade (two or more coats) over and including water thinable priming coat with cement primer as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	808.62	96.85	Rupees ninety six and paise eighty five only.	Per square metre	86063.00
16.01	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	100.10	29.55	Rupees twenty nine and paise fifty five only.	Per square metre	2958.00
17.01	15 mm (fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:4 (one cement four coarse sand) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	100.10	211.50	Rupees two hundred eleven and paise fifty only.	Per square metre	21171.00
<b>Total</b>						<b>414091.00</b>

**Terms and Condition**

1. Work shall be executed as per PWD specification.

DNIT No. 183 for the year 2023-24 duly approved for Rs. 4,14,091/-  
(Rupees four lacs fourteen thousand ninety one) Only.

Executive Engineer,  
Tamil Nadu Division,  
HPPWD, Tamil Nadu


# Schedule of Quantity

NAME OF WORK:- A/R & M/O various road under Tami Devl Division, HP-PWD, Tami Devl (Stt)- Supplying and fixing of dual direction delineators) Job No.2.

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Supplying and fixing of dual direction delineator made of dia 1 1/2 gauge rectangular pipe of size 25x53mm (twenty five into sixty three millimetre) and of length 600mm (six hundred millimetre) pipe stove enamelled and baked to 120c/powder coated head made of ABC plastic rounded moulded with flat face provided with high triangular prismatic reflectors of colour (white/Road) of size 100x125 (one hundred into one hundred twenty five) with additional to reflective strips of 20mm(twenty millimetre) wide make green light and directions of Engineer-in-Charge including entire carriage of material within all heads and fits and other incidentals.	384.00			Per cubic metre	
<b>Total</b>						

## **Terms and Condition**

1. Work shall be executed as per PWD specification.

  
 Executive Engineer,  
 Tami Devl Division  
 HP/PWD, Tami Devl

Draft Schedule of Quantity

NAME OF WORK:- A/R & M/O various road under Tami Devl Division, HP-PWD, Tami Devl (SII: Supplying and fixing retro-reflectorsised cautionary mandatory board etc.) Job No.2.

Draft Schedule of Quantity						
NAME OF WORK:- A/R & M/D various road under Tauni Devt Division, HP-PWD, Tauni Devt.(SH)- Supplying and fixing retro-reflectorsised cautionary mandatory board etc.) Job No.2.						
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
			Time:-			
			Estimated Cost:-		Rs.496000.00	
			Earliest Money:-		Rs.10000.00	
			Time:-		Two Months	
1	Providing and fixing of retro-reflectorsised cautionary, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting vide clause 1701.2.3 fixed over aluminium sheeting, 1.5mm (one point five millimetre) thick supported on RCC post 100mmx100mm (one hundred millimetre into one hundred millimetre) firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450mmx450mmx600mm (four hundred fifty into four hundred fifty into six hundred millimetre) 600mm (six hundred millimetre) below ground level as per approved drawing clause 1701 including carriage of material all labour equipment and materials to be various location through all lands and lifts of transportation in all lands, and directions of Engineer-in-Charge, including entire carriage of material within all lands and lifts and other incidentals.					
(a)	600mm (six hundred millimetre) equilateral triangle.	124.00	4000.00	Rupees four thousand only	Each	496000.00
					Total	496000.00

**Terms and Condition**

1. Work shall be executed as per PWD specification.

DMT No. **78**..... for the year 2023-24 duly approved for Rs. 4,99,200/- (four lac ninety nine thousand two hundred ) Only.

*Ajithan*  
Executive Engineer,  
Tami Devl Division,  
HP-PWD, Tami Devl



# Schedule of Quantity

NAME OF WORK:- Providing and laying of vitrified tiles in cadet dorm of Jharkhand Hostel Sainik School Sujampur Tihra (SH:-  
Leveling/rectification of floors). **Deposit Work**

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Time:-		
1	20mm (twenty millimeters) cement plaster of mix 1:4 (one cement four sand) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	387.83				Per square metre	
<b>Total</b>							

## Terms and Condition

1. Work shall be executed as per PWD specification.

*A. J. J. J.*  
Executive Engineer,  
Tamil Devl Division,  
HPPWD, Tamil Devl

### Schedule of Quantity

**NAME OF WORK:- A/R & M/O NIT Muthan via Khas Gran Km 0/0 to 3/885, (SH:- Construction of U-Shape drain at RD 1/570 to 1/586 and Providing and laying Paver block at RD 1/570 to 1/700)**

**Estimated Cost:-** Rs.438160.00  
**Earliest Money:-** Rs.8800.00  
**Time:-** Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre) on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m(fifty metre) Ordinary rock as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	61.80			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	35.27			Per cubic metre	
3.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver/finisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	19.57			Per cubic metre	
4.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	0.96			Per cubic metre	

5.00	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm(fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 80 mm (eighty millimetre) thick cement concrete paver block of M-30 grade with approved color design and pattern as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Mahkama, toll tax, GST or other taxes imposed by the Government.	130.50					Per square metre	
<b>Total</b>								

# **Terms and Condition**

1. Work shall be executed as per PWD specification.

*Asst Engr*  
 Executive Engineer,  
 Tausal Devi Division,  
 HPPWD, Tausal Devi



# Schedule of Quantity

NAME OF WORK:- C/O Govt. ITI Building at Solapur Thira Dist. Hamirpur (HP). (SH:- P/F collapsible gate and painting etc.).  
(Deposit work).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earliest Money:-	Rs. 159886.00		
			Time:-	Two Months		
1	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm (twenty into ten into two millimeter) and braced with flat iron diagonals 20x5 mm (twenty into five millimeter) size, with top and bottom rail of T iron 40x6x3 mm, forty into forty into six millimeter) with 40 mm (forty millimeter) dia steel pulleys, complete with bolts, nuts, locking arrangement, supports, handles, including applying a priming coat of approved steel primer as per the direction of Engineer-in-Charge including entire cartage of material within all loads and lifts and other incidents. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	14.31	In Fig.	In Words	Per Square metre	
2	Finishing with Deluxe Matt surface paint system for interiors and exteriors using primer as per manufacturers specifications. Painting steel work with Deluxe Matt surface paint to five an even shade. Two or more coat applied @ 0.900/10sqm (zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.800/10 sqm (zero point eight zero litre per ten square metre) of approved brand and manufacture, as per the direction of Engineer-in-Charge including entire cartage of material within all loads and lifts and other incidents. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	475.94			Per Square metre	
Total						

## Terms and Condition

1. Work shall be executed as per FWD specification.

APD  
Executive Engineer,  
Tamil Devl Division,  
MPWD, Tamil Devl

# Schedule of Quantity

NAME OF WORK:- C/O Govt. ITI Building at Saljapur Thira Distt. Hamirpur (HP). (SH:- P/F grilling work in existing windows). (Deposit work).

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earrest Money:-	Time:-		
			In Fig.	In Words		
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Mahantool tax, GST or other taxes imposed by the Government.	3062.00			Per kilogram	
Total						

## Terms and Condition

1. Work shall be executed as per PWD specification.

*Handwritten Signature*  
 Executive Engineer,  
 Tauni Devel Division,  
 HPWD, Tauni Devel

# Schedule of Quantity

NAME OF WORK:-Construction of Ambulance Jeepable standard road Lambera to Dharguola Brahmana Km 0/0 to 2/00. (SH- Providing and laying GSB, WMM and V-Shape drain at RD 1/410 to 1/615)(Under OTMNP)

Estimated Cost:-  
Rs.496932.00  
Earnest Money:-  
Rs.9900.00  
Time:-  
Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete with material conforming to Grade-I (size range 75 mm/seventy five millimetre) to 0.075 mm(zero point zero seven five millimetre) having CBR Value-30(thirty) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	108.16			Per cubic metre	
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	65.65			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	26.60			Per cubic metre	
	Total					

## Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,  
Tajpur Devl Division,  
H.P.W.D. Tauni Devl  
A



**Schedule of Quantity**  
**NAME OF WORK:- C/O link road from Dhar to Drug Khad via Graura km. 0/0 to 2/00.(SH- P/L CSB at RD. 0/000 to 0/500).**  
**(Under OTMNP)**

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Rs. 493772.00		
			Time:-	Rs. 10000.00		
			Rate	Two Months		
			In Fig.	In Words		
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for at least 6 lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge including entire carriage of material within at least 6 lifts and other incidentals. The rates are inclusive of cart, royalty, Mahana, toll tax, GST or other taxes imposed by the Government.	259.88			Per cubic metre	
<b>Total</b>						

**Terms and Condition**

1. Work shall be executed as per PWD specification.

*Handwritten Signature*  
**Executive Engineer,**  
**Tauni Devi Division,**  
**HPPWD, Tauni Devi**



# Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol jungle Beri road km. 15/0 to 30/915 (SH- C/O R./Wall at RD. 19/990 to 19/996).

Estimated Cost:- Rs. 132510.00  
Earliest Money:- Rs. 2700.00  
Time:- Two Months

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm ten square metre on plan), including dressing of sides and ranning of bottoms, in upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils its directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Maharana, toll tax, GST or other taxes imposed by the Government.	15.90				Per cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, floors, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : 10mm graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and fits and other incidentals.	31.58				Per Cubic metre	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm/ one hundred ten millimeter dia PVC pipe De-plasticizer/ recube pipe having pressure 4kg per centimeter square, (four kilograms per centimeter square ) extending through the full width of the structures with slopes of (1V): 20(H) towards drainage face complete as per drawing and technical specification clauses 614, 708, 1204 3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and fits and other incidentals.	10.00				Each.	
Total							

## Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,  
Tauni Devi Division  
HPPWD, Tauni Devi



# Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Kakkar to Chamb road Km 0/0 to 4/100.(SH:- Construction of Breast Wall at RD 0/780 to 0/795)

NAME OF WORK:- Residuo of rain damages on Kakkar to Chamb road Km 0/0 to 4/100.(SH- Construction of Breast Wall at RD 0/780 to 0/795)									
Estimated Cost:- Rs.211483.00									
Earnest Money:- Rs.4200.00									
Time:- Two Months									
Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount		
				In Words					
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 105.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	83.70				Per cubic metre			
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering . All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	43.05				Per cubic metre			
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm ( one hundred ten millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of (1V): 20(H)(twenty ) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	15.00				Each			
Total									

Terms and Condition

## Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,  
Tauri Devi Division,  
HPPWD: Tauri Devi