

Himachal Pradesh
Public Works Department
PW-RD-GA-Tender-2023-24-
To

6/64

dated:- 31-7-2021


The Executive Engineer (IT Cell)
Nigam Bihar, Shimla-2.

Subject: - Tender notice.

Enclosed please find herewith the tender notice of work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter N. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.i8o

DA:- Notice inviting tender & sechdule of quantity.


Executive Engineer,
B&R Division, HPPWD,
Rohru.

Himachal Pradesh
Public Works Department
"NOTICE INVITING TENDERS"

*Sealed item rate tender on form PWD 6&8 are invited by the Executive Engineer
Rohru Division HPPWD, on behalf of Governor of H.P. for the following works from the approved and eligible
contractors enlisted in HPPWD, So as to reach in this office as per time schedule given below:-*

- | | |
|---|----------------------------------|
| 1. Date of receipt of applications for tender forms:- | 07.08.2023 upto 1:00PM |
| 2. Date of issue/sale of tender forms:- | 07.08.2023 upto 2:00PM to 3.00PM |
| 3. Date of receipt of tender:- | 08.08.2023 upto 3:30PM |
| 4. Date of opening of tender:- | 08.08.2023 upto 4:00PM |

Sr.No.	Name of Work.	Estt.Cost.	E/Money	Time.
1	R/R damages on Andhra Dhagoli Gaonsari road km. 0/0 to 8/0 (SH:-C/O R/wall in Wire crate at RD.0/105 to 0/117 & 3/180 to 3/200)	456216	9200	1 Month
2	R/R damages on Seema Rantari road km.0/0 to 12/0 (SH:-C/O R/wall in Wire crate at RD.3/405 to 3/432)	460305	9300	1 Month
3	R/R damages on RCD road km.0/0 to 21/195 (SH:-C/O R/wall in Wire crate at RD.20/060 to 20/082.50)	203579	4100	1 Month
4	R/R damages on Badiyara Masli Jatata Dhakgoan road km. 0/0 to 12/0 (SH:-C/O R/wall in PCC 1:3:6 at RD.4/850 to 4/860 & RD. 4/840 to 4/850)	477762	9600	1 Month
5	R/R damages on Baggi Khabal road km. 0/0 to 10/0 (SH:-C/O R/wall in Wire crate at RD.0/225 to 0/245 & 1/195 to 1/205)	460045	9200	1 Month
6	R/R damages on Baggi Khabal road km. 0/0 to 10/0 (SH:-C/O R/wall at RD.0/225 to 0/245 & 1/195 to 1/205)	254667	5100	1 Month
7	R/R damages on Dhamwari Gajyani road km. 0/0 to 3/0 (SH:-C/O B/wall in PCC 0/146 to 0/158)	463863	9300	1 Month
8	R/R damages on Dhamwari Goakswari road km. 0/0 to 5/500 (SH:-C/O B/wall in wire crate at RD.1/870 to 1/910)	373355	7500	1 Month
9	R/R damages on Dhamwari Goakswari road km. 0/0 to 5/500 (SH:-C/O B/wall in wire crate at RD.0/280to 0/380 & 0/780 to 0/797.5)	350253	7100	1 Month
10	R/R damages on Chanti Raha Panu km. 0/0 to 2/0 (SH:-C/O B/Wall in wire crate at Rd. 0/060 to 0/085 & 1/105 to 1/125)	420305	8500	1 Month
11	R/R damages on RCD road km. 0/0 to 21/195 (SH:-C/O B/wall in wire crate at RD.11/920 to 11/960)	460792	9300	1 Month
12	R/R damages on RCD road km. 0/0 to 21/195 (SH:-C/O B/wall in wire crate at RD.11/962 to 12/0)	458868	9200	1 Month
13	R/R damages on Baggi Khabal road km. 0/0 to 10/0 (SH:-C/O B/wall in wire crate at RD.0/450 to 0/470)	435543	8800	1 Month
14	R/R damages on Seema Rantari road km. 0/0 to 12/0 (SH:-C/O B/wall in wire crate at RD.11/0 to 11/012 ,10/815 to 10/825)	346465	7000	1 Month
15	R/R damages on Seema Rantari road km. 0/0 to 12/0 (SH:-C/O B/wall in wire crate at RD.1/0 to 1/072 ,11/180 to 11/188 ,8/0 to 8/010)	426249	8600	1 Month
16	R/R damages on Dadyara Diwasni road km. 0/0 to 8/0 (SH:-C/O B/wall in wire crate at RD.3/810 to 3/820)	93339	1900	1 Month
17	R/R damages on Badiyara Masli Jitata Dhakgoan road km. 0/0 to 12/0 (SH:-C/O R/wall in wire crate 1:3:6 at RD.8/300 to 8/320)	363809	7300	1 Month

Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

Terms and conditions:- The tender document shall be issued only to these contractors/firms who fulfill the following criteria and submit the following document with the application.

1. The Earnest-money for the above works should be submitted with the application for the purchase of the tender-documents.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. Income tax & GST No latest clearance certificate.
4. The contrs / firm shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The contractors should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

Executive Engineer,
B&R Division, HPPWD,
Rohru.

NO.: -PW-RD-AB-Tender /2023-24- 6064-6/63 Dated:- 31-7-2023

Copy forwarded for information and wide publicity to:-

1. The Chief-Engineer(S), HPPWD, Shimla-2.
3. The S E 14th Circle HPPWD, Rohru
4. All the E.E.'s under 14th Circle, HPPWD, Rohru
5. All the A.E.'s working under this Division (B&R).
6. The Sub Divisional Magistrate, Rohru.
7. The B.D.O. Rohru and Chirgaon.
8. The Tehsildhar, Rohru/Chirgaon and Tikkar.
9. The Chairman, N.A.C. Rohru.
10. A/B. and D/B. in this Office.
11. Notice-Board.

Executive Engineer,
B&R Division, HPPWD,
Rohru.

SCHEDULE OF QUANTITY

Estimated Cost:-456216/-
Earnest Money:-9200/-
Time:-One Month

Job No.1

NAME OF WORK:- R/R damages on Andhra Dhagoli Gaonsari road km. 0/0 to 8/0 (SH:-C/O R/wall in Wire crate at RD.0/105 to 0/117 & 3/180 to 3/200)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	48.52			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	17.56			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	154.69			Cum	0
				Total:-		0

23
Executive Engineer
B&R Division HP.PWD
Rohru

						Job No.2
SCHEDULE OF QUANTITY Estimated Cost:-460305/- Earnest Money:-9300/- Time:-One Month						
NAME OF WORK--: R/R damages on Seema Rantari road km.0/0 to 12/0 (SH:-C/O R/wall in Wire crate at RD.3/405 to 3/432)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	44.28			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	18.63			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	156.25			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY

Job No.3
Estimated Cost:-203579/-
Earnest Money:-4100/-
Time:-One Month

NAME OF WORK--: R/R damages on RCD road km.0/0 to 21/195 (SH:-C/O R/wall in Wire crate at RD.20/060 to 20/082.50)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Change	15.30			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Change	1.76			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Change	70.31			Cum	0
	Total:-					0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY

Estimated Cost:-477762/-
Earnest Money:-9600/-
Time:-One Month

NAME OF WORK:-R/R damages on Badiyara Masli Jatata Dhakgoan road km. 0/0 to 12/0 (SH:-C/O R/wall in PCC 1:3:6 at RD.4/850 to 4/860 & RD. 4/840 to 4/850)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	12.00			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	14.40			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	46.88			Cum	0
4	Providing Concrete for plain/rainforced concrete in open foundations completed as per drawing and technical specifications clause 802.803.1202.1203 PCC grade M 10 nominal mix 1:3:6 as directed by the Engineer-in-Charge	47.00			Cum	0
5	Providing weep hole in brick masonry/stone masonry plain/rainforced concrete abutment wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709.1204.307 as directed by the Engineer-in-Charge	20.83			No.	0
Total:-						0

Executive Engineer
B&R Division
Rohru


SCHEDULE OF QUANTITY						
		Estimated Cost:-460045/-				
		Earnest Money:-9200/-				
		Time:-One Month				
NAME OF WORK--: R/R damages on Baggi Khabal road km. 0/0 to 10/0 (SH:-C/O R/wall in Wire crate at RD.0/225 to 0/245 & 1/195 to 1/205)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	23.80			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	27.30			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	156.25			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PW/D
 Rohru


SCHEDULE OF QUANTITY		Job No.6				
		Estimated Cost:-254667/-				
		Earnest Money:-5100/-				
		Time:-One Month				
NAME OF WORK--: R/R damages on Baggi Khabal road km. 0/0 to 10/0 (SH:-C/O R/wall in Wire crate at RD.0/615 to 0/629)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	18.34			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	5.74			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	87.50			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru


SCHEDULE OF QUANTITY		Estimated Cost:-463863/-				
		Earnest Money:-9300/-				
		Time:-One Month				
NAME OF WORK--:R/R damages on Dhamwari Gajyani road km. 0/0 to 3/0 (SH:-C/O B/wall in PCC 0/146 to 0/158)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	23.40			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	12.36			Cum	0
3	Providing Concrete for plain/rainforced concrete in open foundations completed as per drawing and technical specifications clause 802,803,1202,1203 PCC grade M 10 nominal mix 1:3:6 as directed by the Engineer-in-Charge	64.20			Cum	0
4	Providing weephole in brick masonry/stone masonry .plain /rainforced concrete abutment ,wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204,307 as directed by the Engineer-in-Charge	16.67			No.	0
5	Providing and laying of stone filling behind the retaining wall and return walls as per drgs. And tech specs. As per clause 1204.3.8 as directed by the Engineer-in-Charge	0.00			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru


SCHEDULE OF QUANTITY		Estimated Cost:-373355/-		Job No.8		
		Earnest Money:-7500/-				
		Time:-One Month				
NAME OF WORK--: R/R damages on Dhamwari Goakswari road km. 0/0 to 5/500 (SH:-C/O B/wall in wire crate at RD.1/870 to 1/910)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	27.20			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	31.20			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	125.00			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY		Estimated Cost:-350253/-				
		Earnest Money:-7100/-				
		Time:-One Month				
NAME OF WORK--: R/R damages on Dhamwari Goakswari road km. 0/0 to 5/500 (SH:-C/O B/wall in wire crate at RD.0/280to 0/380 & 0/780 to 0/797.5)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	25.88			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	29.63			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	117.19			Cum	0
					Total:-	0



 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY			Estimated Cost:-420305/-		
			Earnest Money:-8500/-		
			Time:-One Month		
NAME OF WORK--: R/R damages on Chanti Raha Panu km. 0/0 to 2/0 (SH:-C/O B/Wall in wire crate at Rd. 0/060 to 0/085 & 1/105 to 1/125)					
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	31.05			Cum 0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	35.55			Cum 0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	140.63			Cum 0
				Total:-	0



 Executive Engineer
 B&R Division HP.PWD
 Rohru

Job No.11


SCHEDULE OF QUANTITY		Estimated Cost:-460792/- Earnest Money:-9300/- Time:-One Month				
NAME OF WORK--: R/R damages on RCD road km. 0/0 to 21/195 (SH:-C/O B/wall in wire crate at RD.11/920 to 11/960)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	98.00			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	50.00			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	148.44			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru


SCHEDULE OF QUANTITY		Estimated Cost:-458868/- Earnest Money:-9200/- Time:-One Month				
NAME OF WORK--: R/R damages on RCD road km. 0/0 to 21/195 (SH:-C/O B/wall in wire crate at RD.11/962 to 12/0)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	93.10			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	47.50			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	148.44			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY			Estimated Cost:-435543/-		
			Earnest Money:-8800/-		
			Time:-One Month		
NAME OF WORK--: R/R damages on Baggi Khabal road km. 0/0 to 10/0 (SH:-C/O B/wall in wire crate at RD.0/450 to 0/470)					
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	37.20			Cum 0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	15.60			Cum 0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	148.44			Cum 0
				Total:-	0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY			Estimated Cost:-346465/-			
			Earnest Money:-7000/-			
			Time:-One Month			
NAME OF WORK--:R/R damages on Seema Rantari road km. 0/0 to 12/0 (SH:-C/O B/wall in wire crate at RD.11/0 to 11/012,10/815 to 10/825)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	29.21			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	18.81			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	117.19			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY			Estimated Cost:-426249/-			
			Earnest Money:-8600/-			
			Time:-One Month			
NAME OF WORK--:-R/R damages on Seema Rantari road km. 0/0 to 12/0 (SH:-C/O B/wall in wire crate at RD.1/0 to 1/072 ,11/180 to 11/188 ,8/0 to 8/010)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	33.76			Cum	0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	21.66			Cum	0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	144.53			Cum	0
				Total:-		0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY		Estimated Cost:-93339/-			
		Earnest Money:-1900/-			
		Time:-One Month			
NAME OF WORK--:R/R damages on Dadiyara Diwasni road km. 0/0 to 8/0 (SH:-C/O B/wall in wire crate at RD.3/810 to 3/820)					
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Change	6.80			Cum 0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Change	7.80			Cum 0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Change	31.25			Cum 0
				Total:-	0


 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY			Estimated Cost:-363809/-		
			Earnest Money:-7300/-		
			Time:-One Month		
NAME OF WORK---R/R damages on Badiyara Masli Jitata Dhakgoan road km, 0/0 to 12/0 (SH:-C/O R/wall in wire crate 1:3:6 at RD.8/300 to 8/320)					
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	26.20			Cum 0
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	8.20			Cum 0
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	125.00			Cum 0
				Total:-	0


 Executive Engineer
 B&R Division HP.PWD
 Rohru