



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tenders on forms 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **26.08.2023** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **25.08.2023** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **24.08.2023** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of work.	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Repair of PWD Rest House at Chadhiar, Distt Kangra (H.P.) SH: Distempering, Painting, Renewing Glass Panes, Wood work Repair of plaster and etc.	Rs.1,93,277/-	Rs.3,900/-	Rs.350/-	Three Months
2	C/O Chobu Bhullana Road (SH: C/O R/Wall at RD 2/480 to 2/496.20)	Rs.4,98,863/-	Rs.10,000/-	Rs.350/-	One Month

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No(Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. The application form should accompany the earnest money in the shape of FDR/NSC duly pledged in favour of Executive Engineer, PWD Baijnath otherwise no forms will be issued.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper , Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD. Baijnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2023-24/-

6885-94

Dated:- 14-08-23

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.


Executive Engineer,
Baijnath Division.,
H.P.PWD. Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
6885-94 DATED 14-08-2023 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.

D.N.I.T/ SCHEDULE OF QUANTITY

Name of Work:- Repair of PWD Rest House at Chadhar, Distt Kangra (H.P)

(SH:- Distemper, Painting, Renewing Glass Panes, Wood Work Repair of plaster and etc.

Estimated Cost 193277.00
Earnest Money 3900.00
Time limit Three Months

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Distemping with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surface to give an even shade over and including a priming coat with distemper primer of approved brand, as per direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	385.75	Sqm			
2	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point niny litter and ten square meter) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litter and ten square meter) of approved brand and manufacture, as per direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	404.41	Sqm			
3	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty float glass panes of nominal thickness 4mm (four milli meter) as per direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	4.09	Sqm			
4	Providing wood work in frames of doors windows clerestory windows and other frames wrought framed and fixed in position with hold fast lugs or with dash fastners of required dia and length. In first class Decdar wood. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.445	Cum			
5	Taking our existing wooden door shutter repair by cutting painting etc and refixing of repaired door shutter to existing door frames including replacement of hinges with screws etc. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	7.00	Each			
6	Repair to plaster of thickness 12mm to 20 mm (twelve milli meter to twenty milli meter) in patches of area 2.5 sqm (Two point five square meter) and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer- In-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	52.65	Sqm			

7	P.F. wire gauge shutters using galvanizied M.S. wire gauge of 1.5 gauge designation 85G (eighty five gram) average width of aperture 1.4mm (one point four milli meter) in both direction with wire of dia 0.56mm (zero point fifty six milli meter) for door, windows and eilestoriy windows with hinges and necessary screws. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	6.71	Sqm				
8	Providing and applying white cement based putty of average thickness 1 mm, (one milli meter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	77.15	Sqm				
9	Removing white or colour wash by scrapping and sand papering the surface smooth including necessary repairs to scratches etc. complete. As per direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	4.00	Sqm				
TOTAL							

Executive Engineer
Bajina (I) Division
H.P.W.D. Bajinath

SCHEDULE OF QUANTITY

Name of Work: C/O Chobu Bhullana Road
(SH: C/O R/W all at RD 2/480 to 2/496.20).

Estimated Cost: Rs. 498863/-
Earnest Money: Rs. 10000/-
Time Limit : One Month

S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) for retaining walls, breast walls culverts, bridges, drains and parapets etc as per drawing an M.O.R.D. technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable approved materials to the original surface in layers not exceeding 150 (one hundred fifty) millimeter compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) up to any depth and any quantum of water including cleaning of slush which may arise out during dewatering and within all leads and lift complete in all respect as per direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	46.49	Per Cubic Meter			
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 within all leads and lift complete in all respect as per direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	95.74	Per Cubic Meter			
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (V): 20 (H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 including hauling / carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect within all leads and lift complete in all respect as per direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	25.00	Each			

4	Back filling behind abutments, wing walls and return walls complete as per drawing and M.O.R.D. technical specification clause 1203 and 1604 and other incidentals and within all leads and lift complete in all respect as per direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	11.50	Per Cubic Meter			
---	--	-------	-----------------	--	--	--


 Rajiv Engineer
 Rajiv Division
 HPPWD Rajivnath