



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **26/08/2023** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **25/08/2023** up to 4.00 P.M and the application for issue of tender form shall be received on **24/08/2023** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Thural II). (SH:- Removal of Slips).	4,92,768/-	9900/-	One Month	350/-
2	Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Thural & Thural I). (SH:- Removal of Slips).	4,42,476/-	8900/-	One Month	350/-
3	Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Bhagolu da ghatta) (Removal of Slips).	4,94,869/-	9900/-	One Month	350/-
4	Restoration of rain damages on various roads under HPPWD Sub-Division Dheera (Section Rajhoon) (Removal of Slips).	4,90,888/-	9800/-	One Month	350/-
5	Restoration of rain damages on various roads under HPPWD Sub-Division Dheera (Section Dheera & Purba) (Removal of Slips).	4,98,500/-	9900/-	One Month	350/-




Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

6	Restoration of rain damages on Bhawarna Khaira Alampur road Km. 0/0 to 12/260 (SH:- Removal of Slips and Boulder at RD 9/560).	4,80,150/-	9600/-	One Month	350/-
---	--	------------	--------	-----------	-------

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK


Executive Engineer
Bhawarna Division
HPPWD Bhawarna

(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2023-24/- **6685-6744** Dated:- **21-08-2023**

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P.Shimla.
2. The Engineer-in-Chief, HPPWD. Shimla.
3. The Chief Engineer (KZ),HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer(Civil) Palampur/Dheera
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.


Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Thural II).
(SH:- Removal of Slips).

Estimated Cost :-Rs. 4,92,768/-
Earnest Money :- Rs. 9900/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5475.20			Per Cubic metre	
Total :-						


Executive Engineer
Bhawarna Division
HP-PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Thural
Thural & Thural I). (SH:- Removal of Slips).

(Section

Estimated Cost :-Rs. 4,42,476/-
Earnest Money :- Rs. 8900/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4916.40			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Bhagolu da ghatta) (Removal of Slips).

Estimated Cost :-Rs. 4,94,869/-
Earnest Money :- Rs. 9900/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5498.54			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Dheera (Section Rajhoon)
(Removal of Slips).

Estimated Cost :- Rs. 4,90,888/-
Earnest Money :- Rs. 9800/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5454.31			Per Cubic metre	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Dheera (Section Dheera & Purba) (Removal of Slips).

Estimated Cost :- Rs. 4,98,500/-
Earnest Money :- Rs. 9900/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including cartage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5538.89			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bhawarna Khaira Alampur road Km. 0/0 to 12/260.

Estimate Cost :-4,80,150/-
Earnest Money :-9600/-

Time Limit :- One Month

(SH:- Removal of Slips and Boulder at RD 9/560).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slid in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1620.00			Per Cubic metre	
2	Excavation/ breaking of stones for removal of slips of conglomerate rocks on the road/ alongwith mud/ soil in all heights and depths by manual/ mechanical means including comprising of ordinary soil Hard rock, chisseling/wedging out of rock (where blasting is prohibited) as directed by the Engineer in charge at site and disposal of all surplus material to required width of the road along with its levelling fine dressing and carriage of machineries ,materials , tools equipments and safety measures and incidentals necessary to complete.The Rate is inclusive toll tax, GST and any other taxes imposed by the government.The slips/ big boulders are of is hard rock of conglomerate mixed with mud/ soil and as such no servicable material is recoverable from the work. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The work shall be completed with in week time.	743.00			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Divison
 HP PWD Bhawarna