



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **04/09/2023** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **02/09/2023** up to 4.00 P.M and the application for issue of tender form shall be received on **01/09/2023** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Baskehar to Khabli road Km 0/ to 1/0 (SH:- C/o R/wall at RD 0/850 to 0/860, 0/978 to 1/0 & P/L CC work in km 0/850 to 0/860).	3,13,763/-	6300/-	One Month	350/-
2	Restoration of rain damages on Gwal Tilla Saidun road Km 0/00 to 2/500 (SW:- C/o R/wall at RD 0/00 to 30/0 & U-shape drain at RD 2/050 to 2/150).	4,95,444/-	9900/-	Two Month	350/-
3	Restoration of rain damages on Bhilla Sargooni to Malander via Kufru road Km 0/0 to 1/0 (SH:- Construction of R/wall at RD 0/010 to 0/022).	4,85,526/-	9700/-	Two Month	350/-
4	Restoration of rain damages on Bhadroon Kona Lahru road Km 5/0 to 12/800 (SH:- C/o R/wall in Km 12/370 to 12/390).	4,55,272/-	9100/-	Two Month	350/-
5	Restoration of rain Damage on Thural to Bharanta road Km 0/0 to 4/00 (SH:- C/o R/wall at RD 2/890 to 2/900)	4,29,200/-	8600/-	Two Month	350/-
6	Restoration of rain damages on Hamirpur Sujampur Thural Maranda road Km 30/0 to 59/775 (SH:- P/L crate work for protection of Diversion at RD 31/410).	2,33,210/-	4700/-	One Month	350/-
7	Restoration of rain damages on Duhak Garthoon road (SH:- Construction of R/wall at RD 0/090 to 0/110).	4,78,580/-	9600/-	Two Month	350/-
8	Restoration of rain damages on Balakrupi Duhak Dhaniara road (SH:- Construction of R/wall at RD 2/350 to 2/363).	4,65,326/-	9300/-	Two Month	350/-
9	Restoration of rain damages on Santoshi Mata Mandir to Umri via Malander, Garthoon road Km 0/0 to 7/0 (SH:- C/o R/wall with Pusta at RD 6/795 to 6/800).	4,45,838/-	8900/-	Two Month	350/-
10	Restoration of rain damages on Bhadroon Kona Lahru road (SH:- Construction of R/wall at RD 5/560 to 5/580).	4,79,080/-	9600/-	Two Month	350/-
11	Restoration of rain damages on Bairghatta to Sanhoon road Km 0/0 to 7/0 (SH:- C/o R/wall with Pusta at RD 1/885 to 1/900).	4,47,088/-	8900/-	Two Month	350/-

E.C.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

12	Restoration of rain damages on Tikker Balbhurian road Km 0/0 to 4/0 (SH:- C/o R/wall at RD 2/395 to 2/414).	4,75,519/-	9500/-	Two Month	350/-
13	Restoration of rain damages on Extension of Daroh Garh Jamula road upto Bairghatta Km 4/0 to 11/0 (SH:- C/o R/wall at RD 8/990 to 9/003).	4,73,912/-	9500/-	Two Month	350/-
14	Restoration of rain damages on Bandahu to Bairghatta road Km 2/300 to 4/330 (SH:- C/o R/wall with Pusta at RD 4/315 to 4/332).	4,86,278/-	9700/-	Two Month	350/-
15	Restoration of rain damages on Duhak Garthoon road (SH:- Construction of R/wall at RD 1/260 to 1/274).	4,97,498/-	9900/-	Two Month	350/-
16	Restoration of rain damages on Kona Pihri Nahllian road Km 0/0 to 5/0 (SH:- Construction of R/wall at RD 2/540 to 2/553).	4,65,076/-	9300/-	Two Month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2023-24/-

7078-7143

Dated:- 28.08.2023

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P.Shimla.
2. The Engineer-in-Chief, HPPWD. Shimla.
3. The Chief Engineer (KZ),HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer (Civil) Palampur/Dheera
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer,
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Estimate Cost :- Rs. 3,13,763/-
Earnest Money :- Rs. 6300/-
Time Limit :- Two Months

Name of Work :- Restoration of rain damages on Baskehar to Khabli road Km 0/ to 1/0 (SH:- C/o R/wall at RD 0/850 to 0/860, 0/978 to 1/0 & P/L CC work in km 0/850 to 0/860).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	40.74			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	74.68			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	42			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.80			Per Cubic metre	

5	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.50			Per Cubic metre
6	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.00			Per Cubic metre
4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	7.70			Per Cubic metre
Total :-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Gwal Tilla Saidun road Km 0/00 to 2/500

Estimate Cost :- 4,95,444/-

Earnest Money :- 99000/-

Time Limit :- Two Months

(SW:- C/o R/wall at RD 0/00 to 30/0 & U-shape drain at RD 2/050 to 2/150).

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	106.70			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	94.92			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	23.10			Per Cubic metre	

4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bhilla Sargooni to Malander via Kufru road Km 0/0 to 1/0

Estimate Cost :- 4,85,526/-

Earnest Money :- 9700/-

Time Limit :- Two Months

(SH:- Construction of R/wall at RD 0/010 to 0/022).

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.36			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	115.40			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bhadroon Kona Lahru road Km 5/0 to 12/800

Estimate Cost :- 4,55,272/-

Earnest Money :- 9100/-

Time Limit :- Two Months

(SH:- C/o R/wall in Km 12/370 to 12/390).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.80			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	112.80			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.00			Each	
Total :-						

Executive Engineer
Bhawanra Division
HP PWD Bhawanra

Schedule of Quantity

Name of Work :- Restoration of rain Damage on Thural to Bharanta road Km 0/0 to 4/00

Estimate Cost :- 4,29,200/-

Earnest Money :- 8600/-

Time Limit :- Two Months

(SH:- C/o R/wall at RD 2/890 to 2/900)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	57.50			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	108.00			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Hamirpur Sujampur Thural Maranda road Km 30/0 to 59/775 (SH:- P/L
crate work for protection of Diversion at RD 31/410).

Estimate Cost :- Rs. 2,33,210/-
Earnest Money :- Rs. 4700/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	40.69			Per Cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	85.94			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Duhak Garthoon road (SH:- Construction of R/wall at RD 0/090 to 0/110).

Estimate Cost :- Rs. 4,78,580/-
Earnest Money :- Rs. 9600/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	40.40			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	118.20			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Balakrupi Duhak Dhaniara road (SH:- Construction of R/wall at RD 2/350 to 2/363).

Estimate Cost :- Rs. 4,65,326/-
Earnest Money :- Rs. 9300/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	44.72			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	114.14			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	36			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Santoshi Mata Mandir to Umri via Malander, Garthoon road Km 0/0 to 7/0 (SH:- C/o R/wall with Pusta at RD 6/795 to 6/800).

Estimate Cost :- Rs. 4,45,838/-
Earnest Money :- Rs. 8900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	31.55			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	109.80			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	25			Each	
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.50			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bhadroon Kona Lahru road (SH:- Construction of R/wall at RD 5/560 to 5/580).

Estimate Cost :- Rs. 4,79,080/-
Earnest Money :- Rs. 9600/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	40.40			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	118.20			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	32			Each	
Total :-						



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bairghatta to Sanhoon road Km 0/0 to 7/0 (SH:- C/o R/wall with Pusta at RD 1/885 to 1/900).

Estimate Cost :- Rs. 4,47,088/-
Earnest Money :- Rs. 8900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	31.55			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	109.80			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30			Each	
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.50			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Tikker Balbhurian road Km 0/0 to 4/0 (SH:- C/o R/wall at RD 2/395 to 2/414).

Estimate Cost :- Rs. 4,75,519/-
Earnest Money :- Rs. 9500/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	58.14			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	112.48			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	76			Each	
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	41.40			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Extension of Daroh Garh Jamula road upto Bairghatta Km 4/0 to 11/0 (SH:- C/o R/wall at RD 8/990 to 9/003).

Estimate Cost :- Rs. 4,73,912/-
Earnest Money :- Rs. 9500/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	52.39			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	114.66			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	39			Each	
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer-In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	48.62			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bandahu to Bairghatta road Km 2/300 to 4/330 (SH:- C/o R/wall with Pusta at RD 4/315 to 4/332).

Estimate Cost :- Rs. 4,86,278/-
Earnest Money :- Rs. 9700/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	39.78			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	119.34			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34			Each	
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer-In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.09			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Duhak Garthoon road (SH:- Construction of R/wall at RD 1/260 to 1/274).

Estimate Cost :- Rs. 4,97,498/-
Earnest Money :- Rs. 9900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	34.44			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	122.92			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	38			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Kona Pihri Nahllian road Km 0/0 to 5/0


Estimate Cost :- 4,65,076/-

Earnest Money :- 9300/-

Time Limit :- Two Months

(SH:- Construction of R/wall at RD 2/540 to 2/553).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	44.72			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	114.14			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna