



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 11/09/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 08/09/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

* The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Balance work of Alternative road from Barmala Barrier to Industrial area Golathai in Distt. Bilaspur (HP) Km. 0/0 to 4/165 (SH:- repair of existing of 6.00 meter span R.C.C. slab culvert at Rd 0/080, C/o wing wall length 5.00 meter and C/o V-shape drain at RD 0/180 to 0/310) Deposit work	Rs. 3,26,687/-	Rs. 6,600/-	Rs. 350/-	Three Month
2	Construction of Civil Hospital Markand Gassour in Distt. Bilaspur (HP) (SH:- Repair to Boundary wall. C/o Brick work and painting etc.) Deposit work	Rs. 2,87,456/-	Rs. 5,800/-	Rs. 350/-	Three Month
3	Balance work on Alternative road from Barmala Barrier to Industrial area Golathai in Distt. Bilaspur (HP) Km. 0/0 to 4/165 (SH:- C/o R/wall at RD 1/695 to 1/706 & 1/730 to 1/740) Deposit work	Rs. 3,41,595/-	Rs. 6,900/-	Rs. 350/-	Three Month
4	Restoration of Rain damages on Laraghat Bathoh Bholi road Km. 0/0 to 10/500 (SH:- C/o B/wall at RD 2/280 to 2/290)	Rs. 1,02,709/-	Rs. 2,100/-	Rs. 350/-	Three Month
5	Restoration of Rain damages on Deoth to Lagghat Jamli road Km. 0/0 to 13/180 (SH:- C/o Retaining wall in wire crate at RD 9/225 to 9/235) under stage-I	Rs. 4,95,498/-	Rs. 10,000/-	Rs. 350/-	Three Month
6	Balance work on Alternative road from Barmala Barrier to Industrial area Golathai in Distt. Bilaspur (HP) Km. 0/0 to 4/165 (SH:- Providing and laying Gr-I, G-II & premix carpet & Patch work in various RDs)) Deposit work	Rs. 4,58,194/-	Rs. 9,200/-	Rs. 350/-	Three Month
7	A/R & M/O Rest House Swarghat in Tehsil Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- Providing and fixing submersible pump aet with allied accessories and laying jointing testing of Raising Main)	Rs 1,69,941/-	Rs. 3,400/-	Rs. 350/-	Three Month
8	Construction of Balance work of R/wall along with Play Ground in Govt. High School Dollan at Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- Providing and laying boulder filling behind R/wall along the Play ground at RD 0/0 to 0/063.50) Deposit work	Rs 1,30,047/-	Rs. 2,600/-	Rs. 350/-	Three Month
9	Balance work on Alternative road from Barmala Barrier to Industrial area Golathai in Distt. Bilaspur (HP) Km. 0/0 to 4/165 (SH:- C/o R/wall at RD 1/285 to 1/293 & C/o U-shape drain at RD 1/900 to 1/995) Deposit work	Rs. 3,39,921/-	Rs. 6,800/-	Rs. 350/-	Three Month
10	Restoration of Rain damages on Deoth to Lagghat Jamli road 0/0 to 13/180 (SH:- Providing Back filling behind Retiming wall of wire crate at RD 9/215 to 9/235) under Stage-II	Rs 1,30,536/-	Rs. 2,700/-	Rs. 350/-	Three Month

11	Restoration of Rain damages on link road Harizen Basti Tiun Khas Km. 0/0 to 3/0 (SH:- C/o 900mm dia hume pipe culvert at RD 2/060)	Rs 2,09,131/-	Rs. 4,200/-	Rs. 350/-	Three Month
12	Restoration of Rain damages on link road Harizen Basti Tiun Khas Km. 0/0 to 3/0 (SH:- C/o C/ R/wall at RD 2/040 to 2/050)	Rs 1,64,144/-	Rs. 3,300/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 30-8-23

No.PW/NBT/CB/Tender-State/EA-1/2023-

5955-60

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc- pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

11	Restoration of Rain damages on link road Harizen Basti Tiun Khas Km. 0/0 to 3/0 (SH:- C/o 900mm dia hume pipe culvert at RD 2/060)	Rs 2,09,131/-	Rs. 4,200/-	Rs. 350/-	Three Month
12	Restoration of Rain damages on link road Harizen Basti Tiun Khas Km. 0/0 to 3/0 (SH:- C/o C/ R/wall at RD 2/040 to 2/050)	Rs 1,64,144/-	Rs. 3,300/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 30-8-23

No.PW/NBT/CB/Tender-State/EA-1/2023- 5955-60

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc- pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.								Estimated cost:- Rs.3,26,687/-Only.	
								Earnest Money :- Rs.6,600/-	
								Time:- Three Months.	
NAME OF WORK:- Balance work on Alternative road from Barmala Barrier to Industrial area Goalthai in Distt.Bilaspur(HP) Km 0/0 to 4/165 (SH:- Repair of Existing 6.00 meter span R.C.C Slab Culvert at RD 0/080 an, C/o wing wall length 5.00 meter and C/o V-shape drain at RD 0/180 to 0/310.) (Deposit Work)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
				Figure.	Words.				
1	2	3	4	5	6	7			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.03	cubic metre			Per cubic metre			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate) 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.51	Cubic metre			Per Cubic metre			
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.40	Cubic Metre			Per Cubic Metre			
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate) 40 mm (Forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.40	Cubic metre.			Per Cubic Metre			

5	Providing reinforced concrete in sub-structure complete as per drawings and technical specifications clause 802,804,805,806,807,1202 & 1204 .P.C.C. grade M-15 (i) Nominal mix 1:2:5:5)(One Cement two and half sand five graded stone aggregate 40 mm nominal size.The minimum cement contents should not be less then 225 kg per per cubic meter including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.80	Cubic Metre			Per Cubic Metre	
6	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.000	Cubic metre.			Per Cubic Metre	
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.80	Cubic metre.			Per Cubic Metre	
8	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Nos.			Each	
Total:-							

Executive Engineer
Bilaspur
HR PWD, Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,97,456/-Only.

Earnest Money :- Rs.5,800/-

Time:- Three Months.

NAME OF WORK:- Construction of Civil Hospital Markand Gassour in Distt. Bilaspur (HP) (SH:-Repair to Boundary wall , C/O Brick Work and painting etc) (Deposit Work)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.83	cubic metre			Per cubic metre	
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement :Six coarse sand : Twelve graded stone aggregate 20 mm(Twenty millimeter) nominal size) upto plinth level with cement mortar 1:6 (one cement : Six coarse sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.65	cubic metre			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.97	Cubic Metre			Per Cubic Metre	
4	Brick work with common burnt clay modular bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.70	Cubic Metre			Per Cubic Metre	
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) insuperstructure above plinth level up to floor V level Cement mortar 1:4 (one cement : Four coarse sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.00	Square metre.			Per Square metre.	

6	15 mm (fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: Six fine sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	400.65	Square Meter		Per Square Meter
7	steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Kilogram		Per kilogram
8	Providing and fixing M.S.B.P sheet 1.66 mm to 2mm (One point sixty six millimeter to two millimeter) thick in eaves board/facia/soffits/ceiling including cutting , fixing and welding to steel roof members and applying a coat of red lead primer complete as per the direction of the Engineer-in-Charge (base member of steel work shall be measured and paid for separately) ,including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.60	Square metre.		Per Square metre
9	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete on steel work including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.10	Square Meter		Per Square Meter
10	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. two coats including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	400.65	Square Meter		Per Square Meter
	Total:-				

Executive Engineer
Labour Division No.
J.P.W.D., Malappuram

SCHEDULE OF QUANTITY.							
Estimated cost:- Rs.3,41,595/-Only.							
Earnest Money :- Rs.6,900/-							
Time:- Three Months.							
NAME OF WORK:- Balance work on Alternative road from Barmala Barrier to Industrial area Goalthai in Distt.Bilaspur(HP) Km 0/0 to 4/165 (SH:- C/o R/wall at RD 1/695 to 1/706 & 1/730 to 1/740). (Deposit Work)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
			Figure.	Words.			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.03	cubic metre		Per cubic metre		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.25	Cubic metre		Per Cubic metre		
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.37	Cubic metre.		Per Cubic Metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.00	Nos.		Each		
Total:-							

Executive Engineer,
Bilaspur Division No. 2,
H.P. PWD., Bilaspur (P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,02,709/-Only.

Earnest Money :- Rs.2,100/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Laraghat Bathoh Bholi road km 0/00 to 10/500 (SH:- C/O B/wall at RD 2/280 to 2/290)

Description of items.

Sr No.	Quantity	Rates in		Unit	Amount
		Figure.	Words.		
1	3	4	5	6	7
1	13.90	cubic metre		Per cubic metre	
2	4.10	cubic metre		Per cubic metre	
3	21.60	Cubic metre		Per Cubic metre	
4	6.00	Nos.		Each	
Total:-					

SCHEDULE OF QUANTITY.									
						Estimated cost:- Rs.4,95,498/-Only.			
						Earnest Money :- Rs.10,000/-			
						Time:- Three Months.			
NAME OF WORK:-Restoration of Rain Damages on Deoth to Lagghat Jamli road 0/00 to 13/180 (SH:- C/o R/wall in wire crate at RD 9/225 to 9/235) (under Stage-I)									
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
1	2	3	4	5	6	7			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	56.30	cubic metre		Per cubic metre	7			
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire confirming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	156.25	Cubic metre		Per Cubic metre				
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.80	Cubic metre.		Per Cubic Metre				
						Total:-			


 Engineer Division
 ROAD BILASPUR

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.4,58,194/-Only.			
				Earnest Money :- Rs.9,200/-			
				Time:- Three Months.			
NAME OF WORK:- Balance work on Alternative road from Barmala Barrier to Industrial area Goalthai in Distt.Bilaspur(HP) Km 0/0 to 4/165 (SH:- Providing & Laying Gr.-I, G-II & Premix Carpet & Patch Work in various Rds) (Deposit Work)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	38.25	Cubic metres			Per Cubic metre	7
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification clause No. 405 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.69	Cubic metres			Per Cubic metre	
3	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	382.50	square metre			Per square metre	
4	Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting (RS-1) bituminous emulsion on bituminous surface @ 0.25 kg/ sqm (zero point twenty five kilogram per square meter) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	937.19	square metre			Per square metre	

	Providing , laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre)/compacted thickness composed of crushed stone aggregate 13.2 mm to 5.6 mm (Thirteen point two millimetre to five point six millimetre) @ 0.27 cubic metres (Zero point two seven) per 10 square metre (Ten Square metre) mixed with penetration grade paving bitumen V.G-30 (Viscosity grade-Thirty) at the rate of 14.6 kg.(Fourteen point six kilogramme) per ten square metre of road surface to required line, grade and level to serve as wearing course on a previously prepared base including mixing and heating binder and aggregate in suitable plant, laying with paver finisher and rolling with a three wheel 80-100 KN (Eighty - hundred) capacity static road roller finished to required level and grade to be followed by seal coat of type-B by mechanical means as per MORD technical specification 2014. clause 508 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	937.19	Square metre.			Per Square metre.
6	Providing and laying seal coat for sealing the voids in bitumenous surface laid to the specified levels, grade and cross fall using Type-B and as per Technical Specifications,2014 Clause 510 using Bitumen (S-90) by Mechanical means including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax,building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	937.19	Square metre			Per Square metre
	Total:-					

Executive Engineer,
Bilaspur Division No. 2,
HP. PWD., Bilaspur

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.1,69,941/-Only.						
Earnest Money :- Rs.3,400/-						
Time:- Three Months.						
NAME OF WORK:- A/R & M/O Rest House Swarghat in Teh. Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH):- Providing & Fixing Submersible pump set with allied accessories and laying Jointing Testing of Raising Main)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Supply and erection submersible pump set of KSB make Model 2C/25 conforming to ISI 9034-1976 along with a directly coupled submersible tupe squirrel cage electric induction motor suitable for operation of 230 volt single phase 50 C.P.S, AC Supply with water lubricated bearings, provided with pivoted segment type thrust bearing to with stand vertical pressure with minmum wear and tear and dully fitted with device to take up the expension of water with hitting of motor complete in all respect and to the entire satisfaction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each	
2	Providing and fixing single Panel board of BS /L&T make with Automatic timer function, Amp meter and volt meter, over load relay, indicator set. Connector, relay, push button etc. complete in all respect. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each	
3	Supply and fixing submersible cable 4 (four) Squire Millimeter submersible cable of L& T /Havells. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	130.00	Running Metre		Per Running Metre	
4	Supplying and fixing rope wire 6 (six) Squire Millimeter dia suitable to wear the weight of Submersible motor pumps set and riser pipe etc. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	100.00	Running Metre		Per Running Metre	
5	Providing laying jointing testing and lowering in bore 25 mm (Twenty Five Millimeter) dia PPR pipe (PN20/SDR6) 3 layer as standard ISI make including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.00	Running Metre		Per Running Metre	

	Providing and fixing Horizontal nipple connected for submersible pump and PPR riser pipes including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each	
7	Providing and fixing GI Bend, Elbow, Tee Nipple 32 mm dia including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each	
8	Providing and fixing Clamp set Complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each	
9	Providing and Fixing 2 (two) crore alluminium cable 10 (ten) Squire Millimeter Aicon/ Arkaylite make including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	135.00	Running Metre		Per Running Metre	
10	Lifting of hand pump with Ceylinder, connecting Rod, GI pipe head etc and Lowering of submersible motor and pump in the bore well and to the entire satisfaction of the Engineer-in-Charge. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each	
	Total:-					

Executive Engineer,
Bilaspur Division No. 2,
U.P.

SCHEDULE OF QUANTITY.						
						Estimated cost:- Rs.1,30,536/-Only.
						Earnest Money :- Rs.2,700/-
						Time:- Three Months.
NAME OF WORK:-Restoration of Rain Damages on Deoth to Lagghat Jamli road 0/00 to 13/180 (SH:- Providing Back filling behind R/wall of wire crate at RD 9/215 to 9/235)						
(Under Stage.II)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	111.00			Per Cubic Metre	
						Total:-


 Assistant Engineer,
 Assistant Division No. 9
 UPWD Bilaspur-17400


SCHEDULE OF QUANTITY.					
Estimated cost:- Rs.3,39,921/-Only.					
Earnest Money :- Rs.6,800/-					
Time:- Three Months.					
NAME OF WORK:- Balance work on Alternative road from Barmala Barrier to Industrial area Goalthai in Distt.Bilaspur(HP) Km 0/0 to 4/165 (SH:-C/o R/wall at RD 1/285 to 1/293 & C/o U-shape drain at RD 1/900 to 1/995). (Deposit Work)					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2	3	4	5	6
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	71.05	cubic metre		Per cubic metre
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.30	Cubic metre		Per Cubic metre
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.06	Cubic metre.		Per Cubic Metre
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.20	Cubic metre.		Per Cubic Metre

Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Nos.			Each	
Total:-						


 Executive Engineer,
 Bilaspur Division No. 2,
 HP. PWD., Bilaspur (H.P.).

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=1,30,047 /-Only.		
				Earnest Money:- Rs.= 2,600/-		
				Time:- Three Months.		
Name of work :- Construction of Balance Work of R/Wall along with the Play Ground in Govt. High School Dollan at Sh. Naina Devi JI Distt. Bilaspur (HP) (SH:- Providing & Laying Boulder filling behind R/Wall along the Play Ground at RD 0/00 to 0/063.50) (Deposit work)						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3 Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 110.49	5		Per Cubic Metre	6
Total						

Executive Engineer,
Bilaspur Division No. 2,
H.O. P.W.D. Bilaspur

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.2,09,131/-Only.						
Earnest Money :- Rs.4,200/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on link road Harizan Basti Tiun Khas km 0/00 to 3/00 (SH:- C/o 900 mm dia Hume pipe culvert at RD 2/060)						
Sr	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 42.72	4 cubic metre	5 Per cubic metre	6 Per cubic metre	7 7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90	Cubic metre		Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.79	Cubic Metre		Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.88	Cubic metre.		Per Cubic Metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement :Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	7.50	Running Meter		Per Running Meter	

6	Providing & Laying Cement concrete flooring 1:2:4 (one cement :Two coarse sand :Four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm (Forty millimeter) thick with 20 mm (Twenty millimeter) nominal size stone aggregate including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.26	Square Meter		Per Square Meter
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3-8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.96	Cubic metre.		Per Cubic Metre
8	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Nos.		Each
Total:-					


 Engineer Division No. 4
 SPPWD Bhaspar-174001
 (21)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,64,144/-Only.

Earnest Money :- Rs.3,300/-

Time:- Three Months.

R/wall at RD 2/040 to 2/050)

NAME OF WORK:- Restoration of Rain Damages on link road Harizan Basti Tiun Khas km 0/00 to 3/00 (SH:- C/o Description of items.

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		3	4	Figure.	Words.		
1	2	3	4	Figure.	Words.	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.10	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.50	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.60	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.			Each	
Total:-							

Executive Engineer,
Bilaspur Division No. 4
BPPVD Bilaspur-17400