



Tel.01899-299219.

cepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2023-24-
To

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

4/80-82

Dated:- 14-08-2023

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

**Executive Engineer,
Chowari Division,
HPPWD, Chowari.**

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,
Chowari Division,
HPPWD, Chowari.**

Certificate

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2023-24-4182-4233...dated...14/07/23 is emergent nature and in Public interest.

~~Executive Engineer,~~
Chowari Division,
HPWD, Chowari.



Tel.01899-299219.
cepwd-chowari@hp.gov.in

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Scaled percentage/item rate tender (s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari o behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 1 Date of receipt of application for the tender

Form a/w requisite documents: -

21/08/2023

- 2 Date of issued/sale of tender form against

Cash payment (non refundable).

22/08/2023_

The tender shall be received up to 11.00 AM on 23/08/2023 and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 23/08/2023.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	C/o Link Road from Garnota (Bhadela) to Pukhru via Padwal km 0/0 to 6/400 (SH:- C/o 900 mm dai hume pipe culvert at RD 0/975 alongwith wing walls)	325261/-	6505/-	350/-	One month	Class-D
2	Restoration of Rain Damage on Nurpur Sanjha Nallah Lahru Tunuhatti Road km 25/0 to 40/810 (SH :-C/o R/wall at RD 35/694 to 35/702.90)	493728/-	9875/-	350/-	One month	Class-D
3	C/o Link Road from Garnota (Bhadela) to Pukhru via Padwal km 0/0 to 6/400 (SH:- C/o 900 mm dai hume pipe culvert at RD 1/245 alongwith wing walls)	422681/-	8454/-	350/-	One month	Class-D
4	C/o Link Road from Dugred to Naloh Road km 0/0 to 6/300 (SH:- C/o 900 mm dai hume pipe culvert at RD 0/305 alongwith wing walls)	417639/-	8353/-	350/-	One month	Class-D
5	Restoration of rain damage on Link Road Banooni to Awan km 0/0 to 3/00 (SH:- Construction of Retaining walls at RD 2/250 to 2/270)	467762/-	9400/-	350/-	One month	Class-D
6	Restoration of rain damage on Patka to Dalhousie Road Km 14/00 to 32/00(SH:- Construction of Retaining walls at RD 28/010 to 28/023)	492657/-	9853/-	350/-	One month	Class-D
7	Restoration of rain damage on Chowari Kainthly Road km 0/0 to 12/570 (SH:- Construction of Retaining walls at RD 1/375 to 1/387)	460532/-	9300/-	350/-	One month	Class-D
8	Restoration of rain damage on Patka to Dalhousie Road Km 32/0 to 45/00 (SH:- Repair of RCC slab culvert abutment at RD 33/485)	463810/-	9300/-	350/-	One month	Class-D

9	Restoration of Rain Damage on Dhura Sapar to Pukhra (Portion Kunna to Kut Palahan) km 0/0 to 4/030 (SH :- C/O R/wall at RD 2/485 to 2/494.50 & 2/528.50 to 2/535) Near Suhaglu School)	486025/-	9721/-	350/-	One month	Class-D
10	Restoration of rain damage on Chowari Kainthly Road km 0/0 to 12/570 (SH:- Construction of Retaining walls at RD 1/660-1/670)	316132/-	6400/-	350/-	One month	Class-D
11	Restoration of rain damage on Patka to Dalhousie Road Km 32/00 to 45(SH:- Construction of Retaining walls at RD 33//486.50 to 33/498.50)	252650/-	5100/-	350/-	One month	Class-D
12	C/o Chowari Kainthly Road km 0/00 to 12/570 (SH:- P/L 80 mm thick paver block at RD 12/352 to 12/385) BASP	313366/-	6267/-	350/-	One month	Class-D
13	Restoration of rain damages on Shahpur Sihunta Chowari via Jot Chamba Road km 24/0 to 40/0 (SH:- C/o B/wall in wire crate at RD 24/354 to 24/404)	435232/-	8800/-	350/-	One month	Class-D
14	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/810 to 76/00 (SH:- Construction of R/ wall with pusta at RD 51/750 to 51/756.80)	495777/-	9916/-	350/-	One month	Class-D
15	Restoration of rain damage on Chowari Kainthly road Km 0/0 to 12/570 (SH:- C/o R/wall at Rd 2/180 to 2/192.50).	479610/-	9592/-	350/-	One month	Class-D
16.	Construction of link road from Dungred to Naloh road Km 0/0 to 6/300 (SH:- C/o R/wall at Rd 0/120t to 0/140).	493728/-	9875/-	350/-	One month	Class-D
17.	Restoration of rain damage on various roads under Kakira Sub Division (SH:- Hiring of excavator cum loader for removal of slips). Section Mail	49228/- 492450/-	10000/-	350/-	One month	Class-D

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No. /Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
- 4 Application without all documents will not be entertained.
- 5 Proxy application will not be entertained.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

No. PWD-CHW/Tender /2023-24-

4183-4233

Dated:-

14-08-2023

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 The BDO Bhattiyat.
- 7 Sub Divisional Magistrate/B.D.O/Tehsildar Chowari.
- 8 Notice Board of this office.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.


SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Link Road from Garnota (Bhadela) to Pukhru via Padwal km 0/0 to 6/400 (Sub Head:- C/O 900 mm dia H.P. culverts at RD 0/975 along with wing walls)

Estimated Cost	Rs. 3,35,261/-
Earnest Money	Rs. 6705/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts as per the direction of the Engineer in Charge. The rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	60.58			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	2.24			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	18.69			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	7.50			Per running metre	
7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	28.02			Per cubic metre	

8	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V), 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	12			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	3.60			Per cubic metre	



 Executive Engineer,
 Choward Division,
 HP, P.W.D. Choward

Schedule of Quantity

Estimated Cost	Rs 4,93,728/-
Earnest Money	Rs. 9875/-
Time Limit	Three months

Name of work:- Restoration of rain damage on Nurpur Sanjha Nallah Lahru Tunnuhatti Road km 25/0 to 40/810 (SH:- Construction of R/ wall at RD 35/694 to 35/702.90)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	55.27			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads.lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	92.56			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV) ; 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 asper the directions of the Engineer-incharge. i/c carriage of materials with in all leads.lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	28.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	13.08			Per cubic metre	
Total						


Executive Engineer
 Chowari Division
 H.P.W.D. Chowari

SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Link Road from Garmota (Bhadela) to Pukhru via Padwal km 0/0 to 6/400 (Sub Head:- C/O 900 mm dia H.P. culverts at RD 6027 1/245 along with wing walls)

Estimated Cost Rs. 4,22,681/-
Earnest Money Rs. 84,54/-
Time Limit Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	60.08			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	2.32			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	20.41			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection, works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government.	7.50			Per running metre	
7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	43.8			Per cubic metre	

8	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1 V), 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 asper the directions of the Engineer-in-charge. i/c carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	16			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	5.43			Per cubic metre	


 Executive Engineer,
 Chowari Division,
 HP. PWD. Chowari

14


Schedule of Quantity

NAME OF WORK:- C/o Link Road from Bughted to Naloh Road km 0/0 to 6/300 (SH:- C/o 900 mm dal hume pipe culvert at RD 0/305 alongwith wing walls)

Estimated Cost	Rs. 4,17,639/-
Earnest Money	Rs. 8353/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Estimate in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	69.58			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	2.24			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	18.69			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST and other taxes imposed by the Government.	7.50			Per running metre	
7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	43.8			Per cubic metre	

8	Providing weep holes in brick masonry/ stone masonry/ pila reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt	12			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty, Malkana Toll tax, sales tax or any other taxes imposed by the Govt	6.56			Per cubic metre	


 Executive Engineer,
 Chowari Division,
 HP, PWD, Chowari

5

Schedule of Quantity

NAME OF WORK:- Restoration of rain damage on Link Road Banooni to Awan km 0/00 to 3/00 (Sub Head:- C/o Retaining wall at RD 2/250 to 2/270)

S.No.		Description	Quantity	Rate		Unit	Amount
				in Fig.	in Word		
1		Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	35.10			Per cubic metre	
2		Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	84.20			Per cubic metre	
3		Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 asper the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	38.00			Each	
4		Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes	29.80			Per cubic metre	
Total							


Executive Engineer
Chowari Division
HPWD Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Patka to Dalhousie Road Km 14/00 to 32/00(SH:- Construction of Retaining walls at RD 28/010 to 28/023)

Estimated Cost	Rs 4,92,657/-
Earnest Money	Rs. 9853/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	42.25			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	94.38			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	33.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.29			Per cubic metre	
Total						

Executive Engineer
 Chowari Division
 Hppwd Chowari



Schedule of Quantity

Name of work:- Restoration of rain damage on Chowari Kalnithly Road km 0/0 to 12/5/70 (SH:- Construction of Retaining walls at RD 1/375 to 1/387)

Estimated Cost	Rs 4,60,532/-
Earnest Money	Rs. 9300/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detestious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	35.70			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	87.12			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technical specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	30.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.40			Per cubic metre	
Total						


Executive Engineer
 Chowari Division
 HPPYD Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Patka to Dalhousie Road Km 32/0 to 45/00 (SH:- Repair of RCC slab culvert abutment at RD 33/485)

Estimated Cost	Rs. 4,63,810/-
Earnest Money	Rs. 9300/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	48.96			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 1109 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	3.42			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 804, 1202, and 1204 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	63.21			Per cubic metre	
4	Providing and laying concrete flooring 1:2:4 (one cement isto two sand isto four graded/ crushed aggregate 20 mm nominal size) laid over cement concrete bedding complete as per drawing and technical specification within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	1.37			Per cubic metre	
5	Providing weep holes in brick masonry/ stone masonry/ pain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 asper the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	5.00			Each	
Total						

Executive Engineer
Chowari Division
Hppyd Chowari

SCHEDULE OF QUANTITY

Restoration of Rain Damage on DhuraSapar to Pukhra (Portion Kunna to Kut Palahan) km 0/0 to 4/030 (SH :- C/O R/wall at RD 2/485 to 2/494.50 & 2/528.50 to 2/535) Near Sahagla School)

Estimated Cost	Rs. 486025/-
Earnest Money	Rs. 9721/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 3/05.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidentals. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	46.537			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	92.21			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	35.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.06			Per cubic metre	
Total						


Executive Engineer
Chowari Division
Hppva Chowari

Schedule of Quantity

Estimated Cost	Rs 3,16,132/-
Earnest Money	Rs. 6400/-
Time Limit	Three months

Name of work:- Restoration of rain damage on Chowari Kaintly Road km 0/0 to 12/570 (SH:- Construction of Retaining walls at RD 1/660-1/670)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	23.50			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	58.80			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	22.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	14.10			Per cubic metre	
Total						


Executive Engineer
 Chowari Division
 HPPad Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Patka to Dalhousie Road Km 32/0 to 45/00 (SH:- Construction of wing wall at RD 33/486.50 to 33/498.50)

Schedule of Quantity		Estimated Cost			
		Earnest Money	Rs 2,52,650/-		
		Time Limit	Rs. 5100/-		
			Three months		
Name of work:- Restoration of rain damage on Patka to Dalhousie Road Km 32/0 to 45/00 (SH:- Construction of wing wall at RD 33/486.50 to 33/498.50)					
S.No.	Description	Quantity	Rate	Unit	Amount
			in Fig.	in Word	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	20.24			Per cubic metre
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803,1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	47.04			Per cubic metre
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 asper the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	18.00			Each
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	10.88			Per cubic metre
Total					

Executive Engineer
Chowari Division
HPPYD Chowari

SCHEDULE OF QUANTITY

Name of work:- Construction of Chowari to Kainthly Road km 0/00 to 12/570 (SH:- Providing and laying 80 mm thick Paver Block at RD 12/352 to 12/385)

Estimated Cost Rs. 313366/-
Earnest Money Rs. 6267/-
Time Limit Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Loosening of the ground upto a level of 300 mm below the subgrade level, watered, graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per Technical Specification Clause 303.5.2. within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	49.52			Per cubic metre	
2	Stone soling property hand packed filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and camber including spreading, watering and rolling of binding materials moonum or earth etc. complete as per specification, 100 mm (one hundred millimetre) thick including finished work materials and labour within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	24.75			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:4:8) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	16.50			Per cubic metre	
4	Providing and laying heavy duty precast cement concrete 80 m thick interlocking paver blocks vibrocompacted upto M-50 grade concrete edge blocks 300 mmx 300mmx 150mm of grey/coloured over the shade of block including curing, rubbing and polishing complete. Interlocking concrete block pavement shall consists of surface layer of appropriate size concrete paving block paved and compacted over bedding sand layer of specified grading which is spread over a properly constructed and profiled base course and is bounded by properly installed edge restraint the joint shall be filled by fine sand of specified grading. The concrete paving block shall confirm to the relevant IS standard and as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	165.00			Per square metre	
Total						

Executive Engineer
Chowari Division
Hppwd Chowari

Schedule of Quantity

Name of work :- Restoration of rain damage on Shahpur Silhunta Chowari Road Km 24/0 to 40/00 (SH:- C/O crate work in B/Wall at 24/354 to 24/404)

Estimate Cost :- Rs.	Rs 4,35,232/-
Earnest Money	Rs 8800/-
Time Limit	Three Month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per technical specification clause 1603.1 as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	64.00			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimeter) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	117.19			Per cubic metre	
Total						

Executive Engineer
Chowari Division
HPWD Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/810 to 76/00 (SH:- Construction of R/ wall with pista at RD 51/750 to 51/756.80)

Estimated Cost
Earnest Money Rs. 4,95,777/-
Time Limit Rs. - 9916/-
Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	34.14			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	92.07			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	25.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	16.93			Per cubic metre	
Total						


Executive Engineer
Chowari Division
HPPYD Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Chowari Kalinthy Road km 0/0 to 12/570 (SH:- Construction of R/ wall at RD 2/180 to 2/192.50)

Estimated Cost	Rs 479610/-
Earnest Money	Rs 9392/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	36.81			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	90.75			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	32.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	24.00			Per cubic metre	
Total						



Executive Engineer
 Chowari Division
 H.P.W.D Chowari

Schedule of Quantity

Name of work:- Construction of Link Road from Dugred to Naloh km 0/0 to 6/300 (SH:- Construction of R/ wall at RD 0/120 to 0/140)

Estimated Cost	Rs. 4,93,728/-
Earnest Money	Rs. 9875/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidentals. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	34.59			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	110.80			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	34.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.16			Per cubic metre	
Total						


Executive Engineer
 Chigwari Division
 H.P.W.D. Chowari

Schedule of Quantity

Name of Work :- Restoration of Rain Damage on Kakira Sub Division (Section Mail). (SI :- Hiring of Hydraulic excavator Cum loader for removal of slips .

S.No.	Description	Quantity	Rate	in Fig.	in Word	Unit	Amount
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	469				Per Hours	
Total :-							

Executive Engineer
Chowari Division
HPPWD, Chowari