

**Himachal Pradesh  
Public works Department**

**Notice inviting Tender**

Sealed item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **13-09-2023 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **12-09-2023**. The applications for issue of tender forms will be received up to **2.00 P.M. on 11-09-2023**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Cost of Tender form	Time limit	Class of contract or
1	RRD on Jathera to Katal via Gugga Mandir Tamroh Chauntra Upper Pali road km 0/000 to 2/000 (SH: Construction of PCC Breast wall at RD 0/120 to 0/145)	191575/-	4000/-	350/-	Two Months	D&C
2	RRD on Chambi Kangar Jaidevi road km 0/000 to 5/500 (SH: Construction of PCC R/wall at RD 1/270 to 1/285)	246323/-	5000/-	350/-	Two Months	D&C
3	RRD on Chambi Kangar Jaidevi road km 0/000 to 5/500 (SH: Construction of R/wall at RD 1/380 to 1/390)	166390/-	3500/-	350/-	Two Months	D&C
4	RRD on Chambi Kangar Jaidevi road km 0/000 to 5/500 (SH: Construction of R/wall at RD 1/720 to 1/735)	248186/-	5000/-	350/-	Two Months	D&C
5	RRD on Dhanotu Rohangaloo road km 0/00 to 32/400 (SH: Construction of R/wall at RD 7/440 to 7/452)	225404/-	5000/-	350/-	Two Months	D&C
6	RRD on Dhanotu Rohangaloo road km 0/00 to 32/400 (SH: Construction of R/wall at RD 8/820 to 8/795)	289541/-	6000/-	350/-	Two Months	D&C
7	RRD on Mahadev Dinak road via Behli in km 0/000 to 5/000 (SH: Providing and laying Paver Block from km 4/300 to 4/442) Under OTMNP	499061/-	10000/-	350/-	Two Months	D&C
8	RRD on Dhanotu to Dhanotu Chowk road km 0/000 to 1/00 (SH: P/L Cement concrete 1:3:6 under interlocking paver in km 0/00 to 0/040 and U shape drain at RD 0/0 to 0/045)	261236/-	5300/-	350/-	Three Months	D&C
9	Construction of Link road from Jaidevi to Bhalana via Mehli road km 0/000 to 2/400 (SH: Providing and laying Stone soling and CC Pavement in km 2/290 to 2/400)	3,97,460/-	8000/-	350/-	Three Months	D&C
10	SDF/2023/143 Repair of road Sarda to upper to Lower Kathla GP Delag Tikkari RD 0/000 to 4/000 (SH: Construction of Unlined drain, Cutting of branches, surface dressing, earth filling and removal of slips at various KM)	2,37,708/-	5000/-	350/-	Two Months	D&C
11	SDF/2023/142 Repair of road main road Panchyat Ghar to village Shihari in GP Delag Tikkari km 0/000 to 6/000 (SH: Construction of Unlined drain, Cutting of branches, surface dressing, earth filling and removal of slips at various KM)	2,97,387/-	6000/-	350/-	Two Months	D&C
12	RRD on Chail Moviseri road km 0/000 to 11/200 (SH: Removal of land slide slips at various RDs)	4,93,767/-	10000/-	350/-	Two Months	D&C

Certified that tender of above works are being called for emergent nature in exigency of public interest.

**GENERAL CONDITIONS:-**

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.

PTO

5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in-Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

No. PW-GHR-Tender/NIT/2023

6066-85

Executive Engineer,  
Gohar Division (B&R),  
HPPWD Gohar  
Dated 25/8/2023

Copy along with Tender inviting Notice forwarded for Information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1<sup>st</sup>Circle, HP.PWD Mandi.
4. The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar.
8. Various contractors.
9. Notice Board/ DB/AB.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD Gohar.

## SCHEDULE OF QUANTITY

Estimate Cost: Rs 1,91,575/- only  
Earnest Money: Rs 4,000- only  
Time :- Two Months

Name of Work :- RR damages on Jatehra to katal via Gugga Mandir Tamroh Chauntra Upper Pail road KM 0/000 to 2/000 (SH:- Construction of PCC Breast wall at RD 0/120 to 0/145).

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	In Word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead, lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads, lifts and cartage of materials and other incidentals.	26.75			per Cubic metre	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802.803,1202 & 1203 within all leads, lifts and cartage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	37.40			per Cubic metre	
3	-Charge complete in all respect. Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm ( one hundred millimetre ) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	10.00			Each	
					Total	

Executive Engineer  
B & R Division  
H.P.R.W.D Gohar



# SCHEDULE OF QUANTITY

Name of Work :- RRD on Chambi Kangar Jaidevi road km 0/00 to 5/5000 ( SH:- Construction of P.C.C. RWalls at RD 1/270 to 1/285)

Estimate Cost: Rs 2,46,323/- only  
Earnest Money: Rs 5,000- only  
Time :- Two Months

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Ward		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	29.10	cum		per Cubic metre	
2	Providing and laying in position cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) of specified grade excluding the cost of centering and shuttering with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	52.41	cum		per Cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	6.30	cum		per Cubic metre	
4	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment wing wall return wall with 100 mm ( one hundred millimetre ) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614.709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	14.00	Nos		Each	
					Total	

Signature of Engineer  
Deputy Engineer (B&S)  
HPPWD Gannar

# SCHEDULE OF QUANTITY

Name of Work :-RRD on Chambhi Kangar Jaidevi road km 0/00 to 5/5000 ( SH:- Construction of R/Walls at RD 1/380 to 1/390)

Estimate Cost: Rs 1,66,390- only  
Earnest Money: Rs 3500- only  
Time :- Two Months

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	27.70	cum		per Cubic metre	
2	Providing and laying in position cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) of specified grade excluding the cost of centering and shuttering with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	34.99	cum		per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads, lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	3.30	cum		per Cubic metre	
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm ( one hundred millimetre ) dia PVC pipe extended through the full width of the structures with slope of 1 (V) :20 (H) towards drawing face complete as per drawing and technical specification clause 614.709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	10.00	Nos		Each	
					Total	

*[Signature]*  
Executive Engineer  
Gohar Division (B&R)  
HPPWD Gohar

# SCHEDULE OF QUANTITY

Name of Work :-RRD on Chambli Kangar Jaidevi road km 0/00 to 5/5000 ( SH:- Construction of R/Walls at RD 1/720 to 1/735)

Estimate Cost: Rs 2,48,186/- only  
Earnest Money: Rs 5,000- only  
Time :- Two Months

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	33.35			per Cubic metre	
2	Providing and laying in position cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) of specified grade excluding the cost of centering and shuttering with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	52.50			per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads, lifts and cartage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	7.65			per Cubic metre	
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm ( one hundred millimetre ) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614.709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	10.00			Each	
					Total	

Executive Engineer  
Gobar Division (B&R)  
HPGWB Gobar



## SCHEDULE OF QUANTITY

Name of Work :- RRD on Dhanotu to Rohangaloo road km 0/00 to 32/400 ( SH:- Construction of RWalls at RD 7/440 to 7/452)

Estimate Cost: Rs 2,25,404/- only  
Earnest Money: Rs 5,000- only  
Time :- Two Months

S. No.	Sub Head and item of work	Dyl.	Figure	Rate in		Unit	Amount
				Word			
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	34.56	cum			per Cubic metre	-
2	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crashead stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 M10 within all leads , lifts and carriage of materials and other Incidentals as per direction of Engineer -in -Charge complete in all respect	4.41	cum			per Cubic metre	-
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 ( random rubble masonry in cement mortar . 1:6( one cement : six sand ) within all leads , lifts and carriage of materials and other Incidentals as per direction of Engineer -in -Charge complete in all respect	21.08	cum			per Cubic metre	-
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other Incidentals as per direction of Engineer -in -Charge complete in all respect	22.84	cum			per Cubic metre	-
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other Incidentals as per direction of Engineer -in -Charge complete in all respect.	6.72	cum			per Cubic metre	-
	Total						

Executive Engineer  
Gohar Division (B&R)  
FFP, PWD Gohar.

# ⑥ **SCHEDULE OF QUANTITY**

**Name of Work :- R/R Damages on Dhanotu to Rohangaloo road KM 0/00 to 32/400 (SH:- C/O R/Wall at RD 8/780 to 8/735)**

Estimate Cost: Rs 2,89,541.00/- only  
 Earnest Money: Rs 6,000- only  
 Time :- Two Months

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead, lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads, lifts and carriage of materials and other incidentals.	32.85	cum		per Cubic metre	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads, lifts and carriage of materials and other incidentals. as per direction of Engineer -in -Charge complete in all respect	18.00	cum		per Cubic metre	
3	Random rubble masonry Stone masonry in cement mortar in (1:6) for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect	18.60	cum		per Cubic metre	
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect	26.98	cum		per Cubic metre	
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads, lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect	9.45	cum		per Cubic metre	
	<b>Total</b>					



# SCHEDULE OF QUANTITY

Estimate Cost: Rs.4,99,061/- only  
 Earnest Money: Rs 10,000/- only  
 Time : Three month

OTMNP

Name of Work :- RRD on Mahadev Dinak road via Behli in km 0/00 to 5/00(SH:- Providing and laying Paver block from km 4/300 to 4/442) Under

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Fig.	Word		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406. as per direction of Engineer - in - charge.	43.31 cum			per Cubic metre	1
2	Providing and Laying of interlocking concrete Block pavements having thickness 80 mm. as per drawings and Technical Specification clause 1504. within all leads, lifts and carriage of materials and other incidentals. as per direction of Engineer - in - charge.	433.10 cum			per Cubic metre	1
		Total				

Executive Engineer  
 Gohar Division (R.R.)  
 HPPWD Gohar

(78)

## SCHEDULE OF QUANTITY

Estimate Cost: Rs. 2,61,236/- only  
Earnest Money: Rs 5300/- only  
Time : One month

**Name of Work :-** R.R Damages on Dhanotu to Dhanotu Chowk road km 0/00 to 1/00 (SH:- Providing and laying cement concrete 1:3:6 under interlocking paver in km 0/00 to 0/040 and C/o U-shape drain at RD. 0/00 to 0/045)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Ward		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead, lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads, lifts and carriage of materials and other incidentals.	18.750 cum			per Cubic metre	-
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications clause 802.803.1202 & 1203 P.C.C. grade M-10 nominal mix 1: 3: 6 (one cement : three sand : six graded stone aggregate 20mm (twenty millimeter) within all leads, lifts and carriage of materials and other incidentals.	51.960 cum			per Cubic metre	-
					Total	-

*M.C.C.*  
**Executive Engineer**  
B & R Division  
H.P.P.W.D Gohar



QUANTITY

Cost: Rs

2,37,708.00 Only  
5,000.00 Only

9

SCHEDULE OF QUANTITY

Estimate Cost: Rs.3,97,460/- only  
Earnest Money: Rs 8,000/- only  
Time : Two Months

Name of Work :- Construction of link road from jaidevi to Bhalana via Mehli road KM 0/000 to 2/4000( SH:- Providing and Laying Stone soling and CC Pavement in KM 2/290 to 2/400)

S. No.	Sub Head and item of work	Qty.	Rate In		Unit	Amount
			Figure	Word		
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per direction of Engineer -in -Charge complete in all respect.	47.64 cum			Per Cubic metre	-
2	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 PCC 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) with in all leads lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	47.64 cum			Per Cubic metre	-
					Total	-

Executive Engineer  
B & R Division  
H.P.PWD Gohar

## SCHEDULE OF QUANTITY

Estimate Cost: Rs 2,37,708.00 Only  
 Earnest Money: 5,000.00 Only  
 Time :- Two Months

Name of Work :- SDF/2023/143 Repair of road Sarda to Upper to Lower Kathla GP Delag Tikkari RD 0/000 to 4/000( SH:- Construction of Unlined drain, Cutting of Branches, surface dressing, earth filling and removal of slips at various KM) Deposit work

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By Mechanical Means	2000.00			Per Running metre	
2	Cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914 including carriage of materials with in all leads and lifts as per the direction of Engineer - in - Charge.	5040.00			Per Square Meter	
3	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	957.66			Per Cubic Metre	
4	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including all leads, lifts of material and other incidentals.	331.90			Per Cubic metre	
5	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including carriage of materials with in all leads and lifts as per the direction of Engineer - in - Charge.	594.00			Per Square Metre	
	<b>Total</b>					



## SCHEDULE OF QUANTITY

Estimate Cost: Rs 2,97,387.00 Only  
 Earnest Money: 6,000.00 Only  
 Time :- Two Months

Name of Work :- SDF/2023/142 Repair of road Main road Pachayat Ghar to Village Shihari in GP Delag Tikhari KM 0/000 to 5/000 ( SH:-  
 Construction of Unlined drain, Cutting of Branches, surface dressing, earth filling and removal of slips at various KM) Deposit work

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By Mechanical Means	2500.00			per Running metre	
2	Cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914 including carriage of materials with in all leads and lifts as per the direction of Engineer - in - Charge.	7000.00			Per Square Meter	
3	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	1280.53			Per Cubic Metre	
4	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including all leads, lifts of material and other incidentals.	326.25			Per Cubic metre	
5	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including carriage of materials with in all leads and lifts as per the direction of Engineer - in - Charge.	720.00			Per Square Meter	
	<b>Total</b>					

12

## SCHEDULE OF QUANTITY

Estimate Cost: Rs. 493767/- only  
Earnest Money: Rs 10000- only  
Time : Two month

**Name of Work :-** RRD on Chail Moviseri road km 0/000 to 11/200 (SH:- Removal of Land slide slips at various RDs)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with lift upto 1.5 m and lead upto 100 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals charges.	4725.04 cum			per cubic metre	-
					Total	-

  
Executive Engineer  
Gohar Division  
HPPWD Gohar