



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**

PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023-

4638

Dated:- 23 .

08
23

To


✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :-

Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 23.08.2023 per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. As the works mentioned in the Tender Notice are urgent in nature.

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **06.09.2023 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 04.09.2023** for which the application should reach in this office **upto 1.00 PM 04.09.2023**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.


Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Rashog Deyom road Km. 0/00 to 9/00 under Karsog Sub-Division (SH:- Hiring of JCB/Excavator cum loader for removal of slips from Km. 15/00 to 19/00 at various RDs)	99,000/-	1,980/-	One month	350/-
2	R/R damages on various roads under Karsog Sub-Division (SH:- C/o Unlined surface drain, making of earthen shoulders and maintenance of berms at various RDs)	98,094/-	2000/-	One month	350/-
3	R/R damages on Salana to Mehendi road Km. 0/00 to 3/00 (SH:- Removal of slips at various RDs)	98,804/-	2,000/-	One month	350/-
4	R/R damages on Mamail Mehendi road Km. 0/00 to 19/00 (SH:- Hiring of Tipper for disposal/Carriage of material) Section Karsog	98,800/-	2,000/-	26 days	350/-
5	R/R damages on Bagshar to Mahunag via Seri road Km. 0/00 to 14/00 (SH:- C/o unlined drain, maintenance of earthen shoulders and removal of slips at RD 10/765 to 14/00)	99,541/-	2,000/-	Two months	350/-
6	R/R damages on various road under Churag Sub-Division (SH:- Hiring of Tipper for disposal/carriage of material) Churag Section	98,800/-	2,000/-	26 days	350/-

7	R/R damages on various road under Pangna Sub-Division (SH:- C/o unlined drain maintenance of earthen shoulders and maintenance of berm at various RDs)	99,865/-	2,000/-	One month	350/-
8	R/R damages on various road under Karsog Sub-Division (SH:- Removal of slips at various roads & various RDs)	99,224/-	2,000/-	One month	350/-
9	R/R damages on Seri to Shalani road Km. 0/00 to 2/765 to (SH:- C/o unlined surface drain, maintenance of earthen shoulders and removal of slips at various RDs)	99,211/-	2,000/-	Two months	350/-
10	R/R damages on various road under Karsog Sub-Division (SH:- C/o unlined drain maintenance of earthen shoulders, maintenance of berm at various RDs) Kelodhar Section	99,702/-	2,000/-	One month	350/-
11	Preparation of Forest Diversion Case under Forest Right Act, 2006 for the construction of link road from Kao to Kajoun (under OTMNP)	30,000/-	600/-	Two months	350/-
12	R/R damages on Kotlu Katanda road Km. 0/00 to 19/00 (SH:- Hiring of Air compressor for ROFD, Black spots etc.)Section Katanda	98,952/-	2,000/-	21 days	350/-
13	R/R damages on Kotlu Katanda road Km. 0/00 to 19/00 (SH:- Hiring of Tipper for disposal/carriage of material) Section Katanda	98,800/-	2,000/-	26 days	350/-
14	R/R damages on Sanoti Dhawas road Km. 0/00 to 2/700 (SH:- C/o unlined drain maintenance of earthen shoulders, & removal of slips at various RDs in km. 0/00 to 2/700)	99,645/-	2,000/-	One month	350/-
15	R/R damages on Kheel Dharmour Sanoti Nag road Km. 0/00 to 3/00 (SH:- C/o unlined drain maintenance of earthen shoulders, & removal of slips at various RDs in Km. 0/00 to 3/00)	98,083/-	2,000/-	One month	350/-
16	R/R damages on Behali Shangrol road Km. 0/00 to 1/860 (SH:- C/o unlined drain maintenance of earthen shoulders & removal of slips at various RDs in km. 0/00 to 1/860)	99,286/-	2,000/-	One month	350/-
17	R/R damages on various roads under Churag Sub-Division (SH:- hiring of Tipper for disposal/carriage of material) Churag Section)	98,800/-	2,000/-	26 days	350/-
18	R/R damages on Chindi Dachhain road Km. 0/00 to 8/435(SH:- C/o unlined drain maintenance of earthen shoulders, & removal of slips at various RDs)	99,113/-	2,000/-	One month	350/-
19	R/R damages in Karsog Parlog road Km. 0/00 to 19/00 (SH:- removal of slips at various RDs)	97,516/-	2,000/-	One month	350/-
20	R/R damages on Kao Kanda road Km. 0/00 to 5/00 (SH:- C/o unlined drain maintenance of earthen shoulders, & removal of slips at various RDs)	99,520/-	2,000/-	One month	350/-
21	A/R & M/O Katanda Mahog road Km. 0/0 to 10/500 (SH:- Supplying and stacking ordinary stone for repair of pot holes in various RDs)	99,450/-	2,000/-	One month	350/-
22	R/R damages on various road under Karsog Sub-	99,222/-	2,000/-	Two	350/-

	Division (SH:- C/o unlined drain maintenance of earthen shoulders, & removal of slips at various RDs)			months	
23	R/R damages on Bag to Pokhi road Km. 0/0 to 10/0 & Kuthar Rasog Deoum road km. 0/0 to 9/0 (SH:- Hiring of Tipper for disposal/carriage of material) Section Katanda	98,800/-	2,000/-	26 days	350/-
24	A/R & M/O Seri Shout road Km. 0/0 to 19/0 (SH:- Supply of ordinary stone at RD 8/0 to 16/0)	97,750/-	2,000/-	15 days	350/-
25	A/R & M/O Seri Shout road Km. 0/0 to 19/0 (SH:- Supply of ordinary stone at RD 0/0 to 8/0)	97,750/-	2,000/-	15 days	350/-
26	R/R damages on Bag to Pokhi road km. 0/0 to 10/0 & Kuthar Rashog Deoum road km. 0/0 to 9/0 (SH:- hiring of air compressor for ROFD, Black spots etc.)	98,952/-	2,000/-	21 days	350/-

TERMS & CONDITIONS:-


1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


Executive Engineer
B&R Division
HPPWD Karsog,
Distt. Mandi (HP)

No. PW-E-Tender-NIT/23

Dated:-

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1st Circle, HP,PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog
Distt. Mandi H.P.

~~BATCH-I~~/Schedule of Quantity

Estimated Cost Rs. 99000.00
Earnest Money Rs. 1980.00
Time:- One month

Name of Work:- R/R Damages on Rasahog Deyom road 0/0 to 9/00 under Karsog Sub-Division (SH:- Hiring of JCB/Excavator cum loader for Removal of slip from km 15/00 to 19/00 at various RD's)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Hiring of JCB/Excavator cum loader for cutting in earthwork/removal of snow/slip from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable material from the road surface upto any leads and as per direction of Engineer-in-charge. The machine/JCB should work Thrs daily any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The repair charges of machinery during the execution of work will be borne by the contractor. The usefull material shall be stacked along the road side as per direction of Engineer-in-charge	90.00			Per Hours	
	G.Total					

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

SCHEDULE OF QUANTITY

Estimated Cost 98094
Earnest Money 2000
Time One Month

Name of work : - R/R Damages on various road under Karsog Sub-Division (SH:- C/O unlined surface drain, making of earthen shoulders and maintenance of berms at various RD's).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1065.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1440.00			Per Square Meter	
3	Stripping excess soil from the shoulder surface to achive the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1440.00			Per Square Meter	
	Total Amount					


Executive Engineer,
Karsog Division,
HPRWD, Karsog.

Schedule of Quantity

Estimated Cost
Earnest Money
Time

98804
2000
One Month

Name of work : - R/R Damages on Salana to Mehandi road Km. 0/00 to 3/00 (SH :- Removal of slips at various RDS)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			in Figure	in words		
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	719.10			Per Cubic Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule of Quantity

Estimated Cost Rs.	98800
Earnest Money	2000
Time:-	26 Days

Name of work:-RR Damages on Mamail Mehendi road Km. 0/00 to 19/00 (SH:- Hiring of Tipper for disposal/Carriage of Material) Section Karsog					
Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.
			In Fig	In Words	
1	Hiring of Tipper on daily wages basis for carriage of material Le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-charge to Tipper should work 8 hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fule and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26.00			Per Day
Total:-					


 Executive Engineer,
 Karsog Division,
 HPWD, Karsog

SCHEDULE OF QUANTITY

Estimated Cost 99541
Earnest Money 2000
Time Two Months

Name of work : - R/R Damages on Bagshair to Mahunag Via Seri road Km. 0/00 to 14/00 (SH:- C/O unlined drain, maintenance of earthen shoulders and removal of slips at RD. 107/65 to 14/00)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer- in-charge with in all lead and lifts and other incidentals.	825.75			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals..	1050.25			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material. with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	390.25			Per Cubic Meter	
Total Amount						


Executive Engineer,
Karsog Division,
APPWD, Karsog.

DNIT

Estimated Cost Rs.	98800
Earnest Money	2000
Time:-	26 Days

Name of work:-RR Damages on various roads under Churag Sub Division (SH)-Hiring of Tipper for disposal/Carriage of Material) Churag Section

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			In Fig	In Words		
1	Hiring of Tipper on daily wages basis for carriage of material Le. Agreegate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-charge to Tipper should work 8 hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fule and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26.00	3800.00	Rupees Three Thousand Eight Hundred and Paise Zero Only	Per Day	98800.00
Total:-						98800.00

DNIT checked and approved for Rs. 98800 /-only
S.No. 60 For the year 2023-24

Executive Engineer,
Karsog Division,
HPPWD, Karsog

ASSISTANT ENGINEER
CHURAG SUB-DIVISION
HPPWD CHURAG

SCHEDULE OF QUANTITY

Estimated Cost Rs. 99865
Earnest Money 2000
Time:- One month

Name of work:- R/R Damages on Various road Under Pangna Sub Division (SH:-C/O unlined unlined drain maintenance of earthen shoulders and maintenance of berm at various RD's)

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			In Figure	In Words		
1	Construction of unlined surface drains of average cross-sectional area 0.20 Sqm. In ordinary rock to specified lines, grades, levels and dimensions as per approved design and technical specification clause 307. within all leads and lifts and other incidentals as per direction of Engineer-in Charge.	930.00			Per Running Metre	
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge.	1333.50			Per Square Metre	
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903. within all leads and lifts and other incidentals as per direction of Engineer-in Charge.	1333.50			Per Square Metre	


Executive Engineer,
Karsog Division,
DPPWD, Karsog

SCHEDULE OF QUANTITY

Estimated Cost Rs.	99724
Earliest Money	2000
Time:-	One Month

Name of work:- R/R Damages on various road under Karsog Sub Division (SH:- Removal of slips at various roads & various RD's)

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			In Figure	In Words		
1	Removal of land slide slip clearance:- Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanically means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 within all leads and lifts and other incidentals as per direction of Engineer-in Charge.	785.00			Per Cubic Metre	


 Executive Engineer,
 Karsog Division,
 H.P. WD, Karsog

SCHEDULE OF QUANTITY

Estimated Cost 99211
 Earnest Money 2000
 Time Two Months

Name of work : - R/R Damages on Seri to Shalani road Km. 0/00 to 2/765 (SH:- C/O unlined Surface drain, maintenance of earthen shoulders and removal of slips at various RDS) ~~Atinot September~~

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit	Amount
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer-in -charge with in all lead and lifts and other incidentals.	825.50			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals..	1045.25			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	388.75			Per Cubic Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HPWD, Karsog.

SCHEDULE OF QUANTITY

Estimated Cost Rs.

99702

Earnest Money

2000

Time:-

One Month

Name of work:- R/R Damages on Various road under Karsog Sub Division (SH:- C/O Unlined Drain and Maintenance of earthen shoulders, Maintenance of Berm at Various RD's) Kelodhar Section

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit	Amount
			In Fig	In Words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified lines grades, levels and dimension, Excavation material to be used in embankment with a lift upto any lead as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1125.00			Per Running meter	
2	Making of loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment of OMC upto any lead as per technical specification clause 1903 as per direction of Engineer in-Charge including carriage of material within all leads and lifts and other incidentals.	1440.00			Per square meter	
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903. within all leads and lifts and other incidentals as per direction of Engineer-in Charge.	1440.00			Per square meter	
	Total:-					

Executive Engineer,
Karsog Division,
HRPWD, Karsog

DNT /SCHEDULE OF QUANTITY

Name of Work:- Preparation of Forest Diversion Case under Forest Right Act, 2006 for the Construction of Link road from kao to Kajaun (Under OTMNP)

Estimated Cost 30000.00
Earnest Money 600/-
Time Two Months.

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Preparation of Forest Diversion case under Forest Right Act, 2006 including preparation of revenue papers of land falling on the road alignment and collection of the other field data. All relevant documents/ formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and Forest conservation Govt. of India after getting the joint inspection/site including computer typing in six copies, binding complete and getting it through from HPPWD, Sub - Division Karsog, HPPWD Division Karsog , Office of concern Range Officer, Office of Divisional Forest Officer Karsog. Including attending all the observation, if raised, at any time by any above mentioned office and to prepare the same by neatly and accurately filling in all the formats/ Documents complete in all respect as per direction and complete satisfaction of HPPWD and Forest Department.	1.00			Per Case	
Total Amount						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

D.A.T.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Kotlu Katanda Road Km 0/00 to 19/00 (SH :- Hiring of air Compressor for ROFD, Black spots etc.)

Estimated Cost Rs :- 98952/-
Earnest money:- 2000/-
Time :- 21 days

S.No.	Sub-Head and items of work.	Qty.	Rate		Unit.	Amount.
			In Figure	In Words.		
1.	Hiring of air compressor with tractor and jack hammer for hole cutting in all kind of soil fuel, oil lubricants and wages of operating staff, any repair during operation and shifting of machinery from on place to other, required location will be carried out by the owner on this own risk and cost. Actually working hours will be deployed at any location as desired by the Engineer-in charge.	21 Days			Per Days	
	Total :-					

Executive Engineer
Karag Division
HPWD Karag


P.A.T / SCHEDULE OF QUANTITY

Estimated Cost Rs :-98800/-
Earnest money:-2000/-

Time :- 26 Days

Name of Work :- R.R. Damages on Kotlu Katanda road Km 00/0 to 19/0 (Sh.:- Hiring of Tipper for disposal/carrriage of Material) Section Katanda

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
Total						


Engineer-in-Charge
Karag Division
HPPWAD Karag

Schedule of Quantity

Estimated Cost
Earnest Money
Time

99645
2000
One Month

Name of work : - R/R Damages on Sanoti Dhawas road Km. 0/00 to 2/700 (SH :- C/O unlined drain, maintenance of earthen shoulders, & Removal of slips at various RDS in Km. 0/00 to 2/700)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer-in -charge with in all lead and lifts and other incidentals.	1200.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1207.50			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of sops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	197.94			Per Cubic Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule of Quantity

Estimated Cost
Earnest Money
Time

98083
2000
One Month

Name of work : - R/R Damages on Kheel Dharmour Sanoti Nag road Km. 0/00 to 3/00 (SH :- C/O unlined drain, maintenance of earthen shoulders, & Removal of slips at various RDS in Km. 0/00 to 3/00)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer-in-charge with in all lead and lifts and other incidentals.	975.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1102.50			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	240.16			Per Cubic Meter	
Total Amount						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule of Quantity

Estimated Cost
Earnest Money
Time

99286
2000
One Month

Name of work : - R/R Damages on Behali Shangrol road Km. 0/00 to 1/860 (SH :- C/O unlined drain, maintenance of earthen shoulders, & Removal of slips at various RDs in Km. 0/00 to 1/860)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1125.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903. within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1125.00			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	222.38			Per Cubic Meter	
	Total Amount					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

D.N.I.T.

Estimated Cost Rs.	98800
Earnest Money	2000
Time:-	26 Days

NAUGAT WORKS R/R Damages on various road under Churag Sub-Division (SH:- Hiring of Tipper for disposal/Carriage of Material) Churag Section

Sr. No.	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount
			In Fig	In Words		
1	Hiring of Tipper on daily wages basis for carriage of material Le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-charge to Tipper should work 8 hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26.00	3800.00	Rupees Three Thousand Eight Hundred and Paise Zero Only	Per Day	98800.00
Total:-						98800.00

DNIT checked and approved for Rs.
S.No. 63 For the year 2023-24

98800 /-only

CHURAG SUB-DIVISION
CHURAG
CHURAG

Executive Engineer,
Karsog Division,
KPPWD, Karsog

Schedule of Quantity

Estimated Cost 99113
 Earnest Money 2000
 Time One month

Name of work : - R/R Damages on Chindi Dachhain road Km. 0/00 to 8/435 (SH :- C/O unlined drain, making of earthen shoulders and maintenance of berm at various RDs)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	930.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1536.00			Per Square Meter	
3	Stripping excess soil from the shouldr surface to achive the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1536.00			Per Square Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule of Quantity

Estimated Cost 97516
Earnest Money 2000
Time One Month

Name of work : - R/R Damages on Karsog Parlog road Km. 0/00 to 19/00 (SH :- Removal of slips at various RD'S)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	709.73			Per Cubic Meter	
	Total Amount					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Schedule of Quantity

Estimated Cost 99520
 Earnest Money 2000
 Time One month

Name of work : - R/R Damages on Kao Kanda road Km. 0/00 to 5/00 (SH :- C/O unlined drain, making of earthen shoulders and maintenance of berm at various RDS)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in-charge with in all lead and lifts and other incidentals.	810.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1611.00			Per Square Meter	
3	Stripping excess soil from the shouldr surface to achive the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1611.00			Per Square Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HRPWB, Karsog.

Schedule of Quantity

Estimated Cost Rs. 99450
Earnest Money Rs. 2000

Time:- One Month

Name of work:-A/R &M/O Katanda Mahog road. 0/0 to 10/500 (SH:- Supplying and staking ordinary stone for Repair of pot holes in various RDS)

S.No.	Description	Qty.	Rate		Unit	Amount.
			In Figure.	In Words.		
	Supplying and stacking at site of work ordinary stones of approved quality as per PWD Specification including carriage,loading,Un-loading at site of work in proper stacks complete in all respect as per entire satisfaction of Engineer-in-Charge.	117.00			Per Cubic Metre.	
	Total:-					


Executive Engineer,
Karsog Division,
H.P.PWD, Karsog

SCHEDULE OF QUANTITY

Estimated Cost 99222
Earnest Money 2000
Time Two Months

Name of work : - R/R Damages on various road under Karsog Sub Division (SH:- C/O unlined drain, maintenance of earthen shoulders and removal of slips at various RDS) Katanda Section

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension. Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer-in-charge with in all lead and lifts and other incidentals.	775.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals..	1025.45			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	403.75			Per Cubic Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 KPBMD, Karsog.

D.M.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Bag to Pokhi Road Km 0/0 to 10/0 & Kuthar Rasog Deoum road Km 0/0 to 9/0 (SH.- Hiring of Tipper for disposal/carriage of Material)
 Section Katanda

Estimated Cost Rs :-98800/-
 Earnest money:-2000/-
 Time :- 26 Days

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages. basis for carriage of materials I.e. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
Total						


 Executive Engineer
 Karasog Division
 HPP/MD Karasog

Schedule of Quantity

Estimated Cost Rs.	97750
Earnest Money	2000
Time:-	15 days

Estimated Cost Rs.	97750
Earnest Money	2000
Time:-	15 days

Name of work:- A/R & M/O Seri Shout road Km. 0/00 to 19/00 (SH:- Supplying of ordinary stone at RD. 8/00 to 16/00)

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			In Figure	In Words		
1	Supplying and stacking at site of work Ordinary quarried stones of approved quality as per PWD specification including carriage, loading, unloading at site of work in proper stacks complete in all respect as per entire satisfaction of Engineer-in-Charge.	115.00			Per Cubic Metre	
Total:-						

Executive Engineer,
Karsog Division,
BPPWD, Karsog

Calculation of Quantity

Schedule of Quantity

Estimated Cost Rs.	97750
Earnest Money	2000
Time:-	15 days

Name of work:- A/R & M/O Seri Shout road Km. 0/00 to 19/00 (SH:- Supplying of ordinary stone at RD. 0/00 to 8/00

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			In Figure	In Words		
1	Supplying and stacking at site of work Ordinary quarried stones of approved quality as per PWD specification including carriage, loading, unloading at site of work in proper stacks complete in all respect as per entire satisfaction of Engineer-in-Charge.	115.00			Per Cubic Metre	
Total:-						


 Executive Engineer,
 Karsog Division,
 KHPWD, Karsog

B.N.T.T.Y SCHEDULE OF QUANTITY

Estimated Cost Rs :- 98952/-

Earnest money:- 2000/-

Time :- 21 days

Name of Work :- R.R. Damages on Bag to Pokhi Road Km 0/0 to 10/0 & Kuther Rashog Deoum Road Km 0/0 to 9/0 (SH.- Hiring of air Compressor for ROFD, Black spots etc.)

S.No.	Sub- Head and items of work.	Qty.	Rate		Unit.	Amount.
			In Figure	In Words.		
1.	Hiring of air compressor with tractor and jack hammer for hole cutting in all kind of soil fuel ,oil lubricants and wages of operating staff, any repair during operation and shifting of machinery from on place to other, required location will be carried out by the owner on this own risk and cost .Actually working hours will be deployed at any location as desired by the Engineer-in charge.	21 Days			Per Days	
	Total :-					


Executive Engineer
Karsog Division
H.P.W.D Karsog