



OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023-

4039

Dated:- 23/8/2023

To


The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :-

Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 26.08.2023 as per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. As the works mentioned in the Tender Notice are urgent in nature.

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **11.09.2023 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 08.09.2023** for which the application should reach in this office **upto 1.00 PM 08.09.2023**.


The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	C/o Dharmour Ashni Mandir road Km. 0/00 to 5/00 (SH:- F/C 5/7 mtr wide in Km. 3/990 to 4/210)	3,66,304/-	7,350/-	One Month	350/-
2	C/o Dharmour Ashni Mandir road Km. 0/00 to 5/00 (SH:- F/C 5/7 mtr wide in Km. 3/645 to 3/980)	4,91,520/-	9,850/-	One Month	350/-
3	C/o Dharmour Ashni Mandir road Km. 0/00 to 5/00 (SH:- F/C 5/7 mtr wide in Km. 3/345 to 3/630)	4,96,763/-	9,950/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.

8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.



Executive Engineer
B&R Division
HPPWD Karsog,
Distt. Mandi(HP)

No. PW-E-Tender-NIT/23

6039

Dated:- 23.8.23

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1st Circle, HP,PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Time

366304
7350
One Month

Name of Work:- C/O Dharmour Ashni Mandir road Km 0/00 to 5/00 (SH:-FIC 5/7 mtr wide in Km 3/990 to 4/210).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	in words		
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 226.83 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.68,049/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1620.17			Per Cubic Meter	
Total Amount						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Time

491520
9850
One Month

Name of Work:- C/O Dharmour Ashni Mandir road Km 0/00 to 5/00 (SH:-F/C 5/7 mtr wide in Km 3/645 to 3/980).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 304.36 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.91,308/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2174.00			Per Cubic Meter	
	Total Amount					

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Time

496763
9950
One Month

Name of Work:- C/O Dharmour Ashni Mandir road Km 0/00 to 5/00 (SH:-F/C 5/7 mtr wide in Km 3/345 to 3/630).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 307.61 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.92,283/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2197.19			Per Cubic Meter	
	Total Amount					

Executive Engineer,
Karsog Division,
HPPWD, Karsog.